This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

**Usage guidelines**

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

**About Google Book Search**

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

LANE MEDICAL LIBRARY STANFORD
F34 .K59 1905 STOR
Kirkes' Handbook of physiology : Handboo
24503384466

LANE
MEDICAL LIBRARY
SEAL OF THE LELAND STANFORD JUNIOR UNIVERSITY
1885

Gift

Dr. E.M. Whiting

# HAND-BOOK

OF

# PHYSIOLOGY.

# BLOOD-SPECTRA COMPARED WITH SPECTRUM OF ARGAND-LAMP.



1 Spectrum of Argand-lamp with Fraunhofer's lines in position.
2 Spectrum of Oxyhæmoglobin in diluted blood.
3 Spectrum of Reduced Hæmoglobin.
4 Spectrum of Carbonic oxide Hæmoglobin.
5 Spectrum of Acid Hæmatin in etherial solution.
6 Spectrum of Alkaline Hæmatin.
7 Spectrum of Cbloroform extract of acidulated Ox-Bile.
8 Spectrum of Methæmoglobin.
9 Spectrom of Hæmochromogen.
10 Spectrum of Hæmatoporphyrin.

*Most of the above Spectra have been drawn from observations by Mr W. Lapraik F.C.S.*

SACKETT & WILHELMS LITHO CO. NEW YORK

# PHYSIOLOGY

*REVISED BY*

**FREDERICK C. BUSCH, B.S., M.D.**

Professor of Physiology, Medical Department, University of Buffalo

Fifth American Revision

WITH FIVE HUNDRED AND THIRTY-FIVE ILLUSTRATIONS
INCLUDING MANY IN COLORS

BLOOD SPECTRA COMPARED WITH SPECTRUM OF ARGAND LAMP.



1. [illegible] Argand lamp with Fraunhofer's lines in position.
2. [illegible] Oxyhæmoglobin in diluted blood.
3. [illegible] Reduced Hæmoglobin.
4. [illegible] Carbonic oxide Hæmoglobin.
5. [illegible] Acid Hæmatin in etherial solution.
6. [illegible] Alkaline Hæmatin.
7. [illegible] Chloroform extract of acidulated Ox-Bile.
8. [illegible] Methæmoglobin.
9. [illegible] Hæmochromogen.
10. [illegible] Hæmatoporphyrin.

*Most of the above Spectra have been drawn from observations by* [illegible]

[illegible]

KIRKES' HANDBOOK OF PHYSIC

# HANDBOOK

OF

# PHYSIOLOGY

*REVISED BY*

**FREDERICK C. BUSCH, B.S., M.D.**

Professor of Physiology, Medical Department, University of Buffalo.

**Fifth American Revision**

WITH FIVE HUNDRED AND THIRTY-FIVE ILLUSTRATIONS
INCLUDING MANY IN COLORS

NEW YORK
WILLIAM WOOD AND COMPANY
MDCCCCV

Ka

COPYRIGHT, [illegible]
BY WILLIAM WOOD AND COMPANY.

F34
K59
1905

# PREFATORY NOTE.

In the present edition changes have been made throughout the book in order to conform to well-established advances in the various fields of physiology. The text has also been condensed in places, and elaborated in others where it has been deemed advisable for the better elucidation of the subject-matter.

The chapters most affected are those on the blood, the circulation, respiration, food and digestion, and muscle-nerve physiology.

A number of cuts have been replaced by others which more clearly illustrate the text, and several new cuts have been added.

I desire to thank Dr. Charles Van Bergen for valuable assistance in the revision.

F. C. Busch.

*July, 1904.*

47311

# CONTENTS.

## CHAPTER I.

PAGE
THE PHENOMENA OF LIFE . . . . . . . . . . . . . . 1
Properties of Protoplasm, . . . . . . . . . . . . 8
Structure of Protoplasmic Cells, . . . . . . . . . . . 9
The Cell Nucleus, . . . . . . . . . . . . . . 11
Attraction Sphere, . . . . . . . . . . . . . . 13
Cell Division, . . . . . . . . . . . . . . 13
Plants Compared with Animals, . . . . . . . . . . 17

## CHAPTER II.

THE FUNCTIONS OF ORGANIZED CELLS, . . . . . . . . . 23

## CHAPTER III.

THE STRUCTURE OF THE ELEMENTARY TISSUES, . . . . . . . . 26
Epithelial Tissues, . . . . . . . . . . . . . . 28
Connective Tissues, . . . . . . . . . . . . . . 40
The Teeth, . . . . . . . . . . . . . . . 69
Development of the Teeth, . . . . . . . . . . . . 76
Muscular Tissues, . . . . . . . . . . . . . . 81
Nervous Tissues, . . . . . . . . . . . . . . 91

## CHAPTER IV.

THE CHEMICAL COMPOSITION OF THE BODY, . . . . . . . . . 110
Organic Substances, . . . . . . . . . . . . . 111
Inorganic Substances, . . . . . . . . . . . . . 132
Chemico-physiological Tests, . . . . . . . . . . . 135

## CHAPTER V.

THE BLOOD, . . . . . . . . . . . . . . . . 140
Coagulation, . . . . . . . . . . . . . . . 142
The Corpuscles, . . . . . . . . . . . . . . 148
Chemical Composition, . . . . . . . . . . . . . 157
Gases of the Blood, . . . . . . . . . . . . . 161
Globulocidal and Other Properties, . . . . . . . . . 174
Development of Corpuscles, . . . . . . . . . . . 176
Diffusion, Osmosis, Dialysis, . . . . . . . . . . . 179

## CHAPTER VI.

THE CIRCULATION OF THE BLOOD,
- The Heart,
- The Arteries,
- The Capillaries,
- The Veins,
- The Action of the Heart,
- The Action of the Valves of the Heart,
- The Cardiac Cycle,
- The Sounds of the Heart,
- The Impulse of the Heart,
- Endocardiac Pressure,
- Frequency of Heart's Action,
- Force of Heart's Action,
- Blood Pressure,
- The Arterial Flow,
- The Pulse,
- Blood Pressure in Man,
- The Capillary Flow,
- The Venous Flow,
- The Velocity of Flow,
- Local Peculiarities of the Circulation,
- Regulation of the Flow,
- The Properties of Heart Muscle,
- Influence of the Central Nervous System,
- Electrical Phenomena of Heart Beat,
- Vasomotor Nerves,
- Proofs of the Circulation of the Blood,

## CHAPTER VII.

RESPIRATION,
- The Respiratory Apparatus,
- The Respiratory Mechanism,
- Respiratory Changes in Air Breathed,
- Respiratory Changes in the Blood,
- Respiratory Changes in the Tissues,
- Special Respiratory Acts,
- Nervous Mechanism,
- Effect on Circulation,
- Asphyxia,

## CHAPTER VIII.

SECRETION,
- Organs and Tissues of Secretion,
- Secreting Glands,
- The Mammary Glands,
- Milk,
- The Ductless Glands and Internal Secretions,

## CHAPTER IX.

PAGE
Food and Digestion, . . . . . 339
Organic Nitrogenous Foods, . . . . . 339
Organic Non-Nitrogenous Foods, . . . . . 342
Mineral Foods, . . . . . 342
Liquid Foods, . . . . . 343
Enzymes, . . . . . 344
Mastication, . . . . . 345
The Salivary Glands, . . . . . 346
Saliva, . . . . . 350
Nervous Mechanism of Salivary Secretion, . . . . . 354
The Tongue, . . . . . 359
The Pharynx, . . . . . 362
The Œsophagus or Gullet, . . . . . 364
Deglutition . . . . . 365
The Stomach, . . . . . 367
Gastric Juice, . . . . . 371
Influence of Nervous System, . . . . . 379
Vomiting, . . . . . 382
The Intestines, . . . . . 383
The Pancreas and Its Secretions, . . . . . 392
The Liver, . . . . . 398
The Bile, . . . . . 403
The Intestinal Secretion, . . . . . 411
Digestion in the Small Intestine, . . . . . 413
Digestion in the Large Intestine, . . . . . 414
Micro-organisms in the Intestines, . . . . . 414
Movements of the Intestines, . . . . . 416
Defæcation, . . . . . 420

## CHAPTER X.

Absorption, . . . . . 422
Methods of, . . . . . 422
The Lympathic System, . . . . . 425
The Lymph Flow, . . . . . 429
Lymphatic Glands, . . . . . 430
The Lymph and Chyle, . . . . . 434
Channels of Absorption, . . . . . 436
Where Absorption may take Place, . . . . . 438

## CHAPTER XI.

Metabolism, Nutrition, and Diet, . . . . . 441
Effect of Proteid Diet, . . . . . 443
Effect of Albuminoid Diet, . . . . . 444
Formation of Urea, . . . . . 445
Effects of Fat and Carbohydrate Foods, . . . . . 448
Formation of Glycogen, . . . . . 449
Requisites of a Normal Diet, . . . . . 455
Variations in Diet Tables, . . . . . 458
Income and Output of Energy, . . . . . 458

## CHAPTER XII.

**Animal Heat,**
- Heat Production,
- Heat-Producing Tissues,
- Regulation of Body Temperature,
- Variation in Heat Production,
- Influence of the Nervous System,

## CHAPTER XIII.

**Excretion,**
- The Kidneys,
- The Urinary Bladder,
- The Urine,
- Method of Excretion of Urine,
- The Passage of Urine into the Bladder,
- Micturition,
- The Skin,
- Functions of the Skin,
- Influence of the Nervous System,

## CHAPTER XIV.

**Muscle-Nerve Physiology,**
- Chemical Composition of Muscle,
- Muscle at Rest,
- Muscle in Activity,
- Accompaniments of Muscular Contraction,
- Conditions Affecting Character of Contractions,
- Muscle in Rigor Mortis,
- Action of Voluntary Muscles,
- Action of Involuntary Muscles,
- Electrical Currents in Nerves,
- Electrotonus,
- Effects of Battery Currents on Nerves,
- Muscular and Nervous Metabolism,

## CHAPTER XV.

**The Production of the Voice,**
- The Larynx,
- The Laryngoscope,
- Movements of the Vocal Cords,
- The Voice in Singing and Speaking,
- Speech,
- Articulate Sounds,

## CHAPTER XVI.

**The Nervous System,**
- Function of Nerve Fibres,
- Function of Nerve Centres,
- Reflex Action,
- Inhibition and Augmentation,

PAGE
THE NERVOUS SYSTEM (*Continued*).
The Spinal Cord and its Nerves, . . . . . . . . . . . . 575
Functions of the Spinal Nerve Roots, . . . . . . . . . . 586
Functions of the Spinal Cord, . . . . . . . . . . . 587
The Relation of Different Parts of the Brain, . . . . . . . 596
Distribution of the Gray Matter, . . . . . . . . . . . . 602
The Bulb or Medulla Oblongata, . . . . . . . . . . . . 602
Functions of the Bulb, . . . . . . . . . . . . . . . 608
Special Centres in the Bulb, . . . . . . . . . . . . . 609
The Cranial Nerves, . . . . . . . . . . . . . . . 611
The Pons Varolii, . . . . . . . . . . . . . . . . 627
The Crura Cerebri, . . . . . . . . . . . . . . . 628
Corpora Striata, . . . . . . . . . . . . . . . . 630
Corpora Quadrigemina, . . . . . . . . . . . . . . 631
Optic Thalami, . . . . . . . . . . . . . . . . 631
The Cerebrum, . . . . . . . . . . . . . . . . 632
Motor Areas of the Cerebral Cortex, . . . . . . . . . . 641
Functions of the Cerebrum, . . . . . . . . . . . . . 648
Sensory Centres, . . . . . . . . . . . . . . . . 654
Functions of the Corpora Striata and Optic Thalami, . . . . . . 657
The Cerebellum, . . . . . . . . . . . . . . . . 658
Functions of the Cerebellum, . . . . . . . . . . . . 662
Functions of the Corpora Quadrigemina and Geniculata, . . . . . 664
Summary of the Course of Motor and Sensory Impulses within the Cerebro-Spinal Axis, . . . . . . . . . . . . . . . 665
The Sympathetic System, . . . . . . . . . . . . . 667

## CHAPTER XVII.

THE SENSES, . . . . . . . . . . . . . . . . . 674
Common Sensations, . . . . . . . . . . . . . . . 674
Special Sensations, . . . . . . . . . . . . . . . 675
The Sense of Touch, . . . . . . . . . . . . . . . 677
The Muscular Sense, . . . . . . . . . . . . . . . 682
The Sense of Taste, . . . . . . . . . . . . . . . 684
The Sense of Smell, . . . . . . . . . . . . . . . 687
The Sense of Hearing, . . . . . . . . . . . . . . 693
The Sense of Sight, . . . . . . . . . . . . . . . 711

## CHAPTER XVIII.

THE REPRODUCTIVE ORGANS, . . . . . . . . . . . . . 762
Of the Female, . . . . . . . . . . . . . . . . 762
Of the Male, . . . . . . . . . . . . . . . . . 768
Physiology of the Sexual Organs, . . . . . . . . . . 775

## CHAPTER XIX.

DEVELOPMENT, . . . . . . . . . . . . . . . . . 784
Changes in the Ovum, . . . . . . . . . . . . . . 784
Fœtal Membranes, . . . . . . . . . . . . . . . 797
Formation of the Placenta, . . . . . . . . . . . . . 802
Development of the Organs, . . . . . . . . . . . . 806

## CLASSIFICATION OF THE ANIMAL KINGDOM.

### A.—VERTEBRATA.

| | | | *Typical examples.* |
|---|---|---|---|
| **MAMMALIA** | | | |
| | **Monodelphia** | | |
| | | **Primates** | Man, ape. |
| | | **Cheiroptera** | Bat. |
| | | **Insectivora** | Hedgehog. |
| | | **Carnivora** | Cat, dog, bear. |
| | | **Proboscidea** | Elephant. |
| | | **Hyracoidea** | Hyrax. |
| | | **Ungulata** | Horse, sheep, pig. |
| | | **Sirenia** | Dugong. |
| | | **Cetacea** | Whale. |
| | | **Rodentia** | Rabbit, rat. |
| | | **Edentata** | Armadillo. |
| | **Didelphia** | | Kangaroo. |
| | **Ornithodelphia** | | Duck-billed platypus |
| **AVES** | | | |
| | **Carinatæ** | | Fowl, duck. |
| | **Ratitæ** | | Ostrich. |
| **REPTILIA** | | | |
| | **Crocodilia** | | Crocodile. |
| | **Ophidia** | | Snake. |
| | **Chelonia** | | Tortoise. |
| | **Lacertilia** | | Lizard. |
| **AMPHIBIA** | | | |
| | **Anura** | | Frog. |
| | **Urodela** | | Newt. |
| **PISCES** | | | Lamprey, shark, cod |

### B.—INVERTEBRATA.

| | | |
|---|---|---|
| **MOLLUSCA** | | |
| | **Odontophora** | Whelk, snail. |
| | **Lamellibranchiata** | Mussel, oyster. |
| | **Brachiopoda** | Terebratula. |
| | **Polyzoa** | Sea mat. |
| **ARTHROPODA** | | |
| | **Crustacea** | Lobster. |
| | **Arachnida** | Scorpion, spider. |
| | **Insecta** | Bee, fly. |
| | **Myriapoda** | Centipede. |
| **ECHINODERMATA** | | Sea stars. |
| **VERMES** | | |
| | **Annelida** | Earthworm. |
| | **Platyhelminthes** | Tapeworm, fluke. |
| | **Nemathelminthes** | Round-worm, thread-worm |
| **CŒLENTERATA** | | |
| | **Actinozoa** | Sea anemone. |
| | **Hydrozoa** | Hydra. |
| **PROTOZOA** | | Amœba, Vorticella. |

## FAHRENHEIT and CENTIGRADE SCALES.

| F. | C. |
|---|---|
| 500° | 260° |
| 401 | 205 |
| 392 | 200 |
| 383 | 195 |
| 374 | 190 |
| 356 | 180 |
| 347 | 175 |
| 338 | 170 |
| 329 | 165 |
| 320 | 160 |
| 311 | 155 |
| 302 | 150 |
| 284 | 140 |
| 275 | 135 |
| 266 | 130 |
| 248 | 120 |
| 239 | 115 |
| 230 | 110 |
| 212 | 100 |
| 203 | 95 |
| 194 | 90 |
| 176 | 80 |
| 167 | 75 |
| 140 | 60 |
| 122 | 50 |
| 113 | 45 |
| 105 | 40.54 |
| 104 | 40 |
| 100 | 37.8 |

| | |
|---|---|
| 98.5 | 36.9 |
| 95 | 35 |
| 86 | 30 |
| 77 | 25 |
| 68 | 20 |
| 50 | 10 |
| 41 | 5 |
| 32 | 0 |
| 23 | − 5 |
| 14 | − 10 |
| + 5 | − 15 |
| − 4 | − 20 |
| − 13 | − 25 |
| − 22 | − 30 |
| − 40 | − 40 |
| − 76 | − 60 |

1 deg. F. = .54°C.
1.8 " = 1°C.
3.6 " = 2°C.
4.5 " = 2.5°C.
5.4 " = 3°C.

To convert degrees F. into degrees C., subtract 32, and multiply by $\frac{5}{9}$.

To convert degrees C. into degrees F., multiply by $\frac{9}{5}$, and add 32°.

# MEASUREMENTS.

## FRENCH INTO ENGLISH.

### LENGTH.

1 mètre
10 décimètres
100 centimètres
1,000 millimètres } = 39.37 English inches. (or 1 yd. and $3\frac{1}{8}$ in.)

1 décimètre
10 centimètres
100 millimètres } = 3.937 inches (or nearly 4 inches.)

1 centimètre
10 millimètres } = .3937 or about (nearly $\frac{2}{5}$ inch.)
1 millimètre = nearly $\frac{1}{25}$ inch.

OR,

ONE METRE = 39.37079 inches.

(It is the ten-millionth part of a quarter of the meridian of the earth.)

1 Décimètre = 4 in.
1 Centimètre = $\frac{4}{10}$ in.
1 Millimètre = $\frac{1}{25}$ in.
Décamètre = 32.80 feet.
Hectomètre = 109.36 yds.
Kilomètre = 0.62 miles.
One inch = 2.539 Centimètres.
One foot = 3.047 Décimètres.
One yard = 0.91 of a Mètre.
One mile = 1.60 Kilomètre.

The cubic centimètre (15.432 grains—1 gramme) is a standard at 4° C., the grain at 16°.66 C.

### WEIGHT.

(One gramme is the *weight* of a cubic centimètre of water at 4° C. at Paris).

1 gramme
10 décigrammes
100 centigrammes
1,000 milligrammes } = 15.432349 grs. (or nearly $15\frac{1}{2}$).

1 décigramme
10 centigrammes
100 milligrammes } = rather more than $1\frac{1}{2}$ grain.

1 centigramme
10 décigrammes } = rather more than $\frac{3}{20}$ grain.

1 milligramme = rather more than $\frac{3}{200}$ grain.

OR

1 Décigramme = 2 dr. 34 gr.
1 Hectogrm. = $3\frac{1}{2}$ oz. (Avoir.)
1 Kilogrm. = 2 lb. 3 oz. 2 dr. (Avoir.)

A grain equals about 1.16 gram.,
a Troy oz. about 31 gram.,
a lb. Avoirdupois about $\frac{1}{2}$ Kilogrm.,
and 1 cwt. about 50 Kilogrms.

### CAPACITY.

1,000 cubic décimètres
1,000,000 cubic centimètres } = 1 cubic mètre.

1 cubic décimètre
or
1,000 cubic centimètres } = 1 litre.

OR

ONE LITRE = 1 pt. 15 oz. 1 dr. 40.

(For simplicity, *Litre* is used to signify 1 cubic décimètre, a little less than 1 English quart.)

| | |
|---|---|
| Décilitre (100 c.c.) | = $3\frac{1}{2}$ oz. |
| Centilitre (10 c.c.) | = $2\frac{3}{4}$ dr. |
| Millilitre (1 c.c.) | = 17 m. |
| Décalitre | = $2\frac{1}{4}$ gal. |
| Hectolitre | = 22 gals. |
| Kilolitre (cubic mètre) | = $27\frac{1}{2}$ bushels. |

A cubic inch = 16.38 c.c. ; a cubic foot = 28.315 cubic déc., and a gallon = 4.54 litres.

### CONVERSION SCALE.

To convert GRAMMES to OUNCES avoirdupois, multiply by 20 and divide by 567.

To convert KILOGRAMMES to POUNDS, multiply by 1,000 and divide by 454.

To convert LITRES to GALLONS, multiply by 22 and divide by 100.

To convert LITRES to PINTS, multiply by 88 and divide by 50.

To convert MILLIMETRES to INCHES, multiply by 10 and divide by 254.

To convert METRES to YARDS, multiply by 70 and divide by 64.

### SURFACE MEASURE.

1 square mètre = about 1550 sq. inches.
Or 10,000 sq. centimètres, or 10.75 sq. ft.
1 sq. inch = about 6 4 sq. centimètres.
1 sq. foot = " 930 " "

### ENERGY MEASURE.

1 kilogrammètre = about 7.24 ft. pounds.
1 foot pound = " .1381 kgm.
1 foot ton = " 310 kgm.

### HEAT EQUIVALENT.

1 kilocalorie = 424 kilogrammètres.

## ENGLISH MEASURES.

### *Apothecaries Weight.*

7000 grains = 1 lb.

Or

437.5 grains = 1 oz.

### *Avoirdupois Weight.*

| | |
|---|---|
| 16 drams | = 1 oz. |
| 16 oz. | = 1 lb. |
| 28 lbs. | = 1 quarter. |
| 4 quarters | = 1 cwt. |
| 20 cwt. | = 1 ton. |

Measure of 1 décimètre, or 10 centimètres, or 100 millimètres.



The micron (symbol, $\mu$) is the unit of microscopic measurement = $\frac{1}{1000}$ mm. = $\frac{1}{25000}$ inch.



THE SKELETON (AFTER HOLDEN).



DIAGRAM OF THORACIC AND ABDOMINAL REGIONS.

| | |
|---|---|
| *A.* Aortic Valve. | *P.* Pulmonary Valve. |
| *M.* Mitral Valve. | *T.* Tricuspid Valve. |

# HANDBOOK OF PHYSIOLOGY.

## CHAPTER I.

### THE PHENOMENA OF LIFE.

HUMAN Physiology is the science which treats of the various processes or changes which take place during life in the organs and tissues of the body of man. These processes, however, must not be considered as by any means peculiar to the human organism since, putting aside the properties which serve to distinguish man from other animals, as well as those which mark out one animal from another, the changes which go on in the tissues of man go on much in the same way in the tissues of all other animals as long as they live. Furthermore it is found that similar changes proceed in all living vegetable tissues; they indeed constitute what are called *vital phenomena*, and are those properties which mark out living from non-living material.

The lowest types of life, whether animal or vegetable, are found to consist of minute masses of a jelly-like substance, which is now generally known under the name of *protoplasm*. Each such minute mass is called a cell, so that these minute elementary organisms are designated *unicellular*. Not only is it true that the lowest types of life are made up of protoplasm, but it has also been shown that the tissues of which the most complex organisms are composed consist of protoplasmic cells.

Thus, for example, the human body can be shown by dissection to be constructed of various dissimilar parts, bones, muscles, brain, heart, lungs, intestines, etc., and these on more minute examination with the aid of the microscope, are found to be composed of different tissues, such as epithelial, connective, nervous, muscular, and the like. Each of these tissues is made up of cells or of their altered equivalents. Again, we are taught by Embryology, the science which treats of the growth and structure of organisms from their first coming into being, that the human body, made up of all these dissimilar structures, commenced its life as a minute cell or *ovum* (fig. 2) about $\frac{1}{120}$th of an inch in diameter, consisting of a spherical mass of protoplasm in the midst of which was contained a smaller spherical body, the *nucleus* or *germinal vesicle*.

The phenomena of life then are exhibited in cells, whether existing alone or developed into the organs and tissues of animals and plants. It must be at once evident that a correct knowledge of the nature and activities of the cell forms the very foundation of physiology; cells being, in fact, physiological no less than morphological units.

The prime importance of the cell as an element of structure was first established by the researches of the botanist Schleiden, and his conclusions, drawn from the study of vegetable histology, were at once extended by Theodor Schwann to the animal kingdom. The earlier observers defined a cell as a more or less spherical body limited by a membrane, and containing a smaller body termed a *nucleus,* which in its turn incloses one or more still smaller bodies or *nucleoli.* Such a definition applied admirably to most vegetable cells, but the more extended investigation of animal tissues soon showed that in many cases no limiting membrane or cell-wall could be demonstrated.



Fig. 1.—Vegetable cells.


Nucleus or germinal vesicle.
Nucleolus or germinal spot.
Space left by retraction of yelk.
Yelk or vitellus.
Vitelline membrane.

Fig. 2.—Semidiagrammatic representation of a human ovum, showing the parts of an animal cell. (Cadiat.)

The presence or absence of a cell-wall, therefore, was now regarded as quite a secondary matter, while at the same time the cell-substance came gradually to be recognized as of primary importance. Many of the lower forms of animal life, *e.g.,* the Rhizopoda, were found to consist almost entirely of matter very similar in appearance and chemical composition to the cell-substance of higher forms; and this from its chemical resemblance to flesh was termed *Sarcode* by Dujardin. When recognized in vegetable cells it was called *Protoplasm* by Mulder, while Remak applied the same name to the substance of animal cells. As the presumed formative matter in animal tissues it was termed *Blastema,* and in the belief that, wherever found, it alone of all substances has to do with generation and nutrition, Beale has named it *Germinal matter* or *Bioplasm.* Of these terms the one most in vogue at the present day, as we have already said, is Protoplasm, and inasmuch as all life, both in the animal and vegetable kingdoms, is associated with protoplasm, we are justified in describing it, with Huxley, as the "physical basis of life," or simply "living matter."

A cell may now be defined as a nucleated mass of protoplasm, of microscopic size, varying in the human body from the red blood-cell which is about $\frac{1}{3000}$ of an inch in diameter to the ganglion cell, $\frac{1}{300}$ of an inch, which possesses sufficient individuality to have a life-history of its own. Each cell originates from a pre-existing cell, grows, produces other cells, and dies, going through the same, though briefer, cycle as the whole organism. Some of the lower forms of life seem to consist of non-nucleated protoplasm, but the above definition holds good for all the higher plants and animals, though some few cells lose their nuclei in the course of development, *e.g.*, the red blood-cells of all mammals.

## Properties of Protoplasm.

Protoplasm is a semi-fluid substance, which swells up but does not mix with water. It is transparent and generally colorless, with refractive index higher than that of water but lower than that of oil. It is neutral or weakly alkaline in reaction, but may under special circumstances be acid, as, for example, after activity. It undergoes stiffening or coagulation at a temperature of about 54.5° C. (130° F.), and hence no organism can live when its own temperature is raised above that point; it is also coagulated and therefore killed by alcohol, by solutions of many of the metallic salts, by strong acids and alkalies, and by many other substances.

Under the microscope it is seen almost universally to be granular, the granules consisting of different substances, either albuminous, or fatty, or glycogenous matters, or more rarely of inorganic salts. The granules are not equally distributed throughout the whole cell-mass, as they are sometimes absent from the outer part or layer, and very numerous in the interior. The granules may exhibit an irregular shaking, dancing movement, which is not vital and is known as the *Brownian movement*. In addition to granules, protoplasm generally exhibits spaces or vacuoles, generally globular in shape, excepting during movement when they may be irregular, filled with a watery fluid. These vacuoles are more numerous and pronounced in vegetable than in animal cells. Gas bubbles also sometimes exist in cells.

It is impossible to make any definite statement as to the exact chemical composition of living protoplasm, since the methods of chemical analysis necessarily imply the death of the cell; it is, however, stated that protoplasm contains 75 to 85 per cent of water, and of the 15 to 25 per cent of solids, the most important part belongs to the classes of substances called *proteids* or *albumins*. Proteids contain the chemical elements carbon, hydrogen, nitrogen, oxygen, sulphur, and phosphorus, the last two in small quantities only. A proteid-like substance, *nuclein*, found in the nuclei of cells, contains phosphorus in greater abundance. In cell protoplasm a compound of nuclein with proteid, called nucleo-proteid, forms the most abundant proteid substance. Other bodies are frequently found associated with the proteids, such as *glycogen*, *starch*, *cellulose*, which contain the elements carbon, hydrogen, and oxygen, the last two in the proportion to form water, and hence are termed *carbohydrates; fatty bodies*, containing carbon, hydrogen, and oxygen, but not in proportion to form water; *lecithin*, a complicated fatty body containing phosphorus; *cholesterin*, a monatomic alcohol; *chlorophyll*, the coloring matter of plants; *inorganic salts*, particularly the chlorides and phosphates of calcium, sodium, and potassium; *ferments*, and other substances.

The **vital or physiological characteristics** of protoplasm may be well studied in the microscopic animal called the amœba, a unicellular organism found chiefly in fresh water, but also in the sea and in damp earth. These properties may be conveniently studied under the following heads:—



Fig. 3.—Phases of amœboid movement.

1. *The Power of Spontaneous Movement.*—When an amœba is observed with a high power of the microscope, it is found to consist of an irregular mass of protoplasm probably containing one or more nuclei, the protoplasm itself being more or less granular and vacuolated. If watched for a minute or two, an irregular projection is seen to be gradually thrust out from the main body and retracted; a second mass is then protruded in another direction, and gradually the whole protoplasmic substance is, as it were, drawn into it. The amœba thus comes to occupy a new position, and when this is repeated several times we have locomotion in a definite direction, together with a continual change of form. These movements, when observed in other cells, such as the colorless blood-corpuscles of higher animals (fig. 3), in the branched cornea cells of the frog and elsewhere, are hence termed *amœboid.*

The remarkable movement of pigment granules observed in the branched pigment cells of the frog's skin by Lister are also probably due to amœboid movement. These granules are seen at one time distributed uniformly through the body and branched processes of the cell, while at another time they collect in the central mass leaving the branches quite colorless.

This movement within the pigment cells might also be considered an example of the so-called *streaming* movement not infrequently seen in certain of the protozoa, in which the mass of protoplasm extends long and fine processes, themselves very little movable, but upon the surface of which freely moving or streaming granules are seen. A *gliding* movement has also been noticed in certain animal cells; the motile part of the cell being composed of protoplasm bounding a central and more compact mass. By means of the free movement of this layer, the cell may be observed to move along.



Fig. 4.—Changes of form of a white corpuscle of newt's blood, sketched at brief intervals. The figures show also the intussusception of two small granules. (Schäfer.)

In vegetable cells the protoplasmic movement can be well seen in the hairs of the stinging-nettle and Tradescantia and the cells of Vallisneria and Chara; it is marked by the movement of the granules nearly always imbedded in it. For example, if part of a hair of Tradescantia (fig. 5) be viewed under a high magnifying power, streams of protoplasm containing crowds of granules hurrying along, like the foot-passengers in a busy street, are seen flowing steadily in definite directions, some coursing round the film which lines the interior of the cell-wall, and others flowing toward or away from the irregular mass in the centre of the cell-cavity. Many of these streams of protoplasm run together into larger ones and are lost in the central mass, and thus ceaseless variations of form are produced. The movement of the protoplasmic granules to or from the periphery is sometimes called vegetable *circulation*, whereas the movement of the protoplasm round the interior of the cell is called *rotation*.



Fig. 5.—Cell of Tradescantia drawn at successive intervals of two minutes.—The cell-contents consist of a central mass connected by many irregular processes to a peripheral film, the whole forming a vacuolated mass of protoplasm, which is continually changing its shape. (Schofield.)

The first account of the movement of protoplasm was given by Rösel in 1755, as occurring in a small Proteus, probably a large fresh-water amœba. His description was followed twenty years later by

Corti's demonstration of the rotation of the cell sap in characeæ, and in the earlier part of the century by Meyer in Vallisneria, 1827; Robert Brown, 1831, in "Staminal Hairs of Tradescantia." Then came Dujardin's description of the granular streaming in the pseudopodia of Rhizopods and movement in other cells of animal protoplasm (Planarian eggs, v. Siebold, 1841; colorless blood-corpuscles, Wharton Jones, 1846).

2. *The Power of Response to Stimuli, or Irritability.*—Although the movements of the amœba have been described above as spontaneous, yet they may be increased under the action of external agencies which excite them and are therefore called *stimuli*, and if the movement has ceased for the time, as is the case if the temperature is lowered beyond a certain point, movement may be set up by raising the temperature. Again, contact with foreign bodies, gentle pressure, certain salts, and electricity, produce or increase the movement in the amœba. The protoplasm is, therefore, sensitive or irritable to stimuli, and shows its irritability by movement or contraction of its mass.

The effects of some of these stimuli may be thus further detailed:—

*a. Changes of Temperature.*—Moderate heat acts as a stimulant; the movement stops below 0° C. (32° F.), and above 40° C. (104° F.); between these two points the movements increase in activity; the optimum temperature is about 37° to 38° C. Exposure to a temperature even below 0° C. stops the movement of protoplasm, but does not prevent its reappearance if the temperature is raised; on the other hand, prolonged exposure to a temperature of over 40° C. altogether kills the protoplasm and causes it to enter into a condition of coagulation or *heat rigor.*

*b. Mechanical Stimuli.*—When gently squeezed between a cover and object-glass under proper conditions, a colorless blood-corpuscle is stimulated to active amœboid movement.

*c. Nerve Influence.*—By stimulation of the nerves of the frog's cornea, contraction of certain of its branched cells has been produced.

*d. Chemical Stimuli.*—Water generally stops amœboid movement, and by imbibition causes great swelling and finally bursting of the cells. In some cases, however (myxomycetes), protoplasm can be almost entirely dried up, but remains capable of renewing its movements when again moistened. Dilute salt-solution and many dilute acids and alkalies stimulate the movements temporarily. Strong acids or alkalies permanently stop the movements; ether, chloroform, veratria, and quinine also stop it for a time.

Movement is suspended in an atmosphere of hydrogen or carbonic acid and resumed on the admission of air or oxygen, but complete withdrawal of oxygen will after a time kill the protoplasm.

*e. Electrical.*—Weak currents stimulate the movement, while strong currents cause the cells to assume a spherical form and to become motionless.

3. *The Power of Digestion, Respiration, and Nutrition.*—This consists in the power which is possessed by the amœba and similar animal cells of taking in food, modifying it, building up tissue by assimilating it, and rejecting what is not assimilated. These various processes are effected by the protoplasm simply flowing round and inclosing within itself minute organisms such as diatoms and the like, from which it extracts what it requires, and then rejects or *excretes* the remainder, which has never formed part of the body. This latter proceeding is done by the cell withdrawing itself from the material to be excreted. The assimilation constantly taking place in the body of the amœba, is for the purpose of replacing waste of its tissue consequent upon manifestation of energy. The respiratory process of absorbing oxygen goes on at the same time.



Fig. 6.—Cells from the staminal hairs of Tradescantia. *A*, Fresh in water; *B*, the same cell after slight electrical stimulation; *a*, *b*, region stimulation; c, *d*, clumps and knobs of contracted protoplasm. (Kühne.)

The processes which take place in cells, both animal and vegetable, are summed up under the term *metabolism* (from μεταβολή, change). The changes which go on are of two kinds, viz., *assimilation*, or building up, and *disassimilation*, or breaking down; they may be also called composition or decomposition, or, using the nomenclature of Gaskell, *anabolism* or constructive metabolism, and *katabolism* or destructive metabolism. In the direction of anabolism two processes occur, viz., the building up of materials which it takes in, and secondly, the building up of its own substance by those or other materials. As we shall see in a subsequent paragraph, the process of anabolism differs to some extent in vegetable and animal cells. The katabolism of the cell consists in chemical changes which occur in the cell-substance itself, or in substances in contact with it.

The destructive metabolism of a cell is increased by its activity, but goes on also during quiescence. It is probably of the nature of oxidation, and results in the evolution of carbonic anhydride and water on the one hand, and in the formation of various substances on the other, some of which may be stored up in the cell for future use, and are called *secretions*, and others, like the carbonic anhydride and certain bodies containing nitrogen, are eliminated as *excretions*.

4. *The Power of Growth.*—In protoplasm then, it is seen that the two processes of waste and repair go on side by side, and as long as they are equal the size of the animal remains stationary. If, however, the building up exceed the waste, then the animal *grows*; if the waste ex-

ceed the repair, the animal *decays;* and if decay go on beyond a certain point, life becomes impossible, and the animal dies.

Growth, or the inherent power of increasing in size, although essential to our idea of life, is not, it must be recollected, confined to living beings. A crystal of common salt, for example, if placed under appropriate conditions for obtaining fresh material, will grow in a fashion as definitely characteristic and as easily to be foretold as that of a living creature; but the growth of a crystal takes place merely by additions to its outside; the new matter is laid on particle by particle, and layer by layer, and, when once laid on, it remains unchanged. In a living structure, where growth occurs, it is by addition of new matter, not to the surface only, but throughout every part of the mass.

Again, all living structures are subject to constant decay. Thus, a man's body is not composed of exactly the same particles day after day, although to all intents he remains the same individual. Almost every part is changed by degrees; but the change is so gradual, and the renewal of that which is lost so exact, that no difference may be noticed, except at long intervals of time. A lifeless structure, as a crystal, is subject to no such laws; neither decay nor repair is a necessary condition of its existence. That which is true of structures which never had to do with life is true also with respect to those which, although they are formed by living parts, are not themselves alive. Thus, an oyster-shell is formed by the living animal which it incloses, but it is as lifeless as any other mass of inorganic matter; and in accordance with this circumstance its growth takes place layer by layer, and it is not subject to constant decay and reconstruction. The hair and nails are examples of the same fact.

In connection, too, with the growth of lifeless masses there is no alteration in the chemical composition of the material which is taken up and added to the previously existing mass. For example, when a crystal of common salt grows on being placed in a fluid which contains the same material, the properties of the salt are not changed by being taken out of the liquid by the crystal and added to its surface in a solid form. But the case is essentially different in living beings, both animal and vegetable, as the materials which serve ultimately to build them up are much altered before they are finally *assimilated* by the structures they are destined to nourish.

The growth of all living things has a definite limit, and the law which governs this limitation of increase in size is so invariable that we should be as much astonished to find an individual plant or animal without limit as to growth as without limit to life.

5. *The Power of Reproduction.*—The amœba, to return to our former illustration, when the growth of its protoplasm has reached a certain point, manifests the power of reproduction, by splitting up into (or in

some other way producing) two or more parts, each of which is capable of independent existence. The new amœbæ manifest the same properties as their parent, perform the same functions, grow and reproduce in their turn. This cycle of life is being continually passed through.

In more complicated structures than the amœba, the life of individual protoplasmic cells is probably very short in comparison with that of the organism they compose; and their constant decay and death necessitate constant reproduction.

The mode in which this takes place has long been the subject of great controversy.

It is now very generally believed that every cell is descended from some pre-existing (mother-) cell. This derivation of cells from cells takes place by (1) *gemmation,* which essentially consists in the budding off and separation of a portion of the parent cell; or (2) *fission* or *division.*



Fig. 7.—Diagram of an ovum (*a*) undergoing segmentation—In (*b*) it has divided into two, in (*c*) into four; and in (*d*) the process has ended in the production of the so called "mulberry mass." (Frey.)

The exact manner of the division of cells is a matter of some difficulty, and will not be described until the subject of the structure of protoplasmic cells has been considered.

## Structure of Protoplasmic Cells.

Protoplasm was formerly thought to be homogeneous: though this may be true in some cases, it is now generally found to consist of two substances, spongioplasm and hyaloplasm. The *spongioplasm* or *reticulum* forms a fine network, increases in relative amount as the cell grows older, and has an affinity for staining reagents. The *hyaloplasm* is less refractile, elastic, or extensile, and has no affinity for stains; it predominates in young cells, is thought to be fluid, and fills the interspaces of the reticulum. The nodal points of the reticulum, with the granules (*microsomes*) found in the protoplasm, cause the granular appearance. Bütschli has recently asserted that protoplasm is an emulsion made up of numerous microscopic vacuoles whose walls are in close apposition and are seen under the microscope in optical section only, thus causing the reticular appearance. This idea is accepted by few.

The arrangement of the reticulum varies considerably in different cells, and even in different parts of the same cell. Sometimes, for example (fig. 8), the meshwork has an elongated radial arrangement from the nucleus; at others, the meshwork is more evenly disposed, as in fig. 9. At the junctions of the fibrils there are usually slight enlargements or nodes.

In some cells, particularly in plants, but also in some animal cells, there is a tendency toward a formation of a firmer external envelope, constituting in vegetable cells a membrane distinct from the more central and more fluid part of the protoplasm. In such cases the reticulum at the periphery of the cell is made up of very fine meshes. The membrane when formed is usually pierced with pores by which fluid may pass in, or through which protrusion of the protoplasmic filaments forming the cell's connection with other cells surrounding it may take place.


Membrane of cell
Reticulum of cell
Membrane of nucleus.
Achromatic substance of nucleus.
Chromatic substance of nucleus.

Fig. 8.—Cell with its reticulum disposed radially; from the intestinal epithelium of a worm. (Carnoy.)

It is an exceedingly interesting question whether in cells the one part of the protoplasm can exist without the other. Schäfer summarizes the matter thus:—"There are cells, and unicellular organisms both animal and vegetable, in which no reticular structure can be made out, and these *may* be formed of hyaloplasm alone. In that case, this must be looked upon as the essential part of protoplasm. So far as amœboid phenomena are concerned it is certainly so; but whether the chemical



Fig. 9.—(A.) The colorless blood-corpuscle showing the intra-cellular network, and two nuclei with intra-nuclear network. (B.) Colored blood-corpuscle of newt showing the intra-cellular network of fibrils. Also oval nucleus composed of limiting membrane and fine intra-nuclear network of fibrils. × 800. (Klein and Noble Smith.)

changes which occur in many cells are effected by this or by spongioplasm is another matter."

Another question about which there is some difference of opinion is, which part of the protoplasm is chiefly contractile. It is usually concluded that this property rests in the meshwork, but there seems a considerable amount of evidence in favor of the view that part if not all of the contractility resides in the hyaloplasm; for example, in amœboid cells the pseudopodial protoplasm are certainly made of this and not of spongioplasm, and when the corpuscle is stimulated the hyaloplasm flows back into the reticular network. If the view that the hyaloplasm is chiefly contractile be a correct one, the special condition of an amœboid cell must be considered to be condition of contraction, and the flowing out of the process to be relaxation.

## The Cell Nucleus.

All cells at some period of their existence possess *nuclei*. As has been incidentally suggested the origin of a nucleus in a cell is the first trace of the differentiation of protoplasm. The existence of nuclei was first pointed out in the year 1833 by Robert Brown, who observed them in vegetable cells. They are either small transparent vesicular bodies containing one or more smaller particles (nucleoli), or they are semi-solid masses of protoplasm always in the resting condition bounded by a well-defined envelope. In their relation to the life of the cell they are certainly hardly second in importance to the protoplasm itself, and thus Beale is fully justified in comprising both under the term "germinal matter." They control the nutrition of the cell, and probably initiate the process of subdivision. If a cell be mechanically divided, that portion not containing the nucleus dies.

Histologists have long recognized nuclei by two important characters:—

(1.) Their power of resisting the action of various acids and alkalies, particularly acetic acid, by which their outline is more clearly defined, and they are rendered more easily visible. This indicates some chemical difference between the protoplasm of the cells and nuclei, as the former is destroyed by these reagents.

(2.) Their quality of staining in solutions of carmine, hæmatoxylin, etc. Nuclei are most commonly oval or round, and do not generally conform to the diverse shapes of the cells; they are altogether less variable elements than cells, even in regard to size, of which fact one may see a good example in the uniformity of the nuclei in cells so multiform as those of epithelium. But sometimes nuclei occupy almost the whole of the cell, as in the lymph corpuscles of lymphatic glands, and in some small nerve cells, and may even project above the surface.

Their position in the cell is very variable. In many cells, especially where active growth is progressing, two or more nuclei are present.

## Structure of Nuclei.

The nucleus when in a condition of rest is bounded by a distinct membrane, the nuclear membrane, possibly derived from the spongioplasm of the cell, which encloses the nuclear contents or *karyoplasm.* The membrane consists of an inner, or chromatic, and an of outer, or achromatic layer, so called from their reaction to stains. The karyoplasm is made up of a reticular network, or *chromoplasm*, whose interspaces are filled by the karyolymph, or *nuclear matrix*, a homogeneous substance which is rich in proteids, has but slight affinity for stains, and is supposed to be fluid.



**Fig. 10.—The resting nucleus—diagrammatic. (Waldeyer.)**

The network is composed of *linin*, or achromatin, a transparent unstainable framework; and of *chromatin*, which stains deeply, is supported by the linin, and occurs sometimes in the form of granules, but usually as irregular anastomosing threads, both thicker primary fibres and thinner connecting branches. The threads often form thickened nodes, karyosomes or false nucleoli, at their points of intersection. It



**Fig. 11.—Diagram of nucleus showing the arrangement of chief chromatic filaments. A. Viewed from the side, the polar end being uppermost. *p.c.f.*, Primary chromatic filaments; *n.*, nucleolus; *n.o.m.*, node of meshwork. B. Viewed at the polar end. *l.c.f.*, Looped chromatic filament; *i.f.*, irregular filament. (Rabl.)**

is now quite generally believed that the chromatin occurs as short, rod-like and highly refractive masses, which are embedded in the linin in a regular series.

The *nucleoli*, or plasmosomes, are spherical bodies of unknown function. They stain deeply, and may either lie free in the nuclear matrix or be attached to the threads of the network.

## Attraction Sphere.

In addition to the nucleus, a minute spherical body called the *centrosome* is believed to be constantly present in animal cells, though sometimes too small to be demonstrated. The centrosome is smaller than the nucleus, close to which it lies, and exerts a peculiar attraction for the protoplasmic filaments and granules in its vicinity, so that it is surrounded by a zone of fine radiating fibrils, forming the *attraction sphere* or archoplasm. Some authorities assert that the centrosome lies within the nucleus in the resting state, and only passes into the cell proper in the earlier stages of cell division. The attraction sphere is most distinctly seen in cells about to divide. It plays an important rôle in nuclear division, but it is doubted if it gives the initial impulse to the process.



Fig. 11A.—Leucocyte of Salamander Larva, showing attraction sphere. (After Flemming.)

## Cell Division.

The division of a cell is preceded by division of its nucleus, which may be either direct or indirect. Direct or simple division, amitosis or akinesis (κίνησις, movement), occurs without any change in the arrangement of the intranuclear network; it is probably limited to the amœbæ.

A constriction develops at the centre of the nucleus, possibly preceded by division of the nucleoli, and gradually divides it into two equal daughter nuclei. A similar constriction of the protoplasm of the cell occurs between the daughter nuclei and divides it in two parts.



Fig. 12.—Akinesis, amitosis, or direct cell division. *A*, Constriction of nucleus; *B*, division of nucleus and constriction of cell body; *C*, daughter nuclei still connected by a thread, division being delayed; *D*, division of cell body nearly complete. (After Arnold.)

Indirect division, mitosis (*μίτος*, a thread), or karyokinesis (*κάρυον*, a kernel), is the almost universal method, and consists of a series of



Fig. 12A.—Karyokinesis, mitosis, or indirect cell division (diagrammatic). *A*, Cell with resting nucleus; *B*, wreath, daughter centrosomes and early stage of achromatic spindle; *C*, chromosomes; *D*, monaster stage, achromatic spindle in long axis of nucleus, chromosomes dividing; *E*, chromosomes moving toward centrosomes; *F*, diaster stage, chromosomes at poles of nucleus, commencing constriction of cell body; *G*, daughter nuclei beginning return to resting state; *H*, daughter nuclei showing monaster and wreath; *I*, complete division of cell body into daughter cells whose nuclei have returned to the resting state. (After Böhm and von Davidoff.)

changes in the arrangement of the intranuclear network, resulting in the exact division of the chromatic fibres into two parts, which form the chromoplasm of the daughter nuclei. The changes follow a closely similar course in both plant and animal cells. The process has been divided by different authorities into a varying number of stages, with varying names, but for the sake of simplicity it seems best to accept the authority of Verworn and recognize two stages only—a progressive one in which the changes in the nucleus advance to a maximum, and a retrogressive one in which the resulting nuclear halves revert to the resting state.



Fig. 13.—Early stages of karyokinesis. A. The thicker primary fibres remain and the achromatic spindle appears. B. The thick fibres split into two and the achromatic spindle becomes longitudinal. (Waldeyer.)

Progressive stage. The resting nucleus becomes somewhat enlarged, and the centrosome (according to those who regard it as lying normally within the nucleus) migrates into the cell protoplasm. The centrosome then divides into two daughter centrosomes which lie near the nucleus but are separated by a considerable interval. Each is surrounded by the radiating fibrils of the attraction sphere, and some of these fibrils pass continuously from one centrosome to the other, forming the *achromatic spindle*. At the same time (*prophases*) the intranuclear network becomes converted into a fine convoluted coil (*spirem* or *skein*) which may be either continuous or else broken up into several threads. The thread



Fig. 14.—Monaster stage of karyokinesis. (Rabl.)

or threads then shorten and become thicker, while the convolutions, which have become less numerous, arrange themselves in a series of connecting loops, forming the *wreath*. The nuclear membrane and the nucleolus disappear, the latter passing at times into the cell protoplasm and disintegrating. The wreath then breaks up into V-shaped segments, the *chromosomes*, of which each species of animal has a constant and characteristic number. This varies from two to thirty-six in the different animals, but is sixteen in man.



FIG. 15.—Stages of karyokinesis. (Rabl.) A. Commencing separation of the split chromosomes. B. The separation further advanced. C. The separated chromosomes passing along the fibres of the achromatic spindle.

The two centrosomes migrate to the poles of the nucleus, while the achromatic spindle which connects them occupies the long axis of the nucleus. The chromosomes, becoming much shorter and thicker, gather around the spindle in its equatorial plane, with their angles directed toward the centre, forming the *aster* or *monaster*.


Remains of spindle.
Line of separation of the two cells.
Lighter substance of the nucleus.
Antipole of daughter nucleus.
Cell protoplasm.
Hilus.

Fig. 16.—Final stages of karyokinesis. In the lower figure the changes are still more advanced than in the upper. (Waldeyer.)

The actual division of the nucleus is begun at this time (*metaphases*) by the splitting of each chromosome longitudinally into halves which lie at first close together so that each seems doubled. Soon afterward the fibrils of the achromatic spindle begin to contract, and thus separate the halves of the chromosomes in such a way that one-half of each is turned toward one pole, and the other half toward the other. As this continues, the two groups, which are equal in size, draw away from each other and from the equator, each group being formed of daughter chromosomes.

Retrogressive stage (*anaphases* and *telophases*). The two groups (daughter chromosomes) now gradually approach their respective poles, or centrosomes, and the equator becomes free. On reaching the pole, each group gathers in a form which is similar in arrangement to the monaster and is known as the *diaster*. During this time the cell body becomes slightly constricted by a circular groove at its equatorial plane. Soon afterward the fibrils of the achromatic spindle which connect the two groups begin to grow dim and finally disappear. The daughter chromosomes assume the form of threads twisted in a coil and develop each a nuclear membrane and a nucleolus, forming a daughter nucleus. The nuclei enlarge and the nuclear threads assume the appearance of the resting state of the nucleus. Meanwhile, the constriction about the body of the cell has become deeper and deeper until the protoplasm is divided into two equal parts, or daughter cells, each with its daughter nucleus, and the process of karyokinesis is completed.

## Differences between Animals and Plants.

Having considered at some length the vital properties of protoplasm, as shown in cells of vegetable as well as of animal organisms, we are now in a position to discuss the question of the *differences between plants and animals*. It might at the outset of our inquiry have seemed an unnecessary thing to recount the distinctions which exist between an animal and a vegetable as they are in many cases so obvious, but, however great the differences may be between the higher animals and plants, in the lowest of them the distinctions are much less plain.

In the first place, it is important to lay stress upon the differences between vegetable and animal *cells*, first as regards their structure and next as regards their functions.

(1.) It has been already mentioned that in animal cells an envelope or cell-wall is by no means always present. In adult vegetable cells, on the other hand, a well-defined cellulose wall is highly characteristic; this, it should be remembered, is non-nitrogenous, and thus differs chemically as well as structurally from the contained protoplasmic mass.

Moreover, in vegetable cells (fig. 17, B), the protoplasmic contents of the cell fall into two subdivisions: (1) a continuous film which lines the interior of the cellulose wall; and (2) a reticulate mass containing the nucleus and occupying the cell cavity; its interstices are filled with fluid. In young vegetable cells such a distinction does not exist; a finely granular protoplasm occupies the whole cell-cavity (fig. 17, A).

Another striking difference is the frequent presence of a large quantity of intercellular substance in animal tissues, while in vegetables it is comparatively rare, the requisite consistency being given to their tissues by the tough cellulose walls, often thickened by deposits of lignin. As an example of the manner in which this end is attained in animal tissues, may be mentioned the deposition of lime salts in a matrix of intercellular substance which occurs in the formation of bone.

(2.) As regards the respective functions of animal and vegetable cells, one of the most important differences consists in the power which vegetable cells possess of being able to build up new complicated nitrogenous and non-nitrogenous bodies out of very simple chemical substances obtained from the air and from the soil. They obtain from the air, oxygen, carbonic anhydride, and water, as well as traces of ammonia gas; and from the soil they obtain water, ammonium salts, nitrates, sulphates, and phosphates, and such bases as potassium, calcium, magnesium, sodium, iron, and others. The majority of plants are able to work up these elementary compounds into other and more complicated bodies. This they are able to do in consequence of their containing a certain coloring matter called *chlorophyll*, the presence of which is the cause of the green hue of plants. In all plants which contain chlorophyll two processes are constantly going on when they are exposed to light: one, which is called *true respiration*, and is a process common to animal and vegetable cells alike, consists in the taking of the oxygen from the atmosphere and the giving out of carbon dioxide; the other, which is peculiar apparently to bodies containing chlorophyll, consists in the taking in of carbon dioxide and the giving out of oxygen. It seems that the chlorophyll is capable of decomposing the carbon dioxide gas and of fixing the carbon in the structures in the form of some new com-



Fig. 17. (A.) Young vegetable cells, showing cell-cavity entirely filled with granular protoplasm inclosing a large oval nucleus, with one or more nucleoli. (B.) Older cells from same plant, showing distinct cellulose wall and vacuolation of protoplasm.

pound, one of the most rapidly formed of which is *starch*. The first step in the formation of starch is the union of carbon dioxide and water to form formic aldehyde, $CO_2+H_2O=CH_2O+O_2$, oxygen being evolved; then by polymerization the formation of sugar thus, $6\ CH_2O=C_6H_{12}O_6$; and by dehydration, $C_6H_{12}O_6-H_2O=C_6H_{10}O_5$, the production of starch. In this way is starch synthesized or built up. Vegetable protoplasm by the aid of its chlorophyll is able to build up a large number of bodies besides starch, the most interesting and important being proteid or albumin. It appears to be a fact that the power which bodies possess of being able to synthesize is to a large extent dependent upon the chlorophyll they contain. Thus the power is only present to any marked extent in the plants in which chlorophyll is found and is absent in those which do not possess it; while on the other hand it is present in the extremely few animals which contain it and is absent except in certain rare instances as one of the properties of animal protoplasm.

It must be recollected, however, that chlorophyll without the aid of the light of the sun can do nothing in the way of building up substances, and a plant containing chlorophyll when placed in the dark, as long as it lives, and that is not as a rule long, acts as though it did not contain any of that substance. It is an interesting fact that certain of the bacteria have the chlorophyll replaced by a similar pigment which is able to decompose carbon dioxide gas.

Animal cells, except in the very rare cases above alluded to, do not possess the power of building up from simple materials; their activity is chiefly exercised in the opposite direction, viz., they have brought to them as food the complicated compounds produced by the vegetable kingdom, and with them they are able to perform their functions, setting free energy in the direction of heat, motion, and electricity, and at the same time eliminating such bodies as carbon dioxide and water, and producing other bodies, many of which contain nitrogen, but which are derived from decomposition, and only in very rare cases from building up.

It must be distinctly understood, however, that there are instances of animal cells performing synthetic functions and of combining two simpler compounds to produce one more complex, and it is quite possible that many of the processes performed by the cells of certain organs are instances of synthesis, and not as they have been described of breaking down; and the reverse is undoubtedly the case with vegetable cells, so that it is impossible to generalize to a greater extent than to say that the tendency of the activity of the vegetable cell is chiefly toward synthesis, and of the animal cell toward analysis.

With reference to the substance chlorophyll it is necessary to say a few words. It has been noted that the synthetical operations of vege-

table cells are peculiarly associated with the possession of chlorophyl
and that these operations are dependent upon the light of the sun. I
has been further shown that a solution of chlorophyll has a definit
absorption spectrum when examined with the spectroscope, and that i
is particularly those parts of the solar spectrum corresponding to thes
absorption bands which are chiefly active in the decomposition of ca
bonic anhydride, and that, moreover, the position of the maximum absorp
tion corresponds with the maximum of energy of light. In the synthet
ical processes of the plant then, by aid of its chlorophyll, the radian
energy of the sun's rays becomes stored up or rendered potential in th
products formed. The potential energy is set free, or is again mad
kinetic, when these products simply by combustion produce heat, o
when they are taken into the animal organism and used as food and t
produce heat and motion.

The influence of light is not an absolute essential to animal life; ir
deed, it is said not to increase the metabolism of animal tissue to an
extent, and the animal cell does not receive its energy directly from th
sun's light, nor yet to any extent from the sun's heat, but from th
products formed by vegetable metabolism supplied as food, either d
rectly, as in the case of herbivora, or indirectly in the case of carnivor
The potential energy of these food stuffs is set free in the destructiv
metabolism of the animal cell already alluded to. But it must be alway
recollected that anabolism is not peculiar to vegetable, or katabolism t
animal cells; both processes go on in each, but the *chief* function, s
far as we know at present of the former, is to transform kinetic into po
tential energy, and of the latter to render potential energy kinetic, a
in heat, motion, and electricity.

With reference to the food of plants, it should not be forgotten tha
some of the lowest forms of vegetable life, *e.g.*, the bacteria, will liv
only in a highly albuminous medium, and in fact seem to require fo
their growth elements of food stuffs which we shall see later on are es
sential to animal life. In their metabolism, too, they very closely ap
proximate to animal cells, not only requiring an atmosphere of oxyge
but giving out carbonic anhydride freely, and secreting and excretin
many very complicated nitrogenous bodies, as well as forming protei
carbohydrates, and fat, requiring heat but not light for the due perforn
ance of their functions. It must be added, however, that certain bac
teria grow only in the absence of oxygen.

(3.) There is, commonly, a difference in general chemical compositio
between vegetables and animals, even in their lowest forms; for associate
with the protoplasm of the former is a considerable amount of *cellulos*
a substance closely allied to starch and containing carbon, hydrogen, an
oxygen only. The presence of cellulose in animals is much more ra

than in vegetables, but there are many animals in which traces of it may be discovered, and some, the Ascidians, in which it is found in considerable quantity. The presence of starch in vegetable cells is very characteristic, though, as we have seen above, it is not distinctive, and a substance, *glycogen,* similar in composition to starch, is very common in the organs and tissues of animals.

(4.) Inherent power of movement is a quality which we so commonly consider an essential indication of animal nature, that it is difficult at first to conceive it existing in any other. The capability of simple motion is now known, however, to exist in so many vegetable forms, that it can no longer be held as an essential distinction between them and animals, and ceases to be a mark by which the one can be distinguished from the other. Thus the zoöspores of many of the Cryptogamia exhibit ciliary or amœboid movements of a like kind to those seen in amœbæ; and even among the higher orders of plants, many, *e.g., Dionæa Muscipula* (Venus's fly-trap), and *Mimosa sensitiva* (Sensitive plant), exhibit such motion, either at regular times, or on the application of external irritation, as might lead one, were this fact taken by itself, to regard them as sentient beings. Inherent power of movement, then, although especially characteristic of animal nature, is, when taken by itself, no proof of it.

# CHAPTER II.

## THE FUNCTIONS OF ORGANIZED CELLS.

As we proceed upward in the scale of life from unicellular organisms, we find that another phenomenon is exhibited in the life history of the higher forms, namely, that of *Development*. An amœba comes into being derived from a previous amœba; it manifests the properties and performs the functions of its life which have been already enumerated; it grows, it reproduces itself, whereby several amœbæ result in place of one, and it dies. It cannot be said to develop, however, unless the formation of a nucleus can be considered as an indication of such a process. In the higher organisms it is different; they, indeed, begin as a single cell, but this cell on division and subdivision does not form so many independent organisms, but produces the material from which, by development, the complete and perfect whole is to be derived. Thus, from the spherical ovum, or germ, which forms the starting-point of animal life and which consists of a protoplasmic cell with a nucleus and nucleolus, in a comparatively short time, by the process of segmentation which has been already mentioned, a complete membrane of cells, polyhedral in shape from mutual pressure, called the **Blastoderm**, is formed, and this speedily divides into two and then into three layers, chiefly from the rapid proliferation of the cells of the first single layer. These layers are called the **Epiblast**, the **Mesoblast**, and the **Hypoblast** (fig. 18).



Fig. 18.—Transverse section through embryo chick (26 hours). *a*, Epiblast; *b*, mesoblast; *c*, hypoblast; *d*, central portion of mesoblast, which is here fused with epiblast; *e*, primitive groove; *f*, dorsal ridge. (Klein.)

It is found in the further development of the animal that from each of these layers is produced a very definite part of its completed body. For example, from the cells of the epiblast are derived, among other structures, the skin and the central nervous system; from the mesoblast is derived the flesh or muscles of the body, and from the hypoblast the epithelium of the alimentary canal and some of the chief glands, and so on.

It is obvious that the tissues and organs so derived exhibit in a varying degree the primary properties of protoplasm. The muscles, for example, derived from certain cells of the mesoblast are particularly contractile and respond to stimuli readily, while the cells of the liver, although possibly contractile to a certain extent, have to do chiefly with the processes of nutrition.

Thus, in development, we see that as the cells of the embryo increase in number it speedily becomes necessary for the organism to depute to different groups of cells, or to their equivalents (*i.e.*, to the tissues or organs to which they give rise), special functions, so that the various functions which the original cell may be supposed to discharge, and the various properties it may be supposed to possess, become divided up among various groups of resulting cells. The work of each group is specialized. As a result of this division of labor, as it may be called, these functions and properties are, as might be expected, developed and made more perfect, while the tissues and organs arising from each group of cells are developed also, with a view to the more convenient and effective exercise of their functions and employment of their properties.

In studying the functions of the human body it is necessary first of all to know of what it is composed, of what tissues and organs it is made up; this can of course only be ascertained by the dissection of the dead body, and thus it comes that **Anatomy** (ἀνατέμνω, to cut up) the science which treats of the structure of organized bodies, is closely associated with physiology; so closely, indeed, that **Histology** (ἱστός, a web), which is especially concerned with the minute or microscopic structure of the tissues and organs of the body, and which is strictly speaking a department of anatomy, is usually included in works on physiology. There is much to be said in favor of such an arrangement, since it is impossible to consider the changes which take place in any tissue during life, apart from the knowledge of the structure of the tissues themselves. To understand the structure of the human body in an intelligent way, much help is obtained from the study of the structure of other animals, from the lowest to the highest, which is the province of **Comparative Anatomy**; while **Embryology**, which is concerned with the mode of origin of the various tissues in the embryo of each animal, and which is usually studied at the end of physiology, should from some points of view be considered as an introduction to the subject.

A second important essential to the right comprehension of the changes which take place in the living organism is a knowledge of the chemical composition of the body. Here, however, we can only deal with the chemical composition of the dead body, and it is as well a once to admit that there may be many chemical differences betwee living and not living tissues; but as it is impossible to ascertain th exact chemical composition of the living tissues, the next best thin which can be done is to find out as much as possible about the composition of the same tissues after they are dead. This is the assistanc which the science of **Chemistry** can afford to the physiologist, and th same science is concerned with the composition of the ingesta and egesta as well as with that of the fluids of the body.

Having mastered the structure and composition of the body, we ar brought face to face with physiology proper, and have to investigate th vital changes which go on in the tissues, the various actions taking plac as long as the organism is at work. The subject includes not only th observation of the manifest processes which are continually takin place in the healthy body, but the conditions under which these a brought about, the laws which govern them and their effects.

We know from our study of biology that the cells of which the ti sues are composed cannot live without food, both solid and liquid. I a complicated organism like the body of man, the tissues cannot suppl themselves with food directly like the amœba, and so it comes that th various tissues are furnished with what they require by means of fluid, the *blood*, which is carried to them in tubes or canals, the *bloo vessels*, which are distributed to every region of the body. In order th the blood shall reach all parts, the system of vessels in which it is co tained is supplied with a central pumping organ, the *heart*. Then w find that as the oxygen, which is one of the requisites of the life of th tissues, and which is carried to the tissues by the blood, is used up, special means is provided by *respiration*, or breathing, by means which the blood is exposed to a new supply of oxygen of the air, whic is taken into special organs, the *lungs*, for the purpose, and which the same time allows of the elimination of the carbonic anhydride th blood conveys from the tissues. Then again, as the solid food for th tissues cannot be conveyed in the blood in the exact form in which it introduced into the body, a special and complicated apparatus is pr vided, that of *digestion*, by means of which the necessary changes a brought about in the food. The digested food is then *absorbed* an carried to the blood, either directly with little further change by mea of another system of vessels in connection with the blood-vessels, th *lymphatic vessels*, or after passing through a special organ or gland, th *liver*, by means of which some further changes take place. In th digestive apparatus we have the organs, the *stomach* and *intestines*, in which the food is received for the purpose of being acted upon by ce tain chemical agents, of which *ferments*, bodies which are capable setting up profound changes in other bodies without themselves unde going change, are the most important; there is added the apparatus by means of which the altered food stuffs are absorbed or reach the two systems of blood-vessels already mentioned, and a muscular apparatus contained in the walls of the intestinal tube by means of which that part of the food which is not fit for absorption is removed from the body. In addition to this excretory apparatus we have another, the *kidneys*, which are concerned with the removal of certain substances from the blood which have served their purpose in the economy.

Then we have the *muscular system*, which by its special power of contraction is capable of bringing about all the movements of the body —those of the frame, the head, arms, legs, etc., as well as those of the heart, the vessels, the alimentary canal, and the like. The *nervous system*, by the aid of which the processes of the living body may be regulated and controlled. Lastly, we have a special system—that of the *generative system*, by means of which the reproduction of the species may take place.

To these subjects, the merest outline of which has been here sketched, our attention has to be given in the succeeding chapters, but it may be well to mention as a preliminary that the information about them which we have at our disposal has been derived from many sources, the chief of which are as follows:—

(1.) From actual observation of the various phenomena occurring in the human body from day to day, and from hour to hour, as, for example, the estimation of the amount and composition of the ingesta and egesta, the respiration, the beat of the heart, and the like;

(2.) From observations upon other animals, the bodies of which we are taught by comparative anatomy approximate to the human body in structure;

(3.) From observations of the changes produced by experiment upon the various processes in such animals;

(4.) From observations of the changes in the working of the human body produced by disease;

(5.) From observations upon the gradual changes which take place in the functions of organs when watched in the embryo from their earliest beginnings to their completed development.

In accordance with the plan sketched out above, the next chapter will be devoted to a consideration of the minute structure of the elementary tissues, and the one after that to a preliminary account of the chemical composition of the body. These two chapters will serve as an introduction to the study of the problems of physiology proper, which will be commenced in Chapter V.

# CHAPTER III.

## THE STRUCTURE OF THE ELEMENTARY TISSUES.

THE careful examination of the minute anatomy of the body has shown that there are certain elementary structures, of which, alone or when combined in varying proportions, the whole of the organs and tissues of the body are made up. These Elementary Tissues are four in number, called: (1.) *The Epithelial;* (2.) *The Connective;* (3.) *The Muscular,* and (4.) *The Nervous.* To these four, some would add a fifth looking upon the *Blood and Lymph,* containing, as they do, formed elements in a fluid menstruum, as a distinct tissue.

All of these elementary tissues consist of cells and of their altered equivalents. It will be as well therefore to indicate some of the differences between the cells of the body. They are named in various ways, according to their *shape, situation, contents, origin,* and *functions.*

(*a.*) From their **shape,** cells are called *spherical* or *spheroidal,* which is the typical shape of the free cell; this may be altered to *polyhedral* when the pressure on the cells in all directions is nearly the same; of this the primitive segmentation cells afford an example. The *discoid* form is seen in blood-corpuscles, and the *scale-like* form in superficial epithelial cells. Some cells have a jagged outline and are then called *prickle cells.* Cells of *cylindrical, conical,* or *prismatic* form occur in various places in the body. Such cells may taper off at one or both ends into fine processes, in the former case being *caudate,* in the latter *fusiform.* They may be greatly elongated so as to become fibres. Cells with hair-like processes, or *cilia,* projecting from their free surfaces, are a special variety. The cilia vary greatly in size, and may even exceed in length the cell itself. Finally, cells may be *branched* or *stellate* with long outstanding processes.

(*b.*) From their **situation** cells may be called *free,* as in the blood, or *combined,* when connected together or with other elements to form organs and tissues.

(*c.*) From their **contents** cells are called, when containing fat for example, *fat cells;* when containing pigment, *pigment cells,* etc.

(*d.*) From their **function** cells are called *secreting, protective, sensitive, contractile,* and the like.

(*e.*) From their **origin** cells are called *epiblastic* and *mesoblastic* and *hypoblastic* (synonyms = ectodermic, mesodermic, and endodermic).

**Modes of Connection.**—Cells are connected together to form tissues in various ways.

(1.) By mean of a cementing intercellular substance. This is probably always present as a transparent, colorless, viscid, albuminous substance, even between the closely apposed cells of epithelium, while in the case of cartilage it forms the main bulk of the tissue, and the cells only appear as imbedded in, not as cemented together by, the intercellular substance. This intercellular substance may be either homogeneous or fibrillated. In many cases (*e.g.*, the cornea) it can be shown to contain a number of irregular branched cavities, which communicate with each other, and in which branched cells lie: through these branching spaces nutritive fluids can find their way into the very remotest parts of a non-vascular tissue.

As a special variety of intercellular substance must be mentioned the basement membrane (*membrana propria*) which is found at the base of the epithelial cells in most mucous membranes, and especially as an investing tunic of gland follicles which determines their shape, and which may persist as a hyaline saccule after the gland cells have all been discharged.

(2.) By anastomosis of their processes. This is the usual way in which stellate cells, *e.g.* of the cornea, are united: the individuality of each cell is thus to a great extent lost by its connection with its neighbors to form a reticulum: as an example of a network so produced we may cite the stroma of lymphatic glands.

Sometimes the branched processes breaking up into a maze of minute fibrils, adjoining cells are connected by an intermediate reticulum: this is the case in the nerve cells of the spinal cord.

**Derived Tissue-elements.**—Besides the Cell, which may be termed the primary tissue-element, there are materials which may be termed secondary or derived tissue-elements. Such are Intercellular substance, Fibres, and Tubules.

*α. Intercellular substance* is probably in all cases directly derived from the cells themselves. In some cases (*e.g.* cartilage), by the use of reagents the cementing intercellular substance is, as it were, analyzed into various masses, each arranged in concentric layers around a cell or group of cells, from which it was probably derived.

*β. Fibres.* In the case of the crystalline lens, and of muscle both striated and non-striated, each fibre is simply a metamorphosed cell: in the case of a striped fibre, the elongation being accompanied by a multiplication of the nuclei. The various fibres and fibrillæ of connective tissue result from a gradual transformation of an originally homogeneous intercellular substance. Fibres thus formed may undergo great chemical as well as physical transformation: this is notably the case with yellow elastic tissue, in which the sharply defined elastic fibres, possessing great power of resistance to reagents, contrast strikingl with the homogeneous matter from which they are derived.

γ. *Tubules,* such as the capillary blood-vessels, which were originall supposed to consist of a structureless membrane, have now been prove to be composed of flat, thin cells, cohering along their edges.

**Decay and Death of Cells.**—There are two *chief* ways in which th comparatively brief existence of cells is brought to an end. (1) Mechanical abrasion, (2) Chemical transformation.

1. The various epithelia furnish abundant examples of mechanica abrasion. As it approaches the free surface, the cell becomes more an more flattened and scaly in form and more horny in consistency, till a length it is simply rubbed off as in the epidermis. Hence we find epithelial cells in the mucus of the mouth, intestine, and genito-urinar tract.

2. In the case of chemical transformation the cell-contents underg a degeneration which, though it may be pathological, is very often normal process.

Thus we have (a) *fatty* metamorphosis producing oil-globules in th secretion of milk, fatty degeneration of the muscular fibres of the uter after the birth of the fœtus, and of the cells of the Graafian follic giving rise to the "corpus luteum." (b) *Pigmentary* degeneration fro deposit of pigment, *e.g.* in the epithelium of the air vesicles of the lung (c) *Calcareous* degeneration, which is common in the cells of man cartilages.

## I. The Epithelial Tissues.

The term epithelium is applied to the cells covering the skin, th mucous and serous membranes, and to those forming a lining to othe parts of the body as well as entering into the formation of glands. Fo example:—

Epithelium clothes (1) the whole exterior surface of the body, forming the *epidermis* with its appendages—nails and hairs; becoming co tinuous at the chief orifices of the body—nose, mouth, anus, and urethr —with the (2) epithelium which lines the whole length of the (3) resp ratory, alimentary, and genito-urinary tracts, together with the ducts their various glands. Epithelium also lines the cavities of (4) the brai and the central canal of the spinal cord, (5) the serous and synovi membranes, and (6) the interior of all blood-vessels and lymphati (endothelium).

Epithelial cells possess an intracellular and an intranuclear netwo (pp. 9 and 10). When combined together to form a tissue, they are hel together by a clear, albuminous, cement-substance, scanty in amoun The viscid semi-fluid consistency both of cells and intercellular sul stance permits such changes of shape and arrangement in the individu cells as are necessary if the epithelium is to maintain its integrity in organs the area of whose free surface is so constantly changing, as the stomach, lungs, etc. Thus, if there be but a single layer of cells, as in the epithelium lining the air vesicles of the lungs, the stretching of this membrane causes such a thinning out of the cells that they change their shape from spheroidal or short columnar, to squamous, and *vice versâ*, when the membrane shrinks.

Epithelial tissues are non-vascular, that is to say, do not contain blood-vessels, but in some varieties minute channels exist between the cells of certain layers through which they may be supplied with nourishment from the subjacent blood-vessels. Nerve fibres are supplied to the cells of many epithelia.

Epithelial tissue is classified according as the cells composing it are arranged in a single layer when it is *simple*, or in several layers when it is called *stratified* or *laminated*, or in two or three layers occupying a position between the other two forms, when it is termed *transitional*. Of each form, when there are several varieties, they are named according to the shape of the cells composing it.

## Classification of Epithelium.

(a) **Simple.**—(1.) Squamous, scaly, pavement, or tessellated; (2.) Spheroidal or glandular; (3.) Columnar, cylindrical, conical or goblet-shaped; (4.) Ciliated.

(b) **Transitional.**

(c) **Stratified.**

## (a) Simple Epithelium.

*Squamous Epithelium.*—This form of epithelium is found arranged as a single layer of flattened cells, as (*a*) the pigmentary layer of the retina, and forms the lining of (*b*) the interior of the serous and synovial sacs, (*c*) the alveoli of the lungs, and (*d*) of the heart, blood- and lymph-vessels. It consists of cells, which are flattened and scaly, with a more or less irregular outline.

In the pigment cells of the retina there is a deposit of pigment in the cell-substance. This pigment consists of minute molecules of a colored substance, *melanin*, imbedded in the cell-substance and almost concealing the nucleus, which is itself transparent.

In white rabbits and other albino animals, in which the pigment of the eye is absent, this layer is found to consist of colorless pavement epithelial cells.

The squamous epithelium which is found as a single layer lining the serous membranes, and the interior of blood- and lymphatic-vessels, is generally called by a distinct name—**Endothelium.**

The presence of endothelium in any locality may be demonstr
staining the part lined by it with silver nitrate, which brings in
the intercellular ceme
stance.



Fig. 19.—Pigmented epithelial cells from the retina.

It is found that
small portion of a p
fresh serous membr
example (fig. 20),
mersed for a few min
a solution of silver
and exposed to the ac
light, the silver is
tated in some form
intercellular cemen
stance, and the end
cells are thus mapp
by fine, dark, and ge
sinuous lines of extreme delicacy. The cells vary in size and sha
are as a rule irregular in outline; those lining the interior of



Fig. 20.—A piece of the omentum of a cat, stained in silver nitrate. × 100. The tissu
"*fenestrated membrane*," that is to say, one which is studded with holes or windows
figure these are of various shapes and sizes, leaving trabeculæ, the basis of which is fibro
The trabeculæ are of various sizes and are covered with endothelial cells, the nuclei of w
been made evident by staining with hæmatoxylin after the silver nitrate has outlined th
staining the intercellular substance. (V. D. Harris.)

vessels and lymphatics being spindle-shaped with a very wavy o
They inclose a clear, oval nucleus, which, when the cell is vie
profile, is seen to project from its surface. The nuclei are not h
evident unless the tissue which has been already stained in silver

is placed in another dye, such as hæmatoxylin, which has the property of selecting and staining its nuclei.

Endothelial cells in certain situations may be ciliated, *e.g.*, those of the mesentery of the frog, especially during the breeding season.



Fig. 21.—Abdominal surface of central tendon of the diaphragm of rabbit, showing the general polygonal shape of the endothelial cells: each cell is nucleated. (Klein.) × 300.

Besides the ordinary endothelial cells above described, there are found on the omentum and parts of the pleura of many animals, little bud-like processes or nodules, consisting of small polyhedral granular cells, rounded on their free surface, which have multiplied very rapidly by division (figs. 22 and 23). These constitute what is known as *germinating endothelium.* The process of germination doubtless goes on in health, and the small cells which are thrown off in succession are carried into the lymphatics and contribute to the number of the lymph corpuscles. The buds may be enormously increased both in number and size in certain diseased conditions.



Fig. 22.—Peritoneal surface of a portion of the septum of the great lymph-sacs of frog. The stomata, some of which are open, some collapsed, are surrounded by endothelial cells. (Klein.) × 160.

On those portions of the peritoneum and other serous membranes in which lymphatics abound, apertures (fig. 22) are found surrounded by small, more or less cubical, cells. These apertures are called *stomata.* They are particularly well seen in the anterior wall of the great lymph sac of the frog (fig. 22), and in the omentum of the rabbit. These are really the open mouths of lymphatic vessels or spaces, and through



Fig. 23.—A portion of the great omentum of dog, which shows, among the flat endothelium the surface, small and large groups of germinating endothelium between which are many stoma (Klein.) × 300.

them lymph-corpuscles and the serous fluid from the serous cavity pa into the lymphatic system. They should be distinguished from smalle and more numerous apertures between the cells which are not lined b



Fig. 24.



Fig. 25.

Fig. 24.—A small piece of the liver of the horse. (Cadiat.)

Fig. 25.—Glandular epithelium. Small lobule of a mucous gland of the tongue, showing nucleated glandular cells. × 200. (V. D. Harris.)

small cells, although the surrounding cells seem to radiate from them filled up by intercellular substance or by processes of the cells underneath. These are called *pseudo-stomata* (fig. 23).

In the neighborhood of the stomata, the cells often manifest indications of germinating. They may be either large with two or more nuclei, or about half the size of the generality of cells. Germinating cells of this kind or of the kind above described, are generally very granular.

*Spheroidal or glandular epithelium* forms the active secreting agent in the glands, the cells are usually spheroidal, but may be polyhedral from mutual pressure, or even columnar; their protoplasm is generally occupied by the materials which the gland secretes.

Examples of glandular epithelium are to be found in the liver (fig. 24), in the secreting tubes of the kidney, and in the salivary (fig. 25) and gastric glands.

*Columnar epithelium* (fig. 28, *a* and *b*) as a single layer lines (a.) the mucous membrane of the stomach and intestines, from the cardiac orifice of the stomach to the anus, and (b.) wholly or in part the ducts of the glands opening on its free surface; also (c.) many gland-ducts in other regions of the body, *e.g.*, mammary, salivary, etc.



Fig. 26.



Fig. 27.

Fig. 26.—Columnar epithelial cells from the intestinal mucous membrane of a cat. *a* and *b*, Small cells of the lowest layer; *c*, superficial layer; *d*, goblet cells. (Cadiat.)
Fig. 27.—Goblet cells. (Klein.)

Columnar epithelium consists of cells which are cylindrical or prismatic in form containing a large oval nucleus. They vary in size and also to a certain extent in shape; the outline is often jagged and irregular from pressure of neighboring cells, but one end of the cell is always narrower than the other, and by this narrower end the cell is as a rule attached to the membrane beneath. The intracellular and intranuclear networks are well developed, and in some cases the spongioplasm is arranged in rods or longitudinal striæ at one part of the cell, generally the attached border, as in some of the cells of the ducts of salivary glands.

This may also be the case with the columnar epithelial cells of the alimentary canal which possess an apparently structureless layer on their free surface: such a layer, appearing striated when viewed in section, is termed the "striated basilar border" (fig. 28, *e*).

The protoplasm of columnar cells may be vacuolated and may also contain fat or other substances, of which the most likely is mucin or its antecedent mucigen, to be seen in the form of granules. It is to the presence of mucin that a curious transformation which columnar cells may undergo is due, and from which the alteration in their shape whereby "goblet-cells" are produced (fig. 27) arises. These altered cells are hardly ever evident in a perfectly fresh specimen; but if such a specimen be watched for some time, little knobs are seen gradually to appear on the free surface of the epithelium and are finally detached; these consist of the cell-contents which are discharged by the open mouth of the goblet, leaving the nucleus surrounded by the remains of the protoplasm in its narrow stem.

This transformation is a normal process which is continually going on during life, the discharged cell-contents contributing to form *mucus,* the cells themselves being supposed in many cases after discharge t recover their original shape.



Fig. 28.—Cross section of a villus of the intestine. *e*, Columnar epithelium with stria border; *g*, goblet cell, with its mucus partly extruded; *l*, lymph-corpuscles between the epithelial cells; *b*, basement membrane; *c*, sections of blood capillaries; *m*, section of plain mus fibres; *c. l*, central lacteal. (Schäfer.)

*Ciliated epithelium* consists of cells which are generally cylindric in form (figs. 29, 30), but may be spheroidal or even almost squamous.

This form of epithelium lines—(a.) the mucous membrane of th respiratory tract beginning just beyond the nasal aperture and completely covering the nasal passages, except the upper part to which th olfactory nerve is distributed, and also the sinuses and ducts in connection with it and the lachrymal sac; the upper surface of the soft palat and the naso-pharynx, the Eustachian tube and tympanum, the larynx except over the vocal cords, to the finest subdivisions of the bronchi In part of this tract, however, the epithelium is in several layers, o which only the most superficial is ciliated, so that it should more accurately be termed transitional (p. 37) or stratified. (b.) Some portion of the generative apparatus in the male, viz., lining the "vasa efferentia of the testicle, and their prolongations as far as the lower end of th epididymis; in the female (c.) commencing about the middle of the neck of the uterus, and extending throughout the uterus and Fallopian tubes to their fimbriated extremities, and even for a short distance on the peritoneal surface of the latter. (d.) The ventricles of the brain and the central canal of the spinal cord are clothed with ciliated epithelium in the child, but in the adult this epithelium is limited to the central canal of the cord. In the embryo the pharynx, œsophagus, and part of the stomach may also be lined with ciliated cells. (e.) The excretory ducts of certain small glands in different localities. (f.) In certain animals, especially the lower vertebrates, ciliated cells line the beginning of the tubes of the kidneys.

The *Cilia* are fine hair-like processes which give the name to this variety of epithelium; they vary a good deal in size in different classes of animals, being very much smaller in the higher than among the lower orders, in which they sometimes exceed in length the cell itself.



Fig. 29.



Fig. 30.

Fig. 29.—Spheroidal ciliated cells from the mouth of the frog. × 300 diameters. (Sharpey.)

Fig. 30.—Ciliated epithelium from the human trachea. *a*, Large, fully formed cell. *b*, Shorter cell; *c*, developing cells with more than one nucleus. (Cadiat.)

The number of cilia on any one cell ranges from ten to thirty, and those attached to the same cell are often of different lengths, in the human trachea measuring $\frac{1}{4000}$ to $\frac{1}{2500}$ of an inch, but nearly ten times the length in the cells of the epididymis.

The cilia themselves are fine rounded or flattened processes, apparently homogeneous, pointed toward their free extremities. According to some observers these processes are connected through intervening knob-like junctions with longitudinal fibres which pass to the other end of the cell, but which are not connected with the nucleus.

When living ciliated epithelium, *e.g.*, from the gill of a mussel, or oyster, or from the mouth of the frog, or from a scraping from a polypus from the human nose, is examined under the microscope in a drop of 0.6 per cent solution of common salt (*normal saline solution*), the cilia are seen to be in constant rapid motion, each cilium being fixed at one end, and swinging or lashing to and fro. The general impression given to the eye of the observer is very similar to that produced by waves in field of corn, or swiftly running and rippling water, and the result o their movement is to produce a continuous current in a definite direction, and this direction is invariably the same on the same surfac being always, in the case of a cavity, toward its external orifice.

**Ciliary Motion.**—Ciliary, which is closely allied to amœboid an muscular motion, is alike independent of the will, of the direc influence of the nervous system, and of muscular contraction. It ma contiune for several hours after death or removal from the body, provided the portion of tissue under examination be kept moist. Its independence of the nervous system is shown also in its occurrence i the lowest invertebrate animals apparently unprovided with anythin analogous to a nervous system, in its persistence in animals killed b prussic acid, by narcotic or other poisons, and after the direct application of narcotics, such as morphia, opium, and belladonna, to th ciliary surface, or of electricity through it. The vapor of chlorofor arrests the motion; but it is renewed on the discontinuance of th application. The movement ceases when the cilia are deprived o oxygen, although it may continue for a time in the absence of *fre* oxygen, but is revived on the admission of this gas. Carbonic aci stops the movement. The contact of various substances, *e.g.*, bile, stron acids, and alkalies, will stop the motion altogether; but this seems t depend chiefly on destruction of the delicate substance of which t cilia are composed. Temperatures above 45° C. and below 0° C. st the movement, whereas moderate heat and dilute alkalies are favorab to the action and revive the movement after temporary cessation. T exact explanation of ciliary movement is not known; whatever may b the exact cause, however, at any rate the movement must depend upo some changes going on in the cell to which the cilia are attached, a when the latter are cut off from the cell the movement ceases, and whe severed so that a portion of the cilia are left attached to the cell, th attached and not the severed portions continue the movement. Som authorities consider it due to actual contraction of the cilia themselve others assert that it is caused by movements in the cell protoplasm actin upon the rootlets of the cilia. Schäfer suggests a very plausible explanation, viz., that a cilium is either a curved hollow extension of th cell, which is filled by hyaloplasm and invested by a delicate membran or else a straight one whose investing membrane is thicker (or otherwis less extensible) along one side than along the other. In either case rhythmic flowing of the hyaloplasm into and out of the cilium woul cause its alternate flexion and extension.

As a special subdivision of ciliary action may be mentioned the motio of spermatozoa, which may be regarded as cells with a single cilium.

## (b) Transitional Epithelium.

This term has been applied to cells, which are neither arranged in a single layer, as is the case with simple epithelium, nor yet in many superimposed strata as in laminated; in other words, it is employed when epithelial cells are found in two, three, or four superimposed layers.

The upper layer may be either single columnar, columnar ciliated, or squamous. When the upper layer is columnar or ciliated the second layer consists of smaller cells fitted into the inequalities of the cells above them, as in the trachea (fig. 30).

The epithelium which is met with lining the urinary bladder and ureters is, however, the transitional *par excellence*. In this variety there are two or three layers of cells, the upper being more or less flattened according to the full or collapsed condition of the organ, their under surface being marked with one or more depressions, into which the heads of the next layer of club-shaped cells fit. Between the lower and narrower parts of the second row of cells are fixed the irregular cells which constitute the third row, and in like manner sometimes a fourth row (fig. 31). It can be easily understood, therefore, that if a scraping of the mucous membrane of the bladder be teased, and examined under the microscope, cells of a great variety of forms may be made out (fig. 32). Each cell contains a large nucleus and the larger and superficial cells often possess two.



Fig. 31.



Fig. 32.

Fig. 31.—Epithelium of the bladder. *a*, One of the cells of the first row; *b*, a cell of the second row; *c*, cells *in situ*, of first, second, and deepest layers. (Obersteiner.)

Fig. 32.—Transitional epithelial cells from the mucous membrane of the bladder of a rabbit. Highly magnified. *a*, Large flattened cell of superficial layer; *a'*, similar cell in profile; *b*, pear-shaped cell of second layer. (Klein.)

## (c) Stratified Epithelium.

The term stratified epithelium is employed when the cells forming the epithelium are arranged in a considerable number of superimposed layers. The shape and size of the cells of the different layers, as well as the number of the layers, vary in different situations. Thus the superficial cells are as a rule of the squamous, or scaly variety, and th deepest of the columnar form.

The cells of the intermediate layers are of different shapes, but thos of the middle layers are more or less rounded. The superficial cells ar broad and overlap by their edges (figs. 33 and 34). Their chemical com



Fig. 33.—Squamous epithelium scales from the inside of the mouth. × 260. (Henle.)

position is different from that of the underlying cells, as they conta keratin, and are therefore horny in character.

The nucleus is often not apparent. The really cellular nature even the dry and shrivelled scales cast off from the surface of the e dermis can be proved by the application of caustic potash, which cau them rapidly to swell and assume their original form.

The squamous cells exist in the greatest number of layers in the e dermis or superficial part of the skin; the most superficial of these a being continually removed by friction, and new cells from below supp the place of those cast off.

The intermediate cells approach more to the flat variety the near they are to the surface, and to the columnar as they approach the lowe



Fig. 34.—Vertical section of the stratified epithelium covering the front of the corn Highly magnified. (Schäfer.) *c*, Lowermost columnar cells; *p*, polygonal cells above th *fl*, flattened cells near the surface. The intercellular channels, bridged by minute cell process are well seen.

layer. There may be considerable intercellular intervals; and in ma of the deeper layers of epithelium in the mouth and skin, the outline the cells is very irregular, in consequence of processes passing from c to cell across these intervals.

Such cells (fig. 35) are termed "ridge and furrow," "cogged" "prickle" cells. These "prickles" are prolongations of the intracellu network which run across from cell to cell, thus joining them togeth the interstices being filled by the transparent intercellular cement-substance. When this increases in quantity in inflammation the cells are pushed further apart, and the connecting fibrils or "prickles" elongated and therefore more clearly visible.

The columnar cells of the deepest layer are distinctly nucleated; they multiply rapidly by division; and as new cells are formed beneath, they press the older cells forward to be in turn pressed forward themselves toward the surface, gradually altering in shape and chemical composition until they are cast off from the surface.

Stratified epithelium is found in the following situations: (1.) Forming the epidermis, covering the whole of the external surface of the body; (2.) Covering the mucous membrane of the nose, tongue, mouth, pharynx, and œsophagus; (3.) As the conjunctival epithelium, covering the cornea; (4.) Lining the vagina and the vaginal part of the cervix uteri.



Fig. 35.—Jagged cells from the middle layers of pavement epithelium, from a vertical section of the gum of a new-born infant. (Klein.)

**Functions of Epithelium.**—According to function, epithelial cells may be classified as: (1.) *Protective, e.g.*, in the skin, mouth, blood-vessels, etc. (2.) *Protective and moving*—ciliated epithelium. (3.) *Secreting*—glandular epithelium; or, Secreting formed elements—epithelium of testicle secreting spermatozoa. (4.) *Protective and secreting, e.g.*, epithelium of intestine. (5) *Sensorial, e.g.*, olfactory cells, rods and cones of retina, organ of Corti.

Epithelium forms a continuous smooth investment over the whole body, being thickened into a hard, horny tissue at the points most exposed to pressure, and developing various appendages, such as hairs and nails, whose structure and functions will be considered in a future chapter. Epithelium lines also the sensorial surfaces of the eye, ear, nose, and mouth, and thus serves as the medium through which all impressions from the external world—touch, smell, taste, sight, hearing—reach the delicate nerve endings, whence they are conveyed to the brain.

The ciliated epithelium which lines the air-passages serves not only as a protective investment, but also by the movements of its cilia promotes currents of the air in the bronchi and bronchia, and is enabled to propel fluids and minute particles of solid matter so as to aid their expulsion from the body. In the case of the Fallopian tube, this agency assists the progress of the ovum toward the cavity of the uterus. Of the purposes served by cilia in the ventricles of the brain nothing is known.

The epithelium of the various glands, and of the whole intestinal tract, has the power of *secretion*, *i.e.*, of chemically transforming certain materials of the blood; in the case of mucus and saliva this has been proved to involve the transformation of the epithelial cells themselves; the cell-substance of the epithelial cells of the intestine being discharged by the rupture of their envelopes, as mucus.

Epithelium is likewise concerned in the processes of transudation, diffusion, and absorption.

It is constantly being shed at the free surface and reproduced in the deeper layers. The various stages of its growth and development can be well seen in a section of any laminated epithelium such as the epidermis

## II. The Connective Tissues.

This group of tissues forms the Skeleton with its various connection —bones, cartilages, and ligaments—and also affords a supporting framework and investment to the various organs composed of nervous, muscular, and glandular tissue. Its chief function is the mechanical one o support, and for this purpose it is so intimately interwoven with nearl all the textures of the body that if all other tissues could be removed and the connective tissues left, we should have a wonderfully exact mode of almost every organ and tissue in the body, correct even to the smallest minutiæ of structure.

### *Structure of Connective Tissues in General.*

Connective tissue is made up of two chief elements, namely, *cell* and *intercellular substance.*

(A.) **Cells.**—The cells are of two kinds:

(*a.*) *Fixed Cells.*—These are of a flattened shape, with branched pr cesses, which are often united together to form a network: they can b most readily observed in the cornea, in which they are arranged, lay above layer, parallel to the free surface. They lie in spaces in the inte cellular or ground substance, which are of the same shape as the cel they contain, but rather larger, and which form by anastomosis a syste of branching canals freely communicating (fig. 36).

To this class of cells belong the flattened tendon corpuscles whi are arranged in long lines or rows parallel to the fibres (fig. 42).

These branched cells, in certain situations, contain a number of pi ment granules, giving them a dark appearance; they form one varie of pigment cell. Branched pigment cells of this kind are found in t outer layers of the choroid (fig. 37). In many of the lower animal such as the frog, they are found widely distributed, not only in the skin, but also in internal parts, *e.g.*, the mesentery and sheaths of blood-vessels. In the web of the frog's foot such cells may be seen with pigment granules evenly distributed throughout the body of the cell and its processes; but under the action of light, electricity, and other stimuli, the pigment granules become massed in the body of the cell, leaving the processes quite hyaline; if the stimulus be removed, they will gradually be distributed again throughout the processes. Thus the skin in the frog is sometimes uniformly dusky, and sometimes quite light-colored, with isolated dark spots. In the choroid and retina the pigment cells absorb light.

(*b.*) *Amœboid Cells*, of an approximately spherical shape; they have a great general resemblance to colorless blood-corpuscles, with which some of them are probably identical. They consist of finely granular nucleated protoplasm, and have the property, not only of changing their form but also of moving about, hence they are termed *migratory*. They are readily distinguished from the branched connective-tissue corpuscles by their free condition, and the absence of processes. Some are much larger than others, and are found especially in the sublingual gland of the dog and guinea-pig, and in the mucous membrane of the intestine. A second variety of these cells called *plasma cells* are larger than the amœboid cells, apparently granular, less active in their movements. They are chiefly to be found in the inter-muscular septa, in the mucous and sub-mucous coats of the intestine, in lymphatic glands, and in the omentum.



Fig. 36.—Horizontal preparation of the cornea of frog, stained in gold chloride; showing the network of branched cornea corpuscles. The ground substance is completely colorless. × 400. (Klein.)

(B.) **Intercellular Substance.**—This may be *fibrillar*, as in the fibrous tissues, and in certain varieties of cartilage; or *homogeneous*, as in hyaline cartilage.

The fibres composing the former are of two kinds—(*a.*) White fibre (*b.*) Yellow elastic fibres.

(*a.*) *White Fibres.*—These are arranged parallel to each other in wav bundles of various sizes: such bundles may either have a parallel a rangement (fig. 39), or may produce quite a felted texture by their inte lacement. The individual fibres composing these fasciculi are exceeding fine, varying from $\frac{1}{50000}$ to $\frac{1}{25000}$ inch, *i.e.*, $\frac{1}{2000}$ to $\frac{1}{1000}$ mm., or 0.5 1μ, homogeneous, unbranched, and of t same diameter throughout. They can readi be isolated by macerating a portion of whi fibrous tissue (*e.g.*, a small piece of tendo for a short time in lime, or baryta-water, in a solution of common salt, or of potassiu permanganate: these reagents possess t power of dissolving the cementing inte fibrillar substance and of thus separating t fibres from each other. By prolonged bo ing the fibres yield *gelatin.*



Fig. 37.


Fig. 38.


Fig. 39.

Fig. 37.—Ramified pigment cells from the tissue of the choroid coat of the eye. × 350. *a*, c with pigment; *b*, colorless fusiform cells. (Kölliker.)

Fig. 38.—Flat, pigmented, branched connective-tissue cells from the sheath of a large blo vessel of the frog's mesentery: the pigment is not distributed uniformly throughout the substa of the larger cell, consequently some parts of it look blacker than others (uncontracted state). the two smaller cells most of the pigment is withdrawn into the cell-body, so that they appe smaller, blacker, and less branched. × 350. (Klein and Noble Smith.)

Fig. 39.—Fibrous tissue of cornea, showing bundles of fibres with a few scattered fusiform ce (A) lying in the inter-fascicular spaces. × 400. (Klein and Noble Smith.)


Fig. 40.—Elastic fibres from the ligamenta subflava. × 200. (Sharpey.)

(*b.*) *Yellow Elastic Fibres* (fig. 40) are all sizes, from excessively fine fibrils, $\frac{1}{24}$ inch, up to fibres of considerable thickne $\frac{1}{4000}$ inch (*i.e.*, from about 1μ to 6μ): th are distinguished from white fibres by t following characters: (1.) Their great pow of resistance even to the prolonged action of chemical reagents, *e.* caustic soda, acetic acid, etc. (2.) Their well-defined outlines. (

Their great tendency to branch and to form networks by anastomosis. (4.) Their twisted corkscrew-like appearance, and that their free ends usually curl up. (5.) Their yellowish tint and considerable elasticity. (6.) Their resistance to hæmatoxylin and similar reagents, and their affinity for magenta and other aniline staining colors.

These fibres yield on boiling not gelatin, but a gelatinous substance called *elastin*.

The chief varieties of connective tissues may be thus classified:

- I. *The Fibrous Connective Tissues.*
  - A.—*Chief Forms.*
    - *a.* White fibrous.
    - *b.* Elastic.
    - *c.* Areolar.
  - B.—*Special Varieties.*
    - *a.* Gelatinous.
    - *b.* Adenoid or Retiform.
    - *c.* Adipose.
- II. *Cartilage.*
- III. *Bone and dentine.*

## I. FIBROUS CONNECTIVE TISSUES.

### A.—*Chief Forms.*—(*a.*) White Fibrous Tissue.

*Distribution.*—It is found typically in tendon; also in ligaments, in the periosteum and perichondrium, the dura mater, the pericardium, the sclerotic coat of the eye, the fibrous sheath of the testicle; in the fasciæ and aponeuroses of muscles, and in the sheaths of lymphatic glands.

*Structure.*—To the naked eye tendons and many of the fibrous membranes, when in a fresh state, present an appearance as of watered silk. This is due to the arrangement of the fibres in wavy parallel bundles. Under the microscope the tissue appears to consist of long, often parallel, bundles of fibres of different sizes. The fibres of the same bundle now and then intersect each other. The cells in tendons (fig. 42) are arranged in long chains in the ground substance separating the bundles of fibres, and are more or less regularly quadrilateral with large round nuclei containing nucleoli, which are generally placed so as to be contiguous in two cells. Each of these cells consist of a thick body, from which processes pass in various directions into, and partially fill up the spaces between, the bundles of fibres. The rows of cells are separated from one another by lines of cement substance. The cell spaces can be brought into view by silver nitrate. The cells are generally marked by one or more lines or stripes when viewed longitudinally. This appearance is really produced by the wing-like processes of the cell which project away from the chief part of the cell in different directions. These processes not being in the same plane as the body of the cell are out of focus and give rise to these bright stripes are looked at from above and are in focus.

The branched character of the cells is seen in transverse section in fig. 43.

### (*b*) Yellow Elastic Tissue.

*Distribution.*—In the ligamentum nuchæ of the ox, horse, and many other animals; in the ligamenta subflava of man; in the arteries, constituting the fenestrated coat of Henle; in veins; in the lungs and trachea; in the stylo-hyoid, thyro-hyoid, and crico-thyroid ligaments; in the true vocal chords; and in areolar tissue.



Fig. 41.



Fig. 42.

Fig. 41.—Mature white fibrous tissue of tendon, consisting mainly of fibres with a few scattered fusiform cells. (Stricker.)

Fig. 42.—Caudal tendon of young rat, showing the arrangement, form, and structure of the tendon cells. × 300. (Klein.)

*Structure.*—Elastic tissue occurs in various forms, from a structureless, elastic membrane to a tissue whose chief constituents are bundles of fibres crossing each other at different angles; when seen in bundles elastic fibres are yellowish in color, but individual fibres are not so distinctly colored. The varieties of the tissue may be classified as follows:

(*a.*) Fine elastic fibrils, which branch and anastomose to form a network: this variety of elastic tissue occurs chiefly in the skin and mucous membranes, in subcutaneous and submucous tissue, in the lungs and true vocal cords.

(*b.*) Thick fibres, sometimes cylindrical, sometimes flattened like tape, which branch, anastomose and form a network: these are seen most typically in the ligamenta subflava and also in the ligamentum nuchæ of such animals as the ox and horse, in which that ligament is largely developed (fig. 40).

(c.) Elastic membranes with perforations, *e.g.*, Henle's fenestrated membrane: this variety is found chiefly in the arteries and veins.

(*d.*) Continuous, homogenous elastic membranes, *e.g.*, Bowman's anterior elastic lamina and Descemet's posterior elastic lamina, both in the cornea.

A certain number of flattened connective-tissue cells are found in the ground substance between the elastic fibres which make up this variety of connective tissue.

### (*c.*) Areolar Tissue.

*Distribution.*—This variety of fibrous tissue has a very wide distribution and constitutes the subcutaneous, subserous, and submucous tissue. It is found in the mucous membranes, in the true skin, and in the outer sheaths of the blood-vessels. It forms sheaths for muscles, nerves, glands, and the internal organs, and penetrating into their interior, supports and connects the finest parts.



Fig. 43.



Fig. 44.

Fig. 43.—Transverse section of tendon from a cross section of the tail of a rabbit, showing sheath, fibrous septa, and branched connective-tissue corpuscles. The spaces left white in the drawing represent the tendinous fibres in transverse section. × 250. (Klein.)

Fig. 44.—Transverse section of a portion of lig. nuchæ, showing the outline of the fibres. (After Stöhr.)

*Structure.*—To the naked eye it appears, when stretched out, as a fleecy, white, and soft meshwork of fine fibrils, with here and there wider films joining in it, the whole tissue being evidently elastic. The openness of the meshwork varies with the locality from which the specimen is taken. Under the microscope it is found to be made up of fine white fibres, which interlace in a most irregular manner, together with a variable number of elastic fibres. On the addition of acetic acid, the white fibres swell up, and become gelatinous in appearance; but as the elastic fibres resist the action of the acid, they may still be seen arranged in

various directions, sometimes appearing to pass in a more or less
or spiral manner round a small gelatinous mass of changed whi
The cells of areolar tissues are connective-tissue corpuscles. Tl
sist of several varieties: branched, flattened cells which conn
each other; flattened cells which do not branch; plasma cells;
ing cells from the blood; and sometimes pigment cells, as in the
of the eye. The various elements are held together by *cement* su
penetrated by irregular canals carrying lymph.

B.—*Special Forms* (*a.*) **Gelatinous Tissue.**

*Distribution.*—Gelatinous connective tissue forms the chief
the bodies of jelly-fish; it is found in many parts of the human



Fig. 45.



Fig. 46.

Fig. 45.—Mucous connective tissue from the umbilical cord. *a*, Cells; *b*. fibrils.
Fig. 46.—Part of a section of a lymphatic gland, from which the corpuscles have b
most part removed, showing the adenoid reticulum. (Klein and Noble Smith.)

but remains in the adult only in the vitreous humor of the eye.
be best seen in the last-named situation, in the "Whartonian j
the umbilical cord, and in the enamel organ of developing teeth

*Structure.*—It consists of cells, which in the vitreous hu
rounded, and in the jelly of the enamel organ are stellate, imb
a soft jelly-like inter-cellular substance which forms the bulk
tissue, and which contains a considerable quantity of mucin.
umbilical cord, that part of the jelly immediately surrounding
late cells shows marks of obscure fibrillation (fig. 45).

(*b.*) **Adenoid,** this is also called *retiform*, *lymphoid* or *lymphat*

*Distribution.*—This variety of tissue makes up the stroma of th
and lymphatic glands, and is found also in the thymus, in the
in the follicular glands of the tongue, in Peyer's patches, and in
itary glands of the intestines, and in the mucous membranes g

*Structure.*—Adenoid or retiform tissue consists of a very delicate network of minute fibrils, formed originally by the union of processes of branched connective-tissue corpuscles, the nuclei of which, however, are visible only during the early periods of development of the tissue (fig. 46). The network of fibrils is concealed by being covered with flattened connective-tissue corpuscles, which may be readily dissolved in caustic potash, leaving the network bare. The network consists of white fibres, the interstices of which are filled with lymph corpuscles. The cement substance of adenoid tissue is very fluid.

Some authors make a distinction between retiform and adenoid tissues, the former being the meshwork, and the latter the meshwork with its contained lymph cells.

**Development of Fibrous Tissues.**—In the embryo the place of the fibrous tissues is at first occupied by a mass of roundish cells, derived from the "mesoblast."



Fig. 47.—Portion of submucous tissue of gravid uterus of sow. *a*, Branched cells, more or less spindle-shaped; *b*, bundles of connective tissue. (Klein.)

These develop either into a network of branched cells or into groups of fusiform cells (fig. 47).

The cells are imbedded in a semi-fluid albuminous substance derived either from the cells themselves or from the neighboring blood-vessels; this afterward forms the cement substance. In it fibres are developed, either by some of the cells becoming fibrils, the others remaining as connective-tissue corpuscles, or by the fibrils being developed from the outside layers of the protoplasm of the cells, which grow up again to their original size and remain imbedded among the fibres. The process gives rise to fibres arranged in the one case in interlacing networks (areolar tissue), in the other in parallel bundles (white fibrous tissue). In the mature forms of purely fibrous tissue not only the remnants of the cell-substance, but even the nuclei, may disappear. The embryonic tissue, from which *elastic* fibres are developed, is composed of fusiform cells, and a structureless intercellular substance by the gradual fibrillation of which elastic fibres are formed. The fusiform cells dwindle in size and eventually disappear so completely that in mature elastic tissue hardly a trace of them is to be found: meanwhile the elastic fibres steadily increase in size.

Another theory of the development of the connective-tissue fibrils supposes that they arise from deposits in the intercellular substance and not from the cells themselves; these deposits, in the case of elastic fibres, appearing first of all in the form of rows of granules, which, joining together, form long fibrils. It seems probable that even if this view be correct, the cells themselves have a considerable influence in the production of the deposits outside them.

**Functions of Areolar and Fibrous Tissue.**—The main function of connective tissue is mechanical rather than vital: it fulfils the subsidiary but important use of supporting and connecting the various tissues and organs of the body.

In glands the trabeculæ of connective tissue form an interstitial framework in which the parenchyma or secreting gland-tissue is lodged: in muscles and nerves the septa of connective tissue support the bundles of fibres which form the essential part of the structure.

Elastic tissue, by virtue of its elasticity, has other important uses: these, again, are mechanical rather than vital. Thus the ligamentum nuchæ of the horse or ox acts very much as an India-rubber band in the same position would; being stretched when the head is lowered for feeding or other purposes and aiding the muscles materially afterward by its contraction, in raising the head to its normal position and keeping it there.



Fig. 48.—Ordinary fat cells of a fat tract in the omentum of a rat. (Klein.)

### (*c*.) Adipose Tissue.

*Distribution.*—In almost all regions of the human body a larger or smaller quantity of adipose or fatty tissue is present; the chief exceptions being the subcutaneous tissue of the eyelids, penis, and scrotum, the nymphæ, and the cavity of the cranium. Adipose *tissue* is also absent from the substance of many organs, as the lungs, liver, and others.

Fatty matter, but not in the form of a distinct tissue, is also widely present in the body, *e.g.*, in the liver and brain, and in the blood and chyle.

Adipose tissue is almost always found seated in areolar tissue, and forms in its meshes little masses of unequal size and irregular shape, to which the term *lobules* is commonly applied.

*Structure.*—Under the microscope adipose tissue is found to consist essentially of little vesicles or cells which present dark, sharply-defined edges when viewed with transmitted light: they are about $\frac{1}{400}$ or $\frac{1}{500}$ of an inch in diameter, each consisting of a structureless and colorless membrane or bag formed of the remains of the original protoplasm of the cell, filled with fatty matter, which is liquid during life, but in part solidified after death (fig. 48). A nucleus is always present in some part or other of the cell-protoplasm, but in the ordinary condition of the cell it is not easily or always visible (fig. 49).

This membrane and the nucleus can generally be brought into view by staining the tissue: it can be still more satisfactorily demonstrated by extracting the contents of the fat-cells with ether, when the shrunken, shrivelled membranes remain behind. By mutual pressure, fat-cells come to assume a polyhedral figure (fig. 49). When stained with osmic acid fat-cells appear black.



Fig. 49.—Group of fat cells (F C) with capillary vessels (c). (Noble Smith.)

The ultimate cells are held together by capillary blood-vessels (fig. 50); while the little clusters thus formed are grouped into small masses, and held so, in most cases, by areolar tissue.

The oily matter contained in the cells is composed chiefly of the compounds of fatty acids with glycerin, which are named *olein, stearin,* and *palmitin.*

**Development of Adipose Tissue.**—Fat cells are developed from connective-tissue corpuscles: in the infra-orbital connective-tissue cells may be found exhibiting every intermediate gradation between an ordinary branched connective-tissue corpuscle and mature fat-cell. The process of development is as follows: a few small drops of oil make their appearance in the protoplasm and by their confluence a larger drop is produced (fig. 51): this gradually increases in size at the expense of the original protoplasm of the cell, which becomes correspondingly diminished in quantity till in the mature cell it only forms a thin crescentic film, closely pressed against the cell-wall, and with a nucleus imbedded in its substance (figs. 48 and 49).

Under certain circumstances this process may be reversed and fat-cells may be changed back into connective-tissue corpuscles.



Fig. 50.—Blood-vessels of adipose tissue. A. Minute flattened fat-lobule, in which the vessels only are represented. *a*, The terminal artery; *v*, the primitive vein; *b*, the fat-vesicles of one border of the lobule separately represented. × 100. B. Plan of the arrangement of the capillaries (*c*) on the exterior of the vesicles; more highly magnified. (Todd and Bowman.)

**Vessels and Nerves.**—A large number of blood-vessels are found in adipose tissue, which subdivide until each lobule of fat contains a fine meshwork of capillaries ensheathing each individual fat-globule (fig. 50). Although nerve fibres pass through the tissue, no nerves have been demonstrated to terminate in it.

**The Uses of Adipose Tissue.**—Among the uses of adipose tissue these are the chief:—

*a.* It serves as a store of combustible matter which may be reabsorbed into the blood when occasion requires, and, being used up in the metabolism of the tissues, may help to preserve the heat of the body.



Fig. 51.



Fig. 52.

Fig. 51.—A lobule of developing adipose tissue from an eight months' fœtus. *a*, Spherical o from pressure, polyhedral cells with large central nucleus, surrounded by a finely reticulated su stance staining uniformly with hæmatoxylin. *b*, Similar cells with spaces from which the fat ha been removed by oil of cloves. *c*, Similar cells showing how the nucleus with inclosing protoplas is being pressed toward periphery. *d*, Nucleus of endothelium of investing capillaries. (McCarthy. Drawn by Treves.

Fig. 52.—Branched connective-tissue corpuscles, developing into fat-cells. (Klein.)

*b.* That part of the fat which is situate beneath the skin must, by its want of conducting power, assist in preventing undue waste of the heat of the body by escape from the surface.

*c.* As a packing material, fat serves very admirably to fill up spaces, to form a soft and yielding yet elastic material wherewith to wrap tender and delicate structures, or form a bed with like qualities on which such structures may lie, not endangered by pressure. As examples of situations in which fat serves such purposes may be mentioned the palms of the hands and soles of the feet and the orbits.

*d.* In the long bones fatty tissue, in the form known as yellow marrow, fills the medullary canal, and supports the small blood-vessels which are distributed from it to the inner part of the substance of the bone.

### BASEMENT MEMBRANES.

Basement membranes are a special structure upon which the epithelium of mucous membranes rests. They are of homogeneous appearance, and are developed from flattened connective-tissue corpuscles, joined at their edges, or from a concentrated cement substance. Some basement membranes possess elasticity, *e.g.*, in the cornea.

## II. CARTILAGE.

*General Structure of Cartilage.*—All kinds of cartilage are composed of *cells* imbedded in a substance called the *matrix:* the apparent differences of structure met with in the various kinds of cartilage are more due to differences in the character of the matrix than of the cells. Among the latter, however, there is also considerable diversity of form and size.

With the exception of the articular variety, cartilage is invested by a thin but tough firm fibrous membrane called the *perichondrium.* On the surface of the articular cartilage of the fœtus, the perichondrium is represented by a film of epithelium; but this is gradually worn away up to the margin of the articular surfaces when by use the parts begin to suffer friction.

Nerves are probably not supplied to any variety of cartilage.

Cartilage exists in three different forms in the human body, viz., 1, *Hyaline cartilage,* 2, *Yellow elastic-cartilage, and* 3, *White fibro-cartilage.*

### 1. Hyaline Cartilage.

*Distribution.*—This variety of cartilage is met with largely in the human body—investing the articular ends of bones, and forming the costal cartilages, the nasal cartilages, and those of the larynx with the exception of the epiglottis and cornicula laryngis, as well as those of the trachea and bronchi.

*Structure.*—Like other cartilages it is composed of cells imbedded in a matrix. The cells, which contain a nucleus with nucleoli, are irregular in shape, and generally grouped together in patches (fig. 53). The patches are of various shapes and sizes and placed at unequal distances apart. They generally appear flattened **near** the free surface of the mass of cartilage in which they are placed and more or less perpendicular to the surface in the more-deeply seated portions.

The matrix of hyaline cartilage has a dimly granular appearance like that of ground glass, and in man and the higher animals has no apparent structure. In some cartilages of the frog, however, even when examined in the fresh state, it is seen to be mapped out into polygonal blocks or cell-territories, each containing a cell in the centre, and repre



Fig. 53.



Fig. 54.

Fig. 53.—Hyaline articular cartilage (human). The cell bodies entirely fill the spaces in t matrix. × 340 diams. (Schäfer.)
Fig. 54.—Fresh cartilage from the Triton. (A. Rollett.)

senting what is generally called the capsule of the cartilage cells (fig 54). Hyaline cartilage in man has really the same structure, which ca be demonstrated by the use of certain reagents. If a piece of huma hyaline cartilage be macerated for a long time in diluted acid or in ho water 35°–45° C. (95°–113° F.), the matrix, which previously appeare quite homogeneous, is found to be resolved into a number of concentri lamellæ, like the coats of an onion, arranged round each cell or grou of cells. It is thus shown to consist of nothing but a number of larg systems of capsules which have become fused with one another.

The cavities in the matrix in which the cells lie are connected t gether by a series of branching canals, very much resembling those i the cornea: through these canals fluids may make their way into th depths of the tissue.

In the hyaline cartilage of the ribs the cells are mostly larger tha in the articular variety and there is a tendency to the development fibres in the matrix (fig. 55). The costal cartilages also frequently b ome calcified in old age, as also do some of those of the larynx. Fat-lobules may also be seen in many cartilages (fig. 55).

In articular cartilage the cells are smaller and arranged vertically in arrow lines like strings of beads.

In the fœtus cartilage is the material of which the bones are first constructed; the "model" of each bone being laid down, so to speak, in this substance. In such cases the cartilage is termed *temporary*. It closely resembles the ordinary hyaline kind; the cells, however, are not grouped together after the fashion just described, but are more uniformly distributed throughout the matrix.

A variety of temporary hyaline cartilage which has scarcely any ma-



Fig. 55.



Fig. 56.

Fig. 55.—Costal cartilage from an adult dog, showing the fat globules in the cartilage cells. (Cadiat.)

Fig. 56.—Yellow elastic cartilage of the ear. Highly magnified. (Hertwig.)

rix is found in the human subject and in the higher animals generally, early fœtal life, when it constitutes the *chorda dorsalis*.

*Nutrition.*—Hyaline cartilage is reckoned among the so-called *non-scular* structures, no blood-vessels being supplied directly to its own bstance; it is nourished by those of the bone beneath. When hyaline rtilage is in thicker masses, as in the case of the cartilages of the ribs, few blood-vessels traverse its substance. The distinction, however, tween all so-called *vascular* and *non-vascular* parts is at the best a ry artificial one.

## 2. Yellow Elastic Cartilage.

*Distribution.*—In the external ear, in the epiglottis and cornicula yngis, and in the Eustachian tube.

*Structure.*—The cells in this variety of cartilage are rounded or oval, th well-marked nuclei and nucleoli (fig. 56). The matrix in which ey are seated is composed almost entirely of fine elastic fibres, which form an intricate interlacement about the cells, and in their general characters are allied to the yellow variety of fibrous tissue: a small and variable quantity of hyaline intercellular substance is also usually present.

A variety of elastic cartilage, sometimes called *cellular*, is found to form the framework of the external ears of rats, mice, or other small mammals. It is composed, as its name implies, almost entirely of cells which are packed very closely with little or no matrix. When present the matrix consists of very fine fibres which twine about the cells in various directions and inclose them in a kind of network. Elastic cartilage seldom or never ossifies.

### 3. White Fibro-Cartilage.

*Distribution.*—White fibro-cartilage is found to occur:—

1. As *inter-articular* fibro-cartilage, *e.g.*, the semilunar cartilages of the knee-joint.

2. As *circumferential* or marginal cartilage, as on the edges of the acetabulum and glenoid cavity.

3. As *connecting* cartilage, *e.g.*, the inter-vertebral fibro-cartilages.

4. In the *sheaths of tendons* and sometimes in their substance. In the latter situation the nodule of fibro-cartilage is called a *sesamoid* fibro-cartilage, of which a specimen may be found in the tendon of the tibialis posticus in the sole of the foot, and usually in the neighboring tendon of the peroneus longus.



Fig. 57.



Fig. 58.

Fig. 57.—White fibro-cartilage. (Cadiat.)
Fig. 58.—White fibro-cartilage from an inter-vertebral ligament. (Klein and Noble Smith.)

*Structure.*—White fibro-cartilage (fig. 58), which is much more widely distributed throughout the body than the foregoing kind, is composed, like it, of cells and a matrix; the latter, however, being made up almost entirely of fibres closely resembling those of white fibrous tissue.

In this kind of fibro-cartilage it is not unusual to find a great part of its mass composed almost exclusively of fibres, and deriving the name of cartilage only from the fact that in another portion, continuous with it, cartilage cells may be pretty freely distributed.

By prolonged boiling, cartilage yields a substance called *chondrin*—which gelatinizes on cooling. The cells of white fibro-cartilage are as a rule rounded or somewhat flattened but in some places are distinctly branched.

**Functions of Cartilage.**—Cartilage not only represents in the fœtus the bones which are to be formed (*temporary cartilage*) but also offers a firm, yet more or less yielding, framework for certain parts in the developed body, possessing at the same time strength and elasticity. It maintains the shape of tubes as in the larynx and trachea. It affords attachment to muscles and ligaments; it binds bones together, yet allows a certain degree of movement, as between the vertebræ; it forms a firm framework and protection, yet without undue stiffness or weight, as in the pinna, larynx, and chest walls; it deepens joint cavities, as in the acetabulum, without unduly restricting the movements of the bones.

**Development of Cartilage.**—Cartilage is developed out of an embryonal tissue, consisting of cells with a very small quantity of intercellular substance: the cells multiply by fission within the cell-capsules, while the capsule of the parent cell becomes gradually fused with the surrounding intercellular substance. A repetition of this process in the young cells causes a rapid growth of the cartilage by the multiplication of its cellular elements and corresponding increase in its matrix. Thus we see that the matrix of cartilage is chiefly derived from the cartilage cells.

## III. Bone.

*Chemical Composition.*—Bone is composed of *earthy* and *animal* matter in the proportion of about 67 per cent of the former to 33 per cent of the latter. The earthy matter is composed chiefly of *calcium phosphate*, but besides there is a small quantity (about 11 of the 67 per cent) of *calcium carbonate* and *calcium fluoride*, and *magnesium phosphate*.

The animal matter called *collagen* is resolved into *gelatin* by boiling.

The earthy and animal constituents of bone are so intimately blended nd incorporated the one with the other that it is only by chemical ction, as for instance by heat in one case and by the action of acids in nother, that they can be separated. Their close union too is further hown by the fact that when by acids the earthy matter is dissolved out, r on the other hand when the animal part is burnt out, the shape of he bone is alike preserved.

The proportion between these two constituents of bone varies in ifferent bones in the same individual and in the same bone at different ges.

*Structure.*—To the naked eye there appear two kinds of structure in different bones, and in different parts of the same bone, namely, the *dense* or *compact*, and the *spongy or cancellous* tissue.

Thus, in making a longitudinal section of a long bone, as the humerus or femur, the articular extremities are found capped on their surface by a thin shell of compact bone, while their interior is made up of the spongy or cancellous tissue. The *shaft*, on the other hand, is formed almost entirely of a thick layer of the compact bone, and this surrounds a central canal, the *medullary* cavity—so called from its containing the *medulla* or marrow.

In the flat bones, as the parietal bone or the scapula, one layer of the cancellous structure lies between two layers of the compact tissue, and in the short and irregular bones, as those of the *carpus* and *tarsus*, the cancellous tissue alone fills the interior, while a thin shell of compact bone forms the outside.

**Marrow.**—There are two distinct varieties of marrow—the *red* and *yellow*.



Fig. 59.—Cells of the red marrow of the guinea-pig, highly magnified. *a*, A large cell, the nucleus of which appears to be partly divided into three by constrictions; *b*, a cell, the nucleus of which shows an appearance of being constricted into a number of smaller nuclei; *c*, a so-called giant cell, or myeloplaxe, with many nuclei; *d*, a smaller myelo-plaxe, with three nuclei; *e–i*, proper cells of the marrow. (E. A. Schäfer.)

*Red* marrow is that variety which occupies the spaces in the cancellous tissue; it is highly vascular, and thus maintains the nutrition of the spongy bone, the interstices of which it fills. It contains a few fat-cells and a large number of marrow-cells, many of which are undistinguishable from lymphoid corpuscles, and has for a basis a small amount of fibrous tissue. Among the cells are some nucleated cells of very much the same tint as colored blood-corpuscles. There are also a few large cells with many nuclei, termed *giant-cells or myeloplaxes*, which are derived from over-growth of the ordinary marrow-cells (fig. 59).

*Yellow* marrow fills the medullary cavity of long bones, and consists chiefly of fat-cells with numerous blood-vessels; many of its cells also are in every respect similar to lymphoid corpuscles.

From these marrow-cells, especially those of the red marrow, are derived, as we shall presently show, large quantities of red blood-corpuscles.

**Periosteum and Nutrient Blood-vessels.**—The surfaces of bones, except the part covered with articular cartilage, are clothed by a tough, fibrous membrane, the *periosteum;* and it is from the blood-vessels which are distributed in this membrane, that the bones, especially their more compact tissue, are in great part supplied with nourishment,—minute branches from the periosteal vessels entering the little foramina on the surface of the bone, and finding their way to the Haversian canals to be immediately described. The long bones are supplied also by a proper nutrient artery which, entering at some part of the shaft so as to reach the medullary canal, breaks up into branches for the supply of the marrow, from which again small vessels are distributed to the interior of the bone. Other small blood-vessels pierce the articular extremities for the supply of the cancellous tissue.



Fig. 60.—Transverse section of compact bony tissue (of humerus). Three of the Haversian canals are seen, with their concentric rings; also the lacunæ, with the canaliculi extending from them across the direction of the lamellæ. The Haversian apertures were filled with débris in grinding down the section, and therefore appear black in the figure, which represents the object as viewed with transmitted light. The Haversian systems are so closely packed in this section, that scarcely any *interstitial* lamellæ are visible. × 150. (Sharpey.)

*Microscopic Structure of Bone.*—Notwithstanding the differences of arrangement just mentioned, the structure of all bone is found under the microscope to be essentially the same.

Examined with a rather high power its substance is found to contain a multitude of small irregular spaces, approximately fusiform in shape, called *lacunæ,* with very minute canals or *canaliculi,* as they are termed, leading from them, and anastomosing with similar little prolongations from other lacunæ (fig. 60). In very thin layers of bone, no other canals than these may be visible; but on making a transverse section of the compact tissue as of a long bone, *e.g.*, the humerus or ulna, the arrangement shown in fig. 60 can be seen.

The bone seems mapped out into small circular districts, at or about the centre of each of which is a hole, around which is an appearance as of concentric layers—the *lacunæ* and *canaliculi* following the same concentric plan of distribution around the small hole in the centre, with which indeed they communicate.

On making a longitudinal section, the central holes are found to be simply the cut extremities of small canals which run lengthwise through the bone, anastomosing with each other by lateral branches (fig. 61), and are called *Haversian canals*, after the name of the physician, Clopton Havers, who first accurately described them.



Fig. 61.—Longitudinal section from the human ulna, showing Haversian canal, lacunæ, and canaliculi. (Rollett.)

**The Haversian canals**, the average diameter of which is $\frac{1}{500}$ of an inch (50 $\mu$), contain blood-vessels, and by means of them blood is conveyed to all, even the densest parts of the bone; the minute canaliculi and lacunæ absorbing nutrient matter from the Haversian blood-vessels and conveying it still more intimately to the very substance of the bone which they traverse.

The blood-vessels enter the Haversian canals both from without, by traversing the small holes which exist on the surface of all bones beneath the periosteum, and from within by means of small channels which extend from the medullary cavity, or from the cancellous tissue. The arteries and veins usually occupy separate canals, and the veins, which are the larger, often present, at irregular intervals, small pouch-like dilatations.

The **lacunæ** are occupied by branched cells, which are called *bone-cells*, or *bone-corpuscles* (fig. 62), which very closely resemble the ordinary branched connective-tissue corpuscles; each of these little masses of protoplasm ministering to the nutrition of the bone immediately surrounding it, and one lacunar corpuscle communicating with another, and with its surrounding district, and with the blood-vessels of the Haversian canals, by means of the minute streams of fluent nutrient matter which occupy the canaliculi.

It will be seen from the above description that bone is essentially connective-tissue impregnated with lime salts: it bears a very close resemblance to what may be termed typical connective-tissue such as the substance of the cornea. The bone-corpuscles with their proesses occupying the lacunæ and canaliculi correspond exactly to the ornea-corpuscles lying in branched spaces.



Fig. 62.



Fig. 63.

Fig. 62.—Bone-corpuscles with their processes as seen in a thin section of human bone. (Rollett.)
Fig. 63.—Thin layer peeled off from a softened bone. This figure, which is intended to represent e reticular structure of a lamella, gives a better idea of the object when held rather farther off an usual from the eye. × 400. (Sharpey.)

**Lamellæ of Compact Bone.**—In the shaft of a long bone three istinct sets of lamellæ can be clearly recognized.

(1.) *General* or fundamental lamellæ; which are most easily traceable just beneath the periosteum, and around the medullary cavity, forming around the latter a series of concentric rings. At a little distance from the medullary and periosteal surfaces (in the deeper portions of the bone) they are more or less interrupted by

(2.) *Special* or Haversian lamellæ, which are concentrically arranged around the Haversian canals to the number of six to eighteen around each.

(3.) *Interstitial* lamellæ, which connect the system of Haversian lamellæ, filling the spaces between them, and consequently attaining their greatest development where the Haversian systems are few, and *vice versâ*.

The ultimate structure of the lamellæ appears to be reticular. If a thin film be peeled off the surface of a bone, from which the earthy matter has been removed by acid, and examined with a high power of the microscope, it will be found composed of a finely reticular structure, formed apparently of very slender fibres decussating obliquely, but coalescing at the points of intersection, as if here the fibres were fused rather than woven together (fig. 63).

In many places these reticular lamellæ are perforated by tapering fibres called the *Claviculi* of Gagliardi, or the *perforating fibres of Sharpey,* resembling in character the ordinary white or rarely the elastic fibrous tissue, which bolt the neighboring lamellæ together, and may be drawn out when the latter are torn asunder (fig. 64). These perforating fibres originate from ingrowing processes of the periosteum, and in the adult still retain their connection with it.



**Fig. 64.**—Lamellæ torn off from a decalcified human parietal bone at some depth from the surface. *a, a,* Lamellæ, showing reticular fibres: *b, b,* darker part, where several lamellæ are superposed; *c,* perforating fibres. Apertures through which perforating fibres had passed, are seen especially in the lower part, *a, a,* of the figure. (Allen Thomson.)

**Development of Bone.**—From the point of view of their development, all bones may be subdivided into two classes.

(*a.*) Those which are ossified directly or from the first in *membrane* or fibrous tissue, *e.g.*, the bones forming the vault of the skull, parietal, frontal, and a certain portion of the occipital bones.

(*b.*) Those whose form, previous to ossification, is laid down in *hyaline cartilage, e.g.*, humerus, femur.

The process of development, pure and simple, may be best studied in bones which are not preceded by cartilage, *i.e., membrane-formed* (*e.g.*, *parietal*); and without a knowledge of this process (ossification in *membrane*), it is impossible to understand the much more complex series of changes through which such a structure as the cartilaginous femur of the fœtus passes in its transformation into the bony femur of the adult (ossification in *cartilage*).

**Ossification in Membrane.**—The membrane, afterward forming the periosteum, from which such a bone as the parietal is developed, consists of two layers—an external *fibrous*, and an internal *cellular* or *osteo-genetic*.

The external layer is made up of ordinary connective-tissue, being composed of layers of fibrous tissue with branched connective-tissue corpuscles here and there between the bundles of fibres. The internal layer consists of a network of fine fibrils with a large number of nucleated cells with a certain addition of albuminous ground or cement substance between the fibrous bundles, some of which are oval, others drawn out into long branched processes: it is more richly supplied with capillaries than the outer layer. The relatively large number of its cellular elements, which vary in size and shape, together with the abundance of its blood-vessels, clearly mark it out as the portion of the periosteum which is immediately concerned in the formation of bone.

In such a bone as the parietal, which is represented then when ossification commences by the species of fibrous connective tissue with many cells above indicated, the deposition of bony matter, which is preceded by increased vascularity, takes place in radiating spiculæ, starting from a *centre of ossification*, and shooting out in all directions toward the periphery. These primary bony spiculæ consist of the fibres of the tissue which are termed *osteogenetic fibres*, composed of a soft transparent substance called *osteogen*, in which calcareous granules are deposited. The fibres are said to exhibit in their precalcified state indications of a fibrillar structure, and are likened to bundles of white fibrous tissue, to which they are similar in chemical composition, but from which they differ in being stiffer and less wavy. The deposited granules after a time become so numerous as to fill up the substance of the fibres and bony spiculæ result. Calcareous granules are deposited also in the interfibrillar matrix. By the junction of the osteogenetic fibres and their resulting bony spiculæ a meshwork of bone is formed. The osteogenetic fibres, which become indistinct as calcification proceeds, are believed to persist in the lamellæ of adult bone. The osteoblasts, being in part retained within the bone trabeculæ thus produced, form bone corpuscles. On the bony trabeculæ first formed, layers of osteoblastic cells from the osteo-genetic layer of the periosteum are developed side by side, lining the irregular spaces like an epithelium (fig. 65, *b*). Lime-salts are deposited in the circumferential part of each osteoblast, and thus a ring of osteoblasts gives rise to a ring of bone with the remaining uncalcified portions of the osteoblasts imbedded in it as bone corpuscles, as in the first formation; then the central portion of the bony plate becomes harder and less cancellous. At the same time, the plate increases at the periphery not only by the extension of the bony spiculæ, but also by deposits taking place from the osteogenetic layer of the periosteum.

The primitive spongy bone is formed, and its irregular branching spaces are occupied by processes from the osteogenetic layer of the periosteum consisting of numerous blood-vessels and osteoblasts. Portions of this primitive spongy bone are re-absorbed. The osteoblasts are arranged in concentric successive layers and give rise to concentric Haversian lamellæ of bone, while the irregular space in the centre is reduced to a well-formed Haversian canal, containing the usual blood-vessels, the portions of the primitive spongy bone between the Haversian systems remaining as *interstitial* or ground-lamellæ (p. 59). The bulk of the primitive spongy bone is thus gradually converted into compac bony-tissue of Haversian systems. Those portions of the ingrowth from the deeper layer of the periosteum which are not converted int bone remain in the spaces of the cancellous tissue as the red marrow.



Fig. 65.—Osteoblasts from the parietal bone of a human embryo, thirteen weeks old. *a*, Bony septa with the cells of the lacunæ; *b*, layers of osteoblasts; *c*, the latter in transition to bone corpuscles. Highly magnified. (Gegenbaur.)

**Ossification in Cartilage.**—Under this heading, taking the fem as a typical example, we may consider the process by which the soli cartilaginous rod which represents the bone in the fœtus is converte into the hollow cylinder of compact bone with expanded ends forme of cancellous tissue of which the adult femur is made up. We mus bear in mind the fact that this fœtal cartilaginous femur is many time smaller than the medullary cavity even of the shaft of the mature bone, and, therefore, that not a trace of the original cartilage can be present in the femur of the adult. Its purpose is indeed purely temporary; and, after its calcification, it is gradually and entirely absorbed as will be presently explained.

ırtilaginous rod which forms the fœtal femur is sheathed in a e termed the *perichondrium*, which so far resembles the peri- scribed above, as to consist of two layers, in the deeper one of ıeroidal cells predominate and blood-vessels abound, while the er consists mainly of fusiform cells which are in the mature dually transformed into fibres. Thus, the differences between perichondrium and the periosteum of the adult are such as usually exist between the embryonic and mature forms of connective tissue.

Between the hyaline cartilage of which the fœtal femur consists and the bony tissue forming the adult femur, there are *two chief intermediate stages* — viz. (1) of



Fig. 66.



Fig. 67.

Ossifying cartilage showing loops of blood-vessels.
Longitudinal section of ossifying cartilage from the humerus of a fœtal sheep. Cal- ılæ are seen extending between the columns of cartilage cells. *c*, Cartilage cells. pey.)

**cartilage,** and (2) of **embryonic spongy bone.** These ma- hich successively occupy the place of the fœtal cartilage, are ion entirely absorbed, and their place is taken by true bone.

ırocess by which the cartilaginous is transformed into the bony femur may however be divided for the sake of clearness into the following *six stages*:—

*Stage* 1.—**Proliferation and Calcification.**—As ossification is commencing the cartilage cells in and near the centre of ossification become enlarged and proliferate, arranging themselves in rows corresponding to the long axis of the bone (fig. 67). Lime salts are next deposited in the form of fine granules in the hyaline matrix of the cartilage, and this gradually becomes transformed into a number of calcified trabeculæ (fig. 68, 5), inclosing alveolar spaces, which are the *primary areolæ*, and which contain cartilage cells. The cartilage cells, gradually enlarging, become more transparent, and finally undergo disintegration. During this stage the perichondrium has become the periosteum, and is beginning to deposit bone on the outside of the cartilage.



Fig. 68.—Transverse section of a portion of a metacarpal bone of a fœtus, showing—1, fibrous layer of periosteum; 2, osteogenetic layer of ditto; 3, periosteal bone; 4, cartilage, with matrix gradually becoming calcified, as at 5, with cells in primary areolæ; beyond 5 the calcified matrix is being entirely replaced by spongy bone. × 200. (V. D. Harris.)

*Stage* 2.—**Vascularization of the Cartilage.**—Processes from the osteogenetic or cellular layer of the periosteum containing blood-vessels break into the substance of the cartilage and grow much as ivy insinuates itself into the cracks and crevices of a wall. This begins at the "centres of ossification," from which the blood-vessels spread chiefly and down the shaft, etc. Thus the substance of the cartilage, which viously contained no vessels, is traversed by a number of branched anas- osing channels formed by the enlargement and coalescence of the es in which the cartilage-cells lie, and containing loops of blood- els (fig. 66) and spheroidal cells which will become osteoblasts. By her absorption of some of the trabeculæ larger spaces are devel- , which contain cartilage-cells for a very short time only, their s being taken by the so-called osteogenetic layer of the periosteum h constitutes the primary marrow.

*tage* 3.—**Substitution of Embryonic Spongy Bone for Carti-** .—The cells of the primary marrow arrange themselves as a contin- layer like epithelium on the calcified trabeculæ and deposit a layer



69.—A small isolated mass of bone next the periosteum of the lower jaw of human *a*, Osteogenetic layer of periosteum. *g*, multinuclear giant cells, the one on the left acting bably like an osteoclast. Above *c*, the osteoblasts are seen to become surrounded by an matrix. (Klein and Noble Smith.)

ne, and ensheath them: the calcified trabeculæ, encased in the s of young bone, become gradually absorbed, so that finally we trabeculæ composed entirely of spongy bone, all trace of the orig- alcified cartilage having disappeared. It is probable that the large nucleated giant-cells termed *osteoclasts* by Kölliker, which are de- from the osteoblasts by the multiplication of their nuclei, are the s by which the absorption of calcified cartilage, and subsequently bryonic spongy bone, is carried on (fig. 69, *g*). At any rate, they most always found wherever absorption is in progress.

hese stages are precisely similar to what goes on in the growing of a bone which is increasing in length by the advance of the ss of ossification into the intermediary cartilage between the dia- s and epiphysis. In this case the cartilage-cells become flattened multiplying by division, are grouped into regular columns at right angles to the plane of calcification, while the process of calcification extends into the hyaline matrix between them (figs. 67 and 68).

*Stage* 4.—**Substitution of Periosteal Bone for the Primary Embryonic Spongy Bone.**—The embryonic spongy bone, formed as above described, is simply a temporary tissue occupying the place of the fœtal rod of cartilage, once representing the femur; and the stages 1, 2, and 3 show the successive changes which occur *at the centre* of the shaft. Periosteal bone is at the same time deposited in successive layers beneath the periosteum, *i.e.*, *at the circumference* of the shaft, exactly as described in the section on ossification in membrane, and thus a casing of periosteal bone is formed around the embryonic endochondral spongy bone: this casing is thickest at the centre, where it is first formed, and



Fig. 70.—Transverse section through the tibia of a fœtal kitten, semi-diagrammatic. × 60. P, Periosteum. O, Osteogenetic layer of the periosteum showing the osteoblasts arranged side by side, represented as pear-shaped black dots on the surface of the newly-formed bone. B, The periosteal bone deposited in successive layers beneath the periosteum and ensheathing E, the spongy endochondral bone; represented as more deeply shaded. Within the trabeculæ of endochondral spongy bone are seen the remains of the calcified cartilage trabeculæ represented as dark wavy lines. C, The medulla, with V, V, veins. In the lower half of the figure the endochondral spongy bone has been completely absorbed. (Klein and Noble Smith.)

s out toward each end of the shaft. The embryonic spongy bone is rbed, through the agency of osteoclasts, its trabeculæ becoming ually thinned and its meshes enlarging, and finally coalescing into reat cavity—the medullary cavity of the shaft.

*tage* 5.—**Absorption of the Inner Layers of the Periosteal** .—The absorption of the endochondral spongy bone is now com- and the medullary cavity is bounded by periosteal bone: the inner of this periosteal bone are next absorbed, and the medullary cavity reby enlarged, while the deposition of bone beneath the periosteum



71.—Tranverse section of femur of a human embryo about eleven weeks old. *a*, Rudimen- versian canal in cross-section; *b*, in longitudinal section; *c*, osteoblasts; *d*, newly formed ubstance of a lighter color; *e*, that of greater age; *f*, lacunæ with their cells; *g*, a cell still an osteoblast. (Frey.)

ues as before. The first-formed periosteal bone is spongy in ter.

*ge* 6.—**Formation of Compact Bone.**—The transformation of periosteal bone into compact bone is effected in a manner exactly r to that which has been described in connection with ossification nbrane (p. 61). The irregularities in the walls of the areolæ in ongy bone are absorbed, while the osteoblasts which line them are ped in concentric layers, each layer in turn becoming ossified till mparatively large space in the centre is reduced to a well-formed sian canal (fig. 71). When once formed, bony tissue grows to xtent interstitially, as is evidenced by the fact that the lacunæ are further apart in full-formed than in young bone.

From the foregoing description of the development of bone, it will be seen that the common terms *ossification in cartilage* and *ossification in membrane* are apt to mislead, since they seem to imply two processes radically distinct. The process of ossification, however, is in all cases one and the same, all true bony tissue being formed from membrane (perichondrium or periosteum); but in the development of such a bone as the femur, which may be taken as the type of so-called ossification in cartilage, lime-salts are first of all deposited in the cartilage; this calcified cartilage, however, is gradually and entirely re-absorbed, being ultimately replaced by bone formed from the periosteum, till in the adult structure nothing but true bone is left. Thus, in the process of "ossification in cartilage," calcification of the cartilaginous matrix precedes the real formation of bone. We must, therefore, clearly distinguish between *calcification* and *ossification*. The former is simply the infiltration of an animal tissue with lime-salts, and is, therefore, a change of chemical composition rather than of structure; while ossification is the formation of true bone—a tissue more complex and more highly organized than that from which it is derived.

**Centres of Ossification.**—In all bones ossification commences at one or more points, termed *centres of ossification*. The long bones, *e.g.*, femur, humerus, etc., have at least three such points—one for the ossification of the *shaft or diaphysis*, and one for each articular extremity or *epiphysis*. Besides these three primary centres which are always present in long bones, various secondary centres may be superadded for the ossification of different *processes*.

**Growth of Bone.**—Bones increase *in length* by the advance of the process of ossification into the cartilage intermediate between the diaphysis and epiphysis. The increase in length indeed is due entirely to growth at the two ends of the *shaft*. This is proved by inserting two pins into the shaft of a growing bone: after some time their distance apart will be found to be unaltered though the bone has gradually increased in length, the growth having taken place beyond and not between them. If now one pin be placed in the shaft, and the other in the epiphysis of a growing bone, their distance apart will increase as the bone grows in length.

Thus it is that if the epiphyses with the intermediate cartilage be removed from a young bone, growth in length is no longer possible while the natural termination of growth of a bone in length takes place when the epiphyses become united in bony continuity with the shaft.

Increase *in thickness* in the shaft of a long bone occurs by the deposition of successive layers beneath the periosteum.

If a thin metal plate be inserted beneath the periosteum of a growing bone it will soon be covered by osseous deposit, but if it be put be tween the fibrous and osteogenetic layers it will never become enveloped in bone, for all the bone is formed beneath the latter.

Other varieties of connective tissue may become ossified, *e.g.*, the tendons in some birds.

**Functions of Bones.**—Bones form the framework of the body; for this they are fitted by their hardness and solidity together with their comparative lightness; they serve both to protect internal organs in the trunk and skull, and as levers worked by muscles in the limbs; notwithstanding their hardness they possess a considerable degree of elasticity, which often saves them from fracture.

The material of which the chief portion of the teeth is made up, called Dentine, is frequently classed with bone and as one of the connective tissues. The other constituents of the teeth also resemble bone in structure to a considerable degree; it will be as well therefore to give in this place some account of the *teeth*.

## The Teeth.

During the course of his life, man, in common with most other mammals, is provided with two sets of teeth; the first set, called the *temporary* or *milk teeth*, makes its appearance in infancy, and is in the course of a few years shed and replaced by the second or *permanent* set.



Fig. 72.—Normal well-formed jaws, from which the alveolar plate has been in great part removed, so as to expose the developing permanent teeth in their crypts in the jaws. (Tomes.)

The **temporary** or **milk teeth** have only a very limited term of existence.

They are ten in number in each jaw, namely, on either side from the middle line two *incisors*, one *canine*, and two deciduous *molars*, and are replaced by ten permanent teeth. The number of permanent teeth in each jaw is, however, increased to sixteen by the development of thr molars on each side of the jaw, which are called the permanent or tr molars.

The following formula shows, at a glance, the comparative arrang ment and number of the temporary and permanent teeth:—

## Temporary Teeth.

MIDDLE LINE OF JAW.

| MOLARS. | CANINE. | INCISORS. | INCISORS. | CANINE. | MOLARS. | |
|---|---|---|---|---|---|---|
| 2 | 1 | 2 | 2 | 1 | 2=10 | =20 |
| 2 | 1 | 2 | [illegible] | [illegible] | [illegible]=10 | |

| TRUE MOLARS. | BICUSPIDS OR PRE-MOLARS. | C |
|---|---|---|
| 3 | 2 | |
| 3 | 2 | |

From this formu
teeth in the adult a
child. They differ
molars having a stro
diate descendants th
in the jaws.

The temporary in
little except in their
enamel terminates at
edge. Their color is
The following ta
Temporary and Perm
given tooth of the lov
tooth of the upper jaw

T

The figures indicat

| LOWER CENTRAL INCISORS. | UPPER INCIS |
|---|---|
| 6 to 9 | 8 to 12 |

## Permanent Teeth.

**e age at which each tooth is cut is indicated in this table in years.**

| T S. | INCISORS. | | BICUSPIDS OR PRE-MOLARS. | | CANINES. | SECOND MOLARS. | THIRD MOLARS OR WISDOMS. |
|---|---|---|---|---|---|---|---|
| | CENTRALS. | LATERALS. | FIRST. | SECOND. | | | |
| | 7 | 8 | 9 | 10 | 12 to 14 | 12 to 15 | 17 to 25 |

e times of eruption given in the above tables are only approxi- the limits of variation being tolerably wide. Some children may eir first teeth before the age of six months, and others not till the twelfth month. In nearly all cases the two central incisors lower jaw are cut first, these being succeeded after a short inter- the four incisors of the upper jaw; next follow the lateral in- f the lower jaw, and so on as indicated in the table till the com- of the milk dentition at about the age of two years. Certain affecting the bony skeleton, *e.g.*, Rickets, retard the eruptive considerably.

milk-teeth usually come through in batches, each period of n being succeeded by one of quiescence lasting sometimes several . The milk-teeth should be in use from the age of two up to a few months of the time for their successors to appear. Their n serves the purpose of preserving the necessary space sufficient succeeding permanent teeth to occupy.

important to notice that it is a molar which is the first tooth to n the permanent dentition, not an incisor as in the case of the ry set, and also that it appears *behind* the last deciduous molar side.

third molars, often called *Wisdoms*, are sometimes unerupted life from want of sufficient jaw space and the presence of the eth: and in highly civilized races there are evidences to show ey are in process of suppression from the dental series; cases of families in which their absence is a characteristic feature being nally met with.

en the teeth are fully erupted it will be observed that the upper and canines project obliquely over the lower front teeth and the l cusps of the upper bicuspids and molars lie outside those of responding teeth in the lower jaw. This arrangement allows to xtent of a scissor-like action in dividing and biting food in the incisors; and a grinding motion in that of the bicuspids and when the side to side movements of the lower jaw bring the ex- cusps of the lower teeth into direct articulation with those of the upper, and then cause them to glide down the inclined surfaces of the external and up the internal cusps of these same upper teeth during the act of mastication.

The work of the canine teeth in man is similar to that of his incisors. Besides being a firmly implanted tooth and one of stronger substance than the others, the canine tooth is important in preserving the shape of the angle of the mouth, and by its shape, whether pointed or blunt, long or short, becomes a character tooth of the dentition as a whole in both males and females.

Another feature in the fully developed and properly articulated set of teeth is that no two teeth oppose each other only, but that each tooth antagonizes with two, except the upper Wisdom, usually a small tooth. This is the result of the greater width of the upper incisors, which so arranges the "bite" of the other teeth that the lower canine closes in front of the upper one.

Should a tooth be lost, therefore, it does not follow that its former opponent remaining in the mouth is rendered useless and thereby liable to be removed from the jaw by a gradual process of extrusion commonly seen in teeth that have no work to perform by reason of absence of antagonists.

It is worthy of note that from the age of four years to the shedding of the first milk-tooth the child has no fewer than forty-eight teeth, twenty milk-teeth and twenty-eight calcified germs of permanent teeth (all in fact except the four wisdom teeth, which show no signs of development until the third year).

## Structure of a Tooth.

A tooth is generally described as possessing a *crown, neck,* and *root* or *roots.*

The *crown* is the portion which projects beyond the level of the gum. The *neck* is that constricted portion just below the crown which is embraced by the free edges of the gum, and the *root* includes all below this.

On making longitudinal and transverse sections through its centre (fig. 73, A, B), a tooth is found to be principally composed of a hard material, *dentine* or ivory, which is hollowed out into a central cavity which resembles in general shape the outline of the tooth, and is called the *pulp* cavity from its containing the very vascular and sensitive pulp.

The *tooth pulp* is composed of fibrous connective tissue, blood-vessels, nerves, and large numbers of cells of varying shapes, *e.g.*, fusiform, stellate, and on the surface in close connection with the dentine a specialized layer of cells called *odontoblasts*, which are elongated columnar-looking cells with a large nucleus at the tapering ends or those farthest from the *dentine* (the layer is sometimes mentioned as the *membrana eboris*, from the tenacity with which it clings to the dentine), all are imbedded in a mucoid gelatinous matrix.

The blood-vessels and nerves enter the pulp through a small opening at the apical extremity of each root. The exact terminations of the nerves are not definitely known. They have never been observed to enter the dentinal tubes, but they are probably connected with the fibrils in those tubes through the intervention of the odontoblasts and deeper layer of cells. No lymphatics have been traced to the pulp.

A layer of very hard calcareous matter, the *enamel*, caps that part of the dentine which projects beyond the level of the gum; while sheathing the portion of dentine which is beneath the level of the gum, is a layer of true bone, called the *cement* or *crusta petrosa*.



Fig. 73.—A. Longitudinal section of a human molar tooth; *c*, cement; *d*, dentine; *e*, enamel; *v*, pulp cavity (Owen). B. Transverse section. The letters indicate the same as in A.

The enamel and cement are very thin at the neck of the tooth where they come in contact, the cement overlapping the enamel. A thin epithelial and horny membrane (*enamel cuticle*, or *Nasmyth's membrane*) covers the outer surface of the enamel on unworn teeth. It is formed of short flattened prisms which are the remains of the uncalcified last-formed portions of the enamel prisms. The enamel becomes thicker toward the crown, and the cement toward the lower end or apex of the root.

## I.—*Dentine* or *Ivory*.

*Chemical Composition.*—Dentine closely resembles bone in chemical composition. It contains, however, rather less animal matter; the proportion in a hundred parts being about twenty-eight *animal* to seventy-two of *earthy*. The former, like the animal matter of bone, may be resolved into *gelatin* by boiling. It also contains a trace of fat. The earthy matter is made up chiefly of *calcium phosphate*, with a small portion of the *carbonate*, and traces of *calcium fluoride* and *magnesium phosphate*.

*Structure.*—Under the microscope dentine is seen to be finely channelled by a multitude of delicate tubes, which, by their inner ends communicate with the pulp-cavity, and by their outer extremities come into contact with the under part of the enamel and cement, and sometimes even penetrate them for a greater or less distance (figs. 75, 77). The matrix in which these tubes lie is composed of "a reticulum of fine fibres of connective tissue modified by calcification, and where that pro-



Fig. 74.—Premolar tooth of cat *in situ*.



Fig. 75.—Section of a portion of the dentine and cement from the middle of the root of an incisor tooth. *a*, Dental tubuli ramifying and terminating, some of them in the interglobular spaces *b* and *c*, which somewhat resemble bone lacunæ; *d*, inner layer of the cement with numerous closely set canaliculi; *e*, outer layer of cement; *f*, lacunæ; *g*, canaliculi. × 350. (Kölliker.)

s is complete, entirely hidden by the densely deposited lime salts" ummery).

In their course from the pulp-cavity to the surface the minute tubes rm gentle and nearly parallel curves and divide and subdivide dichomously, but without much lessening of their calibre until they are proaching their peripheral termination.

From their sides proceed other exceedingly minute secondary canals, hich extend into the dentine between the tubules and anastomose with ch other. The tubules of the dentine, the average diameter of which t their inner and larger extremity is $\frac{1}{1500}$ of an inch, contain fine pro- ngations from the tooth-pulp, which give the dentine a certain faint ensitiveness under ordinary circumstances and, without doubt, have to lo also with its nutrition. These prolongations from the tooth-pulp are probably processes of the dentine-cells or *odontoblasts* which are branched cells lining the pulp-cavity; the relation of these processes to the tubules in which they lie being precisely similar to that of the processes of the bone-corpuscles to the canaliculi of bone. The outer portion of the dentine, underlying the cement, and the enamel to a much lesser degree, forms a more or less distinct layer termed the *granular* or *interglobular* layer. It is characterized by the presence of a number of irregular minute cell-like cavities, much more closely packed than the lacunæ in the cement, and communicating with one another and with the ends of the dentine-tubes (fig. 75, *b*, *c*), and containing cells like bone-corpuscles.

## II.—*Enamel.*

*Chemical Composition.*—The *enamel*, which is by far the hardest porion of a tooth, is composed, chemically, of the same elements that enter nto the composition of dentine and bone. Its animal matter, howver, amounts only to about 2 or 3 per cent. It contains a larger proortion of inorganic matter and is harder than any other tissue in the ody.

*Structure.*—Examined under the microscope, enamel is found comsed of fine hexagonal fibres (figs. 76, 77) $\frac{1}{5000}$ of an inch in diameter, hich are set on end on the surface of the dentine, and fit into correonding depressions in the same.

They radiate in such a manner from the dentine that at the top of e tooth they are more or less vertical, while toward the sides they tend the horizontal direction. Like the dentine tubules, they are not aight, but disposed in wavy and parallel curves. The fibres are rked by transverse lines, and are mostly solid, but some of them may ntain a very minute canal.

The enamel-prisms are connected together by a very minute quantity hyaline cement-substance. In the deeper part of badly formed enamels, between the prisms, are small *lacunæ*, or "interglobular spaces" which have the processes or fibrils of the dentine tubes in connection with them (fig. 77, *c*).



Fig. 76.—Enamel fibres. A, Fragments and single fibres of the transversely-striated enamel, isolated by the action of hydrochloric acid. B, Surface of a small fragment of enamel, showing the hexagonal ends of the fibres with darker centres, or not so highly calcified. × 350. (Kölliker.)

### III.—*Crusta Petrosa.*

The *crusta petrosa*, or *cement* (fig. 75, *e*, *d*), is composed of true bone, and in it are lacunæ (*f*) and canaliculi (*g*), which sometimes communicate with the outer finely branched ends of the dentine tubules, and generally with the interglobular spaces. Its laminæ are as it were bolted together by perforating fibres like those of ordinary bone (Sharpey's fibres). Cement differs from ordinary bone in possessing no Haversian canals, or, if at all, only in the thickest part. Such canals are more often met with in teeth with the cement hypertrophied than in the normal tooth.

## Development of the Teeth.

*Development of the Teeth.*—The first step in the development of the teeth consists in a downward growth (fig. 78, A, 1) from the Rete Malpighi or the deeper layer of stratified epithelium of the mucous membrane of the mouth, which first becomes thickened in the neighborhood of the maxillæ or jaws now in the course of formation. This process passes downward into a recess of the imperfectly developed tissue of the embryonic jaw. The downward epithelial growth forms the ***primary*** *enamel organ* or *enamel germ*, and its position is indicated by a slight groove in the mucous membrane of the jaw. The next step in the process consists in the elongation downward of the enamel groove and of

ımel germ and the inclination outward of the deeper part (fig.
"), which is now inclined at an angle with the upper portion or
f), and has become bulbous. After this there is an increased de-
ıent at certain points corresponding to the situations of the future
ɜeth. The enamel germ, or common enamel germ, as it may be
becomes divided at its deeper portion, or extended by further





F' . 77

Fig. 78

7.—Thin section of the enamel and a part of the dentine. *a*, Cuticular pellicle of the
Nasmyth = membrane); *b*, enamel fibres, or columns with fissures between them and
ıæ; *c*, larger cavities in the enamel, communicating with the extremities of some of
nal tubuli (*d*). × 350. (Kölliker.)
8.—Section of the upper jaw of a fœtal sheep. A.—1, Common enamel germ dipping down
nucous membrane; 2, palatine process of jaw; 3, rete Malpighi. B.—Section similar to A,
ng through one of the special enamel germs here becoming flask-shaped; *c*, *c'*, epithelium
; *f*, neck; *f'*, body of special enamel germ. C.—A later stage; *c*, outline of epithelium of
ıeck of enamel germ; *f'*, enamel organ; *p*, papilla; *s*, dental sac forming; *f p*, the enamel
ermanent tooth; *m*, bone of jaw; *v*, vessels cut across. (Waldeyer and Kölliker.) Copied
ıin's Anatomy.

, into a number of special enamel germs corresponding to each
above-mentioned milk-teeth, and connected to the common germ
ırrow neck. Each tooth is thus placed in its own special recess in
bryonic jaw (fig. 78, B, *f f'*).

As these changes proceed, there grows up from the underlying t into each enamel germ (fig. 78, c, *p*), a distinct vascular *papilla* (de papilla), and upon it the enamel germ becomes moulded, and pres the appearance of a cap of two layers of epithelium separated by an terval (fig. 78, c, *f'*). While part of the sub-epithelial tissue is elevat to form the dental papillæ, the part which bounds the embryonic tee forms the dental sacs (fig. 78, c, *s*); and the rudiment of the jaw, at fir a bony gutter in which the teeth germs lie, sends up processes formin partitions between the teeth. In this way small chambers are produce in which the dental sacs are contained, and thus the sockets of the teet are formed. The papilla, which is really part of the dental sac (if on thinks of this as the whole of the sub-epithelial tissue surrounding th enamel organ and interposed between the enamel germ and the develop ing bony jaw), is composed of nucleated cells arranged in a meshwor



Fig 79.—Part of section of developing tooth of a young rat, showing the mode of depositio the dentine. Highly magnified. *a*, Outer layer of fully formed dentine; *b*, uncalcified matrix one or two nodules of calcareous matter near the calcified parts; *c*, odontoblasts sending proce into the dentine; *d*, pulp; *e*, fusiform or wedge-shape cells found between odontoblasts; *f*, stel cells of pulp in fibrous connective tissue. The section is stained in carmine, which colors the calcified matrix but not the calcified part. (E. A. Schäfer.)

the outer or peripheral part being covered with a layer of columnar cleated cells called *odontoblasts*. The odontoblasts possibly form dentine, while the remainder of the papilla forms the tooth-pulp. T method of the formation of the dentine from the odontoblasts is said be as follows: The cells elongate at their outer part, and these proces are directly converted into the tubules of dentine (fig. 79, *c*), and, cording to some, into the contained fibrils as well. The continued f mation of dentine proceeds by the elongation of the odontoblasts, their subsequent conversion by a process of calcification into dentine bules. The most recently formed tubules are not immediately calcif The dentine fibrils contained in the tubules are said, by others, to formed from processes of the deeper layer of odontoblasts, which wedged in between the cells of the superficial layer (fig. 79, *e*) which fo the tubules only. There are several theories upon these points. matrix, according to more recent views, is formed by a calcificatio the fibrous connective tissue developed in the papilla.

Since the papillæ are to form the main portion of each tooth, *i.e.*, dentine, each of them early takes the shape of the crown of the tooth to which it corresponds. As the dentine increases in thickness the papillæ diminish, and at last when the tooth is cut only a small amount of the papilla remains as the dental pulp, and is supplied by vessels and nerves which enter at the end of the root. The shape of the crown of the tooth is taken by the corresponding papilla, and that of the single or double root by the subsequent constriction below the crown, or by division of the lower part of the papilla. The number of roots being foreshadowed by the number of arteries going to the papilla. The roots are not completely formed at the time of the eruption of the teeth, but subsequently.



Fig. 80.—Vertical transverse section of the dental sac, pulp, etc., of a kitten. *a*, Dental papilla or pulp; *b*, the cap of dentine formed upon the summit; *c*, its covering of enamel; *d*, inner layer of epithelium of the enamel organ; *e*, gelatinous tissue; *f*, outer epithelial layer of the enamel organ; *g*, inner layer, and *h*, outer layer of dental sac. × 14. (Thiersch.)

The enamel cap is found later on to consist (fig. 80, *d*, *e*, *f*) of four parts: (1) an inner membrane, composed of a layer of columnar epithelium in contact with the dentine, called *enamel cells;* (2) outside of these one or more layers of small polyhedral nucleated cells (*stratum intermedium* of Hannover); (3) an outer membrane of several layers of epithelium; (4) a middle membrane formed of a matrix of non-vascular gelatinous tissue, containing stellate cells. The enamel is formed by the enamel cells of the inner membrane, by the deposit of a keratin-like substance, which subsequently undergoes calcification and forms the first layer. Other layers are formed in the same manner, the cells retiring meanwhile, until when the tooth breaks through the gum it is covered by an uncalcified layer of the keratin-like substance which is called Nasmyth's membrane. At this time the other layers of the enamel cap have disappeared.

The *cement* or *crusta petrosa* is formed from the internal tissue of the tooth sac, the structure and function of which are identical with those of the osteogenetic layer of the periosteum, or, in other words, ossification in membrane occurs in it.

The outer layer or portion of the membrane of the tooth sac forms the fibrous *dental periosteum.*

This periosteum, when the tooth is fully formed, is not only a means of attachment of the tooth to its socket, but also in conjunction with the *pulp* a source of nourishment to it. Additional laminæ of cement are added to the root from time to time during the life of the tooth, as especially well seen in the abnormal condition called exostosis, by the process of calcification taking place in the periosteum. On the other hand absorption of the root may equally occur through the same membrane.

In this manner the first set of teeth, or the milk-teeth, are formed; and each tooth, by degrees developing, presses at length on the wall of the sac inclosing it, and, causing its absorption, is *cut,* to use a familiar phrase.

The *temporary* or *milk-teeth* are speedily replaced by the growth of the permanent teeth, which push their way up from beneath them.

Each temporary tooth is replaced by a tooth of the permanent set which is developed from a small sac set by, so to speak, from the sac of the temporary tooth which precedes it, and called the *cavity of reserve* (fig. 78, *c, fp*). Thus the temporary incisors and canines are succeeded by the corresponding permanent ones, the temporary first molar by the first bicuspid, the temporary second molar develops two offshoots, one for the second bicuspid, the other for the permanent first molar. The permanent second molar is budded off from the first permanent molar and the wisdom from the permanent second molar.

The development of the temporary teeth is said to commence about the sixth week of intra-uterine life, after the laying down of the bony structure of the jaws. Their permanent successors begin to form about the sixteenth week of intra-uterine life.

The second permanent molars are believed to originate about the third month after birth, and the wisdom teeth about the third year.

## III. Muscular Tissue.

There are two chief kinds of muscular tissue, differing both in minute structure as well as in mode of action, viz., (1.) the *plain* or *non-striated*, and (2.) the *striated*.

### Unstriped or Plain Muscle.

*Distribution.*—Unstriped muscle forms the proper muscular coats (1.) of the digestive canal from the middle of the œsophagus to the internal sphincter ani; (2.) of the ureters and urinary bladder; (3.) of the trachea and bronchi; (4.) of the ducts of glands; (5.) of the gall-bladder; (6.) of the vesiculæ seminales; (7.) of the pregnant uterus; (8.) of blood-vessels and lymphatics; (9.) of the iris, and some other parts of the eye. This form of tissue also enters largely into the composition (10.) of the *tunica dartos*, the contraction of which is the principal cause of the wrinkling and contraction of the scrotum on exposure to cold. Unstriped muscular tissue occurs largely also in the true skin generally, being especially abundant in the interspaces between the bases of the papillæ. Hence when it contracts under the influence of cold, fear, electricity, or any other stimulus, the papillæ are made unusually prominent, and give rise to the peculiar roughness of the skin termed *cutis anserina*, or goose skin. It occurs also in the superficial portion of the cutis, in all parts where hairs occur, in the form of flattened roundish bundles, which lie alongside the hair-follicles and sebaceous glands. They pass obliquely from without inward, embrace the sebaceous glands, and are attached to the hair-follicles near their base.



Fig. 81.—A, Unstriped muscle cells from the mesentery of a newt. The sheath exhibits transverse markings. × 180. B, From a similar preparation, showing that each muscle cell consists of a central bundle of fibrils, F (contractile part), connected with the intra-nuclear network, N, and a sheath with annular thickenings, St. The cells show varicosities due to local contraction, and on these the annular thickenings are most marked. × 450. (Klein and Noble Smith.)

*Structure.*—Unstriated muscles are made up of elongated, spindle-shaped, nucleated cells (fig. 81), which in their perfect form are flat, from about $\frac{1}{4500}$ to $\frac{1}{3500}$ of an inch broad (7 to 8$\mu$), and $\frac{1}{600}$ to $\frac{1}{300}$ of an inch ($\frac{1}{12}$ to $\frac{1}{24}$ *mm*) in length—very clear, granular, and brittle, so that when they break they often have abruptly rounded or square extremities. Each cell of these consists of a fine sheath, probably elastic; of a central bundle of fibrils representing the contractile substance; and of an oblong nucleus, which includes within a membrane a fine network anastomosing at the poles of the nucleus with the contractile fibrils. The ends of fibres are usually single, sometimes divided. Between the fibres is an albuminous cementing material or *endomysium* in which are found connective-tissue corpuscles, and a few fibres. The *perimysium* is continuous with the endomysium in the fibrous connective tissue surrounding and separating the bundles of muscle cells.



Fig. 82.—Plexus of bundles of unstriped muscle cells from the pulmonary pleura of the Guinea-pig. × 180. (Klein and Noble Smith.) A, Branching fibres; B, their long central nuclei.

## Striated Muscle.

*Distribution.*—Striated or striped muscle is found in the following situations. It constitutes the whole of the muscular apparatus of the skeleton, of the walls of the abdomen, etc., the whole of those muscles which are under the control of the will and hence termed *voluntary*, as well as certain other muscles, *e.g.*, of the internal ear and pharynx not directly under the control of the will, and the heart.

*Structure.*—For the sake of description, striated muscular tissue may be divided into two classes, (a.) *skeletal*, which comprises the whole of the striated muscles of the body except (b.) the *heart*:—

(a.) **Skeletal Muscle.**—In the majority of cases a skeletal muscle is inclosed in a sheath of areolar tissue called the *epimysium*, which in some cases is a very thick and distinct investment, while in other cases it is much thinner. The sheath sends in partitions which serve to support the *fasciculi* or bundles of fibres, of which the muscle is made up, forming more or less distinct sheaths for them, called *perimysium*. The fibres themselves are supported in their fasciculus by a scanty amount of areolar tissue containing plasma cells and termed *endomysium.* Within the areolar tissue supporting the fasciculi and between the fibres are contained the blood-vessels and nerves of the tissue.

The muscular fibres of each fasciculus are parallel to one another, and generally speaking so are the fasciculi themselves, except that toward their terminations they may converge to their insertion into the tendon of the muscle. The fasciculi extend throughout the whole length of the muscle, but they vary in size and in the number of their contained fibres, both in different muscles and also in the same muscle, some muscles having coarse, others fine fasciculi. In some cases it would seem that the perimysium is altogether independent of the external sheath of the muscle. As to the fibres of which the bundles are made up, they ave a distinct elastic sheath, the *sarcolemma;* their size varies considrably, their cross-section being from 100μ to 10μ, and as regards their ape, it is cylindrical or is triangular, quadrilateral, or pentangular with unded angles. In length the fibres seldom exceed an inch and a half



Fig. 83.



Fig. 84.

Fig. 83.—Transverse section through muscular fibres of human tongue. The muscle-corpuscles are indicated by their deeply-stained nuclei situated at the inside of the sarcolemma. Each muscle-fibre shows "Cohnheim's fields," that is, the sarcous elements in transverse section separated by clear (apparently linear) interstitial substance. × 450. (Klein and Noble Smith.)

Fig. 84.—Muscular fibre torn across; the sarcolemma still connecting the two parts of the fibre. (Todd and Bowman.)



Fig. 85.—Part of a striped muscle-fibre of a water beetle prepared with absolute alcohol. A, rcolemma; B, Krause's membrane. The sarcolemma shows regular bulgings. Above and below ause's membrane are seen the transparent "lateral discs." The chief mass of a muscular comrtment is occupied by the contractile disc composed of sarcous elements. The substance of the ividual sarcous elements has collected more at the extremity than in the centre: hence this ter is more transparent. The optical effect of this is that the contractile disc appears to possess "median disc" (Disc of Hensen). Several nuclei of muscle corpuscles, C and D, are shown, and them a minute network. × 300. (Klein and Noble Smith.)

(3.75 cm). It is thus evident that the same fibre does not exten one end of a muscle to the other, and indeed it is known that i ciculus fibrils are joined together by rounded or angular extremi vested with their proper sheath the sarcolemma.

Each muscular fibre then is thus constructed:—Externally is transparent, structureless membrane, the *sarcolemma*, which in th of a tubular investing sheath forms the outer wall of the fibre and contains the contractile material of which the fibre is chiefly ma Sometimes, from its comparative toughness, the sarcolemma will untorn, when by extension the contained part can be broken (f and its presence is in this way best demonstrated. The fibres a pale yellow color, and apparently marked by fine striæ which pass versely round them, in slightly curved or wholly parallel lines.



Fig. 86.—A. Portion of a medium-sized human muscular fibre. × 800. B. Separated b fibrils equally magnified; *a*, *a*, larger, and *b*, *b*, smaller collections; *c*, still smaller; *d*, *d*, the which could be detached, possibly representing a single series of sarcous element. (Sharp

*sarcolemma* is a transparent structureless elastic sheath of great ance which surrounds each fibre (fig. 84). There is still some do garding the nature of the fibrils.

A striated muscle fibre, when examined with a sufficientl power of the microscope, presents the following appearances, lo dinally :—

(a.) Alternate *dark and light parallel transverse stripes*, to this variety of muscle owes its name, the depth of the strip always being the same.

(b.) With still higher powers of the microscope, the bright may be seen to be divided in the middle line by other very fine transverse dark lines, sometimes called *Dobie's line.*

(c.) Each dark stripe may also sometimes be seen to be divided by a clear line, called *Henson's disc.*

(d.) Each fibre presents an appearance of *longitudinal striation* and after hardening in alcohol may be divided by teasing with needles into longitudinal fibrils, more or less cylindrical or angular, which are named *muscle columns or sarcostyles,* and extend throughout each fibre. Each of these appears to consist of short columns connected together by bright intervals, the former are the *sarcous elements* of Bowman. They may possibly be further longitudinally striated, and so made up of finer fibrillæ still.

After treatment with reagents the fibre may be split up into transverse discs.

(e.) On **Transverse Section.**—The fibre presents most externally, the outline of the sarcolemma.

(f.) The muscular substance proper appears to be mapped out into small polygonal areas by clear lines (fig. 83) called *Cohnheim's fields,* the lines giving the appearance of a meshwork. The lines represent the transverse section of the cementing material between the sarcostyles, which is called *sarcoplasm.*



Fig. 87.—Three muscular fibres running longitudinally, and two bundles of fibres in transverse section, M, from the tongue. The capillaries, C, are injected. × 150. (Klein and Noble Smith.)

(g.) Immediately within the sarcolemma in ordinary muscle or in the centre of the fibre as in the muscle of some insects, are seen clear oval nuclei called *muscle nuclei* or *muscle corpuscle,* surrounding which is a certain amount of granular protoplasm (fig. 85).

The appearances of the muscle fibre when seen under the microscope, cannot be said to be yet thoroughly understood, and have given rise to various theories as to the structure of striped muscle, to several of which it will be as well to allude.

**Muscle Caskets** (Krause) **Theory.**—According to this view a muscle fibre is made up of transverse compartments, bounded laterally by the sarcolemma, and above and below by a fine membrane, called

*Krause's membrane,* which passes from side to side from the sarcolemma across the light stripe. This membrane corresponds to Dobie's line. The transverse compartments are divided longitudinally into smaller ones by lines which correspond with the boundaries of Cohnheim's areas, and each such compartment is termed a *muscle casket.* Within the middle part of the casket is a muscle prism made up of darker rods of contractile material called *muscle rods,* and above and below the muscle prism is a more fluid substance. When the muscle contracts, the fluid substance is pressed more between the muscle rods, causing them to be further away from one another.

**Muscle Reticulum Theory.**—According to the views of certain observers (Retzius, Melland. Marshall, van Gehuchten, and Carnoy), the



Fig. 88



Fig. 88A.

Fig. 88.—Transverse section of one of the truuk muscles of the Hippocampus, stained in chlo of gold. (Rollett.)

Fig. 88A.—Portion of muscle-fibre of Dytiscus, showing network very plainly. One of the tr verse networks is split off, and some of the longitudinal bars are shown broken off. (After Mella

part of fresh muscle which is stained in chloride of gold, is a meshw of fibrils which corresponds to the intracellular meshwork of ordin protoplasmic cells, *i.e.,* the spongioplasm, and is the part which is contractile element in muscle. The meshwork on one level is connec with the meshwork on another level by means of longitudinal fibres, the junction of which the meshes appear more or less knotted (figs. and 88A). The longitudinal fibres of the network are, according to t theory, the chief agents in the active contraction. The transverse me work is more passively elastic, and may be the cause of the speedy rel ation of muscle after contraction has ceased. The material filling the meshwork is a more fluid and non-contractile material.

Rollett has minutely criticised the idea of the gold-staining s stance of the fibre being the contractile portion. His views are

That the muscle-fibre consists of longitudinal fibrillæ ether into *muscle columns,* which are seen in the transverse ohnheim's fields, and that the intercolumnar material is *arcoplasm.* A muscle column consists of segments alternd thick, while in the centre of the thin portion is a dark forming a dot, these dots in Cohnheim's arrangement cor-rause's membrane.

muscle, at low focus, according to this view, the muscle-ear dark and the sarcoplasma appears light, the former are h the granules. At high focus, the reverse is the case, but rcoplasma is now seen in line with two rows of granules

t in gold-stained preparations, the dark row of granules are of the sarcoplasma between the thin segments of the muscle



ram of the appearances in fresh muscle-fibre. A. At low focus (B) the muscle ark and in a line with the granules, sarcoplasm light. At high focus (A) the sarco-uscle columns light, and two rows of granules appear in a line with the sarcoplasm ith the muscle columns. (Marshall, after Rollett.)

ereas the two rows of granules do not correspond with lternate with them, belonging as they do to the muscle not to the sarcoplasm.

as thrown considerable light upon the controversy by hav-observed that when a small portion of the living wing-sects is teased up with needles in a small drop of white of costyles may easily be separated from their surrounding nd may be *actually seen to contract,* whereas the sarcoplasm h property. According to this observer such a sarcostyle ined thus isolated, both living and after treatment with ents, and it shows alternate bright and light stripes, the bisected by a line which corresponds wtih Krause's mem-use's membrane divides the sarcostyle into *sarcomeres,* which he middle the strongly refractive disc-like sarcous element, d below it hyaline material, which is bounded by Krause's The sarcous substance is penetrated by canals, which ex- and downward from the hyaline substance to the middle.

The sarcous substance stains with hæmatoxylin. A light interval
bisect the sarcous substance if the fibre is stretched, which corres
with Hensen's disc.

**Appearances under Polarized Light.**—The appearances
muscle presents when viewed under polarized light vary accordi
the fibres are looked at, as fresh in their own plasma, or as har
fibres prepared and mounted in Canada balsam.

The whole of the living fibre may be doubly refracting, the i
pous part appearing as rows of dots separating transversely the p
pal material of the fibre. Shortly, according to Schäfer, it may b
that the sarcoplasm is singly refracting, and that the sarcostyle
great part doubly refracting. In a fibre which is extended, after
been hardened in alcohol and mounted in Canada balsam, the



Fig. 90.



Fig. 91.

Fig. 90.—Sarcostyles from the wing-muscles of a wasp. A, A'. Sarcostyles showing de
retraction (? contraction). B. A sarcostyle extended with the sarcous elements separated
parts. C. Sarcostyles moderately extended (semidiagrammatic). (E. A. Schäfer.)

Fig. 91.—Diagram of a sarcomere in a moderately extended condition, A. and in a con
condition, B. K, K, Krause's membranes; H, plane of Henson; S.E., poriferous sarcous e
(E. A. Schäfer.)

alternate dark and light bands, the former corresponding to the
intervals as seen in ordinary light, and the latter to the various elen
When the fibre is more contracted the dark line becomes narrowe
the anisotropous intervals broader, but there is no interval of the
on contraction. It appears further that the chromatic portion o
the sarcostyles is anisotropous, and the sarcoplasm and the remain
the fibre is isotropous.

(*b.*) **Heart Muscle.**—The muscular fibres of the heart, unlike
of most of the involuntary muscles, are striated; but although, i
respect, they resemble the skeletal muscles, they have distingu
characteristics of their own. The fibres which lie side by side are
at frequent intervals by short branches (fig. 92). The fibres are s
than those of the ordinary striated muscles, and their striation
marked. No sarcolemma can be discerned. The muscle-corpuscl
situate in the middle of the substance of the fibre; and in corres

these the fibres appear under certain conditions subdivided ıg portions or "cells," the offsets from which are the means by fibres branch and anastomose one with another.

uld be noted, however, that the heart muscular fibres are not nes which branch, since the fibres of the tongue of the frog, where they are attached to the mucous membrane, present iarity; branching muscular fibres have also been noted in the ıd in the facial muscles of other animals. And again, in the ı which two kinds of skeletal muscles occur, red and pale, in uscles the fibres are much less distinctly striated transversely, heir longitudinal striation is more marked than in the pale They are also finer than other skeletal muscles. It should also



Fig. 92.



Fig. 93.

Muscular fibre cells from the heart. (E. A. Schäfer.)
From a preparation of the nerve-termination in the muscular fibres of a snake. *a*, n only broad surfaced. *b*, End plate seen as narrow surface. (Lingard and Klein.)

that in these red muscles the sarcoplasm is much developed, uscle nuclei are very numerous, and may be situated in the the fibre, as is the case with heart muscle fibres.

**l and Nerve Supply.**—The voluntary muscles are freely suph blood-vessels; the capillaries form a network with oblong ound the fibres on the outside of the sarcolemma. No vessels the sarcolemma to enter the interior of the fibre. Nerves also ied freely to muscles; the voluntary muscles receiving them cerebro-spinal system, and the unstriped muscles from the tic or ganglionic system.

erves terminate in the muscular fibre in the following ways:—

**ıstriped** muscle, the nerves first of all form a plexus, called *ıd plexus* (Arnold), corresponding to each group of muscle the plexus is made by the anastomosis of the primitive fibrils is-cylinders. From the ground plexus, branches pass off, and

again anastomosing, form plexuses which correspond to each mu
bundle—*intermediary plexuses*. From these plexuses branches con
ing of primitive fibrils pass in between the individual fibres and a
tomose. These fibrils either send off finer branches, or terminate th
selves in the nuclei of the muscle cells.

(2.) In **striped** muscle the nerves end in *motorial end-plates*, ha
first formed, as in the case of unstriped fibres, ground and intermed



Fig. 94.—Two striped muscle-fibres of the hyoglossus of frog. *a*, Nerve-end plate; *b*, fibres leaving the end-plate; *c*, nerve-fibres, terminating after dividing into branches *d*, a nu
which two nerve-fibres anastomose. × 600. (Arndt.)

plexuses. The fibres are, however, medullated, and when a bran
the intermediary plexus passes to enter a muscle-fibre, its prin
sheath becomes continuous with the sarcolemma, and the axis-cyl
forms a network of its fibrils on the surface of the fibre. This net
lies embedded in a flattened granular mass containing nuclei of se
kinds; this is the *motorial end-plate* (figs. 93 and 94). In batrachi
sides end-plates, there is another way in which the nerves end in the m
fibres, viz., by rounded extremities, to which oblong nuclei are attac

**Development.**—(1.) *Unstriped.*—The cells of unstriped muscle are derived directly from embryonic cells, by an elongation of the cell, and its nucleus; the latter changing from a vesicular to a rod shape.

(2.) *Striped.*—Formerly it was supposed that striated fibres were formed by the coalescence of several cells, but recently it has been proved, that each fibre is formed from a single cell, the process involving an enormous increase in size, a multiplication of the nucleus by fission, and a differentiation of the cell-contents. This view differs but ittle from another, that the muscular fibre is produced, not by multilication of cells, but by arrangement of nuclei in a growing mass of rotoplasm (answering to the cell in the theory just referred to), which ecomes gradually differentiated so as to assume the characters of a fully eveloped muscular fibre.

**Growth of Muscle.**—The growth of muscles, both striated and non-triated, is the result of an increase both in the number and size of the ndividual elements. In the pregnant uterus the fibre-cells may become nlarged to ten times their original length. In involution of the uterus fter parturition the reverse changes occur, accompanied generally by some fatty infiltration of the tissue and degeneration of the fibres.

## IV. Nervous Tissue.

Nervous tissue has usually been described as being composed of two distinct substances, nerve-fibres and nerve-cells. The modern view of the nature of nerve-tissue is, however, that it is composed of one element alone, called the *neuron* or nerve unit, embedded in and supported by a substance called neuroglia. This neuron consists of a cell body, a number of branching processes termed *dendrites*, and a long process running out from it, the *neuraxon*, or *axon*, which becomes eventually a nerve-fibre. The nerve-cell and the nerve-fibre, are really parts of the same anatomical unit, and the nervous centres are made up of these units, arranged in different ways throughout the nervous system (fig 94A). The different neurons do not unite anatomically with each other, but form independent units. A further description of these structures will be given later.

### Nerve-Fibres.

While the nerve-fibre is really to be considered as a process of the erve-cell, it is convenient to describe it separately.

*Varieties.*—Nerve-fibres are of two kinds, *medullated* or *white fibres*, nd *non-medullated* or *gray* fibres.

**Medullated Fibres.**—Each medullated nerve-fibre is made up of the following parts:—(1.) An external sheath called the *primitive* *sheath*, or nucleated sheath of Schwann; (2.) An intermediate or ing substance known as the *medullary* or *myelin sheath*, or whit stance of Schwann; and (3) internally the *axis-cylinder*, primitive axis band, or axial fibre.

Although these parts can be made out in nerves examined time after death, in a recent specimen the contents of the nerve- appear to be homogeneous. But by degrees they undergo changes



Fig. 94A.—Diagram showing the arrangement of the neurons or nerve-units in the ture of the nervous system. *M. Neurons I.* and *II.*, motor neurons; *S. Neurons I.*, sensory neurons; *A. Neuron*, associative or commissural neuron. (Dana.)

show them to be composed of two different materials. The inte central part, occupying the axis of the tube, viz., the axis-cylind comes grayish, while the outer or cortical portion, or white sul of Schwann, becomes opaque and dimly granular or grumous, as i a kind of coagulation. At the same time the fine outline of the ously transparent cylindrical tube is exchanged for a dark doubl tour (fig. 95, B), the outer line being formed by the sheath of th the inner by the margin of curdled or coagulated medullary sub he granular material shortly collects into little masses, which distend rtions of the tubular membrane; while the intermediate spaces col- pse, giving the fibres a varicose, or beaded appearance (fig. 95, C and instead of the previous cylindrical form. The whole contents of nerve-tubules are extremely soft, for when subjected to pressure y readily pass from one part of the tubular sheath to another, and n cause a bulging at the side of the membrane. They also readily pe, on pressure, from the extremities of the tubule, in the form of a ious or granular material.

'he **external nucleated sheath** of Schwann, also called the *neu- ma*, is a pellucid membrane forming the outer investment of the



Fig. 95.



Fig. 96.

;. 95.--Primitive nerve-fibres. A. A perfectly fresh tubule with a single dark outline. B. A or fibre with a double contour from commencing post-mortem change. C. The changes r advanced, producing a varicose or beaded appearance. D. A tubule or fibre, the central f which, in consequence of still further changes, has accumulated in separate portions within eath (Wagner).

g. 96.—Two nerve-fibres of sciatic nerve. A. Node of Ranvier. B. Axis-cylinder. C. Sheath wann, with nuclei. × 800. (Klein and Noble Smith.)

e-fibre. Within this delicate structureless membrane nuclei are at intervals, surrounded by a variable amount of protoplasm. The th is structureless, like the sarcolemma, and the nuclei appear to be in it: together with the protoplasm which surrounds them they are 'elics of embryonic cells, and from their resemblance to the muscle uscles of striated muscle may be termed *nerve-corpuscles*. They are y stained with logwood and other dyes.

'he **medullary or myelin sheath** or white substance of Schwann ie part to which the peculiar opaque white aspect of medullated es is due. The thickness of this layer in nerve-fibres varies considerably, at one time being very well developed, at another forming very thin investment of the axis cylinder. It is a semi-fluid, fatt stance, and in the fibre possesses a double contour. It is said made up of a fine reticulum (Stilling, Klein), in the meshes of w embedded the bright fatty material. It stains well with osmic ac

According to M'Carthy this sheath is composed of small rods ing from the axis-cylinder to the external sheath of Schwann. times the whole space is occupied by them, while at other tim rods appear shortened and compressed laterally into bundles emb in some homogeneous substance. According to oth servers the sheath is made up of segments wh either cylindrical or funnel-shaped (*sections of L mann*). It is not definitely decided that these di exist naturally in the nerve-fibre. In nerves harde alcohol, it is possible to demonstrate a very chromatic recticulum medullary sheath, which is supposed to be of a horny nature, offers much resistance both to chemical reagents and to digestive (*horny reticulum or neuro-keratin network*).


Fig. 97.



Fig. 98.

Fig. 97.—A node of Ranvier in a medullated nerve-fibre, viewed from above. The sheath is interrupted, and the primitive sheath thickened. Copied from Axel Key and × 750. (Klein and Noble Smith.)

Fig. 98.—Gray, pale, or gelatinous nerve-fibres. A. From a branch of the olfactory ne sheep; two dark-bordered or white fibres from the fifth pair are associated with the pale fibres. B. From the sympathetic nerve. × 450. (Max Schultze.)

The **axis-cylinder** consists of a large number of primitive *fi* This is well shown in the cornea, where the axis-cylinders of break up into minute fibrils which form terminal networks, and the spinal cord, where these fibrillæ form a large part of the gray From various considerations, such as its invariable presence a broken continuity in all nerves, though the primitive sheath medullary sheath may be absent, there can be little doubt that th cylinder is the essential part of the fibre, the other parts havi subsidiary function of support and possibly of insulation.

**Nodes of Ranvier.**—At regular intervals in most medullated nerves the nucleated sheath of Schwann possesses annular constrictions; these are called *nodes of Ranvier.* At these points (fig. 97), the continuity of the medullary white substance is interrupted, and the primitive sheath comes into immediate contact with the axis-cylinder. The segment of the fibre between two nodes is termed an *internode,* and the length of the internodes varies in different nerves; their average is said to be 1 mm. There is only one nerve nucleus to each internode. At each node the internodes are united within the external sheath by a band, *constricting band* of Ranvier (fig. 101), and this stains black with silver nitrate; the axis-cylinders at the nodes also are capable of being stained with the same reagent, and so a node of Ranvier when stained with silver nitrate is marked by a black cross.



Fig. 99.—Transverse section of sciatic nerve of the rabbit, hardened in chromic acid and stained with picro-carmine, and showing lamellar sheath, peripheric connective tissue, and intra-fascicular connective tissue. × 550 and reduced one-half. *a*, Perifascicular connective tissue; *b*, lamellar sheath; *c*, intra-fascicular connective tissue; *d*, nerve-fibre cut across, showing nuclei of the same; *e*, axis-cylinder.

*Size.*—The size of the nerve-fibres varies (fig. 99); it is said that the same fibres may not preserve the same diameter through their whole length. The largest fibres are found within the trunks and branches of the spinal nerves, in which the majority measure from 14.4$\mu$ to 19$\mu$ in diameter. In the so-called visceral nerves of the brain and spinal cord medullated nerves are found, the diameter of which varies from 1.8$\mu$ to 3.6$\mu$. In the hypoglossal nerve they are intermediate in size, and generally measure 7.2$\mu$ to 10.8$\mu$.

**Non-medullated Fibres.**—The fibres of the second kind (fig. 98) which are also called *fibres of Remak,* constitute the principal part of the trunk and branches of the *sympathetic nerves,* the whole of the olfactory nerve, and are mingled in various proportions in the cerebro-spinal nerves. They differ from the preceding chiefly in their fineness, being only about ½ to ⅓ as large in their course within the trunks and



Fig. 100.—Transverse section of the sciatic nerve of a cat about × 100.—It consists of bundles (*Funiculi*) of nerve-fibres ensheathed in a fibrous supporting capsule, *epineurium*, A; each bundle has a special sheath (not sufficiently marked out from the *epineurium* in the figure) or *perineurium* B; the nerve-fibres N *f* are separated from one another by *endoneurium*; L, lymph spaces; Ar, artery; V, vein; F, fat. Somewhat diagrammatic. (V. D. Harris.)

branches of the nerves; in the absence of the double contour; in their contents being apparently uniform; and in their having, when in bundles, a yellowish-gray hue instead of the whiteness of the cerebro-spinal



Fig. 101.—Several fibres of a bundle of medullated nerve-fibres acted upon by silver nitrate to show peculiar behavior of nodes of Ranvier, N, toward this reagent. The silver has penetrated at the nodes, and has stained the axis-cylinder, M, for a short distance. S, the white substance. (Klein and Noble Smith.)

nerves. These peculiarities depend on their not possessing the outer layer of medullary substance; their contents being composed exclusively of the axis-cylinder. Yet, since many nerve-fibres may be found which appear intermediate in character between these two kinds, and since the rge fibres, as they approach both their central and their peripheral id, lose their medullary sheath and assume many of the other charac-rs of the fine fibres of the sympathetic system, it is not necessary to ppose that there is any material difference in the two kinds of fibres. he non-medullated fibres frequently branch.

It is worthy of note that in the fœtus, at an early period of develop-ent, all nerve-fibres are non-medullated.

**Nerve-trunks.**—Each nerve-trunk is composed of a variable num-r of different-sized bundles (*funiculi*) of nerve-fibres which have a ecial sheath (*perineurium*). The funiculi are inclosed in a firm fibrous ath (*epineurium*); this sheath also sends in processes of connective tissue which connect the bundles together. In the funiculi between the fibres is a delicate supporting tissue (the *endoneurium*).



Fig. 102.—Small branch of a muscular nerve of the frog, near its termination, showing divisions of the fibres. *a*, into two; *b*, into three. × 350. (Kölliker.)

There are numerous lymph-spaces both beneath the connective tissue investing individual nerve-fibres and also beneath that which surrounds the funiculi.

Every nerve-fibre in its course proceeds uninterruptedly from its rigin in a nerve-centre to near its destination, whether this be the eriphery of the body, another nervous centre, or the same centre whence issued.

Bundles of fibres run together in the nerve-trunk, but merely lie in position to each other; they do not unite: even when they anas-mose, there is no union of fibres, but only an interchange of fibres tween the anastomosing funiculi. Although each nerve-fibre is thus single and undivided through nearly its whole course, yet as *it* proaches the region in which it terminates, individual fibres br*eak* into several subdivisions before their final ending.

**Nerve Collaterals.**—It has been discovered through the researc of Golgi, and confirmed by the further studies of Cajal and other a atomists, that each individual nerve-fibre in the central nervous sy gives off in its course branches which pass out from it at right an for a short distance, and then turn and run in various directions. Th branches are called *collaterals.* They end in fine, brush-like termi tions, known as *end-brushes*, or in little bulbous swellings which co in close contact with some nerve cell (fig. 103).



Fig. 103.—Terminal ramifications of a collateral branch belonging to a fibre of the poste column in lumbar cord of an embryo calf.

These collaterals form a very important part of the nerve-unit. A the point where they are given off, there is usually a little swelling o the neuraxon proper.

The nerve-fibre itself continues on and finally ends in various way according to its function and the organ with which it is connected. I the nerve-centres, that is, in the brain and spinal-cord, the differe nerve-fibres end just as the collaterals do, by splitting up into fi branches which form the *end-brushes.* Collaterals of the nerve-fibres a end-brushes are chiefly found in the nervous centres. The nerve-fib of the peripheral nerves end in the muscles, glands, or special sensor organs, such as the eye and ear. Here, however, some analogy to th end-brush can also be discovered. As the peripheral nerve-fibres ap proach their terminations, they lose their medullary sheath, and consi then merely of an axis-cylinder and primitive sheath. They then lo also the latter, and only the axis-cylinder is left. Finally, the axi cylinder breaks up into its elementary fibrillæ, to end in various ways to be described later.

**Plexuses.**—At certain parts of their course, nerves form *plexuses*, in which they anastomose with each other, as in the case of the brachial and lumbar plexuses. The objects of such interchange of fibres are:—(*a*), to give to each nerve passing off from the plexus a wider connection with the spinal cord than it would have if it proceeded to its destination without such communication with other nerves. Thus, each nerve by the wideness of its connections is less dependent on the integrity of any single portion, whether of nerve-centre or of erve-trunk, from which it may pring. (*b*) Each part supplied rom a plexus has wider relations ith the nerve-centres, and more xtensive sympathies; and, by eans of the same arrangement, roups of muscles may be co-dinated, every member of the roup receiving motor filaments om the same parts of the nerve-ntre. (*c*) Any given part, say limb, is less dependent upon the tegrity of any one nerve.



Fig. 103A.—Nerve-cell with short axis-cylinder from the posterior horn of the lumbar cord of an embryo calf measuring 0.55 cm. (After v. Gehuchten.)

## Nerve-Cells.

The *nerve-cell* is the nodal and nportant part of the neuron, and rom it are given off the dendrites nd axis-cylinder process or neurxon. It consists of a mass of rotoplasm, of varying shape and ize, containing within it a nuleus and nucleolus. All nerve-ells give off a number of procsses which branch out in various directions, dividing and subividing like the branches of a tree, but never anastomosing with each ther or with other cells. These branches are what have already been ferred to as the *dendrites* of the cell. They were formerly called the *proplasmic processes* (figs. 103A, 104). It is thus seen that the neuron or rve-unit consists of a number of subdivisions, namely, the cell-body ith its nucleus and nucleolus, the dendrites, or protoplasmic processes, and the neuraxon or axis-cylinder process, which is continued on to form what is known as a *nerve-fibre*. The nerve-cell is often spoken of as in-



Fig. 104.—Large nerve cells with processes, from the ventral cornua of the cord of man, × On the cell at the right two short processes of the cell-body are present, one or the other of whi may have been an axis-cylinder process (Deiters). A similar process appears also on the cell the left.

cluding the cell-body and its dendrites and the axis-cylinder process fo a short distance. Strictly speaking, however, the name should be ap



Fig. 104A.—Multipolar nerve-cell of the cord of an embryo calf.

plied only to the body of the cell. The nerve-cell is provided with a ver large round nucleus in which one or more nucleoli are visible (fig. 104)

The protoplasm of the cells is shown by various dyes to be striated or reticulated. The network which makes up this cell-body stains more readily with certain dyes and is called *chromophilic*. The material which fills in the spaces between the network of the cell-body is called the *paraplasm*. The cells often contain deposits of yellowish-brown pigment (fig. 105). The nucleus of the cell is sometimes reticulated. Within the nucleus is sometimes seen a nucleolus, and within the nucleolus are bright spots, which are known as nucleolules.

Nerve-cells are not generally present in nerve-trunks, but are found in collections of nervous tissue called *ganglia*. They vary considerably in *shape, size, and structure* in different situations.



Fig. 105.—Cell of the anterior horn of the human spinal-cord, stained by Nissl's Method. (After Edinger.)

*a.* Some nerve-cells are small, generally spherical or ovoid, and have a regular uninterrupted outline. These *single nerve-cells* are most numerous in the sympathetic ganglia; each is inclosed in a nucleated sheath. *b.* Others (fig. 105A) are larger, and have one, two, or more long processes issuing from them, the cells being called respectively *unipolar*, *bipolar*, or *multipolar*, which processes often divide and subdivide, and appear tubular and filled with the same kind of granular material that is contained within the cell. These processes are the dendrites. Generally nly one process from each cell is continuous with a nerve-fibre, the rolongation from the cell by degrees assuming the characters of the nerve-fibre with which it is continuous. This process is the neur In bipolar cells one pole may be continuous with a medullated fibr the other with a non-medullated one, or both poles may pass into of the one or the other kind.

Ganglion-cells are generally inclosed in a transparent membr capsule similar in appearance to the external nucleated sheath of fibres; within this capsule is a layer of small flattened cells.

The process of a nerve-cell or neuraxon which becomes conti with a nerve-fibre is always unbranched as it leaves the cell. It s has all the characters of an axis-cylinder, but soon acquires a med



Fig. 105A.—An isolated sympathetic ganglion-cell of man, showing sheath with nucl lining, B. A. Ganglion-cell, with nucleus and nucleolus. C. Branched process or den Unbranched process or neuraxon. (Key and Retzius.) × 750.

sheath, and then may be termed a nerve-fibre. This continuity of cells and fibres may be readily traced out in the anterior cornua gray matter of the spinal cord. In many large branched nerve distinctly fibrillated appearance is observable; the fibrillæ are p continuous with those of the axis-cylinder of a nerve.

Other points in the structure of nerve-cells will be mentioned the account of the central nervous system.

## Nerve Terminations.

Nerve-fibres terminate peripherally in four different ways: 1, terminal subdivisions which pass in between epithelial cells, a own as inter-epithelial arborizations; 2, by motor-plates which lie in muscles; 3, by special end-organs, connected with the senses of ht, hearing, smell, and taste; and, 4, by various forms of tactile puscles.

1. **The inter-epithelial arborizations** form a most common mode ermination of the sensory nerves of the body. The nerve-fibres pass le surface of the skin or mucous membrane; they then lose their neu-



. 106.—Sensory nerve terminations in stratified pavement epithelium. (After G. Retzius.) Golgi's rapid method.

ma and myeline sheath, the bare axis-cylinder divides and subdi- into minute ramifications which pass among the epithelial cells skin and mucous membrane. In the various glands of the body orm of termination also prevails. The hair-bulbs, the teeth, and ndons of the body are supplied by this same process of terminal zation (figs. 106, 107).

The motor-nerves passing to the muscles end in what are known



107.—Sensory nerve terminations in the epithelium of the mucosa of the inferior vocal in the ciliated epithelium of the subglottic region of the larynx of a cat four weeks old. . Retzius.) Golgi's rapid method. *n*, Nerve-fibres rising from the connective-tissue layer epithelial layer, where they terminate in ramified and free arborizations.

*scle-plates*, the details of whose structure have been already de- d.

The special sensory end-organs will be described later in the r on the Special Senses.

A fourth form of termination consists of corpuscles that are more encapsulated, and these are known as the *corpuscles of Pacini, the corpuscles of Meissner, the tactile corpuscles of Krause, the tactile ues and the corpuscles of Golgi.*

The Pacinian bodies or corpuscles (figs. 108 and 109), named after their discoverer Pacini, also called *corpuscles of Vator*, are little elongated oval bodies, situated on some of the cerebro-spinal and sympathetic nerves, especially the cutaneous nerves of the hands and feet; and on branches of the large sympathetic plexus about the abdominal aorta. They often occur also on the nerves of the mesentery, and are especially well seen even by the naked eye in the mesentery of the cat. They have been observed also in the pancreas, lymphatic glands, and thyroid glands, as well as in the penis of the cat. Each corpuscle is attached by a narrow pedicle to the nerve on which it is situated, and is formed of several concentric layers of fine membrane, consisting of a hyaline ground membrane with connective-tissue fibres, each layer b lined by endothelium (fig. 109); through its pedicle passes a single n fibre, which, after traversing the several concentric layers and immediate spaces, enters a central cavity and, gradually losing its border and becoming smaller, terminates at or near the distal end o cavity, in a knob-like enlargement or in a bifurcation. The enl



Fig. 108.



Fig. 109.

Fig. 108.—Extremities of a nerve of the finger with Pacinian corpuscles attached, abo natural size (adapted from Henle and Kölliker).

Fig. 109.—Pacinian corpuscle of the cat's mesentery. The stalk consists of a nerve-fibr with its thick outer sheath. The peripheral capsules of the Pacinian corpuscle are continuou the outer sheath of the stalk. The intermediary part becomes much narrower near the entra the axis-cylinder into the clear central mass. A hook-shaped termination with the end-bulb seen in the upper part. A blood-vessel (V) enters the Pacinian corpuscle, and approaches th bulb; it possesses a sheath which is the continuation of the peripheral capsules of the Pa corpuscle. × 100. (Klein and Noble Smith.)

mmonly found at the end of the fibre is said by Pacini to re- ganglion corpuscle; but this observation has not been confirmed. cases two nerves have been seen entering one Pacinian body, thers a nerve after passing unaltered through one has been ob-



Summit of a Pacinian corpuscle of the human finger, showing the endothelial membranes lining the capsules. × 220. (Klein and Noble Smith.)

terminate in a second Pacinian corpuscle. The physiological of these bodies is still obscure.

he tactile corpuscles of Meissner (figs. 111, 112) are found in the



Fig. 111.—A touch-corpuscle of Meissner, from the skin of the human hand.

f the skin of the fingers and toes, or among its epithelium. They simple or compound. When simple they are small, slightly flat- nsparent bodies composed of nucleated cells enclosed in a cap- hen compound, the capsule contains several small cells. The es are about $\frac{1}{290}$ of an inch long to $\frac{1}{350}$ of an inch wide. The re penetrates the corpuscle, loses its myeline sheath, and divides and subdivides to form a series of arborizations, more or less disti and destined for the different parts of the corpuscle. The terminal borizations occupy the central part of the corpuscle, and are surroun by a great number of marginal cells. The touch, or tactile corpus



Fig. 112.—Papillæ from the skin of the hand, freed from the cuticle and exhibiting tactile puscles. A. Simple papilla with four nerve-fibres; *a*, tactile corpuscles; *b*. nerves with wi fibres *c* and *e*. B. Papilla treated with acetic acid; *a*. cortical layer with cells and fine elastic ments; *b*, tactile corpuscle with tranverse nuclei; *c*, entering nerve with neurilemma or per rium; *d* and *e*, nerve-fibres winding round the corpuscle. × 350. (Kölliker.)

of Meissner, have been regarded at one time as epithelial, at ano time as nervous, but they are to-day proved to be mesodermic cells, differentiated for the special purpose of the sense of touch (Dejeri



Fig. 113.—End-bulb of Krause. *a*, Medullated nerve-fibre; *b*, capsule of corpuscle.

3. **The Corpuscles of Krause or End-Bulbs.**—These exi great numbers in the conjunctiva, the glans penis, clitoris, lips, and tendon of man; they resemble the corpuscles of Pacini, but much fewer concentric layers to the corpuscle, and contain a relat voluminous central mass composed of polyhedral cells. In man

corpuscles are spherical in shape, and receive many nervous fibres which wind through the corpuscle, and end in the free extremities (fig. 113).

4. **Tactile Menisques.**—In different regions of the skin of man, one meets, in the superficial layers and in the Malpighian layers, nerves which, after having lost their myeline sheath, divide and subdivide to form extremely beautiful arborizations. The branches of these arborizations are flattened down, forming the *tactile menisques*. These menisques, which simulate the form of a leaf, represent a mode of terminal nervous arborization (Ranvier).

5. The corpuscles of Golgi are small terminal placques placed at the union of tendons and muscles, but belonging more properly to the tendon.



Fig. 114.—A termination of a medullated nerve-fibre in tendon, lower half with convoluted medullated nerve-fibre. (Golgi.)

They are fusiform in shape and are flattened upon the surface of the tendon close to its insertion into the muscular fibres. They are composed of a granular substance, enveloped in several concentric hyaline membranes which contain some nuclei. The nerve-fibre passes into this little corpuscle, splitting itself up into fine terminals. The corpuscles of Golgi are believed to be related to the muscular sense (fig. 114).

In addition to the special end-organs, sensory fibres may terminate in **plexuses,** as in the sub-epithelial and intra-epithelial plexus of the cornea.

## The Neuroglia.

The neuroglia, while not a nervous tissue, is closely mingled with it and forms an important constituent of the nervous system. It consists of cells giving off a fine network of richly branching fibres. Neuroglia was at one time considered to be a form of connective tissue, and it is in its functions strictly comparable to the connective tissue which supports the special structures of other organs, like the lungs and kidney (fig. 116). It is, however, derived from the epiblastic cells, *i.e.*, the same cells from which the nerve-tissue proper also develops. In the ult animal the neuroglia-tissue is composed of cells from which are en off immense numbers of fine processes. These extend out in every direction, and intertwine among the nerve-fibres and nerve-cells (fig. 11 The neuroglia-cell differs in size and shape very much in different p



Fig. 115.—Neuroglia cells in the cord of an adult frog. (After Cl. Sala.) *A*, Ependym with their peripheral extremities atrophied and ramified; *B*, *C*, *D*, neuroglia cells in differe grees of emigration and separation from the ependymal canal; their central extremity is phied and much contracted; their peripheral extremity, on the other hand, is greatly ext the ramifications of the latter terminating in conical buttons, *I*, end under the pia mater.



Fig. 116.—Different types of neuroglia cells. (After v. Gehuchten.) *b*, Neuroglia cells white substance, and *c*, of the gray substance of the cord of an embryo calf.

the nervous system in accordance with the arrangement of the nerv-
structures about it. The cell is composed of granular protoplasm,
nd lying in it is a large nucleus, within which is a nucleolus. The
ody of the cell is small in amount and proportion to the nucleus.

Weigert has shown that the processes of the neuroglia-cells branch
d prolong themselves, forming in many places an extremely thick net-
rk. These processes become changed in their chemical and physical
aracters, so that they take a different stain from that of the cell-body
elf, and they thus form a really separate structure, distinct almost
m the mother-cell, just as the muscle tissue is distinct from its origi-
cell-protoplasm, or just as the substance of cartilage is distinct from
original cell-body. While neuroglia-tissue is distributed throughout
whole of the nervous centres, it is especially deposited in certain places.
is found around the central canal of the spinal cord, and upon the
erficial surface of the spinal cord. It was formerly thought to com-
part of the gelatinous substance of Rolando in the spinal cord, but
has been shown by Weigert not to be the case.

In the brain a deposit of neuroglia is found beneath the ependymal
ng of the ventricles, and upon the superficial surface of the gray
ter of the cortex beneath the pia mater. It is distributed to some ex-
in all parts of the brain and spinal cord, but is not found in the
pheral nerves.

# CHAPTER IV.

## THE CHEMICAL COMPOSITION OF THE BODY.

Of the known chemical elements of which about seventy have been isolated no less than seventeen combine, in larger or smaller quantities, to form the chemical basis of the animal body.

The substances which contribute the largest share are the non-metallic elements, *Oxygen*, *Carbon*, *Hydrogen*, and *Nitrogen*—oxygen and carbon making up altogether about 85 per cent of the whole. The most abundant of the metallic elements are *Calcium*, *Sodium*, and *Potassium*.*

Few of the elements, however, appear free or uncombined in the animal body. They are generally united together in variable proportions to form compounds. The only elements which have been found free in the body are oxygen, nitrogen, and hydrogen, the first two in the blood, and hydrogen as well as oxygen and nitrogen in the intestinal canal.

It was formerly thought that the more complex compounds built up by the animal or vegetable *organism* were peculiar and could not be made artificially by chemists, and under this idea they were formed into a distinct class, termed *organic*. This idea has long been given up, but the name is still in use with a different signification. The term is now applied simply to the compounds of the element carbon, irrespective of their origin.

A large number of the animal organic compounds, particularly those of the albuminous group, are characterized by their *complexity*. Many elements enter into their composition, thereby distinguishing them from simple inorganic compounds. Many atoms of the same element occur in each molecule. This latter fact no doubt explains the reason of their *instability*. Another great cause of the instability is the frequent presence of nitrogen, which may be called negative or undecided in its affinities and may be easily separated from combination with other elements.

---

* The following table represents the relative proportion of the various elements.—(Marshall.)

| | | | |
|---|---|---|---|
| *Oxygen* | 72.0 | Fluorine | .08 |
| *Carbon* | 13.5 | *Potassium* | .026 |
| *Hydrogen* | 9.1 | Iron | .01 |
| *Nitrogen* | 2.5 | Magnesium | .0012 |
| *Calcium* | 1.3 | Silicon | .0002 |
| Phosphorus | 1.15 | (Traces of copper, lead, and aluminum) | |
| Sulphur | .1476 | | |
| *Sodium* | .1 | | |
| Chlorine | .085 | | 100 |

Animal tissues, containing as they do these organic nitrogenous comounds, are extremely prone to undergo decomposition. They also conin much *water*, a circumstance very favorable to the breaking up of such ibstances. It is due to this tendency to decomposition that we meet ith so large a number of decomposition products among the chemical bstances forming the basis of the animal body.

The various substances found in the animal organism may be convenitly considered according to the following classification: 1. *Organic*—Nitrogenous and b. Non-Nitrogenous. 2. *Inorganic*.

## Organic Substances.

*Nitrogenous organic bodies* take the chief part in forming the solid tises of the body, and are found also to a considerable extent in the circuing fluids (blood, lymph, chyle), the secretions and excretions. They en contain in addition to carbon, hydrogen, nitrogen, and oxygen, the ments sulphur and phosphorus; but although the composition of most them is approximately known, no general rational formula can at prest be given.

It will be convenient to give an account of the Proteid substances in is Chapter, as these constitute the most important classes of nitrogenus organic substances. According to their chemical composition or surficial differences (*e.g.*, solubility) they are divided into three main asses, viz.: (1) Simple proteids, (2) compound proteids, and (3) albuenoids or proteoids. The other members are *Decomposition products*, the hief of which is Urea, found for the most part in the urine; *Ferments; Pigments;* and other bodies and will be more appropriately treated of later on.

**Proteids** (simple proteids) are also called Albuminous substances. They are the chief of the nitrogenous organic compounds and exist in both plants and animals, one or more of them entering as an essential part into the formation of all living tissue. In the lymph, chyle, and blood, they exist abundantly. Very little is known with any certainty bout their chemical composition. Not a single member of the class has et been synthesized. Their formula is unknown, the chemists who have ttempted to construct it differing very greatly among themselves. In act the very term proteid is an extremely arbitrary one. It simply eans a body which, according to Hoppe-Seyler, contains in its molecule he elements carbon, hydrogen, nitrogen, oxygen, and sulphur, in certain rbitrary but varying amounts, thus—**Carbon**, from 51.5 to 54.5; **Hyrogen**, from 6.9 to 7.3; **Nitrogen**, from 15.2 to 17.; **Oxygen**, from 0.9 to 23.5; **Sulphur**, from .3 to 2. Some proteids contain from .3 to .5 of phosphorus; a small amount of iron is usually associated with proteids, but it is not certain whether or not it is an integral part molecule. Chittenden defines a proteid as a substance which co carbon, hydrogen, oxygen, nitrogen, and sulphur, the nitrogen bein form which serves the physiological needs of the body; and yiel decomposition, a row of crystalline amido-acids and crystalline nit ous bases; nearly all contain 52 per cent of carbon and 16 per cent trogen.

*Properties of Proteids.*—Proteids are for the most part amorpho non-crystallizable. Certain of the vegetable proteids have, it is been crystallized, and according to Hofmeister, egg albumin is als ble of crystallization. They possess as a rule no power (or scarcel of passing through animal membranes. They are soluble, but u alteration in composition in strong acids and alkalies; some are in water, others in neutral saline solutions, some in dilute acids a kalies, none in alcohol or ether. Their solutions exercise a left-l action on polarized light.

The hope that it may be possible in the immediate future to s size proteids is rendered all the weaker because of the extraordina riety of compounds obtained by the decomposition of proteids by chemical methods, the compounds differing according to the meth ployed. In the body it seems clear that living proteid is built up food supplied to it, which necessarily contains proteid derived eithe a vegetable or an animal source; how this process takes place we a unable to say. In the course of later chapters in this book we sh deavor to trace the steps of the breaking up of proteid in the bod we may anticipate by mentioning that it is now generally believe the ultimate products of this decomposition are *urea*, a body the f of which is $CO(NH_2)_2$, *carbon dioxide* and *water*, while the interm substances or by products are probably ammonia compounds (amm carbonate). When proteid material is decomposed by putrefacti the action of chemical reagents, *e.g.*, acids, alkalies, or by heat, bodies are produced, of which amido-acids (acids in which one or n the hydrogen atoms of the radical of the acid are replaced by ami $NH_2$) and bodies belonging to the aromatic or benzene series predon Hence it comes that various theories of the way in which protei built up have arisen. The one which has appeared to have receiv greatest support is that of Latham. This observer has suggeste proteid may be considered as made up of a series of *cyan-alcohols* ( obtained by the union of any aldehyde with hydrocyanic acid) benzene nucleus. Taking ordinary ethyl alcohol, $CH_3CH_2OH$, type, the aldehyde of which is $CH_3CHO$, the corresponding cyan-a would be $CH_3CHCNOH$.

Proteids give certain general chemical reactions. They are a ed in the case of each particular substance. The chief of these are as ws:

i. **Xantho-Proteic Reaction.**—The addition of strong nitric acid, drop by drop, to a solution of any proteid produces a flocculent precipitate which dissolves in an excess of the acid. The solution becomes *canary yellow* in color; when heated, this color is more marked; when cooled, the addition of ammonia in excess changes the color to *orange*. The nitric acid decomposes the proteid to a certain extent and then unites with the decomposition products, forming, among other things, xanthoproteic acid which gives the yellow color. The ammonia unites with this and forms ammonium xanthoproteate which gives the orange color.

ii. **Biuret (Piotrowski's) Reaction.**—With a trace of cupric sulphate and an excess of potassium or sodium hydrate peptones and proteoses give a *rose red*; with ammonia instead of the fixed alkalies, a *blue* coloration. Most proteids, however, give a *violet* (pinkish purple) color; the color is due to reduced copper, cuprous hydroxide being formed along with other compounds of red, yellow, and blue colors.

iii. **Millon's Reaction.**—With Millon's reagent (a solution of mercuric nitrate) proteids give a heavy white precipitate of mercuric albuminate which, with an excess of the reagent, becomes brick red when heated. This test is said to be due to the presence of tyrosin, an aromatic compound in the proteid molecule: it is generally used for solids though it may be used for liquids also. With all substances containing the $C_6H_5OH$ group, *e.g.*, carbolic acid, this reagent gives the same color reaction, though no precipitate is formed, the solution itself becoming red.

iv. **Ammonium Sulphate Reaction.**—They are, with the exception of peptone, entirely precipitated from their solutions by saturation with ammonium sulphate.

ny of the proteids give, in addition, the following tests:

v. With excess of acetic acid, and potassium ferrocyanide, a white precipitate.

vi. With excess of acetic acid and a saturated solution of sodium sulphate, on boiling, a white precipitate. This test is often used to get rid of all traces of proteids, except peptones, from solutions.

vii. Boiled with strong hydrochloric acid, they give a *violet red* coloration.

viii. With cane sugar and strong sulphuric acid, on heating, they give a *purplish* coloration.

ix. They are precipitated on addition of—citric or acetic acid, and picric acid; or citric or acetic acid, and sodium tungstate; or citric or acetic acid, and potassio-mercuric iodide; and with many other metallic salts in solution and by alcohol.

*Varieties.*—Proteids are divided into classes, chiefly on the basis of their solubilities in various reagents. Each class, however, if it contains more than one substance, may often be distinguished by other properties common to its members. Not every one of the proteids enumerated is contained in the animal tissues, some are used as food.

(1.) *Native-Albumins.*—These substances are soluble in water and in saline solutions, and are coagulated, *i.e.*, turned into coagulated proteid, on heating.

(2.) *Albuminates.*—These are soluble in acids or alkalies, insoluble in saline solutions and in water, and not coagulated on heating.

(3.) *Globulins.*—These are soluble in weak saline solutions, in dilute acids and alkalies, and insoluble in water and in strong solutions of neutral salts. They are coagulated on heating.

(4.) *Proteoses.*—These are soluble in water and dilute saline solutions, precipitated by saturation with ammonium sulphate; precipitated but not coagulated by alcohol; precipitated by picric acid: cannot be coagulated by heat.

(5.) *Peptones.*—These are soluble in water, saline solutions, acids, or alkalies; not precipitated on saturation with any neutral salt; they are not coagulated on heating.

(6.) *Coagulated Proteids.*—These are of two classes, either coagulated by (a) action of *ferments*, or (b) *heat.* These are soluble only in gastric or pancreatic fluids, forming peptones, or (with difficulty) in strong acids and alkalies.

**Native-Albumins.**—Of native-albumins there are several varieties: (a) egg-albumin; (b) serum-albumin; (c) lact-albumin, etc.

*Egg Albumin* is contained in the white of the egg.

When in solution in water it is a transparent, frothy, yellowish fluid, neutral or slightly alkaline in reaction. It gives all of the general proteid reactions. It yields 8 per cent of argenin, 22.6 per cent of leucin, and 2 per cent of tyrosin.

At a temperature not exceeding 40° C. it is dried up into a yellowish, transparent, glassy mass, soluble in water. At a temperature of 70° C. it is *coagulated*, *i.e.*, changed into a new substance, *coagulated proteid*, hich is quite insoluble in water. It is coagulated also by the prolonged tion of alcohol; by strong mineral acids, especially by nitric acid, also tannic acid, or carbolic acid; by ethers the coagulum is soluble in stic soda.

It is *precipitated* without coagulation, *i.e.*, forms insoluble compound h the reagent, soluble on removal of the salt by dialysis, with either curic chloride, lead acetate, copper sulphate or silver nitrate, the pretate in each case being soluble in slight excess of the reagent.

With strong nitric acid the albumin is precipitated at the point of act with the acid in the form of a fine white or yellow ring.

*Serum-Albumin* is contained in blood-serum, lymph, serous and synofluids, and in the tissues generally; it may be prepared from serum, r removal of paraglobulin by saturation with magnesium sulphate, by rther saturation with sodium sulphate. It appears in the urine in the lition known as albuminuria.

t gives similar reactions to egg-albumin, but differs from it in not g coagulated by ether. It also differs from egg-albumin in not being y precipitated by hydrochloric acid, and in the precipitate being easily ble in excess of that acid. Serum-albumin, either in the coagulated recipitated form, is more soluble in excess of strong acid than eggmin.

**Albuminates.**—There are two principal substances belonging to this , a, Acid-Albumin; b, Alkali-Albumin.

*Acid-Albumin.*—Acid-albumin is made by adding small quantities of e acid (of which the best is hydrochloric, .4 per cent to 1 per cent), ther egg- or serum-albumin diluted with five to ten times its bulk of r, and keeping the solution at a temperature not higher than 50° C. ot less than half an hour. It may also be made by dissolving coagul native-albumin in strong acid, or by dissolving any of the globulins cids. Solid acid albuminate may be formed by adding strong acid by drop to a strong solution of proteid matter (*e.g.*, undiluted eggmin) until solidification occurs.

t is not coagulated on heating, but on *exactly* neutralizing the solua flocculent precipitate is produced (if it is then heated to 70° C. it coagulate and cannot then be distinguished from any other form of ulated proteids). This may be shown by adding to the acid-albumin tion a little aqueous solution of litmus, and then adding, drop by , a weak solution of caustic potash from a burette until the red r disappears. The precipitate is the derived-albumin. It is soluble ilute acid, dilute alkalies, and dilute solutions of alkaline carbonates. solution of acid-albumin gives the proteid tests. The substance itis coagulated by strong acids, *e.g.*, nitric acid, and by strong alcohol; insoluble in distilled water, and in neutral saline solutions; it is precipitated from its solutions by saturation with sodium chloride. On boiling in lime-water it is partially coagulated, and a further precipitation takes place on addition to the boiled solution of calcium chloride, magnesium sulphate, or sodium chloride.

*Alkali-Albumin.*—If solutions of native-albumin, or coagulated or other proteid, be treated with dilute or strong fixed alkali, alkali-albumin is produced. Solid alkali-albumin (Lieberkühn's jelly) may also be prepared by adding caustic soda or potash, drop by drop, to undiluted egg-albumin, until the whole forms a jelly. This jelly is soluble in an excess of the alkali or in dilute alkalies on boiling. A solution of alkali-albumin gives the tests corresponding to those of acid-albumin. It is not coagulated on heating except after neutralization, as in the case of acid-albumin. It is thrown down on neutralizing its solution, except in the presence of alkaline phosphates, in which case the solution must be distinctly acid before a precipitate falls.

To differentiate between Acid- and Alkali-Albumin, the following method may be adopted. Alkali-albumin is *not* precipitated on exact neutralization, if sodium phosphate has been previously added. Acid-albumin is precipitated on exact neutralization, whether or not sodium phosphate has been previously added.

**Globulins.**—The globulins give the general proteid tests; are insoluble in water; are soluble in dilute saline solutions; are soluble in acids and alkalies forming the corresponding derived-albumin.

Most of them are precipitated from their solutions by saturation with solid sodium chloride, magnesium sulphate, or other neutral salt. They are coagulated, but at different temperatures, on heating.

*Globulin* or *Crystallin.*—It is obtained from the crystalline lens by rubbing it up with powdered glass, extracting with water or with dilute saline solution, and by passing through the extract a stream of carbon iodide. It differs from other globulins in not being precipitated by saturation with sodium chloride.

*Myosin.*—The relation of myosin to living muscle will be considered under the head of the physiology of muscle. It may, however, be prepared from dead muscle by removing all fat, tendon, etc., and washing repeatedly in water until the washing contains no trace of proteids, mincing it and then treating with 10 per cent solution of sodium chloride, or similar solution of ammonium chloride or magnesium sulphate, which will dissolve a large portion into a viscid fluid, which filters with difficulty. If the viscid filtrate be dropped little by little into a large quantity of distilled water, a white flocculent precipitate of myosin will occur.

It is soluble in 10 per cent saline solution; it is coagulated at 60° C into coagulated proteid; it is soluble without change in very dilute acids; it is precipitated by picric acid, the precipitate being redissolved o boiling; it may give a blue color with ozonic ether and tincture of guaiacum.

*Paraglobulin.*—Paraglobulin is contained in plasma and in serum, in serous and synovial fluids, and may be precipitated by saturating plasma after removal of fibrinogen or serum with solid sodium chloride or magnesium sulphate, as a bulky flocculent substance which can be removed by filtration.

It may also be prepared by diluting blood serum with ten volumes of water, and passing carbonic acid gas rapidly through it. The fine precipitate may be collected on a filter, and washed with water containing carbonic acid gas.

It is very soluble in dilute saline solutions (5 to 8 per cent), from which it is precipitated by carbonic acid gas or by dilute acids; its solution is coagulated at 70° C.; even dilute acids and alkalies convert it into acid- or alkali-albumin.

*Fibrinogen.*—Fibrinogen is contained in blood-plasma, from which it may be prepared by addition of sodium chloride to the extent of 13 per cent. It may also be prepared from hydrocele fluid or from other serous transudation by a similar method.

Its general reactions are similar to those of paraglobulin; its solution is coagulated at 52°–55° C. Its characteristic property is that, under certain conditions, it forms fibrin.

*Edestrine.*—Edestrine is a globulin which is found in many edible vegetables, grain, etc. A solution may be prepared by adding hemp seed to a 10 per cent solution of sodium chloride and heating to 50° C.

**Proteoses** are intermediate substances of the digestion of other proteids, the ultimate product of which is peptone. They are produced by the action of the gastric and pancreatic juices and also, slowly, by boiling with dilute acids. The term is a general one, the proteose of albumin being albumose, that of globulin being globulose, etc. They are divided into primary and secondary groups representing the stages of progression from proteids to peptones, so that there may be a primary and a secondary albumose, etc. As digestion is a process of hydration with cleavage, the successive stages present progressively simpler substances. Each group reacts to fewer reagents than the preceding one; *e.g.*, none of the proteoses can be coagulated by boiling, nitric acid will precipitate the primary proteoses but not the secondary ones.

**Peptones.**—Peptone is formed by the action of the digestive ferments, *pepsin*, or *trypsin*, on other proteids, and on gelatin. It is a still simpler form of substance than the proteoses and reacts to still fewer reagents. They will be considered in connection with the physiology of digestion, as will also the intermediate compounds.

**Coagulated proteids** are formed by the action of heat or of ferments

upon other proteids; the temperature necessary to produce coagul
varying in the manner previously indicated. They may also be prod
by the prolonged action of alcohol upon proteids; the process is o
dehydration. They are soluble in strong acids or alkalies; slightly
dilute; are soluble in digestive fluids (gastric and pancreatic). Ar
soluble in water or saline solutions (except fibrin).

*Fibrin.*—Fibrin is formed by the action of fibrin ferment on fibri
and can be obtained as a soft, white, fibrous, and very elastic subs
by whipping blood with a bundle of twigs and washing the adhering
in a stream of water until all the blood-coloring matter is removed
is soluble to a certain extent in strong saline solutions.

**Compound Proteids.**—The compound proteids are compound
simple proteid with some other molecule. According to their che
composition and characteristics they are divided into several classes,

*Chromo-proteids.*—A combination of a proteid substance with
form of pigment. For example, hæmoglobin is a combination of a g
lin with hæmatin, an iron-containing radicle.

*Gluco-proteids.*—A combination of a proteid substance with a c
hydrate radicle. Examples are mucin, which is found in mucous s
tions; and mucoids, which are found in certain tissues, cartilages, e

*Nucleo-proteids.*—A combination of a proteid substance with a n
acid: they are divided into two groups according to the character o
acid. The true nucleo-proteids contain true nucleic acid; the para-nu
proteids, or pseudo-nucleo-proteids contain para-nucleic acid. Both a
and therefore both groups, contain phosphorus; but the true nucleo-pro
yield nuclein (xanthin) bases while the para-nucleo-proteids do not.
are found in the nucleus and protoplasm of every cell, and also in
as caseinogen, and in the yolk of egg, as vitellin.

*Gluco-nucleo-proteids.*—A combination of a nucleo-proteid with a
bohydrate radicle.

**Mucin.**—Mucin is a compound of a globulin with a carbohy
radicle, and is the characteristic component of mucus; it is contained
in fœtal connective tissue, in tendons, and salivary glands. It ca
obtained from mucus by diluting it with water, filtering, treating
insoluble portion with weak caustic alkali, and reprecipitating with a
acid. The mucins derived from different sources probably have diff
compositions.

*Properties.*—Mucin has a ropy consistency. It can be coagulate
insoluble in water, salt solution, and very dilute muriatic acid; is solul
alkalies and concentrated sulphuric acid It gives the proteid rea
with Millon's reagent and with nitric acid. Neither mercuric chl
nor tannic acid gives a precipitate with it (?). It does not dia

When treated with sulphuric acid and then neutralized with solid potassium hydrate, it will give both the Biuret test, denoting the presence of proteid matter, and also Fehling's test, showing the presence of a sugar: the acid splits it into a globulin and a carbohydrate.

**Nucleins.**—The substance known as *nuclein* and found in all cells as well as in milk (caseinogen) and the yolk of egg (vitellin) is really a compound proteid and consists of a whole series of bodies made up of proteid and nucleic acid in varying proportions; there is almost no limit to the possible variations. At one end of the series is *nucleic acid* ($C_{30}$-$H_{15}N_{9}P_{3}O_{17}$, according to Kossel), a body containing the maximum (9 to 11 per cent) of phosphorus, but without any proteid, and found as such only in spermatozoa; in the middle are the *nucleins* proper; and at the other end are the *nucleo-proteids*, containing the minimum of phosphorus. As phosphorus is the characteristic component of nucleic acid, its amount will measure the amount of the acid present in any molecule.

The karyoplasm (nucleus) of every cell is richer in the nucleins, while the cytoplasm (cell body) is richer in the nucleo-proteids which contain a smaller proportion of nucleic acid and, therefore, of phosphorus. The difference in staining power of the nucleus and cell body is thus explained as the relative affinity of these substances for a basic dye is proportional to the amount of nucleic acid they contain. The chemical differences in the action of cytoplasm and karyoplasm toward solvents are due also to the proportion of nucleic acid and proteid which they contain. These differences are quantitative and not qualitative. All of the nucleo-proteids in the cell body are true ones in that they yield nuclein bases.

**Caseinogen.**—Caseinogen, the chief proteid of milk, is strictly a nucleo-albumin and does not yield the nuclein bases; it bears the same relation to casein that fibrinogen does to fibrin. When acted on by rennin it splits into two parts of which one, the smaller, is peptone-like in character. The other, and larger part, is known as soluble casein and does not solidify in the absence of calcium salts; as these are always present in milk, it there unites with them and forms insoluble calcium casein; strictly speaking, therefore, the curd of milk is the calcium compound of soluble casein. Caseinogen may be prepared by adding dilute hydrochloric acid to milk until the mixture is distinctly acid; a flocculent precipitate of caseinogen will be thrown down and may be separated by filtration; the fat which is carried down with this precipitate may be removed by washing with alcohol and then with ether.

Caseinogen may also be prepared by adding to milk an excess of crystallized magnesium sulphate or sodium chloride, either of which salt causes it to separate out.

Caseinogen gives the Biuret and Millon's reactions showing the presence of proteid substances, much the same tests as alkali-albumin. It is soluble in distilled water, dilute or strong alkalies, and sulphuric acid, but insoluble in sodium chloride and .2 per cent of hydrochloric acid.

**Vitellin.**—Vitellin is prepared from yolk of egg by washing with ether until all the yellow matter has been removed. The residue is dissolved in 10 per cent saline solution, filtered, and poured into a large quantity of distilled water. The precipitate which falls is impure vitellin. It gives the same tests as myosin, but is not precipitated on saturation with sodium chloride; it coagulates between 70° and 83° C.

**Albumenoids or Proteoids.**—The albumenoids belong to the simple tissues of the body which are derived from the epiblast and are characterized by a lack of any degree of activity, either physiological or chemical. They are proteid derivatives, nitrogenous bodies derived from proteid matter in the cells, and give crystalline amido-acids and nitrogenous bases on decomposition, but differ from true proteids in not having their nitrogen in a form fit for the physiological needs of the body. In other words, they are not true foods, though gelatin has a certain indirect food value as it protects the body proteids from work in many ways, at times. The albumenoids are soluble in dilute acids or alkalies; they may be distinguished from albumin or globulin by being insoluble in water or salt solution respectively.

**Gelatin.**—Gelatin is contained in the form of *collagen*, its anhydride, in bone (*ossein*), teeth, fibrous connective tissues, tendons, ligaments, etc. It may be obtained by prolonged action of boiling water in a Papin's digester or of dilute acetic acid at a low temperature (15° C.).

*Properties.*—The percentage composition is O, 25.24 per cent, H, 6.56 per cent, N, 17.81 per cent, C, 50 per cent, SO, 25 per cent. It contains more nitrogen and less carbon and sulphur than proteids. It is amorphous, and transparent when dried. It does not dialyse; it is insoluble in cold water, but swells up to about six times its volume: it dissolves readily on the addition of very dilute acids or alkalies. It is soluble in hot water, and forms a jelly on cooling, even when only 1 per cent of gelatin is present; it is also soluble in hot salt solution. Prolonged boiling in dilute acids, or in water alone, destroys this power of forming a jelly on cooling. Its physical properties seem to indicate a closer relationship to albumin than to keratin, but decomposition proves the reverse. On decomposition it gives 2 per cent of leucin and 2.6 per cent of argenin, but no tyrosin; instead there is a large amount of glycocoll (amido-acetic acid or glycin), a crystalline substance.

A fairly strong solution of gelatin—2 per cent to 4 per cent—gives the following reactions:

(A) *With proteid tests:* (i.) *Xanthoproteic test.*—A yellow color but no previous precipitate with nitric acid, becoming darker on the addition of ammonia. (ii.) *Biuret test.*—A blue color. (iii.) *Millon's test*—A pink color but no precipitate. (iv.) *Potassium ferrocyanide and acetic acid.*—No reaction. (v.) Boiling with sodium sulphate and acetic acid. No reaction.

) *Special reactions:* (i.) No precipitate with acetic acid. (ii.) No precipitate with dilute hydrochloric acid. (iii.) A white precipitate with tannic acid, not soluble in excess or in dilute acetic acid. (iv.) No precipitate with mercuric chloride, unlike the reaction with albumose and peptone. (v.) A white precipitate with alcohol. (vi.) A yellowish-white precipitate with picric acid, dissolved on heating and reappearing on cooling.

*llagen* is insoluble in almost everything.

**lastin** is found in elastic tissue, in the ligamenta subflava, ligamen- uchæ, etc. It is insoluble in all ordinary reagents, but swells up in cold and hot water. Is soluble in strong caustic soda slowly, heated. It is precipitated by tannic acid; does not gelatinize. the proteid reactions with strong nitric acid and ammonia, and im- tly with Millon's reagent. On decomposition it gives 4.5 per cent cin, a small amount of argenin, and a mere trace of tyrosin. It is red by boiling with water, then treating with artificial gastric and eatic juices, then boiling again in water, and then extracting with alcohol, and ethers; the remainder is elastin.

**hondrin** is found in the condition of chondrigen in cartilage.

is a mixture of gelatin with a mucin-like substance, and is obtained chondrigen by boiling.

*roperties.*—It is soluble in hot water, and in solutions of neutral *.g.*, sulphate of sodium, in dilute mineral acids, caustic potash, and Insoluble in cold water, alcohol, and ether. It is precipitated its solutions by dilute mineral acids (excess redissolves it), by alum, d acetate, by silver nitrate, and by chlorine water. On boiling with g hydrochloric acid, it yields grape-sugar and certain nitrogenous ances. Prolonged boiling in dilute acids, or in water, destroys its r of forming a jelly on cooling.

**eratin** is obtained from hair, horns, finger nails, etc. Its composi- is very similar to that of ordinary albumin and is approximately ).5, H, 6.5, N, 16.8, S, 4., O, 23.2; the keratins obtained from the us substances are distinct and differ slightly though closely related. hur is the characteristic body found in keratin and occurs as a sul- -containing radicle; a large amount of mercaptan sulphur can usually btained. On decomposition, keratin yields argenin 2.26 per cent, n 10 per cent, and tyrosin 4 per cent.

*roperties.*—Keratin is insoluble in water, salt, sodium carbonate, and e hydrochloric acid; is soluble slowly, when warmed, in caustic pot- nd sulphuric acid; gives Millon's and the xanthoproteic reactions.

*Neurokeratin* is a form of keratin which is found in the white substance of Schwann around the axis-cylinders of nerves. It yields argnin 5 per cent, leucin 10 per cent, and tyrosin 3.5 per cent.

### *Nitrogenous Products of Proteid Decomposition.*

*Amines.*—These are bodies of the ammonia type ($NH_3$) in which one or more of the H atoms of the ammonia are replaced by hydrocarbon radicles; *e.g.*, $NH_2$, $CH_3$ = *methylamine* or mono-methylamine. *Trimethylamine*, $N(CH_3)_3$, often occurs in putrefaction.

*Protamines.*—These are basic proteid bodies which give the Biuret reaction; on decomposition they yield the nitrogenous bases but no leucin or tyrosin. They occur in the decomposition of all proteids and also as primary constituents of cells, especially in spermatozoa. In this group are *argenim*, *lysin*, and *hystidin*.

*Amides.*—These are bodies of the ammonia type ($NH_3$) in which one or more of the H atoms are replaced by organic acid residues (an acid residue = the acid minus hydroxyl; *e.g.*, $CH_3CO$ is the residue of $CH_3$ COOH). Monacetamide = $NH_2$, $CH_3CO$ There are also more complicated amides which are built up from two molecules of ammonia; *e.g.*, *urea* or carbamide, which is formed from carbonic acid and is usually written CO, $NH_2$, $NH_2$.

*Amido-acids.*—These are bodies of the ammonia type ($NH_3$) in which one or more of the H atoms of the ammonia are replaced by organic acid radicles; they may also be regarded as acids in which one or more of the H atoms of the acid radicle are replaced by amidogen, $NH_2$. As the term implies that they are acids, it is necessary that they contain the carboxyl group (COOH) intact. For example, *glycin* (amido-acetic acid) is either $NH_2$, CH, COOH or $CH_2$ ($NH_2$), COOH.

*Nitrogenous* or *Nuclein Bases.*—Also known as *xanthin* or *purin* bases, as all can be derived from the so-called *purin nucleus* $C_5N_4$ by substitution of atoms; the *purin* base, as isolated by Emil Fischer, is $C_5H_4N_4$. The members of this group are very closely related and consist of hypoxanthin ($C_5H_4N_4O$), xanthin ($C_5H_4N_4O_2$), adenin ($C_5H_5N_5$), and guanin ($C_5H_5N_5O$). Besides occurring in ordinary proteid decomposition, they are also always present in all downward chemical changes in the cells. Uric acid ($C_5H_4N_4O_3$), though not a member of the group, is shown to be closely related by studying their chemical composition. By oxidation uric acid yields urea and alloxan ($C_4H_2N_2O_4$); it has been found that in alloxan there is present a radical $C_5N_4$ known as the purin or alloxan-uric nucleus; purin is formed from this radical by the substitution of H atoms. Both uric acid and the nuclein bases can be derived from this base; hypoxanthin is oxypurin, uric acid is try-oxypurin, adenin is amino-oxypurin, etc.

*Protargons.*—These are very complex phosphorus-containing bodies hich are chiefly obtained from nervous tissues. Protargon was at one me considered an entity, but, according to the most recent views, it is erely a mixture of cerebrin and lecithin.

Of the bodies which constitute the above-mentioned groups, only the llowing need be described:

*Glycin, Glycocol, Glycocin,* or *Amido-acetic acid.* } 
$C_2H_5NO_2 = \left( CH_2 < {NH_2 \atop CO\,OH.} \right)$ This substance occurs in the body in combination as in the biliary ds, but is never free. Glycocholic acid, when treated with weak acids, h alkalies, or with baryta water, splits up into cholic acid and glycin, mido-acetic acid. Thus: $C_{26}H_{43}NO_6 + H_2O = C_{26}H_{40}O_5 + C_2H_5NO_2$. cocholic acid + water = cholic acid + glycin, and under similar umstances Taurocholic acid splits up into cholic acid and taurin: $H_{45}O_7NSO_2 + H_2O = C_{26}H_{40}O_5 + C_2H_7NSO_3$, or amido-isethionic l. Taurocholic acid + water = cholic acid and taurin. Glycin occurs in hippuric acid. It can be prepared from gelatin by the action of s or alkalies, and can also be obtained from hippuric acid.

*Sarcosin* or *Methyl amido-acetic acid.* } 
$C_3H_7NO_2 \left( = CH_2 < {NH\,CH_3 \atop CO\,OH.} \right)$ It is a conent of kreatin, and also of caffeine, but has never been found free in human body. It may be obtained from these bodies by boiling with ta water.

*Leucin* or *Amido-caproic acid,* } $C_6H_{13}NO_2$ ($=CH_3.CH_2CH_2CH_2.CH(NH_2)CO\,OH$ rs normally in many of the organs of the body, and is a product of pancreatic digestion of proteids. It is present in the urine in certain ases of the liver in which there is loss of substance, especially in te yellow atrophy. It occurs in circular oily discs or crystallizes in tes, and can be prepared either by boiling horn shavings, or any of gelatins with sulphuric acid, or out of the products of pancreatic estion.

*Guanidin,* 
$CN_3H_5 \left( = CNH < {NH_2 \atop NH_2} \right)$ is a derivative of urea, the atom O being replaced by NH.

*Kreatin,* or *Methyl guanidin acetic acid,* } 
$C_4H_9N_3O_2 \left( = CNH < {NH_2 \atop NCH_3}, CH_2, COOH \right)$ one of the primary products of muscular disintegration. It is always nd in the juice of muscle. It is formed by the action of guanidin on thyl amido-acetic acid. It is generally decomposed in the blood into a and sarcosin, and only appears in the urine as kreatinin. Treated th either sulphuric or hydrochloric acid, it is converted into kreatinin; us—

$$C_4H_9N_3O_2 = C_4H_7N_3O + H_2O.$$

It has been made synthetically by bringing together cyanimid sarcosine.

*Kreatinin*, $C_4 H_7 N_3 O$  $\left(= CNH < {NH - CO \atop N(CH_3)CH_2}\right)$ is present in h urine, derived from dehydration of kreatin. It does not appear present in muscle. It is basic, having lost the COOH group, and as an alkaline body, combining with salts to form double salts, etc. decomposition it yields urea, sarcosin, and methyl guanidin.

*Taurin* or *Amido-isethionic acid*, $C_2 H_7 NSO_3$  $\left(=C_2 H_4 < {SO_3 H \atop NH_2}\right)$ is a const of the bile acid, taurocholic acid, and is found also in traces i muscles and lungs. It has been prepared synthetically from isetl acid. It is a crystalline substance, very stable.

*Hippuric Acid* or *Benzol amido-acetic acid* $C_9 H_9 NO_3 = (C_6 H_5 CONH CH_2 CO$ a normal constituent of human urine, the quantity excreted beir creased by a vegetable diet, and therefore it is present in greater ar in the urine of herbivora. It may be decomposed by acids into g and benzoic acid. It crystallizes in semi-transparent rhombic pr almost insoluble in cold water, soluble in boiling water.

*Tyrosin* or *Para-oxyphenyl-amido-proprionic acid*, $C_9 H_{11} NO_3$  $\left(=C_6 H_4 < {OH \atop C_2H_3, NH_2, CO}\right.$ This is found generally together with leucin, in certain glands, *e.g.*, creas and spleen; and chiefly in the products of pancreatic digesti of the putrefaction of proteids. It is found in the urine in some dis of the liver, especially acute yellow atrophy. It crystallizes in fine dles, which collect into feathery masses. It gives the proteid test Millon's reagent, and heated with strong sulphuric acid, on the adc of ferric chloride gives a violet color.

*Lecithin*, $C_{42} H_{84} PN O_9$



$$\left(\begin{array}{l} =CH_2, O.C_{17} H_{33} CO \\ \;\; | \\ CH, O.C_{15} H_{31} CO \\ \;\; | \\ CH_2, O.PO < {OH \atop O, CH_2, CH_2 N(CH_3)_3 O} \end{array}\right.$$

It is a combination of cholin with glycero-phosphoric acid in whicl two H atoms of the glycerine are replaced by fatty acid radicles. chemical formula varies in accordance with the kind of fatty acid; i above formula one radicle is that of oleic acid and the other that of mitic. In character it is a complex nitrogenous fatty body, conta phosphorus, which has been found mixed with cerebrin and oleo-pho ric acid in the brain. It is also found in blood, bile, and serous f and in larger quantities in nerves, pus, yolk of egg, semen, and blood-corpuscles. On boiling with acids it yields cholin, glycero-phoric acid, and fatty acids.

*Cerebrin*, $C_{17} H_{33} NO_3$, is a light amorphous powder, tasteless and Odorless, which is found in nerves, pus corpuscles, and in the brain. It is a nitrogenous body whose chemical constitution is not known, though the large amount of C which it contains indicates the presence of a fatty acid. It swells up like starch when boiled with water. When decomposed it yields, besides other substances, a sugar (gelactose).

*Uric Acid* or *Tri-oxypurin*, $C_5 H_4 N_4 O_3$, occurs in the urine, sparingly n human urine, abundantly in that of birds and reptiles, where it represents the chief nitrogenous decomposition product. It occurs also in the blood, spleen, liver, and sometimes is the only constituent of urinary calculi. It is probably converted in the blood into urea and carbonic acid. It generally occurs in urine in combination with bases, forming *urates*, and never free unless under abnormal conditions. A deposit of urates may occur when the urine is concentrated or extremely acid, and n febrile disorders.

*Xanthin* or *Di-oxypurin*, $C_5 H_4 N_4 O_2$, has been obtained from the iver, spleen, thymus, muscle, and the blood. It is found in normal urine, and is a constituent of certain rare urinary calculi.

*Hypoxanthin* or *Oxypurin*, $C_5 H_4 N_4 O$, is found in juice of flesh, in he spleen, thymus, and thyroid.

*Guanin* or *Amino-oxypurin*, $C_5 H_5 N_5 O$, has been found in the human iver, spleen, and fæces, but does not occur as a constant product.

*Adenin* or *Amino-purin*, $C_5 H_5 N_5$, is the simplest member of the urin group. It exists abundantly in the liver and urine of leucocyhemic patients.

*Allantoin*, $C_4 H_6 N_4 O_3$, found in the allantoic fluid of the fœtus, and n the urine of animals for a short period after their birth. It is one of he oxidation products of uric acid, which on oxidation gives urea.

In addition to the above compounds and probably related to them, are ertain coloring and excrementitious matters, which are also most likely istinct decomposition compounds.

### *Pigments, Etc.*

***Bilirubin***, $C_{16} H_{18} N_2 O_3$, is the best known of the bile pigments. It best made by extracting inspissated bile or gall stones with water which dissolves the salts, etc.), then with alcohol, which takes out chosterin, fatty and biliary acids. Hydrochloric acid is then added, which ecomposes the lime salt of bilirubin and removes the lime After exacting with alcohol and ether, the residue is dried and finally extracted ith chloroform. It crystallizes of a bluish-red color. It is allied in omposition to hæmatin, as has been described.

*Biliverdin*, $C_{16} H_{18} N_2 O_4$, is made by passing a current of air through an alkaline solution of bilirubin, and by precipitation with hydrochloric acid. It is a green pigment which is an oxidation product of bilirubin.

*Bilifuscin*, $C_9 H_{11} NO_3$, is made by treating gall stones with ether, then with dilute acid, and extracting with absolute alcohol. It is a non-crystallizable brown pigment.

*Biliprasin* is a pigment of a green color, which can be obtained from gall stones, and from bile which has been allowed to decompose.

*Bilihumin* (Staedeler) is a dark brown earthy-looking substance, of which the formula is unknown.

*Urochrome* and *Urobilin* occur in bile and in urine; the latter is probably identical with *stercobilin*, which is found in the fæces. *Uroerythrin* is one of the coloring matters of the urine. It is orange red and contains iron, as is also *Choletelin*.

*Melanin* is a dark brown or black pigment which occurs especially in epidermal tissues, where it is associated with keratin. It is found in the lungs, bronchial glands, hair, choroid, skin of negroes, etc.; also in the urine and in melanotic diseases, *e.g.*, sarcoma. It is a transformation product of proteids, to which it is closely related, and can be made artificially by boiling proteid with sulphuric acid. It contains C, H, O, N, S, and (rarely) Fe.

*Lipochromes* are pigments, usually yellow or yellowish-red, which are associated with fat, being almost always present in adipose tissue. Little is known about them, but they are thought to consist only of C, H, and O.

*Hæmatin* has been fully treated of, p. 169 *et seq.*

*Indican* or *Potassium indoxyl sulphate*, $C_8 H_6 NKSO_4$, is found in the urine and is derived from proteid putrefaction in the intestines. It is colorless.

*Indigo* or *Indigo-blue*, $C_{16} H_{10} N_2 O_2$, is formed from indican. It is usually found free in small amounts in decomposing urine, where it may give a bluish color to the sediment; in very rare instances it makes the whole urine blue.

*Indol*, $C_8 H_7 N$, belongs to the aromatic series and is a product of proteid putrefaction in the intestine. It is found in the fæces and helps cause their odor. When absorbed, it is excreted in the urine as potassium indoxyl sulphate (indican).

*Skatol*, $C_9 H_9 N$, is also one of the aromatic series, a product of proteid putrefaction in the intestines. It is found in the fæces and contributes to their odor. When absorbed, it is excreted in the urine as sodium or potassium skatoxyl sulphate. Both indol and skatol are crystalline and volatile.

### *Nitrogenous Bodies of Uncertain Nature.*

*Ferments* are bodies which possess the property of exciting chemical hanges in matter with which they come in contact. They are at present ivided into two classes, called (1) organized, and (2) unorganized or oluble.

(1.) Of the *organized*, yeast may be taken as an example. Its activty depends upon the vitality of the yeast cell, and disappears as soon as he cell dies, neither can any substance be obtained from the yeast by eans of precipitation with alcohol or in any other way which has the ower of exciting the ordinary change produced by the plant itself. he action of micro-organisms in the alimentary canal and elsewhere is so an example of the same nature.

(2.) *Unorganized or soluble ferments* are those which are found in cretions of glands, or are produced by chemical changes in animal or getable cells in general; when isolated they are colorless, tasteless, morphous solids soluble in water and glycerin, and precipitated from e aqueous solutions by alcohol and acetate of lead. Chemically many f these are said to contain nitrogen.

*Mode of action.*—Without going into the theories of how these unrganized ferments act, it will suffice to mention that:

(1.) Their activity beyond a certain point does not depend upon the tual amount of the ferment present. (2.) That the activity is detroyed by high temperature, and various concentrated chemical regents, but increased by moderate heat, about 40° C., and by weak soluons of either an acid or alkaline fluid. (3.) The ferments themselves ppear to undergo no change in their own composition, and waste very ightly during the process.

The chief classes of unorganized ferments are:—

(1.) *Amylolytic,* which possess the property of converting starch to glucose. They add a molecule of water, and may be called hydrotic. The principal amylolytic ferments are *Ptyalin,* found in the liva, and a ferment, probably distinct, in the pancreatic juice, called *mylopsin.* These both act in an alkaline medium. Amylolytic ferents have been found in the blood and elsewhere.

(2.) *Proteolytic* convert proteids into peptones. The nature of their tion is probably hydrolytic. The proteolytic ferments of the body re called *Pepsin,* from the gastric juice acting in an acid medium. *rypsin,* from the pancreatic juice acting in alkaline, neutral, or id media. The Succus entericus is said to contain a third such ferent.

(3.) *Inversive,* which convert cane sugar or *saccharose* into grape sugar or *glucose*. Such a ferment was found by Claude Bernard in th Succus entericus; and probably exists also in the stomach mucus.

(4.) *Ferments which act upon fats.*—Such a body, called *Steapsin*, h been found in pancreatic juice.

(5.) *Milk-curdling ferments.*—It has been long known that rennet, decoction of the fourth stomach of a calf, in brine, possessed the pow of curdling milk. This power does not depend upon the acidity of th gastric juice, since the curdling will take place in a neutral or alkali medium; neither does it depend upon the *pepsin*, as pure pepsin scarcely curdles milk at all, and the rennet which rapidly curdles milk has n proteolytic action. From this and other evidence it is believed that distinct milk-curdling ferment exists in the stomach. W. Roberts h shown that a similar but distinct ferment exists in pancreatic extract which acts best in an alkaline medium, next best in an acid medium, an worst in a neutral medium. The ferment of rennet acts best in an aci medium, and worst in an alkaline, the reaction ceasing if the alkalinit be more than slight. Also in the Succus entericus.

In addition to the above ferments, many others most likely exist i the body, of which the following are the most important:

(6.) *Fibrin-forming ferment* (Schmidt), (see p. 146 *et seq.*), found in the blood, lymph and chyle.

(7.) *A ferment which converts glycogen into glucose* in the liver; bein therefore an amylolytic ferment.

(8.) *Myosin ferment.*

*Non-nitrogenous organic bodies* consist of

(a) **Oils and Fats**, which are for the most part mixtures of *tri-palmitin*, $C_{51}H_{98}O_6$, *tri-stearin* $C_{57}H_{110}O_6$, and *tri-olein* $C_{57}H_{104}O_6$ in differen proportions. They are formed by the union of three molecules of fatty acid with one molecule of the triatomic alcohol, *glycerin* $C_3H_5(OH)_3$, an are ethereal salts or esters of that alcohol. Palmitic acid is $C_{16}H_{32}O_2$; stearic acid is $C_{18}H_{36}O_2$; oleic acid is $C_{18}H_{34}O_2$. Human fat consists o a mixture of *tri-palmitin*, *tri-stearin*, and *tri-olein*, of which the two forme contribute three-quarters of the whole. Olein is the only liquid constituent. The fat of milk (and butter) is tri-butyrine; butyric acid is $C_4H_8O_2$.

Fats are insoluble in water and in cold alcohol; soluble in hot alcohol ether, and chloroform. Colorless and tasteless; easily decomposed or saponified by alkalies or super-heated steam into glycerin and the fatty acids.

And (b) **Carbohydrates**, which are bodies composed of six or twelv atoms of carbon with hydrogen and oxygen, the two latter elements bein in the proportion to form water. There are three main classes of carbohydrates.

*Monosaccharides* or *Glucoses*, $C_6H_{12}O_6$, containing one molecule of sugar, and comprising Dextrose or Grape Sugar, Lævulose or Fruit Sugar

, etc. *Disaccharides* or *Saccharoses*, $C_{12}H_{22}O_{11}$, containing two les of sugar from which one molecule of water has been with- and comprising Saccharose or Cane Sugar, Lactose, Maltose, etc. *ccharides* or *Amyloses*, $C_6H_{10}O_5$, containing a large but unknown r of molecules of sugar from which water has been withdrawn, and sing Starch, Dextrin, Glycogen, etc.

e *glucoses* may be considered as the aldehydes of mannite, thus:



$$\left.\begin{array}{l} CH_2\,OH \\ (CH\,OH)_4 \\ CH_2\,OH \end{array}\right\} C_6\,H_{14}\,O_6, \quad \left.\begin{array}{l} CH_2\,OH \\ (CH\,OH)_4 \\ CO\,H \end{array}\right\} C_6\,H_{12}\,O_6$$

mannite. glucose.

e *Saccharoses* or *sucroses* are made up of two volumes of glucose one molecule of water.

$$C_6\,H_{12}\,O_6 + C_6\,H_{12}\,O_6 - H_2\,O = C_{12}\,H_{22}\,O_{11}.$$

*perties.*—Monosaccharides are especially soluble and polysaccha- re especially insoluble; monosaccharides and disaccharides do not lored solutions with iodine while polysaccharides do; monosaccha- nd (except saccharose) disaccharides reduce Fehling's solution olysaccharides do not.

these the most important are:

**rch** ($C_6H_{10}O_5$), which is contained in nearly *all plants*, and in *eeds*, *roots*, *stems*, and *some fruits*. It is a soft white powder com- of granules having an organized structure, consisting of *granulose* e in water) contained in a coat of *cellulose* (insoluble in water); pe and size of the granules varying according to the source whence rch has been obtained. It is not crystalline and will not dialyze. soluble in cold water, in alcohol, and in ether; it is soluble after for some time, and may be filtered, in consequence of the swelling the granulose, which bursts the cellulose coat, and becoming free, rely dissolved in water. This solution is a solution of soluble or amydin. It gives a blue coloration with iodine, which disap- n heating and returns on cooling. It is converted into maltose by e, and by boiling with dilute acids into dextrose.

**ycogen,** which is contained in the liver, is also present in all mus- t especially in those of very young animals, in the placenta, in ss corpuscles, and in embryonic tissues. It is sometimes called starch and gives many reactions proper to starch itself. It is soluble in water, and its solution looks opalescent; it gives a port- loration with iodine, which disappears on heating and returns on . It is precipitated by basic lead acetate and is insoluble in abso- cohol and in ether. It exists in the liver during life, but very soon eath is changed into sugar. It may be prepared by grinding mus- h sand till a pasty mass is formed, boiling the mass in water for minutes, filtering, and then precipitating the glycogen from the filtrate by adding a little more than an equal quantity of 95 per cent alcohol. It is converted into sugar by diastase ferments, or into de trose by boiling with dilute acids.

**Dextrin.**—This substance is made in commerce by heating dry pot to-starch to a temperature of 400°. It is also produced in the process the conversion of starch into sugar by diastase, and by the salivary a pancreatic ferments. A yellowish amorphous powder, soluble in wate but insoluble in absolute alcohol and in ether. It corresponds almost e actly in tests with glycogen; but one variety (achroo-dextrin) does n give the port-wine coloration with iodine.

**Cane Sugar,** or **Saccharose,** is contained in the juices of man plants and fruits, and is as a rule extracted from the sugar cane, fro beetroot, or from the maple. It is crystalline and is precipitated fro concentrated solutions by absolute alcohol. It has no power of reducin copper salts on boiling. It is dextro-rotatory. It is not subject t alcoholic fermentation, until by inversion it is converted into glucose, i chars on addition of sulphuric acid, and on heating with potassium o sodium hydrate.

**Lactose** is the chief carbohydrate of milk. It is less soluble i water than glucose; not sweet, and is gritty to the taste; but it is insol ble in absolute alcohol. In digestion it yields a molecule of dextrose an a molecule of galactose. Undergoes alcoholic fermentation with extre difficulty; gives the tests similar to glucose, but less readily. It is de tro-rotatory + 59°.

**Maltose** is produced by the action of the saliva and pancreatic jui on starch. It is also formed by the action of malt upon starch by th ferment diastase, and in the formation of glucose from starch. It is con verted into dextrose by dilute sulphuric acid. It is dextro-rotatory; fe ments with yeast; reduces copper salts, and crystallizes in fine needles.

**Glucose** occurs widely diffused in the vegetable kingdom, in diabe urine, in the blood, etc.; it is usually obtained from grape-juice, hone beet-root or carrots. It really is a mixture of two isomeric bodies, *De trose* or grape-sugar, which turns a ray of polarized light to the rig (+ 56°), and *Lævulose* or fruit-sugar, which turns the ray to the left.

It is easily soluble in water and in alcohol: not so sweet as cane-s gar; the relation of its sweetness to that of cane-sugar is as 3 to 5. It i not so easily charred by strong sulphuric acid as cane-sugar. It is not e tirely soluble in alcohol. It undergoes alcoholic fermentation with yea

**Dextrose** is the characteristic carbohydrate of the blood. It has t power of reducing the salts of silver, bismuth, mercury, and copper, eit to the form of the metal in the first three cases, or to the form of t suboxide in the case with cuprous salts. Upon this property t chief tests for the sugar, *e.g.*, Trommer's and Böttcher's, dep ɜn boiled with potash, glucic and melanic acids are formed, and llowish fluid results (Moore's test). It is oxidized by the action itric acid to saccharic acid. It forms compounds with acids and with sh and lime. It undergoes alcoholic fermentation with yeast, and ic-acid fermentation with bacteria lactis. It forms caramel when ngly heated, and is also charred with strong acids. For the method uantitative estimation, etc.

**Lævulose** is one of the products of the decomposition of cane-sugar means of dilute mineral acids, or by means of the ferment *invertin* in alimentary canal.

It reacts to the same test as glucose, but is non-crystallizable, and is o-rotatory – 1060. It is soluble in water and in alcohol. Its com- nd with lime is solid, whereas that with dextrose is not.

**Galactose** is formed from lactose by the action of dilute mineral s, or inverting ferments; it may also be obtained from cerebrin. It ergoes alcoholic fermentation, and reduces copper salts to the sub- le.

**Inosite.**—Inosite occurs in the heart and voluntary muscles, as well ı beans and other plants. It crystallizes in the form of large color- monoclinic tables, which are soluble in water, but insoluble in alco- or ether. It has the formula of glucose, but is not a sugar. Inosite be detected by evaporating the solution containing it nearly to dry- , and by then adding a small drop of solution of mercuric nitrate, and rward evaporating carefully to dryness, a yellowish-white residue is ined; on further cautiously heating, the yellow changes to a deep -color, which disappears on cooling, but reappears on heating. If inosite be almost pure, its solution may be evaporated nearly to dry- . After the addition of nitric acid, the residue mixed with a little ıonia and calcium chloride, and again evaporated, yields a rose-red ration.

Certain of the **monatomic Fatty Acids** are found in the body, *Formic* $CH_2O_2$, acetic $C_2H_4O_2$, and *propionic* $C_3H_6O_3$, present in ıt, but normally in no other human secretion. They have been found where in diseased conditions. *Butyric acid*, $C_4H_8O_2$, is found in ıt. Various others of these acids have been obtained from blood, cular juice, fæces and urine.

)f the diatomic fatty acids, one acid, *Lactic acid*, $C_3H_6O_3$, exists in a state in muscle plasma, and is increased in quantity by muscular raction, is never contained in healthy blood, and when present in ɔrmal amount seems to produce rheumatism.

**Soaps and Fats.**—The fatty acids in combination with soda or ısh, or similar bases, form *soaps*, and when combined with glycerine n *fats*.

*Other series of hydrocarbons.*—The first series of paraffins consists of saturated hydrocarbons; many other series exist, however, in which th C is unsaturated. Their general formulæ are as follows: $C_nH_{2n}$ $C_nH_{2n-2}$; $C_nH_{2n-4}$; $C_nH_{2n-6}$, and so on.

From each series of hydrocarbons, the corresponding alcohols, acids, aldehydes, and ethers are obtainable. The alcohols derived from serie of *ethene*, $C_2H_4$, are called glycols. But in glycols there are two OH united to the radical instead of one—these are therefore called diatomi alcohols; and similar acids, of two kinds, may be obtained by the sub stitution of one or of two atoms of O for the corresponding $H_2$ or H An example or two may be cited:—

$C_2H_4$, *ethene;* $C_2H_4OH$, *ethene glycol;* $C_2H_4O_3$, *glycolic acid* $C_2H_2O_4$, *oxalic acid;* and $C_3H_6$, *propene;* $C_3H_6OH_2$, *propene glyc* $C_3H_6O_3$, *lactic acid;* $C_3H_4O_4$, *malonic acid.*

The next series of hydrocarbons, $C_nH_{2n-2}$, is represented by $C_2H$ *acetylene;* the next $C_nH_{2n-4}$, by terebinthene, $C_{10}H_{16}$; the next $C_nH_{2n-}$ by benzene, $C_6H_6$.

From these we obtain triatomic alcohols, *e.g.*, *glycerine*, $C_3H_5$ OH tetratomic alcohols, *e.g.*, *erythrite*, $C_4H_6OH_4$, and hexatomic alcohol *e.g.*, *mannite*, $C_6H_8OH_6$; from the last, the carbohydrates are derived.

Of the hydrocarbons, only one is, as we have said, found in the body viz., methane; of the alcohols, cholesterine, $C_{26}H_{43}OH$, a monatomi and glycerine, $C_3H_5OH_3$, a triatomic alcohol.

Of the aldehydes and ketones (analogous products to aldehyde, ob tained from isomeric alcohols), *acetone*, or propyl ketone, is found in blood and in urine, particularly in diabetes. The glucoses are aldehydes of mannite, and the other carbohydrates are derived from that class.

*Fatty Acids.*—Formic, acetic, propionic, butyric, caproic and capryl are all more or less represented in the secretions and tissues of the bod Palmitic and stearic in fats.

AROMATIC SERIES.—The foundation is the benzol ring, $C_6H_6$, and bodies containing this radical are closely related. They differ in rega to the position in the ring of the H atoms which are replaced, as well in regard to the substances which replace them; the derivatives ofte occur in the decomposition of proteids. *Phenol* or oxybenzol ($C_6H_5O$ is found in combination in the urine and fæces. Oxybenzoic acid ($C_6H$ OH, COOH) is a common decomposition product of proteids; one at of H is replaced by hydroxyl and another by carboxyl. The action Millon's reagent is due to the benzol ring. *Benzoic Acid*, $C_7H_6O_2$ is alw found in the urine of herbivora and can be obtained from stale hum urine. It does not exist free elsewhere.

## Inorganic Principles.

The inorganic proximate principles of the human body are numero They are derived, for the most part, directly from food and drink, ss through the system unaltered. Some are, however, decomposed on eir way, as chloride of sodium, of which only four-fifths of the quantity gested are excreted in the same form; and some are newly formed thin the body,—as, for example, a part of the sulphates and carbo-tes, and some of the water.

Much of the inorganic saline matter found in the body is a necessary nstituent of its structure,—as necessary in its way as albumin or any her organic principle; another part is important in regulating or modi-ing various physical processes, as absorption, solution, and the like; hile a part must be reckoned only as matter, which is, so to speak, ccidentally present, whether derived from the food or the tissues, and which will, at the first opportunity, be excreted from the body.

*Gases.*—The gaseous matters found in the body are *Oxygen*, *Hydro-en*, *Nitrogen*, *Carburetted and Sulphuretted hydrogen, and Carbonic acid.* The first three have been referred to. Carburetted and sulphuretted ydrogen are found in the intestinal canal. Carbonic acid is present in he blood and other fluids, and is excreted in large quantities by the ungs, and in very minute amount by the skin. It will be specially con-idered in the chapter on Respiration.

*Water*, the most abundant of the proximate principles, forms a large roportion,—more than two-thirds of the weight of the whole body. Its lative amount in some of the principal solids and fluids of the body is own in the following table (from Robin and Verdeil's):—

QUANTITY OF WATER IN 1000 PARTS.

| | | | |
|---|---|---|---|
| eth | 100 | Bile | 880 |
| nes | 130 | Milk | 887 |
| rtilage | 550 | Pancreatic juice | 900 |
| uscles | 750 | Urine | 936 |
| gament | 768 | Lymph | 960 |
| ain | 789 | Gastric juice | 975 |
| ood | 795 | Perspiration | 986 |
| novia | 805 | Saliva | 995 |

The importance of water as a constituent of the animal body may be sumed from the preceding table, and is shown in a still more striking anner by its withdrawal. If any tissue, as muscle, cartilage, or ten-on, be subjected to heat sufficient to drive off the greater part of its ater, all its characteristic physical properties are destroyed; and what as previously soft, elastic, and flexible becomes hard and brittle, and rny, so as to be scarcely recognizable.

In all the fluids of the body—blood, lymph, etc.,—water acts the rt of a general solvent, and by its means alone circulation of nutrient atter is possible. It is the medium also in which all fluid and solid iments are dissolved before absorption, as well as the means by which all, except gaseous, excretory products are removed. All the vario processes of secretion, transudation, and nutrition depend of necessity o its presence for their performance.

The greater part, by far, of the water present in the body is tak into it as such from without, in the food and drink. A small amoun however, is the result of the chemical union of hydrogen with oxyge the blood and tissue. The total amount taken into the body every d is about 4½ lbs.; while an uncertain quantity (perhaps ½ to ¾ lb.) formed by chemical action within it.—(Dalton.)

The loss of water from the body is intimately connected with exc tion from the lungs, skin, and kidneys, and, to a less extent, from t alimentary canal. The loss from these various organs may be thus portioned (quoted by Dalton from various observers).

| | |
|---|---|
| From the Alimentary canal (fæces) . . . . . . . | 4 per cent |
| “ Lungs . . . . . . . . . . | 20 “ |
| “ Skin (perspiration) . . . . . . . . . | 30 “ |
| “ Kidneys (urine) . . . . . . . . | 46 “ |
| | 100 |

*Sodium and Potassium Chlorides* are present in nearly all parts of t body. The former seems to be especially necessary, judging from t instinctive craving for it on the part of animals in whose food it is de cient, and from the diseased condition which is consequent on its wit drawal. In the blood, the quantity of sodium chloride is greater th that of all its other saline ingredients taken together. In the muscle on the other hand, the quantity of sodium chloride is less than that of t chloride of potassium.

*Calcium Fluoride*, in minute amount, is present in the bones and teet and traces have been found in the blood and some other fluids.

*Calcium, Potassium, Sodium, and Magnesium Phosphates* are found i nearly every tissue and fluid. In some tissues—the bones and teeth—t phosphate of calcium exists in very large amount and is the princip source of that hardness of texture on which the proper performance their functions so much depends. The phosphate of calcium is intimate incorporated with the organic basis or matrix, but it can be removed b acids without destroying the general shape of the bone; and, after t removal of its inorganic salts, a bone is left soft, tough, and flexible.

Potassium and sodium phosphates with the carbonates, maintain t alkalinity of the blood.

*Calcium Carbonate* occurs in bones and teeth, but in much small quantity than the phosphate. It is found also in some other parts. T small concretions of the internal ear (otoliths) are composed of crystalli calcium carbonate, and form the only example of inorganic crystalli matter existing as such in the body.

*tassium and Sodium Carbonates* are found in the blood, and some luids and tissues.

*'assium, Sodium, and Calcium Sulphates* are met with in small t in most of the solids and fluids.

*icon.*—A very minute quantity of silica exists in the urine, and in od. Traces of it have been found also in bones, hair, and some oarts.

*n.*—The especial place of iron is in hæmoglobin, the coloring-mat- the blood, of which a full account will be given with the chemistry blood. Peroxide of iron is found, in very small quantities, in the of bones, muscles, and many tissues, and in lymph and chyle, n of serum, fibrin, bile, milk and other fluids; and a salt of iron, ly a phosphate, exists in the hair, black pigment, and other deeply l epithelial or horny substances.

*uminium, Manganese, Copper, and Lead.*—It seems most likely that human body, copper, manganesium, aluminium, and lead are accidental elements, which, being taken in minute quantities with d, and not excreted at once with the fæces, are absorbed and de- l in some tissue or organ, of which, however, they form no neces- art. In the same manner, arsenic, being absorbed, may be depos- the liver and other parts.

## CHEMICO-PHYSIOLOGICAL TESTS.

*ts for Glucose*—(i.) *Trommer's*—This test depends upon the power possesses of reducing copper salts to their suboxide. It is done in lowing way:—An excess of caustic potash and then a solution of sulphate, drop by drop, are added to the solution containing the n a test-tube, as long as the blue precipitate which forms redis- on shaking the tube. The upper portion of the fluid is then heated, ellowish-brown precipitate of copper suboxide appears. The test so be done by taking only a drop or two of the copper sulphate n.

) *Moore's.*—If a solution of sugar in a test-tube is boiled with potash, a brown coloration appears.

) *Fermentation.*—If a solution of sugar be kept in the warm plate me after the addition of yeast, the sugar is converted into alcohol bon dioxide. ($C_6H_{12}O_6 = 2C_2H_5OH + 2CO_2$.)

) *Böttcher's test.*—A little bismuth oxide or subnitrate and an of caustic potash are added to the solution in a test-tube, and the e is heated; the solution becomes at first gray and then black.

) *Picric acid test.*—To the solution about a fourth of its bulk of acid (saturated solution) and an equal quantity of caustic potash are added, and the solution is boiled; the liquid becomes of a very dee coffee-brown.

(vi.) *Indigo-carmine test.*—Add a solution of indigo carmine to col sugar solution distinctly blue, and add solution of sodium carbonate, a heat. The blue color changes to purple and then to brown and yell but is restored on shaking the solution.

(vii.) *Phenyl hydrazine test.*—A solution of phenyl hydrazine drochloride and sodium acetate is added. Keep in water-bath at boili for some minutes, then cool. Yellow crystals result.

### *Quantitative Estimation of Grape Sugar.*

1. *Fehling's Method.—Solution required* = copper sulphate and c tic soda, with some sodic potassic tartrate of such a strength that 10 of solution contain the amount of cupric oxide which 0.5 grm. of s can reduce to cuprous oxide. (This solution should be freshly pared.) It is made as follows: Take of sulphate of copper, 40 gr neutral tartrate of potash, 160 grms.; caustic soda (sp. gr. 1.12), grms.; add distilled water to 1154.5 c.c. Each 10 c.c. contains .05 of sugar.

*Method.*—Take 10 c.c. of the saccharine solution free from albu and add 90 c.c. of distilled water. Place this in a burette. Put in flask or dish 10 c.c. of the standard solution, and dilute with four ti its bulk of water and boil. Run into it, from burette, some of diluted urine, say 20 c.c., and boil. Allow precipitate to settle, a supernatant fluid is still blue, add, say, 5 c.c. from burette, and again, and so on, till the fluid ceases to have a blue tinge, taking toward the end of the process, to add only a few drops each time. after adding 20 c.c. of diluted urine and boiling, the fluid has decolorized, too much of the solution has been added, and another mation with a second 10 c.c. of standard solution must be made, less than 20 c.c. of the saccharine solution should be added (say 10 in first instance.

When the number of c.c. of diluted urine required to decolorize solution has been determined, that volume contains the amount of s necessary to reduce 10 c.c. of standard solution, *i.e.*, .05 grm. But tenth only of this is the saccharine solution, ∴ one-tenth of numbe c.c. used contains .05 grm. of sugar. From this, the percentage ca easily calculated.

2. *Pavy's Modification of Fehling's Method.*—By Fehling's metho is difficult and tedious to judge of the point of complete reductio the cupric oxide. Dr. Pavy, accordingly, uses a strongly ammoni solution of the above. A certain amount is introduced into a s flask, which is then heated till the vapor of ammonia escapes by a

ow tube. The sugar solution is then allowed to flow from a burette nto the flask until the blueness has disappeared, the solution being ept boiling all the time. The blueness is apt to disappear suddenly, nd care should therefore be taken toward the end of the process.

Calculate as in Fehling's method.

3. *Estimation of sugar by fermentation.*—In the case of saccharine rine, it is allowable as a single test to use the following method:—Take pecific gravity of urine before and after fermentation. Each degree f specific gravity lost by the urine represents one grain of sugar per nce of urine.

4. Sugar may also be estimated by adding yeast to urine, and col- ting the carbon dioxide evolved. The carbon dioxide is a measure the amount of sugar present.

5. The estimation may also be done by the saccharimeter, an instru- nt for the estimation of the degree of polarization which a ray of ht undergoes in passing through a solution of sugar, either to the left to the right.

Urea, CO $(NH_2)_2$. The properties and relations of urea have been ted of at some length in the chapter upon excretion. There re- ns to be described the method of its quantitative estimation in the ne. There are two chief methods, viz.:—

(i.) Hypobromite Method.—One of the forms of apparatus employed this method (Russell and West's) consists of (*a*) a water-bath sup- ted by three iron bands, arranged as a tripod. The bath is provided a cylindrical depression, and with a hole, into which fits a perfo- d india-rubber cork; (*b*) a bulb tube with a constricted neck; (*c*) a s rod provided with an india-rubber band at one extremity; (*d*) a tte of five cubic centimetres capacity; (*e*) a graduated glass collect- tube; (*f*) a spirit lamp; (*g*) a wash-bottle with distilled water; (*h*) obromous solution. The hypobromous solution is made in the fol- ng way: three and a half ounces (100 grm.) of solid caustic soda is olved in nine ounces (250 grm.) of distilled water. When the solu- is cold, seven drachms (25 c.c.) of pure bromine are to be added fully and gradually. The mixture is not to be filtered; it keeps y, and for this reason it should be made shortly before it is required; he solution of caustic soda in water may be made in large quantities does not undergo any change, the bromine in the proper propor- being added at the time it is required for use.

***Method.***—Fill the pipette to the mark on the stem with the urine to xamined; pour the 5 c.c. of urine thus measured out into the bulb; p the bulb tube as far as the constricted neck with distilled water the wash-bottle; insert the glass rod (*c*) in such a way that the a-rubber band at the extremity fills up the constricted neck; the diluted urine should exactly occupy the bulb and neck of the tube, no bubble of air being below the elastic band on the one hand, while on the other the fluid should not rise above the band; in the former case a little more water should be added, in the latter a fresh portion of urine must be used, and the experiment repeated. After adjusting the glass rod, fill up the rest of the bulb tube with hypobromous solution; it will not mix with the urine so long as the rod is in place. The water-bath having been previously erected, and the india-rubber cork fixed firmly into the aperture, the bulb tube is to be thrust from below through the perforation in the cork. The greater part of the tube is then beneath the water-bath, the upper extremity alone being grasped by the cork. Fill the water-bath half full of water, fill also the grad uated glass tube (*e*) with water, and invert it in the bath; in doin this no air must enter the tube, which when inverted should be com pletely filled with water. Now slide the graduated tube toward th orifice of the bulb tube, at the same time withdrawing the glass ro which projects into the bath through the cork. At the instant that th rod is withdrawn the hypobromous solution mixes with the dilut urine, and a decomposition takes place represented thus: $CON_2H_4$ $3NaBrO + 2NaHO = 3\ NaBr + 3H_2O + Na_2CO_3 + N_2$. Urea + sodiu hypobromite + caustic soda = sodium bromide + water + sodium carbo ate + nitrogen. The nitrogen produced is given off as gas, and d places the water in the graduated tube, which is held over it. The is at first evolved briskly, but afterward more slowly; to facilitate evolution, the bulb of the tube may be *slightly warmed* with a spi lamp; as a rule, however, this is unnecessary. After ten minutes, amount of water displaced by the gas should be read off on the tu which is divided into tenths. Each number on the tube represents gram of urea in 100 c.c. of urine. Normal urine should yield roug 1.5–2.5 parts of nitrogen by this test. If 5 c.c. of urine gives off m nitrogen than fills the tube to iii., dilute the urine with an equal volu of water, and take 5 c.c.; read off and multiply by two.*

Several apparatus may be employed instead of the one described, v those of Dupré, Gerard, and Squibb. The chemical reactions in ea case are the same.

(ii.) Liebig's Method.—This method is of greater accuracy. T *solutions required are* (*a*) *baryta mixture* = 2 vols. of saturated soluti of barium nitrate and 1 vol. of saturated solution of barium hydra (*b*) standard solution of *mercuric nitrate,* such that 1 c.c. will precipit .01 grm. of urea, and (*c*) a solution of *carbonate of soda.*

*Method.*—Take 40 c.c. of urine, add 20 c.c. of (*a*), filter off the p cipitate of sulphates and phosphates; keep the filtrate. Fill a buret with (*b*), and take 15 c.c. of the filtrate in a dish. Let (*b*) fall drop by drop into the 15 c.c. in the dish, stirring constantly. Have ready a glass plate with several separate drops of (*c*), and from time to time add a rop of the urine mixture by means of a glass rod to one of the drops. Vhen a yellow color *first* appears in a drop of the NaCO$_3$, the mercuric itrate is just in excess. Read the burette. Calculate as follows:

---

* Several corrections have to be made before the result can be considered accurate; for these the detailed accounts in practical handbooks of Physiolo should be consulted.

1 c.c. of mercuric solution precipitates .01 grm. of urea,∴ the No. of c. used × .01 = amount of urea in 15 c.c. of filtrate, *i.e.*, in 10 c.c. of rine. But 10 c.c. of urine usually contains enough NaCl to act on 2 c.c. mercury solution.* Hence, *when reckoning the number of c.c. of anding mercury solution used, a deduction of 2 c.c. must always be ade.*

### *Quantitative Estimation of Chlorides.*

*Liebig's Method.—The solutions required are a baryta mixture* as ove; and (*b*) standard solution of *mercuric nitrate,* such that 1 c.c. uld be capable of decomposing .01 grm. of sodium chloride.

*Method.*—Take 40 c.c. of urine free from albumen, and add 20 c.c. of ). Filter. Take 15 c.c. of filtrate and place in a flask or dish, adding drop or two of nitric acid. Fill a burette with (*b*), and slowly run ne of this solution into the filtrate in the dish, stirring constantly. *soon as* a distinct cloud appears in the diluted urine, and does not appear on stirring, then all the sodium chloride in urine has been omposed. Read burette. Calculate as follows:

1 c.c. of mercury solution decomposed .01 grm. of NaCl, ∴ the mber of c.c. used × .01 grm. = number of grms. of NaCl in 15 c.c. of rate, *i.e.*, 10 c.c. of urine.

### *Quantitative Estimation of Phosphates.*

*The solutions required are* (*a*) solution of *sodium acetate,* containing grm. of sodium acetate, 100 c.c. of acetic acid, and 900 c.c. of distilled er; (*b*) a solution of *uranium acetate* or *nitrate,* such that 1 c.c. will cipitate .005 grm. of phosphoric acid; and (*c*) a solution of *ferronide of potassium.*

*Method.*—Take 50 c.c. of urine. Add some (*a*) solution, and heat on er-bath to nearly 100° C. Fill burette with (*b*), and allow this to into the urine slowly. Have ready a glass plate with several distinct ps of potassium ferro-cyanide solution. From time to time add a p of urine mixture to one of the drops; and when there FIRST aprs a reddish-brown color in a drop of potassium ferro-cyanide, all the sphates are precipitated. Read burette. Calculate thus:

1 c.c. precipitates .005 grm. of phosphoric acid, ∴ the number of c.c. d × .005 grm. = number of grms. of phosphoric acid *in 50 c.c. of ne.*

---

* This is only a rough estimate.

# CHAPTER V.

## THE BLOOD.

THE blood is the fluid medium by means of which all the tissues of the body are directly or indirectly nourished, oxygen being carried to the lungs and products of absorption from the alimentary canal to the tissues. By means of it also such of the materials which result from the metabolism of the tissues as are of no further use in the economy, are carried to the excretory organs to be removed from the body. Finally, it also acts as a medium of exchange for products of glandular activity between the various tissues themselves (internal secretions), and is a factor in the regulation of body temperature. It is a somewhat viscid fluid, and in man and in all other vertebrate animals with the exception of two,* is red in color. The exact shade of red is variable; that taken from the arteries, from the left side of the heart and from the pulmonary veins is of a bright scarlet hue, that obtained from the systemic veins, from the right side of the heart, and from the pulmonary artery, is of a much darker color, and varies from bluish-red to reddish-black. At first sight, the red color appears to belong to the whole mass of blood, but on further examination this is found not to be the case. In reality blood consists of an almost colorless fluid, called **plasma** or **liquor sanguinis**, in which are suspended numerous minute rounded masses of protoplasm, called **blood corpuscles**, which are, for the most part, colored, and it is to their presence in the fluid that the red color of the blood is due.

Even when examined in very thin layers, blood is *opaque*, on account of the different refractive powers possessed by its two constituents, viz., the plasma and the corpuscles. On treatment with various reagents, such as distilled water and chloroform, it becomes transparent and assumes a lake color (**laky blood**) in consequence of the extrusion of the coloring matter from the red corpuscles into the plasma in which it dissolves. Under normal conditions, the average *specific gravity* in adults is about 1.059, the extreme variations, taken from tables by various authorities, being 1.045 to 1.066. These variations are due principally to changes in the cellular constituents, the fluid portion tending under all conditions to maintain its specific gravity at a constant. A rapid and useful method estimating the specific gravity of blood is the one devised by Hammer-hlag as a modification of Roy's method. Chloroform and benzol, which e respectively heavier and lighter than blood, are mixed in such propor-ons that the resultant specific gravity is about 1.059. A drop of blood then added to this mixture, with which it does not mix at all, but floats s a red bead. Accordingly as it sinks to the bottom or rises to the top, ither chloroform or benzol is added. When the drop remains stationary n the body of the liquid the specific gravity of the mixture will be the same as that of the blood, and can be ascertained by a hydrometer. Since hæmoglobin is the principal constituent of the cellular elements, Hammerschlag and others have based tables of changes of hæmoglobin percentage upon variations of specific gravity. The physiological va-riations may be considerable, depending on the age, sex, time of day, amount of exercise or sleep, etc. The specific gravity is increased by residence in high altitudes. According to Jones it is very high (1.066) in new-born infants, but, after the second week, sinks throughout the first year of life (to 1.048–1.050) and then rises again, becoming almost as high in old age as in infancy. In pathological conditions the variations may be most marked, *e.g.*, the specific gravity is constantly lowered in næmia, while in cachexia resulting from malignant new growths it may ven be reduced to 1.030 (Lyonnet). Various drugs (*e.g.*, diuretics and iaphoretics) also affect the specific gravity. The *reaction* of blood is aintly alkaline and the *taste* saltish. Its *temperature* varies slightly, he average being 37.8° C. (100° F.). The blood stream is warmed by assing through the muscles, nerve centres, and glands, but is somewhat ooled on traversing the capillaries of the skin. Recently drawn blood as a distinct *odor*, which in many cases is characteristic of the animal rom which it has been taken. It may be further developed also by add-g to blood a mixture of equal parts of sulphuric acid and water.

---

* The *amphioxus* and the *leptocephalus*.

**Quantity of the Blood.**—The quantity of blood in any animal nder normal conditions bears a fairly constant relation to the body-eight. The methods employed for estimating it are not so simple as ight at first sight have been thought.

The result of many experiments shows that the quantity of blood in an averages $\frac{1}{12}$ to $\frac{1}{14}$ of the total body-weight.

An estimate of the quantity in man which corresponded nearly with is proportion has been more than once made from the following data: criminal was weighed before and after decapitation; the difference in e weight representing the quantity of blood which escaped. The blood-essels of the head and trunk were then washed out by the injection of ater, until the fluid which escaped had only a pale red or straw color. his fluid was then also weighed; and the amount of blood which it rep-esented was calculated by comparing the proportion of solid matter contained in it with that of the first blood which escaped on decapitation. Two experiments of this kind gave precisely similar results (Weber and Lehmann.)

In the rabbit, according to Vierordt, the distribution of the blood is as follows:

| | |
|---|---|
| Heart, lungs, and large vessels | ¼ |
| Liver | ¼ |
| Resting muscle | ¼ |
| Remaining organs | ¼ |

It should be remembered, in connection with these estimations, that the quantity of the blood must vary very considerably, even in the same animal, with the amount of both the ingesta and egesta of the period immediately preceding the experiment; it has been found, for example, that the quantity of blood obtainable from the body of a fasting animal rarely exceeds a half of that which is present soon after a full meal.

## Coagulation of the Blood.

One of the most characteristic properties which the blood possesses is that of *clotting* or *coagulating*. This phenomenon may be observed under the most favorable conditions in blood which has been drawn into an open vessel. In about two or three minutes, at the ordinary temperature of the air, the surface of the fluid is seen to become semi-solid or *jelly-like*, and this change takes place, in a minute or two afterward, at the sides of the vessel in which it is contained and then extends throughout the entire mass. The time which is occupied in these changes is about eight or nine minutes. The solid mass is of exactly the same volume as the previously liquid blood, and adheres so closely to the sides of the containing vessel that if the latter be inverted none of its contents escape. The solid mass is the *crassamentum* or *clot*. If the clot be watched for a few minutes, drops of a light, straw-colored fluid, the *serum*, may be seen to make their appearance on the surface, and, as they become more and more numerous, to run together, forming a complete superficial stratum above the solid clot. At the same time the fluid begins to transude at the sides and at the under surface of the clot, which in the course of an hour or two floats in the liquid. The first drops of serum appear on the surface about eleven or twelve minutes after the blood has been drawn; and the fluid continues to transude for from thirty-six to forty-eight hours.

The clotting of blood is due to the development in it of a substance called *fibrin*, which appears as a meshwork (fig. 117) of fine fibrils. This meshwork entangles and encloses within itself the blood corpuscles. The first clot formed, therefore, includes the whole of the constituents of the blood in an apparently solid mass, but soon the fibrinous meshwork begins to contract and the serum which does not belong to the clot is squeezed out. When the whole of the serum has transuded, the clot is found to be smaller, but firmer and harder, as it is now made up of fibrin and blood corpuscles only. Thus coagulation rearranges the constituents of the blood; liquid blood being made up of plasma and blood corpuscles, and clotted blood of serum and clot.



Under ordinary circumstances, coagulation occurs before the red corpuscles have had time to subside; and thus, from their being entangled in the meshes of the fibrin, the clot is of a deep red color throughout, probably slightly darker at the most dependent part, from greater accumulation of red corpuscles there than elsewhere. When, however, coagulation is from any cause delayed, as when blood is kept at a temperature slightly above 0° C. (32° F.), or when clotting is naturally slow, as is the case with horse's blood, or, lastly, in certain diseased conditions, particularly in inflammatory states, time is allowed for the colored corpuscles to sink to the bottom of the fluid. When clotting after a time occurs, the upper layers of the blood are free of colored corpuscles and consist chiefly of fibrin. This forms a superficial stratum differing in appearance from the rest of the clot, and is of a grayish-yellow color. This is known as the *buffy coat* or *crusta phlogistica*. The buffy coat, produced in the manner just described, commonly contracts more than the rest of the clot, on account of the absence of colored corpuscles from its meshes, and because contraction is less interfered with by adhesion to the interior of the containing vessel in the vertical than the horizontal direction. A cup-like appearance of the buffy coat results, and the clot is not only buffed but *cupped* on the surface. The buffy coat also contains numerous white blood corpuscles which have emerged from the clot.

*Formation of Fibrin.*—That the clotting of blood is due to the gradual appearance in it of fibrin may be easily demonstrated. For example, if recently drawn blood be whipped with a bundle of twigs, the fibrin may be withdrawn from the blood before it can entangle the blood corpuscles within its meshes, as it adheres to the twigs in stringy threads almost free from corpuscles; the blood from which the fibrin has been withdrawn no longer exhibits the power of spontaneous coagulability (defibrinate blood). Although these facts have long been known, the closely associated problem as to the exact manner in which fibrin is formed is by n means so simple. It will be most convenient to treat of the question st by step.

Fibrin is derived from the plasma.

Pure plasma may be procured by delaying coagulation in blood by keeping it at a temperature slightly above freezing point, until the colored corpuscles have subsided to the bottom of the containing vessel; the bloo of the horse being specially suited for the purposes of this experiment A portion of the colorless supernatant plasma, if decanted into anoth vessel and exposed to the ordinary temperature of the air, will coagulat



FIG. 117.—Reticulum of fibrin, from a drop of human blood, after treatment with rosanilin. (Ranvier.)

just as though it were the entire blood, producing a clot similar in all respects to blood clot, except that it is almost colorless from the absence of red corpuscles If some of the plasma be diluted with twice or three times its bulk of normal saline solution (0.9 per cent), coagulation is delayed, and the stages of the gradual formation of fibrin in it may be conveniently watched. The viscidity which precedes the complete coagulation may be actually seen to be due to the formation of fibrin fibrils—first of all at the edge of the fluid-containing vessel, and then gradually extending throughout the mass.

If a further portion of plasma, diluted or not, be whipped with a bundle of twigs, the fibrin may be obtained as a solid, stringy mass, just in the same way as from the entire blood, and the resulting fluid no longer retains its power of spontaneous coagulability.

It is not indeed necessary that the plasma shall have been obtained by the process of cooling above described, as if it had been separated fro the corpuscles in any other way, *e.g.*, by allowing blood to flow direc he vessels of an animal into a vessel containing a third or a fourth bulk of a saturated solution of a neutral salt (preferably of magne- r sodium sulphate) and mixing carefully, will answer the purpose ist as in the other case, the colored corpuscles will subside, leaving ar superstratum of (salted) plasma. In order that salted plasma agulate, however, it is necessary to get rid of the salts by dialysis, ilute it with several times its bulk of water.

**ieories of Coagulation.**—All present theories of coagulation n that fibrin is formed by a reaction between fibrinogen and throm- the presence of calcium salts. Beyond this, however, there is ifference of opinion. The chief points at issue are: (1) the origin nogen; (2) the nature of thrombin; (3) the nature of the reaction n fibrinogen and thrombin.

Hammarsten has shown that the presence of paraglobulin is not ry for coagulation. Schmidt believes, however, that fibrinogen red from paraglobulin after the blood is shed from the body.

The nature of thrombin is not as yet satisfactorily determined. aring has concluded from experiment that thrombin is a compound ucleo-albumin with the calcium salts of the blood. He has suc- in separating from blood-plasma a nucleo-albumin, which when t into solution with fibrinogen and calcium salts will form fibrin. wever, this nucleo-albumin be brought into contact with either gen alone or calcium salts alone, no clotting will occur.

SCHEMA OF COAGULATION.



elharing further supposes that thrombin is not present in blood ting in the body—at any rate in greater than minimal quantities; it when blood is drawn or for other reasons coagulates in the body, ite blood-cells break down, nucleo-albumin is liberated, and then with the calcium salts to form thrombin.

3. The nature of the reaction between fibrinogen and thrombin not been definitely determined. Hammarsten has proved, however, t the entire fibrinogen molecule does not enter into the reaction to bec fibrin. A part of it splits off and passes into solution as fibrin-glob There is strong evidence that fibrin is a compound of calcium with a tion of the fibrinogen molecule. There are three factors, then, in reaction—fibrinogen, nucleo-albumin, calcium salts. According to P haring, the nucleo-albumin first combines with the calcium salts, for thrombin, which in turn causes a splitting of the fibrinogen molec the calcium remaining with one portion of the molecule to form inso fibrin, the other portion passing into solution as fibrin-globulin. Ac ing to Lilienfeld, the reaction first occurs between the fibrinogen mo and the nucleo-albumin, resulting in a splitting of the former. A p of the fibrinogen molecule then unites with the calcium salts to fibrin.

*Importance of Calcium Salts in Coagulation.*—Blood will nc except in the presence of soluble calcium salts. If potassium dium oxalate be added to blood as it is drawn from the vessels in tities sufficient to precipitate the calcium salts, coagulation will no occur. But blood which has thus lost its coagulability may be m clot upon the addition of soluble calcium salts in proper proportion. fact has been demonstrated not only for blood, but for solutions o fibrinogen.

*Sources of the Fibrin Ferment.*—Fibrin ferment cannot be obtai any appreciable amount from blood which is allowed to flow direc the living vessel into absolute alcohol. It is almost certainly a re the more or less complete disintegration of the colorless corpuscle blood is shed, or of the third corpuscles which will be described la under the name of blood-plates. The proofs of this may be summarized as follows: (1) That all strongly coagulable fluids c these corpuscles almost in direct proportion to their coagulabilit That clots formed on foreign bodies, such as needles projecting in interior or lumen of living blood-vessels, are preceded by an aggre of colorless corpuscles; (3) That plasma in which these corpuscle pen to be scanty, clots feebly. (4) That if horse's blood be kept cold, so that the corpuscles subside, it will be found that the lowes [illegible] removed, clot [illegible] whereas the colorless p [illegible] the colorless corpuscl [illegible] in the cold will not [illegible] from colorless cor [illegible] all the fibrin factors [illegible] coagulating blood ol ler the microscope the fibrin fibrils are seen to start from the colorless puscles.

**Conditions affecting Coagulation.**—The coagulation of the blood **hastened** by the following means:—

1. *Moderate warmth*,—from about 37.8–49° C. (100° to 120° F.).

2. *Rest* is favorable to the coagulation of blood. Blood, of which the hole mass is kept in uniform motion, as when a closed vessel completely led with it is constantly moved, coagulates slowy and imperfectly.

3. *Contact with foreign matter*, and especially multiplication of the ints of contact. Thus, as before mentioned, fibrin may be quickly tained from liquid blood by stirring it with a bundle of small twigs; even in the living body the blood will coagulate upon rough bodies jecting into the vessels.

4. *Injury to the walls of the blood-vessels.*

5. *The addition of less than twice the bulk of water.*

The blood last drawn is said, from being more watery, to coagulate re quickly than the first.

The coagulation of the blood is **retarded, suspended,** or **prevented** the following means:—

1. *Cold* retards coagulation; and so long as blood is kept at a tempera- e of 0° C. (32° F.), it will not coagulate at all. Freezing the blood, course, prevents its coagulation; yet it will coagulate, though not ly, if thawed after being frozen; and it will do so even after it has n frozen for several months. A *higher temperature than* 49° *C.* (120° retards coagulation by coagulating the albumen of the serum, and a higher one above 56° C. (133° F.) prevents it altogether.

2. The addition of *water in greater proportions than twice the bulk* of blood, also the addition of *syrup, glycerine*, and *other viscid substances.*

3. *Contact with living tissues*, and especially with the interior of a ng blood-vessel. Blood may be kept fluid in a tortoise's heart after oval from the body for several days, and if the jugular vein of a horse igatured in two places so as to include within it blood, and then be oved from the body and placed in a cool place, the contained blood remain unclotted for hours or even days.

4. *The addition of neutral salts* in the proportion of 2 or 3 per cent upward. When added in large proportion most of these saline sub- ces prevent coagulation altogether. Coagulation, however, ensues on tion with water. The time during which blood can be thus preserved liquid state and coagulated by the addition of water, is quite indefi-

5. In *inflammatory states of the system* the blood coagulates more ly although more firmly.

The coagulation of the blood is prevented altogether *by the addition* *of strong acids and caustic alkalies*, and also by the addition of a 0.1-p cent solution of *potassium oxalate*, which precipitates the soluble calci salt present in the blood, in the form of insoluble calcium oxalate. Wi out the presence of soluble calcium salt, blood does not coagulate.

7. The *injection of commercial peptone* containing albumoses, *or of rious digestive ferments, e.g.*, trypsin or pepsin, into the vessels of animal appears to prevent or stay coagulation of its blood if it be kill soon after. The *secretion of the mouth of the leech*, and possibly the bl squeezed out of its body when full, also prevents the clotting if added blood.

It is stated that the reason why *blood does not coagulate in the liv vessels* is, that the factors which are necessary for the formation of fib are not in the exact state required for its production, and that at any m the fibrin ferment is not formed or is not free in the living blood, that it is produced (or set free) at the moment of coagulation by the di integration of the colorless corpuscles. This supposition is certai plausible, and, if it be a true one, it must be assumed either that the ing blood-vessels exert a restraining influence upon the disintegration the corpuscles in sufficient numbers to form a clot, or that they rend inert any small amount of fibrin ferment which may have been set f by the disintegration of a few corpuscles; as it is certain, firstly, th white corpuscles must from time to time disintegrate in the blood with causing it to clot; and, secondly, that shed and defibrinated blood whi contains blood corpuscles, broken down and disintegrated, will not, wh injected into the vessels of an animal, under ordinary conditions, prod clotting. There must be a distinct difference, therefore, if only in amou between the normal disintegration of a few colorless corpuscles in the li ing uninjured blood-vessels and the abnormal disintegration of a lar number which occurs whenever the blood is shed without suitable prec tion, or when coagulation is unrestrained by the neighborhood of the li ing uninjured blood-vessels.

## The Blood Corpuscles.

There are two principal forms of corpuscles, the *red* and the *white*, as they are now frequently named, the *colored* and the *colorless*. In t moist state, the red corpuscles form about 45 per cent by weight of t whole mass of the blood. The proportion of colorless corpuscles is o as 1 to 500 or 600 of the colored.

**Red or Colored Corpuscles.**—Human red blood corpuscles circular, biconcave discs with rounded edges, from $\frac{1}{3000}$ to $\frac{1}{4000}$ inch diameter $7\,\mu$ to $8\,\mu$, and $\frac{1}{12000}$ inch or about $2\,\mu$ in thickness, becom flat or convex on addition of water. When viewed singly they appear a pale yellowish tinge; the deep red color which they give to the bl ng observable in them only when they are seen *en masse*. They are posed of a colorless, structureless, and transparent filmy framework or *oma*, infiltrated in all parts by a red coloring matter termed *hæmoglo-* The *stroma* is tough and elastic, so that, as the corpuscles circu- e, they admit of elongation and other changes of form, in adaptation the vessels, yet recover their natural shape as soon as they escape m compression. The term cell, in the sense of a bag or sac, although metimes applied, is scarcely applicable to the red blood corpuscle; it ust be considered, if not solid throughout, yet as having no such marked ifference of consistence in different parts as to justify the notion of its eing a membranous sac with fluid contents. The stroma exists in all arts of its substance, and the coloring matter uniformly pervades this; ut at the same time it is probable that the consistence of the peripheral art of the protoplasm is more solid than that of the more central mass.

The adult red corpuscles have no nuclei, although, in their usual state, he unequal refraction of transmitted light gives the appearance of a central spot, brighter or darker than the border, according as it is viewed or out of focus. Their specific gravity is about 1,088.

The corpuscles of all mammals with the exception of the camelidæ are ircular and biconcave. In the camelidæ they are oval and biconvex. n all mammals the corpuscles are non-nucleated, and in all other verte- rates (birds, reptiles, amphibia, and fish) the corpuscles are oval bicon- ex and nucleated (fig. 121).

*Numbers.*—The normal number of red blood cells in a cubic millimetre human blood was estimated by Welcker, in 1854, to be 5,000,000 in en and 4,500,000 in women. Recent observations, however, have own that these estimates are a little low, especially in men, and the erage number has been placed by different authorities at various points etween 5,000,000 and 5,500,000, or even 6,000,000. Still the original umbers as given by Welcker are accepted at the present day as being fficiently accurate for ordinary purposes. It has also been shown that ere are many distinct physiological variations in the number, depending the time of day, digestion, sex, and pregnancy. The number of red lls usually diminishes in the course of each day, while the leucocytes rease in number. It has been suggested that this is due to the influ- ce of digestion and exercise.

It has generally been found that within half an hour or an hour after full meal the number of red cells begins to diminish, and that this keeps for from two to four hours, when it is followed by a gradual rise to normal. The usual fall is 250,000 to 750,000 per cubic millimetre. ese results are most marked after a largely fluid meal, and are prob- ly due to dilution of the blood as a result of the absorption of fluids. animals the number of red cells is increased by fasting, but in man the results are variable, some authorities claiming an increase and others a decrease. In childhood there is no difference between the sexes in the number of red cells per cubic millimetre, but after menstruation is established, a relative anæmia develops in women. Welcker's original estimate placed the difference at 500,000 per cubic millimetre, and these figures have been generally accepted, though one observer (Leichtenstein) asserted that the difference was 1,000,000. Recent investigations, however, seem to show that Welcker's estimate is a little too great.

Menstruation in healthy subjects has practically no effect, as not mor than 100–200 cubic centimetres are lost normally in the course of sever days. Under such circumstances the normal diminution of red cells pe cubic millimetre is probably less than 150,000, though one observer (Sf meni) has placed the loss at about 225,000. Some observers, on th other hand, claim an increase. The leucocytes are slightly increas during menstruation. It is now the general opinion that pregnancy h little or no effect on the number of red cells, and that any anæmia mu be due to abnormal conditions. Post-partum anæmia should not l longer than two weeks.

*Varieties.*—The red corpuscles are not all alike. In almost eve specimen of blood a certain number of corpuscles smaller than the n may be observed. They are termed ***microcytes***, or ***hæmatoblasts***, and probably immature corpuscles.



Fig. 118.



Fig. 119.

Fig. 118.—Red corpuscles in rouleaux. The rounded corpuscles are white or uncolored.
Fig. 119.—Corpuscles of the frog. The central mass consists of nucleated colored corpuscles. other corpuscles are two varieties of the colorless form.

A peculiar property of the red corpuscles, which is exaggerated inflammatory blood, may be here again noticed, *i.e.*, their great tende to adhere together in rolls or columns (rouleaux), like piles of co These rolls quickly fasten together by their ends, and cluster; so t when the blood is spread out thinly on a glass, they form a kind of irr ıetwork, with crowds of corpuscles at the several points corresponding ı the knots of the net (fig. 118). Hence the clot formed in such a layer of blood looks mottled with blotches of pink upon a white nd, and in a larger quantity of blood such masses help, by the conent rapid subsidence of the corpuscles, in the formation of the buffy already referred to.

**ction of Reagents.**—Considerable light has been thrown on the physical and ical constitution of red blood-cells by studying the effects produced by mechanieans and by various reagents: the following is a brief summary of these reac-

—

**ressure.**—If the red blood-cells of a frog or man are gently squeezed, they it a wrinkling of the surface, which clearly indicates that there is a superficial le partly differentiated from the softer mass within; again, if a needle be rapidıwn across a drop of blood, several corpuscles will be found cut in two, but s not accompanied by any escape of cell contents; the two halves, on the conassume a rounded form, proving clearly that the corpuscles are not mere ıranous sacs with fluid contents like fat-cells.

**luids.** i. *Water.*—When water is added gradually to frog's blood, the oval haped corpuscles become spherical, and gradually discharge their hæmoglobin, , transparent stroma being left behind; human red blood cells change from a idal to a spheroidal form, and discharge their cell contents, becoming quite parent and all but invisible (ghost corpuscles).

i. *Strong saline solution* produces no appreciable effect on the red blood-cells of og. In the red blood-cells of man the discoid shape is exchanged for a spherie, with spinous projections, like a horse chestnut (crenation) 120). Their original forms can be at once restored by the use bonic acid.



Fig. 120. Effect of saline solution.

ii. *Acetic acid* (dilute) causes the nucleus of the red blood-cells e frog to become more clearly defined; if the action is prod, the nucleus becomes strongly granulated, and all the coloratter seems to be concentrated in it, the surrounding cell-substance and e of the cell becoming almost invisible; after a time the cells lose their color ether. The cells in the figure (fig. 122) represent the successive stages of the e. A similar loss of color occurs in the red cells of human blood, which, howfrom the absence of nuclei, seem to disappear entirely.

. *Alkalies* cause the red blood-cells to swell and finally to disappear.

. *Chloroform* added to the red blood-cells of the frog causes them to part with hæmoglobin; the stroma of the cells becomes gradually broken up. A similar is produced on the human red blood-cell.

i. *Tannin.*—When a 2-per-cent fresh solution of tannic acid is applied to frog's it causes the appearance of a sharply defined little knob, projecting from the urface (*Roberts' macula*): the coloring matter becomes at the same time concenin the nucleus, which grows more distinct (fig. 123). A somewhat similar is produced on the human red blood corpuscle.

ii. *Magenta,* when applied to the red blood-cells of the frog, produces a similar nob or knobs, at the same time staining the nucleus and causing the discharge hæmoglobin. The first effect of the magenta is to cause the discharge of the globin, then the nucleus becomes suddenly stained, and lastly a finely granuıtter issues through the wall of the corpuscle, becoming stained by the magenta, and a *macula* is formed at the point of escape. A similar macula is produced the human red blood-cells.

viii. *Boric acid.*—A 2-per-cent solution applied to nucleated red blood-cells (fro will cause the concentration of all the coloring matter in the nucleus; the colored body thus formed gradually quits its central position, and comes to be partly, sometimes entirely, protruded from the surface of the now colorless cell (fig. 124). Th



Fig. 121.—The above illustration is somewhat altered from a drawing by Gulliver, in the Proce Zool. Society, and exhibits the typical characters of the red blood-cells in the main divisions of Vertebrata. The fractions are those of an inch, and represent the average diameter. In the case the oval cells, only the long diameter is here given. It is remarkable, that although the size of the blood-cells varies so much in the different classes of the vertebrate kingdom, that of the white puscles remains comparatively uniform, and thus they are, in some animals, much greater, in oth much less than the red corpuscle existing side by side with them.

result of this experiment led Brücke to distinguish the colored contents of the (*zooid*) from its colorless stroma (*æcoid*). When applied to the non-nucleated ma malian corpuscle its effect merely resembles that of other dilute acids.

ix. *Ammonia.*—Its effects seem to vary according to the degree of concentrati Sometimes the outline of the corpuscles becomes distinctly crenated; at other ti the effect resembles that of boric acid, while in other cases the edges of the c puscles begin to break up.

**Gases.** *Carbonic acid.*—If the red blood-cells of a frog be first exposed to action of water-vapor (which renders their outer pellicle more readily permeabl gases), and then acted on by carbonic acid, the nuclei immediately become clea defined and strongly granulated: when air or oxygen is admitted the original appearance is at once restored. The upper and lower cell in fig. 125 show the effect of carbonic acid; the middle one the effect of the re-admission of air. These effects can be reproduced five or six times in succession. If, however, the action of the carbonic acid be much prolonged, the granulation of the nucleus becomes permanent; it appears to depend on a coagulation of the paraglobulin.


Fig. 122.
Effect of acetic acid.


Fig. 123.
Effect of tannin.


Fig. 124.
Effect of boric acid.


Fig. 125.
Effect of gases.


Fig. 126.
Effect of heat.

**Heat.**—The effect of heat up to 50°—60° C. (120—140° F.) is to cause the formation of a number of bud-like processes (fig. 126).

**Electricity** causes the red blood corpuscles to become crenated, and at length mulberry-like. Finally they recover their round form and become quite pale.

**The Colorless Corpuscles.**—In human blood the white or colorless corpuscles or *leucocytes* are nearly spherical masses of granular protoplasm without cell wall. In all cases one or more nuclei exist in each corpuscle. The corpuscles vary considerably in size, but average $\frac{1}{2500}$ of an inch ($10\,\mu$) in diameter.

There was for some time a general acceptance of the original estimate of Welcker that there were about 13,500 leucocytes in each cubic millimetre of normal human blood. But improved methods and appliances, especially the introduction of the Thoma hæmatocytometer, soon proved that these figures were too high, and that the number was about 7,500. The latter estimate is upheld by the results of the most recent investigations, Rieder placing the number in adults at 7,680, Limbeck at 8,000 to 9,000, and Reinert at 5,125 at 6 A.M and 8,262 at 4 P.M. Therefore the proportion of white to red cells (counting 5,000,000 of the latter to each cubic millimetre) is about 1 to 666. This proportion is in no way to be regarded as a constant one in health, as considerable variations occur frequently, even in the course of the same day. The chief physiological variations are those due to the influence of digestion, of pregnancy, and of infancy.

After a full meal the white cells in a healthy adult are increased in number about one-third (Rieder), the increase beginning within an hour, attaining a maximum in three or four hours, and then gradually falling to normal. This process is frequently modified by the character of the food, the greatest increase occurring with an exclusively meat diet, while a purely vegetarian diet has usually no effect. The increase is also more marked in children, and especially in infants. The essential factor is probably the absorption of albuminous matter in considerable quantities;

this causes proliferation of leucocytes in the adenoid tissue of the gastro-intestinal tract. In pregnancy there is often a moderate increase in the number of white cells during the latter months. This does not begin until after the third month, and is most marked and constant in primiparæ. After parturition the leucocytes gradually diminish under normal conditions, and usually reach the normal within a fortnight. The essential factor is probably the general stimulation in the maternal organism. It is well established that the white cells are very numerous in the new-born, though different observers have made very conflicting estimates. Still all agree that there is a very rapid decrease in their numbers during the first few days, and that this is followed by a less marked increase, which continues for many months. According to Rieder, who is perhaps the most reliable, there are at birth from 14,200 to 27,400 per cubic millimetre, on the second to fourth day from 8,700 to 12,400, and after the fourth day from 12,400 to 14,800.

*Varieties.*—The colorless corpuscles present greater diversities of form than the red ones. They are usually classified according to their reaction to staining agents, or to the presence or absence of granules in their cytoplasm. Kanthack and Hardy offer the following classification, based upon both phenomena:

| | |
|---|---|
| *A.* Oxyphil (staining with acid dyes). | 1. Finely granular.<br>2. Coarsely granular. |
| *B.* Basophil (staining with basic dyes).— | 1. Finely granular. |
| *C.* Hyaline ........................ | 1. Small.<br>2. Large. |

The *finely granular oxyphil* constitutes 75 per cent of all leucocytes. It has an average diameter of 10 µ, and possesses *phagocytic* action to a marked degree—that is, it possesses the power of ingesting foreign particles. Its nucleus consists of several lobes united by threads of chromatin. This cell was formerly known under the term *neutrophil*, because of its supposed reaction to neutral dyes.

The *coarsely granular* form or *eosinophil* constitutes only 2 per cent o the leucocytes. It has a diameter of 12 µ and a reniform nucleus.

The *basophil* cell is rarely found in normal blood. It may occur occasionally during periods of digestion. It is a small, spherical cell, wit an irregular nucleus and a diameter of 7 µ.

The *small hyaline* leucocyte is also called a *lymphocyte*, because of th large numbers found in adenoid tissue, and is supposed to be an immature form. The nucleus is proportionately large, and is surrounded b but little protoplasm in which no granules can be detected. The cell i about the size of a red blood-cell, and constitutes from 10 to 20 per cen of all leucocytes.

The *large hyaline* or *myelocyte* varies in diameter from 8.5 to 10 µ Its nucleus is spherical or reniform, and is surrounded by more proto m than in the case of the lymphocyte. It forms about 10 per cent of leucocytes.

**Amœboid Movement.**—The remarkable property of the colorless scles of spontaneously changing their shape was first demonstrated harton Jones in the blood of the skate. If a drop of blood be ex-



127.—(*a*) Red blood-corpuscle for comparison; (*b*) small hyaline cell or lymphocyte; (*c*) large cell or myelocyte; (*d*) fine granular oxyphil; (*e*) coarse granular oxyphil or eosinophil; phil. (F. C. Busch.)

d with a high power of the microscope, under conditions by which f moisture is prevented, and at the same time the temperature is ained at about that of the body, 37° C. (98.5° F.), the colorless cles will be observed slowly to alter their shapes, and to send out ses at various parts of their circumference. The amœboid move- which can be demonstrated in human colorless blood corpuscles, most conveniently studied in the newt's blood. The processes are sent out from the corpuscle are either lengthened or withdrawn.



28.—Human colorless blood-corpuscle, showing its successive changes of outline within ten minutes when kept moist on a warm stage. (Schofield.)

thened, the protoplasm of the whole corpuscle flows as it were into cess, and the corpuscle changes its position; if withdrawn, protru- another process at a different point of the circumference speedily s. The change of position of the corpuscle can also take place by ng movement of the whole mass, and in this case the locomotion is ratively rapid. The activity both in the processes of change of and also of change in position is much more marked in some corpuscles than in others. Klein states that in the newt's blood the changes are especially noticeable in a variety of the colorless corpuscle, which consists of a mass of finely granular protoplasm with jagged outline, and contains three or four nuclei, or in large irregular masses of protoplasm containing from five to twenty nuclei.

**Action of reagents upon the colorless corpuscles.**—*Feeding the corpuscles.*—If some fine pigment granules, *e.g.*, powdered vermilion, be added to a fluid containing colorless blood corpuscles, on a glass slide, these will be observed, under the microscope, to take up the pigment. In some cases colorless corpuscles have been seen with fragments of colored ones thus embedded in their substance. They have also been seen, in diseased states, to contain micro-organisms, *e.g.*, bacilli, and according to some pathologists are capable of destroying them (phagocytosis). They may too take up other foreign matter or even other colorless corpuscles. This property of the colorless corpuscles is especially interesting as helping still further to connect them with the lowest forms of animal life, and to connect both with the organized cells of which the higher animals are composed.

The property which the colorless corpuscles possess of passing through the walls of the blood-vessels will be described later on.

**The Blood-Plates.**—A third variety of corpuscle is found in the blood, and is known as the *blood-plate*. It is circular or elliptical in shape, of nearly homogeneous structure, and varies in size from .5–5.5$\mu$. Hence it is smaller than the red cell. It is altogether probable that they are derived chiefly from the red cells, being extruded therefrom in the form of masses or chains of globular material. Chemically they contain a nucleo-proteid, and it is supposed that they take part in the phenomenon of coagulation. According to Deetjen and others, amœboid movement has been demonstrated in these bodies.

**Enumeration of the blood corpuscles.**—Several methods are employed for counting the blood corpuscles, most of them depending upon the same principle, *i.e.*, the dilution of a minute volume of blood with a given volume of a colorless solution similar in specific gravity to blood plasma, so that the size and shape of the corpuscles are altered as little as possible. A minute quantity of the well-mixed solution is then taken, examined under the microscope, either in a flattened capillary tube (Malassez) or in a cell (Hayem & Nachet, Gowers) of known capacity, and the number of corpuscles in a measured length of the tube, or in a given area of the cell is counted. The length of the tube and the area of the cell are ascertained by means of a micrometer scale in the microscope ocular; or in the case of Gowers' modification, by the division of the cell area into squares of known size. Having ascertained the number of corpuscles in the diluted blood, it is easy to find out the number in a given volume of normal blood.

The hæmacytometer, which is most used at the present time, is known as the Thoma-Zeiss hæmacytometer. It consists of a carefully graduated pipette, in which the dilution of the blood is done; this is so formed that the capillary stem has a capacity equalling one-hundredth of the ball above it. If the blood is drawn up in the capillary tube to the line marked 1 (fig. 130) the saline solution may afterward be drawn up the stem to the line 101; in this way we have 101 parts of which the rms 1. As the contents of the stem can be displaced unmixed we shall have ixture the proper dilution. The blood and the saline solution are well mixed ng the pipette, in the ball of which is contained a small glass bead for the of aiding the mixing. The other part of the instrument consists of a glass . 129) upon which is mounted a covered disc, *m*, accurately ruled so as to ne square millimetre divided into 400 squares of one-twentieth of a milli- ch. The micrometer thus made is surrounded by another annular cell, *c*,



Fig. 129.—Thoma-Zeiss Hæmacytometer.

as such a height as to make the cell project exactly one-tenth millimetre n. If a drop of the diluted blood be placed upon *m*, and *c* be covered with ly flat cover-glass, the volume of the diluted blood above each of the squares icrometer, *i.e.*, above each $\frac{1}{400}$, will be $\frac{1}{4000}$ of a cubic millimetre. An aver- n or more squares are then taken, and this number multiplied by 4000 × 100 number of corpuscles in a cubic millimetre of undiluted A separate pipette is also used for making dilutions for f leucocytes. In this, the dilution is made of one part and ten parts of diluting fluid. Acetic acid, 0.2 of one is usually employed for this purpose.



Fig. 130.—Thoma-Zeiss Hæmacytometer.

## CHEMICAL COMPOSITION OF THE BLOOD.

ore considering the chemical composition of the s a whole, it will be convenient to take in order position of the various chief factors which have t out in the table on p. 143, into which the blood separated, viz.:—(1.) *The Plasma*; (2.) *The* (3.) *The Corpuscles*; (4.) *The Fibrin.*

**The Plasma.**—The Plasma, or liquid part of od, in which the corpuscles float, may be ob- free from colored corpuscles in either of the ways ed below.

it are the fibrin factors, inasmuch as when ex- to the ordinary temperature of the air it under- agulation and splits up into fibrin and serum. rs from the serum in containing fibrinogen, but arance and in reaction it closely resembles that ts alkalinity, however, is greater than that of um obtained from it. It may be freed from white corpuscles by n at a temperature below 5° C. (41° F.) or by the centrifugal e.

chief methods of obtaining plasma free from corpuscles may be here epit- (1) by cold; the temperature should be about 0° C. and may be two or three degrees higher, but not lower. (2) The addition of neutral salts, in certain proportions, either solid or in solution, *e.g.*, of sodium sulphate, if solid 1 part to 12 parts of blood; if a saturated solution 1 part to 6 parts of blood; of magnesium sulphate, of a 23%, or if saturated solution 1 part to 4 of blood. (3) A third way is to mix frog's blood with an equal part of a 5% solution of cane sugar, and to get rid of the corpuscles by filtration; or (4) by the injection of commercial peptone into the veins of certain mammals, previous to bleeding them to death, allowing the corpuscles to subside, and afterward subjecting the supernatant plasma to the action of a centrifugal machine; by the rapid rotation of which (fig. 131) the whole of the remaining solid particles, if any, is driven to the outer end of the test-tubes in which the plasma is placed.



Fig. 131.—Plan and section of centrifugal machine. A, An iron socket secured to top of table B; C, a steel spindle carrying the turntable D, and turning freely in A; E, a flange, round turntable D; F F, shallow grooves on face of D, in which the test tubes are fixed by clamps G G; H, a pulley fixed to end of spindle C, and turned by the cord K; I I are two-guide pulleys for cord K. (Gamgee.)

**Composition of Plasma.**

| | | |
|---|---|---|
| Water | | 902.9 |
| Solids— | | |
| 1. Proteids— | | |
| Fibrinogen<br>Paraglobulin<br>Serum-albumin | 82.89 | |
| 2. Extractives | 5.66 | |
| 3. Inorganic salts | 8.50 | |
| | | 97.1 |
| | | 1000. |

a. *Water.*—The water of the plasma varies in amount according to he amount of food, drink, and exercise, and with many other circumstances.

b. *Proteids.*—*α*. Fibrinogen, the substance to which plasma owes its property of spontaneous coagulability. It belongs to the class of proteids called globulins. It is precipitated from plasma with serum-globulin by saturation with $MgSO_4$ and NaCl, but is not soluble in water. It can be distinguished from serum-globulin by a number of special reactions; (1) its coagulation temperature is lower, 52° to 55° C. (2) It is completely precipitated by saturation with NaCl as well as with $MgSO_4$. (3) It gives rise to an insoluble proteid, *fibrin*. It is, however, probable that the substance found in plasma and called fibrinogen is not a simple proteid, but a mixture or loose chemical combination of two or more proteids.

*β*. Serum globulin or paraglobulin closely resembles fibrinogen in its reactions and is regarded by many authorities as the mother substance of fibrinogen. It is completely precipitated by $MgSO_4$; incompletely, by NaCl and coagulates at a temperature of 75° C. It is likewise insoluble in water.

*γ*. Serum albumin. This is the proteid which predominates in plasma. It has been shown by Halliburton to be a compound body to which he has given the name of *serine*, being made up of three proteids having different coagulating temperatures, *α*, at 73° C., *β*, at 77° C., and *γ*, at 84° C. It may be considered as the chief source of proteid nourishment of the tissues and originates from the digested proteids of foods; but as it is known that the final product of digestion is a group of different proteids, namely, peptones and proteoses, it is probable that during the act of absorption into the blood these undergo a further change into serine. It is readily obtained in crystalline form; is insoluble in $MgSO_4$ and NaCl solutions, and coagulates in neutral or acid solutions at 70° to 75° C.

(c) *Extractives.*—*a*. Non-nitrogenous organic substances.

Glycogen. Traces in fresh blood. May be derived from the disintegration of the white blood corpuscles.

Animal gum, $(C_6H_{10}O_5)_n$. Converted by boiling with dilute mineral acids into a substance resembling sugar, which reduces Fehling's solution, but which is not fermentable or rotatory to polarized light.

Dextrose. Constant even in starving animals.

Fats (palmatin, stearin, olein, etc.) present in small, variable quantities; increased after meals.

Cholesterin, combined with fatty acids.

Lipochrome, a yellow pigment of this group for which the name serum lutein has been suggested, and to which plasma owes its yellow tint.

Lactic acid, also found, but its presence during life is not certain.

β. Non-proteid nitrogenous substances. Of these the most imp tant are, urea, creatin, creatinin, and uric acid.

Four ferments are also found in blood; first a diastatic ferment c verting amyloids into sugars; second, a glycolytic ferment causing a appearance of sugar; third, a fat-splitting ferment (lipase) and, fou fibrin ferment, thrombin, or its precursor, prothrombin.

(d) *Inorganic Substances.*—In 1,000 parts of plasma there are:—

| | |
|---|---|
| Chlorine | 3.536 |
| Sulphuric acid | .129 |
| Phosphoric acid | .145 |
| Potassium | .314 |
| Sodium | 3.410 |
| Phosphate of lime | .298 |
| Phosphate of magnesia | .218 |
| Oxygen | .455 |
| | 8.505 |

It is to be noted that the sodium salts predominate.

(2.) **The Serum.**—The serum is the liquid part of the blood the plasma which remains after the separation of the clot. It is a t parent, yellowish, alkaline fluid, with a specific gravity of from 10 1032 In the usual mode of coagulation, part of the serum remai the clot, and the rest, squeezed from the clot by its contraction around it Since the contraction of the clot may continue for thirt or more hours, the quantity of serum in the blood cannot be even rou estimated till this period has elapsed. There is nearly as much weight, of serum as there is clot in coagulated blood.

Serum may be obtained from blood corpuscles by allowing bloo clot in large test-tubes, and subjecting the test-tubes to the action of a trifugal machine (fig. 131) for some time.

(3) **The Corpuscles.**—a. *Colored.*—Analysis of a thousand of moist blood corpuscles shows the following result:—

| | | |
|---|---|---|
| Water | | 688 |
| Solids— | | |
| Organic | 303.88 | 312=1000 |
| Mineral | 8.12 | |

Of the solids the most important is *Hæmoglobin*, the substanc which the blood owes its color. It constitutes, as will be seen from appended table, more than 90 per cent of the organic matter of the puscles. Besides hæmoglobin there are proteid and fatty matters former chiefly consisting of *globulins*, and the latter of *cholesterin lecithin.*

In 1000 parts *organic* matter are found:—

| | |
|---|---|
| Hæmoglobin | 905.4 |
| Proteids | 86.7 |
| Fats | 7.9=1000 |

Of the *inorganic salts* of the corpuscles, with the iron omitted—
In 1000 parts corpuscles (Schmidt) are found:—

| | |
|---|---|
| *Potassium Chloride* | 3.679 |
| *Potassium Phosphate* | 2.343 |
| Potassium sulphate | .132 |
| Sodium | .633 |
| Calcium | .094 |
| Magnesium | .060 |
| Soda | .341=7.282 |

The properties of hæmoglobin will be considered in relation to the Gases of the blood.

b. *Colorless.*—In consequence of the difficulty of obtaining colorless corpuscles in sufficient number to make an analysis, little is accurately known of their chemical composition; in all probability, however, the protoplasm of the corpuscles is made up of proteid matter, and the nucleus of *nuclein*, a nitrogenous phosphorus-containing body akin to *mucin*, capable of resisting the action of the gastric juice. The proteid matter is made up probably of one or more nucleo-albumins, and of one or more globulins with a small amount of serum albumin. There are also present *lecithin*, a fatty body containing phosphorus, *fatty granules* staining black with osmic acid, *cholesterin*, a monatomic alcohol, *glycogen*, and *salts* of sodium, potassium, calcium, and magnesium, of which the phosphate of potassium is in greatest amount.

(4.) **Fibrin.**—The part played by fibrin in the formation of a clot and its tests have been already described, and it is only necessary to consider here its general properties. It is a stringy elastic substance belonging to the proteid class of bodies. Blood contains only .2 per cent of fibrin. It can be converted by the gastric or pancreatic juice into peptone. It possesses the power of liberating the oxygen from solutions of hydric peroxide $H_2O_2$ or ozonic ether. This may be shown by dipping a few shreds of fibrin in tincture of guaiacum, and then immersing them in a solution of hydric peroxide. The fibrin becomes of a bluish color, from its having liberated from the solution oxygen, which oxidizes the resin of guaiacum contained in the tincture, and thus produces the coloration.

## The Gases of the Blood.

The gases contained in the blood are carbonic acid, oxygen, and nitrogen, 100 volumes of blood containing from 50 to 60 volumes of these gases collectively.

Arterial blood contains relatively more oxygen and less carbonic acid than venous. But the absolute quantity of carbonic acid is in both kinds of blood greater than that of the oxygen.

| | *Oxygen.* | *Carbonic Acid.* | |
|---|---|---|---|
| **Arterial Blood** . . . | 20 vol. per cent. | 39 vol. per cent. | 1 |
| **Venous** " . <br>(from muscles at rest). | 8 to 12 " " | 46 " " | 1 |

*The Extraction of the Gases from the Blood.*—As the ordinary air-pump
sufficiently powerful for the purpose, the extraction of the gases from t
is accomplished by means of a mercurial air-pump, of which there are n
rieties, those of Ludwig, Alvergnidt, Geissler, and Sprengel being the chi
principle of action in all is much the same. Ludwig's pump, which may
as a type, is represented in fig. 132. It co
two fixed glass globes, *C* and *F*, the upper
municating by means of the stopcock *D*, and
india-rubber tube with another glass globe,
can be raised or lowered by means of a pulle
communicates by means of a stopcock, *B*, an
glass tube, *A*, with a gas receiver (not repre
the figure), *A*, dipping into a bowl of mer
that the gas may be received over mercu
lower globe, *F*, communicates with *C* by
the stopcock, *E*, with *I* in which the bloo
tained by the stopcock, *G*, and with a mova
globe, *M*, similar to *L*, by means of the stop
and the stout india-rubber tube, *K*



Fig. 132.—Ludwig's Mercurial Pump.

In order to work the pump, *L* and *M*
with mercury, the blood from which the
to be extracted is placed in the bulb *I*, the st
*H*, *E*, *D*, and *B*, being open, and *G* close
raised by means of the pulley until *F* is ful
cury, and the air is driven out. *E* is the
and *L* is raised so that *C* becomes full of
and the air driven off. *B* is then closed.
ing *L* the mercury runs into it from *C*, and a
is established in *C*. On opening *E* and low
a vacuum is similarly established in *F*; if
opened, the blood in *I* will enter ebullition,
gases will pass off into *F* and *C*, and on raisi
then *L*, the stopcock *B* being opened, the gas
through *A*, and is received into the receiver
cury. By repeating the experiment seve
the whole of the gases of the specimen
is obtained, and may be estimated.

A. **The Oxygen of the Blood.**—It has been found that
small proportion of the oxygen which can be obtained, by the ai
mercurial pump from the blood, exists in a state of simple solutio
plasma (about 5 per cent). If the gas were in simple soluti
amount of oxygen in any given quantity of blood, exposed to an
atmosphere, ought to vary with the amount of oxygen contained
atmosphere. Since, speaking generally, the amount of any gas a

a liquid such as plasma would depend upon the proportion of the gas the atmosphere to which the liquid is exposed—if the proportion is eat, the absorption will be great; if small, the absorption will be simi- rly small. The absorption continues until the proportions of the gas in e liquid and in the atmosphere are equal. Other things will, of course, fluence the absorption, such as the *nature of the gas* employed, the *na- re of the liquid* and the *temperature*, but *cæteris paribus*, the amount of gas which a liquid absorbs depends upon the proportion—the so-called **artial pressure**—of the gas in the atmosphere to which the liquid is bjected. And conversely, if a liquid containing a gas in solution be posed to an atmosphere containing none of the gas, the gas will be ven up to the atmosphere until the amount in the liquid and in the mosphere becomes equal. This condition is called a *condition of equal nsions.*

The condition may be understood by a simple illustration. A large amount of rbonic acid gas is dissolved in a bottle of water by exposing the liquid to extreme essure of the gas, and a cork is placed in the bottle and wired down. The gas ists in the water in a condition of tension, and therefore exhibits a tendency to ape into the atmosphere, in order to relieve the tension; this produces the violent pulsion of the cork when the wire is removed, and if the aërated water is placed a glass the gas will continue to be evolved until it has almost entirely passed into e atmosphere, and the tension of the gas in the water approximates to that of the mosphere, in which, it should be remembered, the carbon dioxide is, naturally, in ry small amount, viz., .04 per cent.

The oxygen of the blood does not obey this law of pressure. For if od which contains little or no oxygen be exposed to a succession of at- spheres containing more and more of that gas, we find that the absorp- n is at first very great, but soon becomes relatively very small, not ing therefore regularly in proportion to the increased amount (or ten- n) of the oxygen of the atmospheres, and that conversely, if arterial od be submitted to regularly diminishing pressures of oxygen, at first y little of the contained oxygen is given off to the atmosphere, then denly the gas escapes with great rapidity, and again disobeys the law pressures.

Very little oxygen can be obtained from plasma freed from blood cor- scles, even by the strongest mercurial air-pump, neither can it be made absorb a large quantity of that gas; but the small quantity which is given up or so absorbed follows the laws of absorption according to ssure.

It must be, therefore, evident that the chief part of the oxygen is con- ned in the corpuscles, and not in a state of simple solution. The chief d constituent of the colored corpuscles is *hæmoglobin*, which consti- es more than 90 per cent of their bulk. This body has a very remarkable affinity for oxygen, absorbing it to a very definite extent under favorable circumstances, and giving it up when subjected to the action of reducing agents, or to a sufficiently low oxygen pressure. From these facts it is inferred that the oxygen of the blood is *combined with hæmoglobin*, and not simply dissolved; but inasmuch as it is comparatively easy to cause the hæmoglobin to give up its oxygen, it is believed that the oxygen is but *loosely combined* with the substance.

**Hæmoglobin.**—Hæmoglobin is a crystallizable body which constitutes by far the largest portion of the colored corpuscles. It is intimately distributed throughout their stroma, and must be dissolved out before it will undergo crystallization. Its percentage composition is C. 53.85; H. 7.32; N. 16.17; O. 21.84; S. .63; Fe. .42. Jacquet gives the empirical formula for the hæmoglobin of the dog, $C_{758}H_{1203}N_{195}S_3FeO_{218}$. The most interesting of the properties of hæmoglobin are its powers of crystallizing and its attraction for oxygen and other gases.



Fig. 133.—Crystals of oxy-hæmoglobin—prismatic, from human blood.



Fig. 134.—Oxy-hæmoglobin crystals—tetrahedral, from blood of the guinea-pig.

*Crystals.*—The hæmoglobin of the blood of various animals possesses the power of crystallizing to very different extents (oxyhæmoglobin). In some animals the formation of crystals is almost spontaneous, whereas in others it takes place either with great difficulty or not at all. Among the animals whose blood coloring-matter crystallizes most readily are the guinea-pig, rat, squirrel, and dog; and in these cases to obtain crystals it is generally sufficient to dilute a drop of recently drawn blood with water and to expose it for a few minutes to the air. Light seems to favor the formation of the crystals. In many instances other means must be adopted, *e.g.*, the addition of alcohol, ether, or chloroform, rapid freezing, and then thawing, in electric current, a temperature of 60° C. (140° F.), the addition of sodium sulphate, or the addition of decomposing serum of another animal.

The hæmoglobin of human blood crystallizes with difficulty, as does also that of the ox, the pig, the sheep, and the rabbit.

The forms of hæmoglobin crystals, as will be seen from the appended figures, differ greatly.

Hæmoglobin crystals are soluble in water. Both the crystals themselves and also their solutions have the characteristic color of arterial blood.

A dilute solution of oxyhæomglobin gives a characteristic appearance with the spectroscope. Two absorption bands are seen between the solar lines D* (which is the sodium band in the yellow) and E* (see plate), one in the yellow, with its middle line some little way to the right of D, is very intense, but narrower than the other, which lies in the green near to the left of E. Each band is darkest in the middle and fades away at the ides. As the strength of the solution increases the bands become broader nd deeper, and both the red and the blue ends of the spectrum become ncroached upon until the bands coalesce to form one very broad band, nd only a slight amount of the green remains unabsorbed, and part of he red; on still further increase of strength the former disappears.



g. 135.—Hexagonal oxy-hæmoglobin crystals, from blood of squirrel. On these hexagonal plates prismatic crystals grouped in a stellate manner not unfrequently occur (after Funke).

If the crystals of oxyhæmoglobin be subjected to a mercurial air-ump they give off a definite amount of oxygen (1 gramme giving off 1.59 ccm. of oxygen), and they become of a purple color; and a solution of oxyhæmoglobin may be made to give up oxygen, and to become purple in a similar manner.

This change may be also effected by passing through the solution of blood or of oxyhæmoglobin, hydrogen or nitrogen gas, or by the action of reducing agents, of which Stokes's fluid* or ammonium sulphide a the most convenient.

---

* These letters refer to "*Fraunhofer's*" lines.

With the spectroscope, a solution of deoxidized or *reduced hæmoglobi* is found to give an entirely different appearance from that of oxidi hæmoglobin. Instead of the two bands at D and E we find a singl broader but fainter band occupying a position midway between the tw and at the same time less of the blue end of the spectrum is absorbe Even in strong solutions this latter appearance is found, thereby differin from the strong solution of oxidized hæmoglobin which lets through on the red and orange rays; accordingly to the naked eye the one (reduc hæmoglobin solution) appears purple, the other (oxyhæmoglobin solutio red. The deoxidized crystals or their solutions quickly absorb oxygen o exposure to the air, becoming scarlet. If solutions of blood be taken instead of solutions of hæmoglobin, results similar to the whole of th foregoing can be obtained.

Venous blood never, except in the last stages of asphyxia, fails t show the oxyhæmoglobin bands, inasmuch as the greater part of th hæmoglobin even in venous blood exists in the more highly oxidized condition

**Action of Gases on Hæmoglobin.**—*Carbonic oxide* gas, passe through a solution of hæmoglobin, causes it to assume a cherry-red colo and to present a slightly altered spectrum; two bands are still visible, but are slightly nearer the blue end than those of oxyhæmoglobin (se plate) The amount of carbonic oxide taken up is equal to the amoun of the oxygen displaced. Although the carbonic oxide gas readily displaces oxygen, the reverse is not the case, and upon this property depends the dangerous effect of coal-gas poisoning. Coal gas contai much carbonic oxide, and when breathed, the gas combines with the hæmoglobin of the blood, and produces a compound which cannot easily be reduced This compound (carb-oxyhæmoglobin) is by no means an oxyge carrier, and death may result from suffocation due to the want of oxyg notwithstanding the free entry of pure air into the lungs. Crystals o carbonic-oxide hæmoglobin closely resemble those of oxyhæmoglobin.

*Nitric oxide* produces a similar compound to the carbonic-oxide hæmoglobin, which is even less easily reduced.

*Nitrous oxide* reduces oxyhæmoglobin, and therefore leaves the reduced hæmoglobin in a condition to actively take up oxygen.

*Sulphuretted Hydrogen.*—If this gas be passed through a solution o

---

* *Stokes's Fluid* consists of a solution of *ferrous sulphate*, to which ammonia h been added and sufficient tartaric acid to prevent precipitation. Another reduc agent is a solution of *stannous chloride*, treated in a way similar to the ferrous s phate, and a third reagent of like nature is an aqueous solution of yellow *ammoni sulphide*, $NH_4HS$.

emoglobin, the hæmoglobin is reduced and an additional band ap-
in the red. If the solution be then shaken with air, the two bands
yhæmoglobin replace that of reduced hæmoglobin, but the band in
ed persists.

**lethæmoglobin.**—If an aqueous solution of oxyhæmoglobin is
sed to the air for some time, its spectrum undergoes a change; the
D and E bands become faint, and a new line in the red at C is de-
ped. The solution, too, becomes brown and acid in reaction, and is
ipitable by basic lead acetate. This change is due to the decompo-
n of oxyhæmoglobin, and to the production of *methæmoglobin*. On
ng ammonium sulphide, reduced hæmoglobin is produced, and on
ng this up with air, oxyhæmoglobin is reproduced. Methæmoglo-
probably a stage in the deoxidation of oxyhæmoglobin. It appears
ntain less oxygen than oxyhæmoglobin, but more than reduced hæ-
bin. Its oxygen is in more stable combination, however, than is
se with the former compound.



Fig. 136.—Fleischl's Hæmoglobinometer.

**stimation of Hæmoglobin.**—The most exact method is by the
ation of the amount of iron (dry hæmoglobin containing .42 per cent
n) in a given specimen of blood, but as this is a somewhat compli-
process, various methods have been proposed which, though not
act, have the advantage of simplicity. Of the several varieties of
globinometer that which appears to be the best adapted to its pur-
s that invented by Professor Fleischl, of Vienna. In this instru-
the amount of hæmoglobin in a solution of blood is estimated by

comparing a stratum of diluted blood with a standard solid substance uniform tint similar spectroscopically to diluted blood. The Flei instrument has been recently modified and made more accurate Miescher. The Fleischl-Miescher apparatus consists of a stand wit metal plate having a circular opening and a plaster mirror (*S*, fig. 1 below, which casts light through the opening. Beneath the plate i metal framework containing a colored glass wedge, and along the side the same is a scale graduated so as to indicate the percentage of h globin corresponding to the shades of the different parts of the we This framework can be moved by the wheel (*T*) which fits into a rack its lower surface The scale can be read through a small opening (*m*) the plate. Into the large circular opening of the plate fits a cylindri metal cell (*M*) with a glass bottom and divided by a metal partition i two equal parts. One of these halves lies over the wedge and is fil with distilled water. The other contains the solution of blood in wh the hæmoglobin is to be estimated. The apparatus is usually suppl with three cells (*M*, *M′*, *M″*) Of these, the first two are used in e mating the hæmoglobin according to Miescher's modification of Fleisc original method. This is the method now generally used. These ce are furnished with a glass cover (*D*), having a groove which fits upon partition of the cell. Over this cover is placed a diaphragm (*Bl*) wit longitudinal slit, which only permits of the central part of each side the cell being seen. The third cell (*M″*) is for use when the origi Fleischl method is employed.

*Procedure.*—The patient's ear or finger is pricked with the pric (*St*) and the blood from the wound sucked up into the graduated pipe (*Mel*) until it reaches the mark $\frac{1}{2}$, $\frac{2}{3}$, or $\frac{1}{1}$ water, or a one-per-cent so tion of sodium carbonate is then sucked in until the upper mark reached. The pipette is then well shaken in order to mix the blood th oughly One-half of each of the two cells (*M*, *M′*), which are resp tively 12 and 15 millimetres high, are then filled with the mixture, other half being filled with water. An important point is that the liqu should completely fill the cells. The cover-glasses and diaphragms then applied and the cells are ready for examination. This must be do by artificial light. Moreover, in order to have accurate results, light the same intensity should be always used. One of the cells is placed the plate and the wheel (*T*) turned until the colors of the two hal exactly correspond. When this point is reached, the result is read on the scale through the opening (*m*). This should be repeated seve times with each of the cells and the average of the readings taken. Th result obtained with the 12-millimetre cell being multiplied by $\frac{5}{4}$ to bri it up to that of the larger. For example, suppose the result of seve readings to be:

| | |
|---|---|
| With the large cell (15 mm.) | 54.00 |
| With the small cell (12 mm.) | 42.00 |

If the readings obtained with the large cell are exactly correct, then the readings with the smaller one should be 43.2, since $54 \times \frac{4}{5} = 43.2$. Or, if the readings with the smaller cells are exact, the readings with the larger should be 52.5, since $42 \times \frac{5}{4} = 52.5$. Hence the mean of 54 and 52.5, namely 53.25, should be taken as the correct figure. On looking at the corrected table of hæmoglobin values supplied with each instrument, we would find that this number on the scale corresponded to a solution containing 400 milligrams of hæmoglobin per 1,000 cubic centimetres of solution. But our original dilution was either 1:200, 1:300, 1:400, according as our pipette had been filled with blood up to the mark 1, $\frac{2}{3}$, or $\frac{1}{2}$; so that in order to obtain the actual percentage of hæmoglobin in the blood under examination we should be obliged to multiply our result by 200, 300, or 400. In the example we have taken, the amount of hæmoglobin would be, if our dilution was 1:200, $400 \times 200 = 80{,}000$ milligrams $= 80$ grams in 1,000 cubic centimetres $= 8$ grams in 100 cubic centimetres, or 8 per cent.

*Talquist.*—Another very simple method of approximately determining the hæmoglobin percentage is the hæmoglobin scale devised by T. W. Talquist. This consists of a series of shades of color corresponding to undiluted blood of various hæmoglobin values, ranging from ten to one hundred per cent of an arbitrary scale. This scale is included in a book, the remaining pages of which consist of filter paper, which is used for absorbing the specimen of blood whose hæmoglobin percentage is to be estimated. The blood-stained filter paper is compared with the hæmoglobin scale by direct daylight until a shade is found with which it corresponds. For approximate results this method has proved very satisfactory.

**Distribution of Hæmoglobin.**—Hæmoglobin occurs not only in the red blood-cells of all vertebrata (except amphioxus and leptocephalus whose blood-cells are all colorless), but also in similar cells in many Worms; moreover, it is found diffused in the vascular fluid of some other Worms and certain Crustacea; it also occurs in all the striated muscles of Mammals and Birds. It is generally absent from unstriated muscle except that of the rectum. It has also been found in Mollusca in certain muscles which are specially active, viz., those which work the rasp-like tongue.

## Derivatives of Hæmoglobin.

**Hæmatin.**—By the action of heat, or of acids or alkalies in the presence of oxygen, hæmoglobin can be split up into a substance called *Hæmatin*, which contains all the iron of the hæmoglobin from which it was derived, and a proteid residue. Of the latter it is impossible to say more than that it probably consists of one or more bodies of the globulin class. If there be no oxygen present, instead of hæmatin a body called **hæmochromogen** is produced, which, however, will speedily undergo oxidation into hæmatin.

Hæmatin is a dark brownish or black non-crystallizable substance of metallic lustre. Its percentage composition is C. 64.30; H. 5.50; N. 9.06; Fe. 8.82; O. 12.32; which gives the formula $C_{68}$, $H_{70}$, $N_{8}$, $Fe_{2}$, $O_{10}$ (Hoppe-Seyler). It is insoluble in water, alcohol, and ether; soluble in the caustic alkalies; soluble with difficulty in hot alcohol to which is added sulphuric acid. The iron may be removed from hæmatin by heating it with fuming hydrochloric acid to 160° C. (320° F.), and a new body, **hæmatoporphyrin**, the so-called iron-free hæmatin, is produced. Hæmatoporphyrin ($C_{68}$, $H_{74}$, $N_{8}$, $O_{12}$, Hoppe-Seyler) may also be obtained by adding blood to strong sulphuric acid, and if necessary filtering the fluid through asbestos. It forms a fine crimson solution, which has a distinct spectrum, viz., a dark band just beyond D, and a second all but midway between D and E. It may be precipitated from its acid solution by adding water or by neutralization, and when redissolved in alkalies presents four bands, a pale band between C and D, a second between D and E, nearer D, another nearer E, and a fourth occupying the chief part of the space between *b* and F.

*Hæmatin in acid solution.*—If an excess of acetic acid is added to blood, and the solution is boiled, the color alters to brown from decomposition of hæmoglobin and the setting free of hæmatin; by shaking this solution with ether, a solution of hæmatin in acid solution is obtained. The spectrum of the ethereal solution (colored plate) shows no less than four absorption bands, viz., one in the red between C and D, one faint and narrow close to D and then two broader bands, one between D and E, and another nearly midway between *b* and F. The first band is by far the most distinct, and the acid aqueous solution of hæmatin shows it plainly.

*Hæmatin in alkaline solution.*—If a caustic alkali is added to blood and the solution is boiled, alkaline hæmatin is produced, and the solution becomes olive green in color. The absorption band of the new compound is in the red, near to D, and the blue end of the spectrum is absorbed to a considerable extent. If a reducing agent be added, two bands resembling those of oxyhæmoglobin, but nearer to the blue, appear; this is the spectrum of [illegible], or **hæmochromogen**. On violently shaking the reduced hæmatin with air or oxygen the two bands are replaced by the single band of alkaline hæmatin.

**Hæmatoidin.** This substance is found in the form of yellowish crystals (fig. 137) in old blood extravasations and is derived from the hæmoglobin. Their crystalline form and the reaction they give with aining nitric acid seem to show them to be closely allied to *Bilirubin*, he chief coloring matter of the bile, and in composition they are probbly either identical or isomeric with it.

**Hæmin.**—One of the most important derivatives of hæmatin is hæin. It is usually called *Hydrochlorate of Hæmatin* (or hydrochloride), ut its exact chemical composition is uncertain. Its formula is said to e $C_{32}H_{30}N_4FeO_3HCl$, and it contains 5.18 per cent of chlorine, but by ome it is looked upon as simply crystallized hæmatin. Although diffiult to obtain in bulk, a specimen may be easily made for the microscope



Fig. 137.—Hæmatoidin crystals. (Frey.)



Fig. 138.—Hæmin crystals. (Frey.)

the following way:—A small drop of dried blood is finely powdered th a few crystals of common salt on a glass slide and spread out; a ver-glass is then placed upon it, and glacial acetic acid added by means a capillary pipette. The blood at once turns of a brownish color The de is then heated, and the acid mixture evaporated to dryness at a high nperature. The excess of salt is washed away with water from the ied residue, and the specimen may then be dried and mounted A ge number of small, dark, reddish black crystals of a rhombic shape, netimes arranged in bundles, will be seen if the slide be subjected to croscopic examination (fig 138)

The formation of these hæmin crystals is of great interest and imporce from a medico-legal point of view, as it constitutes the most certain d delicate test we have for the presence of blood (not of necessity the od of man) in a stain on clothes, etc. It exceeds in delicacy even the ectroscopic test. Compounds similar in composition to hæmin, but ntaining hydrobromic or hydriodic acid, instead of hydrochloric, may also readily obtained.

B **The Carbon Dioxide Gas in the Blood.**—Of this gas in the od, part exists in a state of simple solution in the plasma, and is given p in vacuo (35.2 per cent), and the rest in a state of weak chemical comination. Of the latter, part is in loose combination with the hæmolobin, probably with the globulin part, and part is more firmly united ith the alkalies, possibly with the carbonates in the form of bicarbonate.

The amount which can be absorbed depends on the alkalescence of th blood.

C. **The Nitrogen in the Blood.**—The whole of the small qua tity of the nitrogen contained in the blood is simply dissolved in the flui plasma.

**Chemical Composition of the Blood in Bulk.**—Analyses o the blood as a whole differ slightly, but the following table may be take to represent the average composition:

| | | |
|---|---|---|
| Water | | 784 |
| Solids— | | |
| Corpuscles | 130 | |
| Proteids (of serum) | 70 | |
| Fibrin (of clot) | 2.2 | |
| Fatty matters (of serum) | 1.4 | |
| Inorganic salts (of serum) | 6 | |
| Gases, kreatin, urea and other extractive matter, glucose and accidental substances | 6.4— | |
| | | 216 |
| | | 1000 |

## Variations in the Composition of Healthy Blood.

The conditions which appear most to influence the composition of th blood in health are these: Sex, Pregnancy, Age, and Temperament. Th composition of the blood is also, of course, much influenced by diet.

1. *Sex.*—The blood of men differs from that of women, chiefly i being of somewhat higher specific gravity, from its containing a relativ ly larger quantity of red corpuscles.

2. *Pregnancy.*—The blood of pregnant women is rather lower tha the average specific gravity. The quantity of the colorless corpuscles i increased in the latter months, especially in primiparæ; it is also claime that the fibrin is increased in amount.

3. *Age.*—The blood of the fœtus is very rich in solid matter, an especially in colored corpuscles; and this condition, gradually diminish ing, continues for some weeks after birth. The quantity of solid matt then falls during childhood below the average, rises during adult lif and in old age falls again.

4. *Temperament.*—There appears to be a relatively large quantity o solid matter in those of a plethoric or sanguineous temperament.

5. *Diet.*—Such differences in the composition of the blood as are d to the temporary presence of various matters absorbed with the food an drink, as well as the more lasting changes which must result from ge erous or poor diet respectively, need be here only referred to

6. *Effects of Bleeding.*—The result of bleeding is to diminish the sp cific gravity of the blood; and so quickly, that in a single venesectio the portion of blood last drawn has often a less specific gravity than th

e blood that flowed first. This is, of course, due to absorption of from the tissues of the body. The physiological import of this fact, ly, the instant absorption of liquid from the tissues, is the same as of the intense thirst which is so common after either loss of blood, e abstraction from it of watery fluid, as in cholera, diabetes, and the

or some little time after bleeding the want of colored corpuscles is marked, but with this exception, no considerable alteration seems to oduced in the composition of the blood for more than a very short ; the loss of the other constituents, including the colorless corpuscles, very quickly repaired.

*ariations in different parts of the Body.*—The composition of the l, as might be expected, is found to vary in different parts of the . Thus arterial blood differs from venous; and although its com- ion and general characters are uniform throughout the whole course he systemic arteries, they are not so throughout the venous system e blood contained in some veins differing markedly from that in rs.

*ifferences between Arterial and Venous Blood.*—The differences be- n arterial and venous blood are these:—

*a.*) Arterial blood is bright red, from the fact that almost all its hæ- obin is combined with oxygen (oxyhæmoglobin, or scarlet hæmo- in), while the purple tint of venous blood is due to the deoxidation certain quantity of its oxyhæmoglobin, and its consequent reduction e purple variety (deoxidized, or purple hæmoglobin).

*b.*) Arterial blood coagulates somewhat more quickly.

*c.*) Arterial blood contains more oxygen than venous, and less car- acid.

ome of the veins contain blood which differs from the ordinary stand- considerably. These are the Portal, the Hepatic, and the Splenic .

*ortal vein.*—The blood which the portal vein conveys to the liver is lied from two chief sources; namely, from the gastric and mesenteric , which contain the soluble elements of food absorbed from the ach and intestines during digestion, and from the splenic vein; it , therefore, combine the qualities of the blood from each of these ces.

he blood in the gastric and mesenteric veins will vary much accord- to the stage of digestion and the nature of the food taken, and can efore be seldom exactly the same. Speaking generally, and without idering the sugar and other soluble matters which may have been orbed from the alimentary canal, this blood appears to be deficient in d matters, especially in colored corpuscles, owing to dilution by the quantity of water absorbed, to contain an excess of proteid matter, to yield a less tenacious kind of fibrin than that of blood generally.

The blood from the *splenic vein* is generally deficient in colored puscles, and contains an unusually large proportion of proteids. fibrin obtainable from the blood seems to vary in relative amount, b be almost always above the average. The proportion of colorless cor cles is also unusually large. The whole quantity of solid matter is creased, the diminution appearing to be of colored corpuscles. The ma is said to be colored in consequence of its containing dissolved h atin.

The blood of the *portal vein*, combining the peculiarities of its factors, the splenic and mesenteric venous blood, is usually of lower cific gravity than blood generally, is more watery, contains fewer col corpuscles, more proteids, and yields a less firm clot than that yielde other blood, owing to the deficient tenacity of its fibrin.

Guarding (by ligature of the portal vein) against the possibility error in the analysis from regurgitation of hepatic blood into the p vein, recent observers have determined that ***hepatic venous blood*** con less water, proteids, and salts than the blood of the portal veins; that it yields a much larger amount of extractive matter, in which i constant element, namely, grape-sugar, which is found, whether charine or farinaceous matter has been present in the food or not.

## Globulocidal and Other Properties of Serum.

(*a.*) *Cytolysis.*—It has been known for some time that the sera of tain animals when injected into the circulation of animals of another cies will cause destructive changes in the blood corpuscles, accompa by symptoms of poisoning, which may even end fatally. These re served to bring into disrepute the use of foreign blood in transfu which has consequently been practically abandoned. This dischar the hæmoglobin of the red blood-corpuscles and solution in the pl (laking) is now included in the general term *Cytolysis*, and more cifically known as *Hæmolysis.* Agents which produce such an effec known as hæmolytic or hæmotoxic agents. Sera of one species are hæmolytic for blood of all other species, but the serum of one an may be made to acquire such properties for the blood of another.

This adaptation is brought about in the following way: For insta the blood of the guinea-pig, which is not normally lytic for the red of the rabbit, may be adapted to the latter by previously, at several cessive intervals (three to seven days) injecting into the abdominal ca or subcutaneous tissues of the guinea-pig small quantities of rab blood. If now a small quantity of serum be obtained from the gui pig by the usual methods and mixed in a test tube with some of the rabbit's blood diluted with physiological salt solution, hæmolysis occurs; that is, the coloring matter of the rabbit's red blood-cells goes into solution and the cells appear under the microscope as shadow corpuscles or ghosts, devoid of hæmoglobin. Such an artificially produced hæmolytic serum is only lytic for the blood of the animal species for which it has been adapted. It is true that it may also show slightly lytic properties for closely allied species. It has therefore been suggested as a possible valuable aid in determining relationships of various animal species.

Concerning the nature of the lytic substance, it has been found that it robably consists of two bodies acting conjointly, for if the serum be eated to 56° C. for a short time, its lytic powers are lost, but may be estored by adding a little serum of another animal of the same species hich has not been adapted, and whose serum is consequently not in self lytic. Of these two bodies, therefore, one is stable and is formed nly in the adapted serum, while the other is more unstable or labile estroyed at 56° C.) and exists normally in the blood plasma. The rmer is known as the immune body and the latter as alexin. Lysis curs only when both are present at the same time, and not through the ency of one or the other singly.

This cytolytic adaptation has been extended to include other cells sides the red blood-corpusles. Thus in a similar manner *leucolytic*, *patolytic*, *nephrolytic*, and a number of other lytic sera have been veloped.

It is further possible, under certain circumstances, that substances ay be developed in the tissues which are lytic for other tissue cells of e same animal, *autolytic substances*. This may be an important physi-ogical process in the elimination of worn out tissue cells, cellular ele-ents in injury, inflammation, etc.

(*b.*) *Agglutinative Substances.*—A further property of adapted sera is at of agglutination. The adaptation is secured in the same way as in e production of cytolysins. In fact, both cytolysis and agglutination ay occur at the same time. The normal blood serum of some animals ay be agglutinative for the blood-cells of some other species. In nor-l serum, agglutinative and cytolytic properties may be present together one only may be normally present.

The activity of agglutinative substances is not destroyed at a tempera-e of 56° C. They do become inert, however, at 70° C., and further-re, they cannot be restored by adding normal serum, as is the case with olysins.

(*c.*) *Precipitins.*—Other forms of adaptive substances which may be nd in animal serum are those which, when mixed with the substances means of which adaptation has been secured, form a precipitate. By this means blood of different species of animals may be detected e when in a dried state. It has been suggested as a possible valuable ai medico-legal cases, since human blood in a dilution of 1 to 50,000 been recognized.

## Development of the Blood-Corpuscles.

The first formed blood-corpuscles of the human embryo differ m in their general characters from those which belong to the later per of intra-uterine, and to all periods of extra-uterine life. Their ma of origin is at first very simple.

Surrounding the early embryo is a circular area, called the vasc area, in which the first rudiments of the blood-vessels and blood-cor cles are developed. Here the nucleated embryonal cells of the mesobl



Fig. 139.—Part of the network of developing blood-vessels in the vascular area of a guine *bl*, blood-corpuscles becoming free in an enlarged and hollowed-out part of the network; *a*, proc protoplasm. (E. A. Schäfer.)

from which the blood-vessels and corpuscles are to be formed, send processes in various directions, and these, joining together, form an irr lar meshwork. The nuclei increase in number, and collect chiefly in larger masses of protoplasm, but partly also in the processes. It app that hæmoglobin then makes its appearance in certain of these nucle embryonal cells, which thus become the earliest red blood-corpus The protoplasm of the cells and their branched network in which t corpuscles lie then become hollowed out into a system of canals inclo fluid, in which the red nucleated corpuscles float. The corpuscles at are from about $\frac{1}{2500}$ to $\frac{1}{1500}$ of an inch ($10\,\mu$ to $16\,\mu$) in diameter, mo spherical, and with granular contents, and a well-marked nucleus. T nuclei, which are about $\frac{1}{5000}$ of an inch ($5\,\mu$) in diameter, are central, cular, very little prominent on the surfaces of the corpuscles, and ap ently slightly granular or tuberculated.

The corpuscles then strongly resemble the colorless corpuscles of the ally developed blood, but are colored. They are capable of amœboid ovement and multiply by division.

When, in the progress of embryonic development, the liver begins to e formed, the multiplication of blood-cells in the whole mass of blood ases, and new blood-cells are produced by this organ, and also by the leen. These are at first colorless and nucleated, but afterward acquire e ordinary blood tinge, and resemble very much those of the first set. hey also multiply by division. About this time the bone marrow also gins to form red corpuscles, though at first in small amounts only. This nction develops rapidly, however, so that at birth the marrow repre-nts the chief seat of production of the red cells. Nevertheless, nucle-ed red cells are usually found at birth, sometimes in considerable quan-ties, in the liver, and, less often, the spleen. Non-nucleated red cells gin to appear soon after the first month of fœtal life, and gradually crease, so that at the fourth month they form one-fourth of the whole ount of colored corpuscles; at the end of fœtal life they almost com-etely replace the nucleated cells. In late fœtal life the red cells are rmed in almost the same way as in extra-uterine life.

Various theories have prevailed as to the mode of origin of the non-



140.



141.

Fig. 140.—Multiplication of the nucleated red corpuscles. Marrow of young kitten after bleeding, wing above karyokinetic division of erythroblast, and below the formation of mature from imma-erythrocysts. (Adapted from Howell.)

Fig. 141.—Shows the way in which the nucleus escapes from the nucleated red corpuscles. 3, 4, represent different stages of the extrusion noticed upon the living corpuscles. *a*, Specimen the circulating blood of an adult cat, bled four times; *b*, specimen from the circulating blood of ten forty days old, bled twice; *c*, specimens from the blood of a fœtal cat, 9 cm. long. Others from marrow of an adult cat, two of the figures showing the granules present in the corpuscles, which been interpreted erroneously as a sign of the disintegration of the nucleus. (After Howell.)

leated colored corpuscles. For a time it was thought that they were endoglobular origin, and merely fragments of some original cell, being duced by subdivision of the cell body itself This theory easily ac-nted for the absence of the nuclei, but it has not been supported by recent investigations. At present it is the general belief that the no nucleated cells are derived from nucleated cells by a process of mitot division, and further that their nuclei gradually shrink or fade and then extruded. Extrusion undoubtedly occurs with great frequency, the use of some of the more recent stains seems to prove that there traces of nuclear material in the non-nucleated corpuscles. Owing these facts and other recent investigations, Maximow asserts that whi the greater part of the nucleus is extruded, still a small portion usual remains in a finely granular form and gives a basic staining quality the centres, especially of the young red cells.

**Origin of the Mature Colored Corpuscles.**—It has alrea been shown that during uterine life the marrow gradually assumes m and more completely the function of forming red cells. This functi prevails after birth, and most authorities now regard the red marrow the exclusive seat, under normal conditions, of the production of red puscles. The original cell, or *erythroblast*, is generally considered to a large colorless cell which is devoid of hæmoglobin, is larger than



Fig. 142.—Colored nucleated corpuscles, from the red marrow of the guinea-pig. (E. A. Schäfer.)

ordinary red cell, and has a single nucleus but no nucleolus; it diffe but very slightly from the original mesoblastic cell.

By mitotic division of these original cells there are derived seve series of cells which approach, more and more completely, the type nucleated red corpuscles, becoming rich in hæmoglobin. The nucleus then extruded (or partly extruded and partly broken up) and the no non-nucleated red corpuscle results. A few authorities, however, in tra ing the red cells back to colorless cells, think that all the lymphoid sues are also probable sources of the erythroblasts. In infancy and ea childhood the red marrow, which produces the colored corpuscles, is fou in large amount in the cavities of almost all the bones. In adult life is normally confined to the ribs, flat bones, vertebræ, and upper and lo thirds of the long bones. In *pathological conditions* it has been fou that the spleen in the adult, or both the spleen and the liver in infa and early childhood, can resume the function of producing red corpusc

Without doubt, the red corpuscles have, like all other parts of organism, a tolerably definite term of existence, and in a like manner and waste away when the portion of work allotted to them has been formed. Neither the length of their life, however, nor the fashio their decay has been yet clearly made out. It is, however, probable the red blood-cells are short-lived, owing to their lack of a nucleus. F er, the formation of bile being constant and its pigments being derived om hæmoglobin (hæmatoidin), there must be a continuous disintegra- on of the red cells, which probably takes place throughout the circula- on. Although the spleen has been considered, the place of disintegra- on of red blood-corpuscles, it must be of minor importance, as there eems to be no increase of hæmoglobin in the blood of the splenic vein.

**Origin of the Colorless Corpuscles.**—In fœtal life the white orpuscles are not found in the blood until the vascular system has been ery extensively developed, long after the appearance of red cells; the xact time of their appearance, however, has not yet been fully deter- ined. It is now quite generally believed that in the fœtus both red and hite cells are derived from a common origin, and that they become dif- erentiated in the course of development. The earliest known progenitors f the leucocytes are the primary wandering cells of mesodermal origin, hich are found chiefly in the connective tissues, thus lying outside of e vessels. Gathering in groups, partly at the sites of the future lymph odes, but chiefly in the embryonal liver, these wandering cells pass rough several generations of mitotic division, and thus gradually as- ume the type of leucocytes. According to a few observers the leuco- tes are also formed in the circulating blood and lymph by amitotic, less equently by mitotic, division. Later on in fœtal life the function of rming leucocytes is gradually transferred from the liver to the lymphoid d adenoid tissues, *i.e.*, the lymph nodes, spleen, marrow, and thymus.

In adult life, under normal conditions, the leucocytes are formed only the lymphoid tissues, including the lymph nodes, spleen and marrow. e process is also one of mitotic division (a few authorities claim that is amitotic), and the resulting cells pass into the circulation by way of e thoracic duct.

**Diffusion, Osmosis, Dialysis.**—The term diffusion has been long plied to the regular mixing of the molecules of two gases when brought to contact in a confined space, this interpenetration being due to the to- d-fro movements of their molecules. More recently it has been applied the mixing of the molecules of two solutions when brought into con- et, as it has been found that they act in the same way and obey the ne laws as gases. If, however, the two solutions are separated by a embrane, permeable to the solutions, diffusion will still occur. To this m of diffusion the terms *Osmosis*, in the case of water, and *Dialysis*, the case of diffusable substances, have been applied. All bodies can divided into two groups, *crystalloids* and *colloids*. To the former oup belong bodies having a crystalline form. All such bodies are dif- sable (dialysable), their power of dialysis, however, varying consider- ly. To the second group belong such bodies as have no crystalline m (amorphous). These are generally bodies with a large molecule, and are only slightly or not at all diffusable. An exception to this s ond group is hæmoglobin which has a crystalline form and is diffusal The following may serve as simple illustrations: Take a jar and divid in two equal parts by an animal membrane (*M*, fig. 143) and place equal amount of distilled water in the two sides, *A* and *B*. Now, si the molecules of water act like those of a gas, and are continually mov to and fro, bombarding all the surfaces of their retainer, the molecules water in *A* and *B* will be continually striking all the surfaces of *A* and *B*; but since the membrane is permeable to the water molecules, there will be a continual interchange of molecules between *A* an *B*. If now, in one side (*A*) we place a solution of sodium chloride, still keeping wate *B*, the membrane being permeable to the sodium chloride, the first th we should notice would be an increase in the amount of water in *A*. F merly it would have been said that "the salt had attracted the wat Now we should say that the salt had a certain osmotic pressure. T salt, however, being able to pass (dialyse) through the membrane, w do so, and this will continue until the strength of the two salt solutio and therefore the osmotic pressure on both sides, is equal.



Fig. 143.



Fig. 144.

**Osmotic Pressure.**—If now in *A* we place a solution of so soluble colloidal substance to which the membrane is impermeable, else replace the membrane (*M*), we used in our former experiment by which is not permeable to the sodium chloride, and arrange our jar as fig. 144, so as to be able to read off any increase of water which may p into *A*, we will notice that the amount of water liquid in *A* will conti to increase up to a certain point. Once that point is reached, there w be no further change, since the substance in solution, in *A*, cannot p through the membrane as in the previous example. This pressure can be measured and expressed in millimetres of mercury. It is constant for all solutions of this substance of the same concentration under like conditions of temperature and pressure, and is called the *Osmotic pressure* of this solution.

Numerous explanations regarding the nature of osmotic pressure have een given, but as yet none have been found perfectly satisfactory. A imple one, and one that can be easily understood, is as follows: In fig. 44 one surface of our membrane is being bombarded by the molecules of non-diffusable substance mixed with those of a diffusable one (water), ss water is able to diffuse out, since less gets to the surface of the memrane. The other surface, being bombarded entirely by water molecules, ermits all of these, which reach it, to pass through. Osmotic pressure an be estimated in several different ways in addition to the above, viz., e determination of the freezing point of the solution, determination of e boiling point, determination of the electrical conductivity. The relts obtained with the various methods agree very closely.

The following solutions have the same osmotic pressure: Sodium loride, 0.64 per cent; potassium nitrate, 1.09 per cent; sugar, 5.5 per nt. Such solutions are called *isotonic* to each other.

**Isotonic Solutions.**—The term isotonic is a relative one, implying at a certain solution is of the same osmotic pressure as some other soluon, taken as a standard. In physiology it has been customary to take lood plasma as a standard. A solution of 0.64 per cent sodium chlode is isotonic for the blood of the frog, and a 0.85 per cent one for that f man. Further, any solution which is of a lower osmotic pressure than e standard solution is said to be *hypoisotonic* (*hypotonic*) in relation to at solution. A solution of a higher osmotic pressure is said to be *perisotonic* (*hypertonic*). The following may be taken as an example hypoisotonic and hyperisotonic solutions: If a hypotonic solution be ixed with blood, water from the hypotonic solution passes through the ll membrane of the red corpuscles into the stroma, and causes it to well. The hæmoglobin at the same time passes out and goes into soluon in the diluted plasma. On the other hand, the addition of a hypernic solution to the plasma causes the red corpuscles to lose their water d become crenated. The principles of osmosis have been derived from e action of substances separated by dead animal or plant membranes. must be, however, remembered that in the application of these prinples to processes occurring in the living organism, the cells, forming e various membranes, are an important modifying factor. It is proble that physico-chemical processes, occurring in the protoplasm of the ll, may change its permeability to the same substance at different times.

# CHAPTER VI.

## THE CIRCULATION OF THE BLOOD.

The blood is made to circulate within the system of closed tubes in which it is contained by means of the alternate contraction and relaxation of the heart. The heart is a hollow muscular organ consisting of four chambers, two auricles and two ventricles, arranged in pairs. On the right and left sides is an auricle joined to and communicating with a ventricle, but the chambers on the right side do not directly communicate with those on the left side. The blood is conveyed away from the left side of the heart (as in the diagram, fig. 145) by the *arteries*, and returned to the right side of the heart by the *veins*, the arteries and veins being continuous with each other at one end by means of the heart, and at the other by a fine network of vessels called the *capillaries*.



Fig. 145.—Diagram of the circulation.

From the right side of the heart the blood passes to the lungs through the pulmonary artery, then through the pulmonary capillaries, and through the pulmonary veins to the left side of the heart (Fig. 145). Thus there are two circulations through which the blood *must* pass; the one, a shorter circuit from the right side of the heart to the lungs and back again to the left side of the heart; the other and larger circuit, from the left side of the heart to all parts of the body and back again to the right side; strictly speaking, however, there is but one complete circulation, which may be diagrammatically represented by a double loop, as in fig. 145, in which there is one continuous stream, the whole of which must, at one part of its course, pass through the lungs. Subordinate to the circulations through the lungs and through the system generally, respectively named the **Pulmonary** and **Systemic,** it will be noticed also in the same figure that a portion of the stream of blood having been diverted once into the capillaries of the intestinal canal, and some other organs, and gathered up again into a single stream, is a second time divided in its passage through the liver, before it finally reaches the heart and completes a revolution. This subordinate stream through the liver is called the **Portal** circulation. A somewhat similar accessory circulation is that through the kidneys, called the **Renal** circulation. Such then is the outline of the course of the circulation. The problems in connection with its maintenance cannot be well understood without a more detailed knowledge of the structure and mode of action of the heart, and of the structure and properties of the blood-vessels. These subjects will now be considered seriatim.

## The Heart.

The heart is contained in the chest or thorax, and lies between the right and left lungs (fig. 146), inclosed in a membranous sac—the **Pericardium,** which is made up of two distinct parts, an *external* fibrous membrane, composed of closely interlacing fibres, which has its base attached to the diaphragm or midriff, the great muscle which forms the floor of the chest and divides it from the abdomen—both to the central tendon and to the adjoining muscular fibres, while the smaller and upper end is lost on the large blood-vessels by mingling its fibres with that of their external coats; and an *internal* serous layer, which not only lines the fibrous sac, but also is reflected on to the heart, which it completely invests. The part which lines the fibrous membrane is called the *parietal* layer, and that inclosing the heart, the *visceral* layer or *epicardium*, and these being continuous for a short distance along the great vessels of the base of the heart, form a closed sac, the cavity of which in health contains just enough fluid to lubricate the two surfaces, and thus to enable them to glide smoothly over each other during the movements of the heart. The vessels passing in and out of the heart receive investments from this sac to a greater or less degree.

The heart is situated in the chest behind the sternum and costal cartilages, being placed obliquely from right to left, quite two-thirds of it being to the left of the mid-sternal line. It is of pyramidal shape, with the apex pointing downward, outward, and toward the left, and the base backward, inward, and toward the right. It rests upon the diaphragm, and its pointed apex, formed exclusively of the left side of the heart, is in contact with the chest wall, and during life beats against it at a point called the *apex beat*, situated in the fifth left intercostal space, and about three inches from the mid-sternal line. The heart is, as it were, suspended in the chest by the large vessels which proceed from its base, but, excepting at this part, the organ itself lies free within the sac of the pericardium. The part which rests upon the diaphragm



Fig. 146.—View of heart and lungs in situ. The front portion of the chest-wall, and the or *parietal* layers of the pleuræ and pericardium have been removed. The lungs are part lapsed.

is flattened, and is known as the *posterior* surface, while the free u part is called the *anterior* surface. The margin toward the left is t and obtuse, while the lower margin toward the right is thin and

On examination of the external surface the division of the he parts which correspond to the chambers inside of it may be tra a deep transverse groove called the *auriculo-ventricular groov* the auricles which form the base of the heart fro form the remainder, including the apex, the v by far the greater; and, again, the *inter-ventr* the ventricles both front and back, and sepa The anterior groove is nearer the left ma the right, as the front surface of the right ventricle and the po surf r grooves run the coronary vessels, which supply the tissue of with blood, as well as nerves and lymphatics imbedded in ess fatty material.

**Chambers of the Heart.**—The interior of the heart is divided itudinal partition in such a manner as to form two chief chamvities—right and left. Each of these chambers is again sub-



t auricle and ventricle opened, and a part of their right and anterior walls their interior. ⅙.—1, Superior vena cava; 2, inferior vena cava; 2', hepatic t auricle; 3', placed in the fossa ovalis, below which is the Eustachian valve; the aperture of the coronary vein; +, +, placed in the auriculo-ventricular portion of the adjacent walls of the auricle and ventricle has been preserved; t ventricle, the upper figure is immediately below the semilunar valves; 4', or musculus papillaris; 5, 5', 5", tricuspid valve; 6, placed in the interior of a part of the anterior wall of that vessel having been removed, and a narrow at its commencement, where the semilunar valves are attached; 7, concavity to the cord of the ductus arteriosus; 8, ascending part or sinus of the arch ment by the auricular appendix and pulmonary artery; 9, placed between carotid arteries; 10, appendix of the left auricle; 11, 11, outside of the left near the apex. (Allen Thomson.)

ly int and a lower portion, called respect- ioned, auricle and ventricle, which er; the aperture of communication, sposed as to allow blood to pass le, but not in the opposite direction. There are thus four cavities in the heart—the auricle and ventricle of one side being quite separate from those of the other (fig. 147).

*Right Auricle.*—The right auricle is situated at the right part of the base of the heart as viewed from the front. It is a thin-walled cavity of more or less quadrilateral shape, prolonged at one corner into a tongue-shaped portion, the right auricular *appendix*, which slightly o laps the exit of the great artery, the aorta, from the heart.



Fig. 148.—The left auricle and ventricle opened and a part of their anterior and left walls removed. ½.—The pulmonary artery has been divided at its commencement; the opening into the left ventricle is carried a short distance into the aorta between two of the segments of the semilunar valves; and the left part of the auricle with its appendix has been removed. The right auricle is out of view. 1, The two right pulmonary veins cut short; their openings are seen within the auricle; 1', placed within the cavity of the auricle on the left side of the septum and on the part which forms the remains of the valve of the foramen ovale, of which the crescentic fold is seen toward the left hand of 1'; 2, a narrow portion of the wall of the auricle and ventricle preserved round the auriculo-ventricular orifice; 3, 3', the cut surface of the walls of the ventricle, seen to become very much thinner towards 3", at the apex; 4, a small part of the anterior wall of the left ventricle which has been preserved with the principal anterior columna carnea or musculus papillaris attached to it; 5, 5, musculi papillares; 5', the left side of the septum, between the two ventricles, within the cavity of the left ventricle; 6, 6', the mitral valve; 7, placed in the interior of the aorta near its commencement and above the three segments of its semilunar valve which are hanging loosely together; 7', the exterior of the great aortic sinus; 8, the root of the pulmonary artery and its semilunar valves; 8', the separated portion of the pulmonary artery remaining attached to the aorta by 9, the cord of the ductus arteriosus; 10, the arteries rising from the summit of the aortic arch. (Allen Thomson.)

The interior is smooth, being lined with the general lining of the heart, the *endocardium*, and into it open the superior and inferior venæ cavæ, or great veins, which convey the blood from all parts of the body to the heart. The former is directed downward and forward, the latter upward and inward; between the entrances of these vessels is a slight tubercle called *tubercle of Lower*. The opening of the inferior cava is protected and partly covered by a membrane called the *Eustachian valve*. In the posterior wall of the auricle is a slight depression called the *fossa ovalis*, which corresponds to an opening between the right and left auricles which exists in fœtal life. The right auricular appendix is of oval form, and admits three fingers. Various veins, including the coronary *sinus*, or the dilated portion of the right coronary vein, open into this chamber. In the appendix are closely set elevations of the muscular tissue covered with endocardium, and on the anterior wall of the auricle are similar elevations arranged parallel to one another, called *musculi pectinati*.



Fig. 149.—Transverse section of bullock's heart in a state of cadaveric rigidity. (Dalton.) *b*, Cavity of right ventricle. *a*, Cavity of left ventricle.

*Right Ventricle.*—The right ventricle occupies the chief part of the anterior surface of the heart, as well as a small part of the posterior surface: it forms the right margin of the heart. It takes no part in the formation of the apex. On section its cavity, in consequence of the encroachment upon it of the septum ventriculorum, is semilunar or crescentic (fig. 149); into it are two openings, the auriculo-ventricular at the base and the opening of the pulmonary artery also at the base, but more to the left; the part of the ventricle leading to it is called the *conus arteriosus* or *infundibulum;* both orifices are guarded by valves, the former called *tricuspid* and the latter *semilunar* or *sigmoid*. In this ventricle are also the projections of the muscular tissue called *columnæ carneæ* (described at length p. 190).

*Left Auricle.*—The left auricle is situated at the left and posterior part of the base of the heart, and is best seen from behind. It is quadrilateral, and receives on either side two pulmonary veins. The auricular appendix is the only part of the auricle seen from the front, and responds with that on the right side, but is thicker, and the interior more smooth. The left auricle is only slightly thicker than the right. left auriculo-ventricular orifice is oval, and a little smaller than that on the right side of the heart. There is a slight vestige of the foramen between the auricles, which exists in fœtal life, on the septum between them.

*Left Ventricle.*—Though taking part to a comparatively slight extent in the anterior surface, the left ventricle occupies the chief part of the posterior surface. In it are two openings very close together, viz. the auriculo-ventricular and the aortic, guarded by the valves corresponding to those of the right side of the heart, viz. the *bicuspid* or *mitral* and the *semilunar* or *sigmoid*. The first opening is at the left and back part of the base of the ventricle, and the aortic in front and toward the right. In this ventricle, as in the right, are the columnæ carneæ, which are smaller but more closely reticulated. They are chiefly found near the apex and along the posterior wall. They will be again referred to in the description of the valves. The walls of the left ventricle, which are nearly half an inch in thickness, are, with the exception of the apex, twice or three times as thick as those of the right.



Fig. 150.—Network of muscular fibres from the heart of a pig. The nuclei of the muscle-corpuscles are well shown. × 450. (Klein and Noble Smith.)

**Capacity of the Chambers.**—During life each ventricle is capable of containing about four to six ounces (about 180 grms.) of blood. The capacity of the auricles after death is rather less than that of the ventricles: the thickness of their walls is considerably less. The latter condition is adapted to the small amount of force which the auricles require in order to empty themselves into their adjoining ventricles; the former to the circumstance of the ventricles being partly filled with blood before the auricles contract.

**Size and Weight of the Heart.**—The heart is about 5 inches long (about 12.6 cm.), 3½ inches (8 cm.) greatest width, and 2½ inches (6.3 cm. ) in its extreme thickness. The average weight of the heart in the adult is from 9 to 10 ounces (about 300 grms.); its weight gradually increasing throughout life till middle age; it diminishes in old age.

**Structure.**—The walls of the heart are constructed almost entirely of layers of muscular fibres; but a ring of connective tissue, to which some of the muscular fibres are attached, is inserted between each auricle and ventricle, and forms the boundary of the *auriculo-ventricular* ing. Fibrous tissue also exists at the origins of the pulmonary y and aorta.

he muscular fibres of each auricle are in part continuous with those e other, and partly separate; and the same remark holds true for entricles. The fibres of the auricles are, however, quite separate those of the ventricles, the bond of connection between them only the fibrous tissue of the auriculo-ventricular openings.

he minute structure of the striated muscular fibres of the heart een already described (p. 88).

**ndocardium.**—As the heart is clothed on the outside by a thin parent layer of pericardium, so its cavities are lined by a smooth



Fig. 151.—Diagram of the circulation through the heart (Dalton).

hining membrane, or *endocardium*, which is directly continuous the internal lining of the arteries and veins. The endocardium is osed of connective tissue with a large admixture of elastic fibres; n its inner surface is laid down a single tesselated layer of flat-endothelial cells. Here and there unstriped muscular fibres are times found in the tissue of the endocardium.

**alves.**—The arrangement of the heart's valves is such that the can pass only in one direction (fig. 151).

he *tricuspid* valve (5, fig. 147) presents *three* principal cusps or sub-ons, and the mitral or *bicuspid* valve has *two* such portions (6, fig. But in both valves there is between each two principal portions ller one; so that more properly, the tricuspid may be described as ting of six, and the mitral of four, portions. Each portion is of ular form. Its base is continuous with the bases of the neighboring portions, so as to form an annular membrane around the auriculo-ventricular opening, and is fixed to a tendinous ring which encircles the orifice between the auricle and ventricle and receives the insertions of the muscular fibres of both. In each principal cusp may be distinguished a central part, extending from base to apex, and including about half its width. It is thicker and much tougher than the border pieces or edges.

While the bases of the cusps of the valves are fixed to the tendinous rings, their ventricular surface and borders are fastened by slender tendinous fibres, the *chordæ tendineæ*, to the internal surface of the walls of the ventricles, the muscular fibres of which project into the ventricular cavity in the form of bundles or columns—the *columnæ carneæ*. These columns are not all alike, for while some are attached along their whole length on one side, and by their extremities, others are attached only by their extremities; and a third set, to which the name *musculi papillares* has been given, are attached to the wall of the ventricle by one extremity only, the other projecting, papilla-like, into the cavity of the ventricle (4, fig. 148), and having attached to it chordæ tendineæ. Of the tendinous cords, besides those which pass from the walls of the ventricle and the musculi papillares to the margins of the valves, there are some of especial strength, which pass from the same parts to the edges of the middle and thicker portions of the cusps before referred to. The ends of these cords are spread out in the substance of the valve giving its middle piece its peculiar strength and toughness; and from the sides numerous other more slender and branching cords are given off, which are attached all over the ventricular surface of the adjacent border-pieces of the principal portions of the valves, as well as to those smaller portions which have been mentioned as lying between each two principal ones. Moreover, the musculi papillares are so placed that from the summit of each, tendinous cords proceed to the adjacent halves of two of the principal divisions, and to one intermediate or smaller division, of the valve.

The preceding description applies equally to the mitral and tricuspid valve; but it should be added that the mitral is considerably thicker and stronger than the tricuspid, in accordance with the greater force which it is called upon to resist.

The *semilunar valves* guard the orifices of the pulmonary artery and of the aorta. They are nearly alike on both sides of the heart; but the aortic valves are altogether thicker and more strongly constructed than the pulmonary valves, in accordance with the greater pressure which they have to withstand. Each valve consists of three parts which are of semilunar shape, the convex margin of each being attached to a fibrous ring at the place of junction of the artery to the ventricle, and the concave or nearly straight border being free, so as to form a little pouch a watch-pocket (7, fig. 148). In the centre of the free edge of the ch, which contains a fine cord of fibrous tissue, is a small fibrous lule, the *corpus Arantii*, and from this and from the attached border fibres extend into every part of the mid substance of the valve, ept a small lunated space just within the free edge, on each side of corpus Arantii. Here the valve is thinnest, and composed of little re than the endocardium. Thus constructed and attached, the three nilunar pouches are placed side by side around the arterial orifice of ch ventricle, which can be separated by the blood passing out of the ntricle, but which immediately afterward are pressed together, so as prevent any return (6, fig. 147, and 7, fig. 148). This will be again eferred to. Opposite each of the semilunar cusps, both in the aorta nd pulmonary artery, there is a bulging outward of the wall of the essel: these bulgings are called the *sinuses of Valsalva*.

*Structure.*—The valves of the heart are formed essentially of thick yers of closely woven connective and elastic tissue, over which, on ery part, is reflected the endocardium.

## The Arteries.

**Distribution.**—The arterial system begins at the left ventricle in a gle large trunk, the aorta, which almost immediately after its origin es off in the thorax three large branches for the supply of the head, ck, and upper extremities; it then traverses the thorax and abdomen, ing off branches, some large and some small, for the supply of the ious organs and tissues it passes on its way. In the abdomen it ides into two chief branches, for the supply of the lower extremities. e arterial branches wherever given off divide and subdivide, until the ibre of each subdivision becomes very minute, and these minute ves- s pass into capillaries. Arteries are, as a rule, placed in situations tected from pressure and other dangers, and are, with few exceptions, aight in their course, and frequently communicate (anastomose or sculate) with other arteries. The branches are usually given off at acute angle, and the areas of the branches of an artery generally ex- d that of the parent trunk; and as the distance from the origin is reased, the area of the combined branches is increased also. After th, arteries are usually found dilated (not collapsed as the veins are) d empty, and it was to this fact that their name (ἀρτηρία, the wind- pe) was given them, as the ancients believed that they conveyed air the various parts of the body. As regards the arterial system of the gs, the pulmonary artery is distributed much as the arteries belong- to the general systemic circulation.

*Structure.*—The walls of the arteries are composed of three principal ts, termed (*a*) the external or tunica adventitia, (*b*) the middle or ica media, and (*c*) the internal or tunica intima.

(*a*) The *external coat* or *tunica adventitia* (figs. 152 and 153, *a*), the strongest and toughest part of the wall of the artery, is formed of areolar tissue, with which is mingled throughout a network of elastic fibres. At the inner part of this outer coat the elastic network forms in most arteries so distinct a layer as to be sometimes called the *external elastic coat* (fig. 153, *e*).

(*b*) The *middle coat* (fig. 153, *m*) is composed of both muscular and elastic fibres, with a certain proportion of areolar tissue. In the larger arteries (fig. 153) its thickness is comparatively as well as absolutely much greater than in the small, constituting, as it does, the greater part of the arterial wall. The muscular fibres are unstriped (fig. 154), and are arranged for the most part transversely to the long axis of the artery (fig. 155, *m*); while the elastic element, taking also a transverse direction, is disposed in the form of closely interwoven and branching fibres, which intersect in all parts the layers of muscular fibre. In arteries of various size there is a difference in the proportion of the muscular and elastic element, elastic tissue preponderating in the largest arteries, and unstriped muscle in those of medium and small size.



Fig. 152.



Fig. 153.



Fig. 154.

Fig. 152.—Minute artery viewed in longitudinal section. *e*, Nucleated endothelial membrane with faint nuclei in lumen, looked at from above; *i*, thin elastic tunica intima; *m*, muscular coat or tunica media; *a*, tunica adventitia. (Klein and Noble Smith.) × 250.

Fig. 153.—Transverse section through a large branch of the inferior mesenteric artery of a pig. *e*. Endothelial membrane; *i*, tunica elastica interna, no subendothelial layer is seen; *m*, muscular tunica media, containing only a few wavy elastic fibres; *e*, *c*, tunica elastica externa, dividing the media from the connective tissue adventitia, *a*. (Klein and Noble Smith.) × 350.

Fig. 154.—Muscular fibre-cells from human arteries, magnified 350 diameters. (Kölliker.) *a*, Nucleus. *b*, a fibre-cell treated with acetic acid.

(*c*) The *internal coat* is formed by a layer of elastic tissue, called the *fenestrated coat of Henle*. It is peculiar in its tendency to curl up, when peeled off from the artery, and in the perforated and streaked appearance which it presents under the microscope. Its inner surface is lined with a delicate layer of elongated endothelial cells (fig. 153, *e*),

make it smooth and polished, and furnish a nearly impermeable
e, along which the blood may flow with the smallest possible
t of resistance from friction.

mediately external to the endothelial lining of the artery is fine
ctive tissue, the *sub-endothelial layer*, with branched corpuscles.
the internal coat consists of three parts, (*a*) an endothelial lining,
e sub-endothelial layer, and (*c*) elastic layers.

*sa Vasorum.*—The walls of the arteries, with the exception of



155.—Transverse section of aorta through internal and about half the middle coat.

dothelial lining and the layers of the internal coat immediately
e it, are not nourished by the blood which they convey, but are,
ther parts of the body, supplied with little arteries, ending in
ries and veins, which, branching throughout the external coat,
l for some distance into the middle, but do not reach the internal
These nutrient vessels are called *vasa vasorum*.

*rves.*—Most of the arteries are surrounded by a plexus of sympa-
nerves, which twine around the vessel very much like ivy round
and ganglia are found at frequent intervals. The smaller arter-
also surrounded by a very delicate network of similar nerve-fibres,
of which appear to end near the nuclei of the transverse muscular
(fig. 156).

## The Capillaries.

*Distribution.*—In all vascular textures except some parts of th
pora cavernosa of the penis, and of the uterine placenta, and
spleen, the transmission of the blood from the minute branches
arteries to the minute veins is effected through a network of capil
They may be seen in all minutely injected preparations.

The point at which the arteries terminate and the minute vein
mence, cannot be exactly defined, for the transition is gradual; b



Fig. 156.—Ramification of nerves and termination in the muscular coat of a small arter
frog. (Arnold.)

capillary network has, nevertheless, this peculiarity, that the
vessels which compose it maintain the same diameter throughout
do not diminish in diameter in one direction, like arteries and
and the meshes of the network that they compose are more un
in shape and size than those formed by the anastomoses of the m
arteries and veins.

*Structure.*—This is much more simple than that of the arter
veins. Their walls are composed of a single layer of elongated or
ate, flattened and nucleated cells, so joined and dovetailed toget
to form a continuous transparent membrane (fig. 157). Outside
cells, in the larger capillaries, there is a structureless or very
fibrillated membrane, on the inner surface of which they are laid
In some cases this external membrane is nucleated, and may th
regarded as a miniature representative of the tunica adventitia of art
Here and there at the junction of two or more of the delicate end
lial cells which compose the capillary wall, pseudo-stomata may be

'he *diameter* of the capillary vessels varies somewhat in the different ıres of the body, the most common size being about $\frac{1}{3000}$th of an , $12\mu$. Among the smallest may be mentioned those of the brain, of the follicles of the mucous membrane of the intestines; among largest, those of the skin, and especially those of the medulla of ·s.

[he *size* of capillaries varies necessarily in different animals in rela-



7.—Capillary blood-vessels from the omentum of rabbit, showing the nucleated endothelial membrane of which they are composed. (Klein and Noble Smith.)

to the size of their blood corpuscles: thus, in the Proteus, the capil- circulation can just be discerned with the naked eye.

'he *form* of the capillary network presents considerable variety in lifferent textures of the body: the varieties consisting principally odifications of two chief kinds of mesh, the rounded and the elon- d. That kind in which the meshes or interspaces have a roundish ı is the most common, and prevails in those parts in which the llary network is most dense, such as the lungs (fig. 158), most ds, and mucous membranes, and the cutis. The meshes of this of network are not quite circular but more or less angular, some- s presenting a nearly regular quadrangular or polygonal form, but g more frequently irregular. The capillary network with elongated ıes is observed in parts in which the vessels are arranged among lles of fine tubes or fibres, as in muscles and nerves. In such parts, meshes form parallelograms, the short sides of which may be from e to eight or ten times less than the long ones; the long sides being e or less parallel to the long axis of the fibre. The rounded and gated meshes vary according as the vessels composing them are ght or tortuous.

[he *number* of the capillaries and the *size of the meshes* in different s determine in general the degree of *vascularity* of those parts.

The capillary network is closest in the lungs and in the choroid co
the eye. In the iris and ciliary body, the interspaces are some
wider, yet very small. In the human liver the interspaces are of
same size, or even smaller than the capillary vessels themselves. In
human lung they are smaller than the vessels; in the human kid
and in the kidney of the dog, the diameter of the injected capilla
compared with that of the interspaces, is in the proportion of on
four, or of one to three. The brain receives a very large quantit
blood; but its capillaries are very minute, and are less numerous
in some other parts. In the mucous membranes—for example in
conjunctiva and in the cutis vera, the capillary vessels are much l
than in the brain, and the interspaces narrower,—namely, not



Fig. 158.



Fig. 159.

Fig. 158.—Network of capillary vessels of the air-cells of the horse's lung magnified
Capillaries proceeding from *b*, *b*, terminal branches of the pulmonary artery. (Frey.)
Fig. 159.—Injected capillary vessels of muscle seen with a low magnifying power. (Sha

than three or four times wider than the vessels. In the perios
the meshes are much larger. In the external coat of arteries, the
of the meshes is ten times that of the vessels.

It may be held as a general rule, that the more active the func
of an organ are, the more vascular it is. Hence the narrowness o
interspaces in all glandular organs, in mucous membranes, and in
ing parts; their much greater width in bones, ligaments, and other
tough and comparatively inactive tissues; and the usually com
absence of vessels in cartilage, and such parts as those in which, p
bly, very little vital change occurs after they are once formed.

## The Veins.

*Distribution.*—The venous system begins in small vessels which are lightly larger than the capillaries from which they spring. These vessels are gathered up into larger and larger trunks until they terminate (as regards the systemic circulation) in the two venæ cavæ and the coronary veins, which enter the right auricle, and (as regards the pulmonary circulation) in four pulmonary veins, which enter the left auricle. The total capacity of the veins diminishes as they approach the heart; but, as a rule, their capacity exceeds by twice or three times that of their corresponding arteries. The pulmonary veins, however, are an exception to this rule, as they do not exceed in capacity the pulmonary arteries. The veins are found after death more or less collapsed, and often contain blood. They are usually distributed in a superficial and a deep set which communicate frequently in their course.



**Fig. 160.—Transverse section through a small artery and vein of the mucous membrane of a child's epiglottis: the artery is thick-walled and the vein thin-walled. A. Artery, the letter is placed in the lumen of the vessel. *e*. Endothelial cells with nuclei clearly visible; these cells appear very thick from the contracted state of the vessel. Outside it a double wavy line marks the elastic tunica intima. *m*. Tunica media consisting of unstriped muscular fibres circularly arranged; their nuclei are well seen. *a*. Part of the tunica adventitia showing bundles of connective-tissue fibre in section, with the circular nuclei of the connective-tissue corpuscles. This coat gradually merges into the surrounding connective-tissue. V. In the lumen of the vein. The other letters indicate the same as in the artery. The muscular coat of the vein (*m*) is seen to be much thinner than that of the artery. × 350. (Klein and Noble Smith.)**

*Structure.*—In structure the coats of veins bear a general resemblance to those of arteries (fig. 160). Thus, they possess outer, middle, and internal coats.

The *outer* coat is constructed of areolar tissue like that of the arteries, but is thicker. In some veins it contains muscular fib which are arranged longitudinally.

The *middle* coat is considerably thinner than that of the art contains circular unstriped muscular fibres, mingled with a la portion of yellow elastic and white fibrous tissue. In the larg near the heart, namely the *venæ cavæ* and pulmonary veins, th coat is replaced, for some distance from the heart, by circularly striped muscular fibres, continuous with those of the auricles.



Fig. 161.—Diagram showing valves of veins. A, part of a vein laid open and spread o pairs of valves. B, longitudinal section of a vein, showing the apposition of the edges o in their closed state. C, portion of a distended vein, exhibiting a swelling in the situati of valves.



Fig. 162.—A, vein with valves open. B, vein with valves closed: stream of blood pa lateral channel. (Dalton.)

The *internal* coat of veins consists of a fenestrated membran may be absent in the smaller ones, lined by endothelium.

**Valves.**—The chief influence which the veins have in the tion, is effected with the help of the valves, contained in all v ject to local pressure from the muscles between or near which t

eral construction of these valves is similar to that of the semi-
lves of the aorta and pulmonary artery, already described; but
e margins are turned in the opposite direction, *i. e.*, *toward* the
as to prevent any movement of blood backward. They are
ly placed in pairs, at various distances in different veins, but
niformly in each (fig. 161). In the smaller veins single valves
met with; and three or four are sometimes placed together, or
e another, in the largest veins,
in the subclavians, at their junc-
h the jugular veins. The valves
ilunar; the unattached edge be-
ome examples concave, in others
They are composed of inexten-
us tissue, and are covered with
ium like that lining the veins.
the period of their inaction, when
us blood is flowing in its proper
, they lie by the sides of the veins;
n in action, they come together
valves of the arteries (figs. 161 and
heir situation in the superficial
the forearm is readily discovered
ing along its surface, in a direc-
osite to the venous current, *i.e.*,
elbow toward the wrist; when
ellings (fig. 161, c) appear in the
of each pair of valves. These
at once disappear when the pres-
emoved.



Fig. 163.—Surface view of an artery from the mesentery of a frog, ensheathed in a peri-vascular lymphatic vessel. *a*. The artery, with its circular muscular coat (media) indicated by broad, transverse markings, with an indication of the adventitia outside. *l*. Lymphatic vessel, its wall is a simple endothelial membrane. (Klein and Noble Smith.

es are not equally numerous in all
nd in many they are absent al-
. They are most numerous in
s of the extremities, and more
ose of the leg than the arm. They are commonly *absent* in
less than 2 mm. in diameter, and, as a general rule there
or none in those which are not subject to muscular pres-
mong those veins which have no valves may be mentioned the
and inferior vena cava, the trunk and branches of the portal
hepatic and renal veins, and the pulmonary veins; those in the
of the cranium and vertebral column, those of the bones, and
k and branches of the umbilical vein are also destitute of valves.

*phatics of Arteries and Veins.*—Lymphatic spaces are present
ats of both arteries and veins; but in the tunica adventitia or
coat of large vessels they form a distinct plexus of more or less

tubular vessels. In smaller vessels they appear as sinous spaces lined by endothelium. Sometimes, as in the arteries of the omentum, mesentery, and membranes of the brain, in the pulmonary, hepatic, and splenic arteries, the spaces are continuous with vessels which distinctly ensheath them—*perivascular lymphatic sheaths* (fig. 163). Lymph channels are said to be present also in the tunica media.

## The Action of the Heart.

The heart's action in propelling the blood consists in the successive alternate contraction (**systole**) and relaxation (**diastole**) of the muscular walls of its two auricles and two ventricles.

**Action of the Auricles.**—The description of the action of the heart may be commenced at that period in each cycle which immediately precedes the beat of the heart against the chest wall. The whole heart is then in a passive state; the auricles are gradually filling with blood flowing into them from the veins; and a portion of this blood is passing at once through them into the ventricles, the opening between the cavity of each auricle and that of its corresponding ventricle being, during all the *pause*, free and patent. The auricles, however, receiving more blood than at once passes through them to the ventricles, become, near the end of the pause, fully distended; and at the end of the pause, they contract and expel their contents into the ventricles.

The contraction of the auricles is sudden and very quick; it commences at the entrance of the great veins into them, and is thence propagated toward the auriculo-ventricular opening, forcing the contained blood into the ventricle. The reflux of blood into the great veins during the auricular systole is resisted not only by the mass of blood within them, but also by the simultaneous contraction of the muscular coats with which the large veins are provided near their entrance into the auricles. Any slight regurgitation from the right auricle is limited by the valves at the junction of the subclavian and internal jugular veins, beyond which the blood cannot move backward; and the coronary vein is preserved from it by a valve at its mouth.

The force of the blood propelled into the ventricle at each auricular systole is transmitted in all directions, but being insufficient to open the semilunar valves, it is expended in distending the ventricle.

**Action of the Ventricles.**—The dilatation of the ventricles which proceeds during the chief part of the dilatation of the auricles is completed by the forcible injection of the contents of the latter. Thus distended, the ventricles immediately contract: so immediately, indeed, that their systole looks as if it were continuous with that of the auricles. The ventricles contract much more slowly than the auricles, and in their contraction probably always thoroughly empty themselves

ng in this respect from the auricles, in which, even after their
ete contraction, a small quantity of blood remains. The shape of
entricles during systole undergoes an alteration when the chest is
l, the diameter in the plane of the base being diminished, but the
of the heart as a whole is not altered (Ludwig). Haycraft states
he heart undergoes no change of shape in the unopened chest.
g the systole of the ventricles, too, the aorta and pulmonary
, being filled with blood by the force of the ventricular ac-
gainst considerable resistance, elongate as well as expand, and
ole heart moves slightly toward the right and forward, twisting
long axis, and exposing more of the left ventricle anteriorly than
lly in front. When the systole ends the heart resumes its former
n, rotating to the left again as the aorta and pulmonary artery
ct. After the whole of the blood has been expelled from the
les, the walls are believed to remain contracted for a short period
the rapid re-dilatation of the chambers begins.

**tion of the Valves.**—(1) *The Auriculo-Ventricular.*—During
e of both ventricles and auricles, blood flows directly through the
into the ventricle, the auricle, during this period, acting as a
uation of the large veins which empty into it. At the end of this
, the ventricle has already been nearly filled. The systole of the
, which now takes place, completes this filling and at the same
ightly overdistends the ventricle. When the force of the auricu-
ntraction is spent, the ventricular walls reassume their former
n, and in so doing exert some pressure upon the ventricular side
auriculo-ventricular valves, which are gently forced toward the
. In connection with this, another force comes into play, viz.:
or back currents, resulting from the flow of blood under increased
re during auricular systole from the auricle into the ventricle
h a comparatively narrow orifice into a wider cavity. These cur-
which continue for a moment after the central current ceases,
floating the valve leaflets into apposition. Thus, the auriculo-
cular openings are closed at the end of auricular systole or the end
tricular diastole, and before ventricular systole has actually begun.
ntricular systole which follows simply serves to place the valves
greater tension and to close them still more firmly. It should be
cted that the diminution in the breadth of the base of the heart
transverse diameters during ventricular systole is especially
l in the neighborhood of the auriculo-ventricular rings, and this
rendering the auriculo-ventricular valves competent to close the
gs, by greatly diminishing their diameter. The margins of the
f the valves are still more secured in apposition with one another,
simultaneous contraction of the musculi papillares, whose chordæ

tendineæ have a special mode of attachment for this object. The cu of the auriculo-ventricular valves meet not by their edges only, but b the opposed surfaces of their thin outer borders.

The form and position of the fleshy columns on the internal walls o the ventricle no doubt help to produce the obliteration of the ventricu lar cavity during contraction; and the completeness of the closure m often be observed on making a transverse section of a heart short after death, in any case in which *rigor mortis* is very marked (Fig. 149) In such a case only a central fissure may be discernible to the eye in th place of the cavity of each ventricle.

If there were only circular fibres forming the ventricular wall, it evident that on systole the ventricle would elongate; if there were o longitudinal fibres, the ventricle would shorten on systole; but th are both. The tendency to alter in length is thus counterbalanc and the whole force of the contraction is expended in diminishing t cavity of the ventricle; or, in other words, in expelling its contents.

On the conclusion of the systole the ventricular walls tend to exp by virtue of their elasticity, and a negative pressure is set up, wh tends to suck in the blood. This negative or suctional pressure on t left side of the heart is of the highest importance in helping the p monary circulation. It has been found to be equal to 23 mm. of m cury, and is quite independent of the aspiration or suction power of t thorax itself, which will be described in a later chapter.

The musculi papillares prevent the auriculo-ventricular valves fro being everted into the auricle. For the chordæ tendineæ might allo the valves to be pressed back into the auricle, were it not that when t wall of the ventricle is brought by its contraction nearer the auricul ventricular orifice, the musculi papillares more than compensate for th by their own contraction—holding the chords tight, and, by pullin down the valves, adding slightly to the force with which the blood i expelled.

These statements apply equally to the auriculo-ventricular valves both sides of the heart; the closure of both is generally complete ev time the ventricles contract. But in some circumstances the tricus valve does not completely close, and a certain quantity of blood forced back into the auricle. This has been called the *safety-valve acti* The circumstances in which it usually happens are those in which t vessels of the lung are already completely full when the right ventri contracts, as, *e.g.*, in certain pulmonary diseases, in very active exertio and in great efforts. In these cases, the tricuspid valve does not co pletely close, and the regurgitation of the blood may be indicated by pulsation in the jugular veins synchronous with that in the caro arteries.

(2.) *The Semilunars.*—It has been shown that the commencement

ricular systole precedes the opening of the semilunar valves by a
of a second. This would seem to show that the intraventricular
does not exceed the arterial pressure until the systole has actually
or the opening of the valves takes place at once when there is a
difference in favor of the intraventricular over the arterial press-
continues open only as long as this difference continues. When
ial begins to exceed the intraventricular pressure, there is, as it
eflux of blood toward the heart, and the valves close. The dila-
the arteries is, in a peculiar manner, adapted to bring this about.
er borders of the semilunar valves are attached to the inner
f the tendinous ring, which is, as it were, inlaid at the orifice
rtery, between the muscular fibres of the ventricle and the
bres of the walls of the artery. The tissue of this ring is tough,
not admit of extension under such pressure as it is commonly
to; the valves are equally inextensile, being, as already men-
formed mainly of tough, close-textured, fibrous tissue, with
nterwoven cords. Hence, when the ventricle propels blood
the orifice and into the canal of the artery, the lateral pressure
exercises is sufficient to dilate the walls of the artery, but not
o stretch in an equal degree, if at all, the unyielding valves and
to which their lower borders are attached. The effect, there-
each such propulsion of blood from the ventricle is, that the
he first portion of the artery is dilated into three pouches behind
the valves, while the free margins of
the valves are drawn inward toward its
centre (fig. 164 B). Their positions
may be explained by the diagrams, in
which the continuous lines represent
a transverse section of the arterial
walls, the dotted ones the edges of the
valves, firstly, when the valves are
nearest to the walls (A), as in the dead
heart, and secondly, when, the walls
being dilated, the valves are drawn
away from them (B).



Sections of aorta, to show the
semilunar valves. A is intended
valves, represented by the dotted
ear the arterial walls, represented
nuous outer line. B (after Hun-
the arterial wall distended into
s (a), and drawn away from the
h are straightened into the form
teral triangle as represented by
es.

This position of the valves and ar-
lls is retained so long as the ventricle continues in contraction:
on as it relaxes, and the dilated arterial walls can recoil by their
, the blood is forced backward toward the ventricles and on-
the course of the circulation. Part of the blood thus forced
in the pouches (sinuses of Valsalva) (*a*, fig. 164, B) between the
d the arterial walls; and the valves are by it pressed together
thin lunated margins meet in three lines radiating from the
the circumference of the artery (7 and 8, fig. 148).

The contact of the valves in this position and the complete closure of the arterial orifice are secured by the peculiar construction of their borders before mentioned. Among the cords which are interwoven in the substance of the valve are two of greater strength and prominence than the rest; of which one extends along the free border of each valve, and the other forms a double curve or festoon just below the free border. Each of these cords is attached by its outer extremities to the outer end of the free margin of its valve, and in the middle to the corpus Arantii; they thus enclose a lunated space from 2 to 3 mm. in width, in which space the substance of the valve is much thinner and more pliant than elsewhere. When the valves are pressed down, all these parts or spaces of their surfaces come into contact, and the closure of the arterial orifice is thus secured by the apposition not of the mere edges of the valves, but of all those thin lunated parts of each which lie between the free edges and the cords next below them. These parts are firmly pressed together, and the greater the pressure that falls on them the closer and more secure is their apposition. The corpora Arantii meet at the centre of the arterial orifice when the valves are down, and they probably assist in the closure; but they are not essential to it, for, not unfrequently, they are wanting in the valves of the pulmonary artery, which are then extended in larger, thin, flapping margins. In valves of this form, also, the inlaid cords are less distinct than in those with corpora Arantii; yet the closure by contact of their surfaces is not less secure.

**Cardiac Cycle.**—Taking 72 as the average number of cardiac revolutions per minute, each revolution may be considered to occupy ⅚ of a second, or about .8, which may be approximately distributed in the following way:—

| | | | | |
|---|---|---|---|---|
| Auricular systole, about | .1 | + | Auricular diastole . . . . | .7 = .8 |
| Ventricular systole " | .3 | + | Ventricular diastole . . . | .5 = .8 |
| Period of joint auricular and ventricular diastole | .4 | + | Period of systole of auricles or ventricles . . | .4 = .8 |

If the speed of the heart be quickened, the time occupied by each cardiac revolution is of course diminished, but the diminution affects only the diastole and pause. The systole of the ventricles occupies very much the same time, whatever the pulse-rate.

The exact period in which the several valves of the heart are in action is a matter of some uncertainty; the auriculo-ventricular valves are probably closed during the whole time of the ventricular contraction, while, during the dilatation and distention of the ventricles, they are open. The semilunar valves are only certainly open during the middle period of the ventricular contraction.

## The Sounds of the Heart.

When the ear is placed over the region of the heart, two *sounds* may heard at every beat of the heart, which follow in quick succession, d are succeeded by a *pause* or period of silence. The *first* sound is ll and prolonged; its commencement coincides with the impulse of e heart against the chest wall, and just precedes the pulse at the wrist. he *second* is shorter and sharper, with a somewhat flapping character, d follows close after the arterial pulse. The periods of time occupied spectively by the two sounds taken together and by the pause between e second and the first, are unequal. According to Foster, the interval time between the beginning of the first sound and the second sound .3 second, while between the second and the succeeding first it is arly .5 (see fig. 165). The relative length of time occupied by each nd, as compared with the other, may be best appreciated by consider- g the different forces concerned in the production of the two sounds. one case there is a strong, comparatively slow, contraction of a large ss of muscular fibres, urging forward a certain quantity of fluid ainst considerable resistance; while in the other it is a strong but orter and sharper recoil of the elastic coat of the large arteries—shorter cause there is no resistance to the flapping back of the semilunar valves, there was to their opening. The sounds may be expressed by the ords *lŭbb—dŭp*.

The events which correspond, in point of time, with the *first* sound, re (1) the contraction of the ventricles, (2) the first part of the dilata- ion of the auricles, (3) the tension of the auriculo-ventricular valves, (4) the opening of the semilunar valves, and (5) the propulsion of blood into the arteries. The sound is succeeded, in about one-thirtieth of a econd, by the pulsation of the facial arteries, and in about one-sixth of second, by the pulsation of the arteries at the wrist. The *second* sound, n point of time, immediately follows the cessation of the ventricular ontraction, and corresponds with (*a*) the tension of the semilunar alves, (*b*) the continued dilatation of the auricles, (*c*) the commencing ilatation of the ventricles, and (*d*) the opening of the auriculo-ventric- lar valves. The *pause* immediately follows the second sound, and rresponds *in its first part* with the completed distention of the auri- es, and *in its second* with their contraction, and the completed disten- on of the ventricles; the auriculo-ventricular valves being all the time the pause open, and the arterial valves closed.

**Causes.**—The exact cause of the first sound of the heart is not own. Two factors probably enter into it, viz., firstly *the vibration the auriculo-ventricular valves* and of the chordæ tendineæ. This bration is produced by the increased intraventricular pressure set up when the ventricular systole commences, which puts the valves on the stretch. The question whether this stretched condition of the valve continues throughout the whole of the ventricular systole cannot be definitely settled, but if it does not, the valvular element may possibly take part in the production of the first part of the first sound only. It is not unlikely too that the vibration of the ventricular walls themselves, and of the aorta and pulmonary artery, all of which parts are suddenly



Fig. 165.—Diagrammatic representation of the events of the cardiac cycle. For events which occur in sequence, read in the direction of the curved arrow; for synchronous events, read from the centre to the periphery in any direction. (Coleman.)

put into a state of tension at the moment of ventricular contraction, may have some part in producing the first sound. Secondly, *the muscular sound* produced by contraction of the mass of muscular fibres which form the ventricle. Looking upon the contraction of the heart as a single contraction and not as a series of contractions or tetanus, it is at first sight difficult to see why there should be any muscular sound at all when the heart contracts, as a single muscle contraction does not produce sound. It has been suggested, however, that it arises fr the repeated unequal tension produced when the wave of muscular co tractions passes along the very intricately arranged fibres of the ventric-ar walls. The valvular element is probably the more important of e two factors.

The cause of the *second* sound is more simple than that of the first. is entirely due to the vibration consequent on the sudden closure of e semilunar valves when they are pressed down across the orifices of e aorta and pulmonary artery. The influence of these valves in procing the sound was first demonstrated by Hope who experimented th the hearts of calves. In these experiments two delicate curved edles were inserted, one into the aorta, and another into the pulmory artery, below the line of attachment of the semilunar valves, and, er being carried upward about half an inch, were brought out again rough the coats of the respective vessels, so that in each vessel one lve was included between the arterial walls and the wire. Upon apying the stethoscope to the vessels, after such an operation, the second und had ceased to be audible. Disease of these valves, when sufficient interfere with their efficient action, also demonstrates the same fact modifying the valvular cause of the second sound or destroying its tinctness.

One reason that the second sound is clearer and sharper than the first ay be, that the semilunar valves are not covered in by the thick layer fibres composing the walls of the heart to such an extent as are the riculo-ventricular. It might be expected therefore that their vibraion would be more easily heard by means of a stethoscope applied to he walls of the chest.

The contraction of the auricles which takes place in the end of the pause is inaudible outside the chest, but is said to be heard, when the heart is exposed and the stethoscope placed on it, as a slight sound preceding and continued into the louder sound of the ventricular contraction.

## The Impulse of the Heart.

With each contraction the heart may be felt to beat with a slight shock or *impulse* against the walls of the chest. The force of the impulse and the extent to which it may be perceived beyond this point vary considerably in different individuals, and in the same individual under different circumstances. It is felt more distinctly, and over a larger extent of surface, in emaciated than in fat and robust persons, and more during a forced expiration than in a deep inspiration; for, in the one case, the intervention of a thick layer of fat or muscle between the heart and the surface of the chest, and in the other the inflation of the portion of lung which overlaps the heart, prevents the impulse from eing fully transmitted to the surface. An excited action of the heart, and especially a hypertrophied condition of the ventricles, will increase the impulse; while a depressed condition, or an atrophied state of the ventricular walls, will diminish it.

*Cause of the Impulse.*—During the period which precedes the ventricular systole the apex of the heart is situated upon the diaphragm and against the chest-wall in the fifth intercostal space. When the ventricles contract, their walls become hard and tense, since to expel their contents into the arteries is a distinctly laborious action, as it is resisted by the elasticity of the vessels. It is to this sudden hardening that the impulse of the heart against the chest-wall is due, and the shock of the sudden tension may be felt not only externally, but also internally, if the abdomen of an animal be opened and the finger be placed upon the


Tube to communicate with tambour.
Tympanum.
Ivory knob.
Tape to attach the instrument to the chest.

Fig. 166.—Cardiograph. (Sanderson's.)



Fig. 167.—Marey's Tambour, to which the movement of the column of air in the first tympanum is conducted by a tube, and from which it is communicated by the lever to a revolving cylinder, so that the tracing of the movement of the impulse beat is obtained.

rface of the diaphragm, at a point corresponding to the under
f the ventricle. The shock is felt, and possibly seen more dis-
ecause of the partial rotation of the heart, already spoken of,
long axis toward the right. The movement produced by the
lar contraction against the chest-wall may be registered by means
strument called the *cardiograph*, and it will be found to corre-
most exactly with a tracing obtained by the same instrument
ver the contracting ventricle itself.

**rdiograph** (fig. 166) consists of a cup-shaped metal box over the open
hich is stretched an elastic India-rubber membrane, upon which is
mall knob of hard wood or ivory. This knob, however, may be at-
in the figure, to the side of the box by means of a spring, and may
o act upon a metal disc attached to the elastic membrane.

ob is for application to the chest-wall over the place of the great-
e of the heart. The box or *tympanum* communicates by means of
ht tube with the interior of a second tympanum, in connection with
a long and light lever. The shock of the heart's impulse being
ated to the ivory knob, and through it to the first tympanum, the



Cardiogram of Frog's Heart. C, Tracing of auricular and ventricular systole; T, time in half seconds.

of course, at once transmitted by the column of air in the elastic tube
terior of the second tympanum, also closed, and through the elastic
ble lid of the latter to the lever, which is placed in connection with
ing apparatus. This generally consists of a cylinder or drum covered
ked paper, revolving by clock-work with a definite velocity. The
the lever writes upon the paper, and a tracing of the heart's impulse
ram is thus obtained.

## Endocardiac Pressure.

nnot be considered, however, that the cardiogram represents
actually occurring within the heart itself. For determining
mmunication must be established with the cavities of the heart.

By placing three small India-rubber air-bags or *cardiac sounds* in th interior respectively of the right auricle and the right ventricle, and i an intercostal space in front of the heart of living animals (horse), an placing these bags, by means of long, narrow tubes, in communicatio with three levers, arranged one over the other in connection with a re



Fig. 168.—Apparatus of MM. Chauveau and Marey for estimating the variations of endocard pressure, and production of impulse of the heart.

istering apparatus (fig. 168), Chauveau and Marey have been able to r cord and measure with much accuracy the variations of the endocardi pressure and the comparative duration of the contractions of the auricl and ventricles. By means of the same apparatus, the synchronism the impulse with the contraction of the ventricles, is also well show and the causes of the several vibrations of which it is really compose have been demonstrated.

In the tracing (fig. 169), the intervals between the vertical lines re resent periods of a tenth of a second. The parts on which any giv vertical line falls represent simultaneous events. It will be seen th the contraction of the auricle, indicated by the marked curve at A first tracing, causes a slight increase of pressure in the ventricle whi is shown at A′ in the second tracing, and produces also a slight impul which is indicated by A″ in the third tracing. The closure of the sem lunar valves causes a momentarily increased pressure in the ventricle D′, affects the pressure in the auricle D, and is also shown in the traci of the impulse D″.

The large curve of the ventricular and the impulse tracings, betw A′ and D′, and A″ and D″, are caused by the ventricular contraction, wh the smaller undulations, between B and C, B′ and C′, B″ and C″, caused by the vibrations consequent on the tightening and closure the auriculo-ventricular valves.

It seems by no means certain that Marey's curves properly repres the variations in intraventricular pressure. Much objection has b o his method of investigation. Firstly, because his tambour arent does not admit of both positive and negative pressure being neously recorded. Secondly, because the method is only applicable animals, such as the horse. And thirdly, because the intravenchanges of pressure are communicated to the recording tambour ig elastic column of air; and fourthly, because the tambour arent has a tendency to record inertia vibrations. H. D. Rolleston, pointed out the above imperfections of Marey's method, has reated the subject with a more suitable apparatus. The method



Tracings of (1), Intra-auricular, and (2), Intra-ventricular pressures, and (3), of the imthe heart, to be read from left to right, obtained by Chauveau and Marey's apparatus.

by Rolleston is as follows: a window is made in the chest of thetized and curarized animal, and an appropriately curved glass introduced through an opening in the auricular appendix. ula is then passed through the auriculo-ventricular orifice withsing any appreciable regurgitation, into the auricle, or it may be ced into the cavity of the right or left ventricle by an opening n the apex of the heart. In some experiments the trocar is through the chest wall into the ventricular cavity. The appafilled with a solution of leech extract in .75 per cent saline soor with a solution of sodium bicarbonate of specific gravity 1083. imals employed were chiefly dogs. The movement of the column l is communicated to the writing lever by means of a vulcanite which moves with little friction in a brass tube connected with s canula by means of a short connecting tube.

en the lower part of the tube (A) is placed in communication with the cavities of the heart, the movements of the piston are reby means of the lever (C). Attached to the lever is a section of (H), the axis of which coincides with that of the steel ribbon ile, firmly fixed to the piston, is the curved steel piston rod (1), from the top of which a strong silk thread (J) passes downward in groove on the pulley.

This thread (J), after being twisted several times round a sma at the side of the lever, enters the groove in the pulley from above ward, and then passes to be fixed to the lower part of the curve piston-rod as shown in the smaller figure.

The rise and fall of the lever (C) is controlled by the resista



Fig. 170.—Apparatus for recording the endocardial pressure. (Rolleston.)

torsion of the steel ribbon (E), to the middle of which one end lever is securely fixed by a light screw clamp (F). At some di from this clamp—the distance varying with the degree of resi which it is desired to give to the movements of the lever—are two ers (G.G′) which securely clamp the steel ribbon.

As the torsion of a steel wire or strip follows Hooke's law, th sion being proportional to the twisting force—the movements lever point are proportional to the force employed to twist the stee or ribbon—in other words to the pressures which act on the pisto

To make it possible to record satisfactorily the very varying v ular and auricular pressures, the resistance to torsion of a steel adapts itself very conveniently.

This resistance can be varied in two ways, 1st, by using one or pieces of steel ribbon or by using strips of different thicknesses;

ing the distance between the holders (G.G.) and the central part
teel ribbon to which the lever is attached.

ston's conclusions are as follows:—

'hat there is no distinct and separate auricular contraction



—Endocardial pressure-curve from the left ventricle. The thorax was opened and a
duced through the apex of the ventricle; abscissa is line of atmospheric pressure. G
nts ventricular contraction; from D to the next rise at G represents the ventricular
he notch at the top of which is F is a post-ventricular rise in pressure from below that
sphere and not a pre-systolic or auricular rise in pressure.

in the curves obtained from either right or left ventricles, the
· and ventricular rises of pressure being merged into one con-
rise.

ıat the auriculo-ventricular valves are closed before any great
ressure within the ventricle above that which results from the
r systole (*a*, fig. 172). The closure of the valve occurs probably



urve with dicrotic summit from left ventricle; abscissa shows atmospheric pressure.

ower third of the rise A B (fig. 172), and does not produce any
r wave.

'hat the semilunar valves open at the *point* in the ventricular
situated (at G) about or a little above the junction of the mid-
pper third of the ascending line (A B), and the closure about or
before the shoulder (D).

'hat the minimum pressure in the ventricle may fall below that
tmosphere, but that the amount varies considerably.

## Frequency of the Heart's Action.

**The heart of a healthy adult man contracts about 72 times minute; but many circumstances cause this rate, which of cours responds with that of the arterial pulse, to vary even in health. chief are age, temperament, sex, food and drink, exercise, time o posture, atmospheric pressure, temperature; as follows:—**

**(1.) *Age.*—The frequency of the heart's action gradually dimi from the commencement to near the end of life, but is said t again somewhat in extreme old age, thus:—**

| | | | |
|---|---|---|---|
| **Before birth the average number of pulsations per minute is** | **150** | **About the seventh year . . . from** | **90** |
| **Just after birth . from** | **140 to 130** | **About the fourteenth year . . .** | **85** |
| **During the first year** | **130 to 115** | **In adult age . .** | **80** |
| **During the second year . . .** | **115 to 100** | **In old age . .** | **70** |
| **During the third year** | **100 to 90** | **In decrepitude . .** | **75** |

**(2.) *Temperament and Sex.*—In persons of sanguine tempera the heart acts somewhat more frequently than in those of the matic; and in the female sex more frequently than in the male.**

**(3 and 4.) *Food and Drink. Exercise.*—After a meal the action is accelerated, and still more so during bodily exertion or excitement; it is slower during sleep.**

**(5.) *Diurnal Variation.*—In health the pulse is most frequent morning, and becomes gradually slower as the day advances: an diminution of frequency is both more regular and more rapid evening than in the morning.**

**(6.) *Posture.*—The pulse, as a general rule, especially in the male, is more frequent in the standing than in the sitting postur in the latter than in the recumbent position; the difference greatest between the standing and the sitting postures. The eff change of posture is greater as the frequency of the pulse is g and, accordingly, is more marked in the morning than in the ev By supporting the body in different positions, without the aid of cular effort of the individual, it has been proved that the increase quency of the pulse in the sitting and standing positions is depe upon the muscular exertion engaged in maintaining them; the effect of these postures on the pulse being almost entirely pre when the usually attendant muscular exertion was rendered unnec**

**(7.) *Atmospheric Pressure.*—The frequency of the pulse incre a corresponding ratio with the elevation above the sea.**

**(8.) *Temperature.*—The rapidity and force of the heart's c tions are largely influenced by variations of temperature. The heart, when excised, ceases to beat if the temperature be redu**

C. (32° F.). When heat is gradually applied to it, both the speed d force of the contractions increase till they reach a maximum. If e temperature is still further raised, the beats become irregular and eble, and the heart at length stands still in a condition of "heat-gor." Similar effects are produced in warm-blooded animals. In the bbit, the number of heart-beats is more than doubled when the temrature of the air was maintained at 40°.5 C. (105° F.). At 45° C. (113° 114° F.), the rabbit's heart ceases to beat.

In health there is observed a nearly uniform relation between the quency of the beats of the heart and of the respirations; the propor-n being, on an average, 1 respiration to 3 or 4 beats. The same rela-n is generally maintained in the cases in which the action of the heart naturally accelerated, as after food or exercise; but in disease this ation may cease. In many affections accompanied with increased quency of the heart's contraction, the respiration is, indeed, also elerated, yet the degree of its acceleration may bear no definite pro-rtion to the increased number of the heart's actions: and in many er cases, the heart's contraction becomes more frequent without any ompanying increase in the number of respirations; or, the respiration ne may be accelerated, the number of pulsations remaining station-, or even falling below the ordinary standard.

## The Force of the Cardiac Action.

(*a.*) *Ventricular.*—The force of the left ventricular systole is more an double that exerted by the contraction of the right ventricle: this ference results from the walls of the left ventricle being about twice three times as thick as those of the right. And the difference is apted to the greater degree of resistance which the left ventricle has overcome, compared with that to be overcome by the right: the rmer having to propel blood through every part of the body, the latter ly through the lungs. The actual amount of the intraventricular essures during systole in the dog has been found to be 2.4 inches (60 m.) of mercury in the right ventricle, and 6 inches (150 mm.) in the eft.

During *diastole* there may be in the right ventricle a negative or suc-tion pressure of about $\frac{2}{3}$ of an inch (− 17 to − 16 mm.), and in the left ntricle from 2 inches to $\frac{4}{5}$ of an inch (− 52 to − 20 mm.). Part of this fall in pressure, and possibly the greater part, is to be referred to the influence of respiration; but without this the negative pressure of the left ventricle caused by its active dilatation is about equal to $\frac{4}{5}$ of an inch (20 mm. )of mercury.

The right ventricle is undoubtedly aided by this suction power of the left, so that the whole of the work of conducting the pulmonary

circulation does not fall upon the right side of the heart, but is as
by the left side.

(*b.*) *Auricular.*—The maximum pressure within the right auric
equal to about ¾ of an inch (20 mm.) of mercury, and is probably so
what less in the left. It has been found that during diastole the p
sure within both auricles sinks considerably below that of the at
phere; and as some fall in pressure takes place, even when the th
of the animal operated upon has been opened, a certain proportio
the fall must be due to active auricular dilatation independent of r
ration in the right auricle, this negative pressure is equal to a
−10 mm.

In estimating the work done by any machine it is usual to ex
it in terms of the unit of work. In England, the unit of work i
*foot-pound,* and is defined to be the energy expended in raising a
of weight (1 lb.) through a unit of height (1 ft.): in France, the
*gram-metre.* The **work done** by the heart at each contraction c
readily found by multiplying the weight of blood expelled by the
tricles by the height to which the blood rises in a tube tied in
artery. This height is probably about 9 ft. (3.21 metres) in man.
ing the weight of blood expelled from the left ventricle at each s
at 6 oz., *i.e.,* ⅜ lb., we have $9 \times \frac{3}{8} = 3.375$ foot-pounds, or $3.21 \times 180$
or 578 gram-metres, as the work done by the left ventricle at eac
tole; and adding to this the work done by the right ventricle (
one-fourth that of the left) we have $3.375 + .822 = 4.19$ foot-poun
722 gram-metres as the work done by the heart at each contractio

## Blood Pressure.

The subject of blood-pressure has been already incidentally
tioned more than once in the preceding pages, the time has now a
for it to receive more detailed consideration.

That the blood exercises pressure upon the walls of the vessel
taining it, is due to the following facts:—

*Firstly,* that the heart at each contraction forcibly injects a c
erable amount of blood, viz., 4 to 6 oz. (120 to 180 grms.) sudden
quickly into the arteries.

*Secondly,* that the arteries are already full of blood at the
mencement of the ventricular systole, since there is not sufficien
between the heart beats for the blood to pass into the veins.

*Thirdly,* that the arteries are highly distensible and stretch
commodate the extra amount of blood forced into them; and

*Fourthly,* that there is a distinct resistance interposed to th
sage of the blood from the arteries into the veins, from the enc
number of minute vessels, small arteries (arterioles) and capillari

h the main artery has been ultimately broken up. The sectional of the capillaries is several hundred times that of the aorta, and riction generated by the passage of the blood through these minute nels opposes a considerable hindrance or resistance in its course. resistance thus set up is called **peripheral resistance.** The fric- is greater in the arterioles where the current is comparatively rapid in the capillaries where it is slow.

hat the blood exerts considerable pressure upon the arterial walls eping them in a stretched or distended condition, may be readily by puncturing any artery; the blood is instantly projected with force through the opening, and the jet rises to a considerable t, the exact level of which varies with the size of the artery expe- ted with. If a large artery be punctured, the blood may be pro- upward for many feet, whereas if a small artery be similarly dealt he jet does not rise to such a height. Another marked feature of t of blood from a cut artery, particularly well marked if the vessel rge one, and near the heart, is the jerky character of the outflow. artery be cut across, the jet issues with force, chiefly from the l end, unless there is considerable anastomosis of vessels in the orhood, when the jet from the peripheral end may be as forcible intermittent as that from the other end. The intermittent flow arteries which is due to the intermittent action of the heart, and represents the systolic and diastolic alterations of blood pressure, e felt if the finger be placed upon a sufficiently superficial artery. nger is apparently raised and lowered by the intermittent systolic tion of the vessel, occurring at each heart beat. This intermittent ion of the artery is what is known as the **Pulse,** to the further eration of which we shall presently return, but we may say here, a normal condition the pulse is a characteristic of the arterial, absent from the venous flow. At the same time it must be recol- that in the veins the blood exercises a pressure on its containing but as we shall see presently this is small when compared with erial blood-pressure. As might be expected, therefore, the blood expelled with so much force if a vein be punctured or cut, and r, the flow from the cut vein is continuous and not intermittent, e greater amount of blood comes from the peripheral and not he central end as is the case when an artery is severed.

e result produced by the experiment of cutting or puncturing a vessel may be modified by introducing into the vessel a glass f a calibre corresponding to that of the vessel, and allowing the to rise in it. If the vessel be an artery, the blood will rise l feet, according to the distance of the vessel from the heart, and it has reached its highest point will be seen to oscillate with art's beats. This experiment shows that the pressure which the blood exerts upon the walls of the contained artery, equals the sure of a column of blood of a certain height; in the case of th bit's carotid it is equal to 3 feet of blood, or rather more than 3 f water. In the case of the vein, if a similar experiment be perfor blood will rise in the tube for an inch or two only.

The usual method of estimating the amount of blood pressure d somewhat from the foregoing simple experiment. Instead of a si straight tube of glass inserted into the vessel, a U-shaped tube con



Fig. 173.—Diagram of mercurial kymograph. A, revolving cylinder, worked by a clock-arrangement contained in the box (B), the speed being regulated by a fan above the box; cyl supported by an upright (*b*), and capable of being raised or lowered by a screw (*a*), by a h attached to it; D, C, E, represent mercurial manometer, a somewhat different form of whi shown in next figure.

ing mercury, **mercurial manometer,** is employed, and the ar is made to communicate with it by means of a small canula whic inserted into the vessel, and a connecting tube, an arrangement be made whereby the canula, tubes, etc., are filled with a saturated sa solution to prevent the clotting of blood when it is allowed to pass fr the artery into the apparatus. The passage of blood is prevented dur the arrangement of the details of the experiment by a pair of clamp bull-dog forceps. The free end of the U-tube of mercury contain very fine glass piston, the bulbous end of which floats upon the surf of the mercury, rising with its rise and oscillating with its oscillatio

As soon as there is free communication between the artery and the tube of mercury, the blood rushes out and pushes before it the column of mercury. The mercury will therefore rise in the free limb of the tube, and will continue to do so until a point is reached which corresponds to the mean pressure of the blood-vessel used. The blood-pressure is thus communicated to the upper part of the mercurial column; and the depth to which the latter sinks, added to the height to which it rises in the other, will give the height of the mercurial column which the blood-pressure balances; the weight of the saline solution being subtracted. For the estimation of the amount of blood pressure at any given moment, no further apparatus than this, which is called Poiseuilles's *hæ-*



Fig. 174.—Ludwig's Kymograph. The manometer is shown in fig. 173, D. C. E. The mercury hich partially fills the tube supports a float in form of a piston, nearly filling the tube; a wire is ced to the float, and the writing style or pen is guided by passing through the brass cap of the be fixed to the wire; the pressure is communicated to the mercury by means of a flexible metal be filled with fluid.

*adynamometer*, is necessary; but for noting the *variations* of pressure the arterial system, as well as its absolute amount, the instrument is sually combined with a recording apparatus, in this form called a *ymograph* (fig. 173).

The recording apparatus consists of a revolving cylinder (fig. 173, ), which is moved by clockwork, and the speed of which is capable of egulation. The cylinder is covered with glazed paper blackened in the ame of a lamp, and the mercurial manometer is so fixed (fig. 173, D) hat its float provided with a style writes on the cylinder as it revolves. There are many ways in which the mercurial manometer may be varied; n fig. 174 is seen a form, which is known as Ludwig's Kymograph. In rder to obviate the necessity of a large quantity of blood entering the ube of the apparatus, it is usual to have some arrangement by means of which the mercury may be made to rise in the tube of the manometer to the level corresponding to the mean pressure of the artery experimented with, so that the writing style simply records the variations of the blood pressure above and below the mean pressure. This is done by causing the saline solution, generally a saturated solution of sodium carbonate or sulphate, to fill the apparatus from a bottle suspended at a height, and capable of being raised or lowered as required for the purpose, or by injecting the saline solution into the tube by means of a syringe. The canula inserted and tied into the artery may be of two kinds. In one case a fine glass tube is used with the end drawn out and cut so that its end is oblique, and provided with a shoulder to prevent its coming out easily, the peripheral end of the cut artery being tied to obviate the escape of blood. By this means, the pressure communicated to the column of mercury is the forward and not the lateral pressure of blood, or a T-canula may be employed and may be tied into the two ends of a divided artery, and the free arm of the T piece being made to communicate with the manometer. This communicates the lateral blood pressure.



Fig. 175.—Normal tracing of arterial pressure in the rabbit obtained with the mercurial kymograph. The smaller undulations correspond with the heart beats; the larger curves with the respiratory movements. (Burdon-Sanderson.)

As soon as the experiment is completed, the writing float is seen to oscillate in a regular manner, and a curve of blood pressure is traced upon the smoked paper by the style (or, if a continuous roll of unsmoked paper be used instead, by an inked pen), when a figure similar to fig. 175 will be obtained.

This indicates two main variations of the blood pressure; the smaller excursions of the lever corresponds with *the systole and diastole of the heart*, and the large curves correspond with the respirations, being called the *respiratory undulations* of blood pressure, to which attention will be directed in the next chapter. Of course, the undulations spoken of are only seen in records of arterial blood pressure; they are more clearly marked in the arteries nearer the heart than in those more remote, in the smaller arteries the amount of the pressure as well as the indication of the systolic rise of pressure, being, comparatively speaking, small.

In order to record the undulations of arterial pressure, for some purposes it is better to use Fick's Spring Kymograph than the mercurial manometer. Two forms of this instrument are shown in figs. 176 and

It consists of a hollow C-spring, filled with fluid, the interior of h is made to communicate with the artery by means of a flexible l tube and canula. In response to the pressure, transmitted to nterior, the spring tends to straighten itself, and the movement produced is communicated by means of a lever to a writing style so to a recording apparatus. This instrument obviates the errors h might be caused by the inertia of the mercury in the mercurial meter; it also shows in more detail the variations of the blood ure in the vessel during and after each individual beat of the heart.



176.—A form of Fick's Spring Kymograph. *a*, Tube to be connected with artery; *c*, hollow the movement of which moves *b*, the writing lever; *e*, screw to regulate height of *b*; *d*, outtective spring; *g*, screw to fix on the upright of the support.

fig. 178 is seen a tracing taken with Fick's Kymograph from an of a dog.

regards the actual amount of blood pressure, from observations have been made by means of the mercurial manometer, it has found that the pressure of blood in the carotid of a rabbit is capasupporting a column of 2 to 3.5 inches (50 to 90 mm.) of mercury, e dog 4 to 7 inches (100 to 175 mm.), in the horse 5 to 8 inches to 200 mm.), and in man the pressure is estimated to be about the

measure the absolute amount of this pressure in any artery, it is sary merely to multiply the area of its transverse section by the t of the column of mercury which is already known to be supported by the blood-pressure in any part of the arterial system. The weight of a column of mercury thus found will represent the pressure of the blood. Calculated in this way, the blood-pressure in the human aorta is equal to 1.93 kgm.; that in the aorta of the horse being 5.2 kgm.; and that in the radial artery at the human wrist only 8 gm. Supposing the muscular power of the right ventricle to be only one-half that of the left, the blood-pressure in the pulmonary artery will be only 1 kgm. The amounts above stated represent the arterial tension to the time of the ventricular contraction.



Fig. 177.—Fick's Kymograph, improved by Hering (after McKendrick). *a*, Hollow spring filled with alcohol, bearing lever arrangement *b*, *d*, *c*, to which is attached the marker *e*; the rod *c* passes downward into the tube *f*, containing castor oil, which offers resistance to the oscillations of *c*; *g*, syringe for filling the leaden tube *b* with saturated sulphate of sodium solution, and to apply sufficient pressure as to prevent the blood from passing into the tube *h* at *i*, the canula inserted into the vessel; *l*, abscissa-marker, which can be applied to the moving surface by turning the screw *m*; *k*, screw for adjusting the whole apparatus to the moving surface; *o*, screw for elevating or depressing by a rack and pinion movement the Kymograph; *n*, screw for adjusting the position of the tube *f*.

The blood-pressure is greatest in the left ventricle and at the beginning of the aorta, and decreases toward the capillaries. It is greatest in the arteries at the period of the ventricular systole. The blood-pressure gradually lessens then as we proceed from the arteries near the heart to those more remote, and again from these to the capillaries, and thence along the veins to the right auricle. The **blood-pressure in the veins** is nowhere very great, but is greatest in the small veins, while in the large veins toward the heart the pressure becomes *negative*, or, in other words, when a vein is put in connection with a mercurial man-meter the mercury will fall in the arm furthest away from the vein and ill rise in the arm nearest the vein, the action being that of suction ather than pressure forward. In the large veins of the neck the ten- ency to suck in air is especially marked, and is the cause of death in me surgical operations in that region. The amount of pressure in the achial vein is said to support 9 mm. of mercury, whereas the pressure the veins of the neck may fall to a negative pressure of rather more an $\frac{1}{3}$ inch or — about $\frac{1}{8}$ to $\frac{1}{3}$ inch or — 3 to — 8 mm.

The variations of venous pressure during systole and diastole of the art are very slight, and a distinct pulse is never seen in veins except der extraordinary circumstances. From observations upon the web the frog's foot, the tongue and mesentery of the frog, the tails of wts, and small fishes (Roy and Brown), as well as upon the skin of e finger behind the nail (Kries), by careful estimation of the amount pressure required to empty the vessels of blood under various condi- ons, it appears that the **blood-pressure** is subject to variations **in e capillaries,** apparently following the variations of that of the



Fig. 178.—Normal arterial tracing obtained with Fick's kymograph in the dog. (Burdon-Sanderson.)

teries; and that up to a certain point, as the extravascular pressure is reased, so does the pulse in the arterioles, capillaries, and venules be- me more and more evident. The pressure in the first case (web of e frog's foot) has been found to be equal to about $\frac{1}{2}$ to $\frac{4}{5}$ inch or 14 to mm. of mercury; in other experiments to be equal to about $\frac{1}{5}$ to $\frac{1}{2}$ of e ordinary arterial pressure.

The arterial blood-pressure may be made to vary by variations of her of the two chief factors upon which the pressure in the vessels pends, viz., the cardiac contractions and the peripheral resistance. us, increase of blood-pressure may be brought about by either (a) a ore frequent or more forcible action of the heart, or (b) by increase of peripheral resistance; and on the other hand, diminution of the od-pressure may be produced, either by (a) a diminished force or fre- ency of the contractions of the heart, or by (b) a diminished periphe- resistance. These different factors, however, although varying con- ntly, are so combined that the general arterial pressure remains fairly nstant; for example, the heart may, by increased force or frequency its contractions, distinctly increase the blood-pressure, but this in- eased action is almost certainly followed by diminished peripheral resistance, and thus the two altered conditions may balance, with result of bringing back the blood-pressure to what it was before heart began to beat more rapidly or more forcibly.

It will be clearly seen that the circulation of the blood within blood-vessels must depend upon the diminution of the pressure f the heart to the capillaries, and from the capillaries to the veins, blood flowing in the direction of least resistance; we shall presently further that the general or local flow also depends upon the relati between the heart's action and the peripheral resistance, general or lo



Fig. 179. Schema, showing the relation between blood pressure, velocity of flow and va area, in the arteries, capillaries, and veins. Ordinates represent height of pressure and speed of The abscissa, *b c*, represents zero pressure and speed. Space between lines *a-b* and *d-c* repr arterial system; between *d c* and *f g*, capillary system, and between *f-g* and *h-i*, the venous sy Line *A B* equals pressure; line *C D*, speed of flow, and line *E-F*, vascular area.

## The Arterial Flow.

The character of the flow of blood through the arterial system pends to a very considerable extent upon the structure of the art walls, and particularly upon the elastic tissue which is so highly d oped in them.

The elastic tissue first of all guards the arteries from the sudd exerted pressure to which they are subjected at each contraction of ventricles. In every such contraction as is above seen the content the ventricles are forced into the arteries more quickly than they be discharged through the capillaries. The blood, therefore, being an instant, resisted in its onward course, a part of the force with w it was impelled is directed against the sides of the arteries; under force their elastic walls dilate, stretching enough to receive the b and, as they stretch, becoming more tense and more resisting. by yielding they break the shock of the force impelling the blood. the subsidence of the pressure, when the ventricles cease contrac

s are able, by the same elasticity, to resume their former cali-
lastic tissue also equalizes the current of blood by maintaining
n it in the arteries during the period at which the ventricles
or are dilating. If the arteries were rigid tubes, the blood
flowing, as it does, in a constant stream, would be propelled
he arterial system in a series of jerks corresponding to the
r contractions, with intervals of almost complete rest during
n of the ventricles. But in the actual condition of the ves-
rce of the successive contractions of the ventricles is expended
he direct propulsion of the blood, and partly in the dilatation
stic arteries; and in the intervals between the contractions of
cles, the force of the recoil is employed in continuing the on-

Of course the pressure exercised is equally diffused in every
and the blood tends to move backward as well as onward; all
backward, however, is prevented by the closure of the semi-
es, which takes place at the very commencement of the recoil
erial walls.

y the exercise of the elasticity of the arteries, all the force of
cles is expended upon the circulation; for that part of the
h is used up or rendered potential in dilating the arteries is
r made active or kinetic, in full when they recoil. There is
force; neither is there any gain, for the elastic walls of the
not originate any force for the propulsion of the blood—they
re that which they received from the ventricles. It is by this
influence of the successive branches of every artery that at
intermittent accelerations produced in the arterial current
ion of the heart, cease to be observable, and the jetting stream
ed into the continuous and equable movement of the blood
see in the capillaries and veins. In the production of a con-
ream of blood in the smaller arteries and capillaries, the re-
hich is offered to the blood-stream in these vessels is a neces-
. Were there no greater obstacle to the *escape* of blood from
arteries than exists to its *entrance* into them from the heart,
would be intermittent, notwithstanding the elasticity of walls
ries.

ns of the elastic and muscular tissue in their walls again the
e enabled to dilate and contract readily in correspondence
temporary increase or diminution of the total quantity of
he body; and within a certain range of diminution of the
till to exercise due pressure on their contents. The elastic
her assists in restoring the normal channel after diminution
re, whether this has been caused by a contraction of the mus-
or by the temporary application of a compressing force from
This action is well shown in arteries which, having contracted

by means of their muscular element, after death regain their avera potency on the cessation of post-mortem rigidity.

The office of the muscular coat also is employed to adjust the fl of the blood locally, to regulate the quantity of blood to be received each part or organ, and to adjust it to the requirements of each, accor ing to various circumstances, but, chiefly, according to the activity wit which the functions of each are at different times performed. Th amount of work done by each organ of the body varies at different time and the variations often quickly succeed each other, so that, as in th brain, for example, during sleep and waking, within the same hour part may be now very active and then inactive. In all its active exe cise of function, such a part requires a larger supply of blood than sufficient for it during the times when it is comparatively inactive. is evident that the heart cannot regulate the supply to each part at ferent periods; neither could this be regulated by any general and form contraction of the arteries: but it may be regulated by the pow which the arteries of each part have, in their muscular tissue, of c tracting so as to diminish, and of passively dilating or yielding so as permit an increase of, the supply of blood, according to the requirement of the part to which they are distributed. And thus, while the ventr cles of the heart determine the total quantity of blood, to be sent onwa at each contraction, and the force of its propulsion, and while the lar and merely elastic arteries distribute it and equalize its stream, th smaller arteries, in addition, regulate and determine, by means of thei muscular tissue, the proportion of the whole quantity of blood whi shall be distributed to each part.

This regulating function of the arteries is governed and directed the nervous system in the way to be presently described.

The muscular element of the middle coat also co-operates with th elastic in adapting the calibre of the vessels to the quantity of blo which they contain. For the amount of fluid in the blood-vessels vari very considerably even from hour to hour, and can never be quite co stant; and were the elastic tissue only present the pressure exerci by the walls of the containing vessels on the contained blood would sometimes very small, and sometimes inordinately great. The prese of a muscular element, however, provides for a certain uniformity in amount of pressure exercised; and it is by this adaptive, uniform, ge tle, muscular contraction, that the normal tone of the blood-vessels maintained. Deficiency of this tone is the cause of the soft and yie ing pulse, and its unnatural excess of the hard and tense one.

The elastic and muscular contraction of an artery may also be garded as fulfilling a natural purpose when, the artery being cut, it fi limits and then, in conjunction with the coagulated fibrin, arrests escape of blood. It is only in consequence of such contraction and lation that we are free from danger through even very slight wounds; it is only when the artery is closed that the processes for the more rmanent and secure prevention of bleeding are established. But there pears no reason for supposing that the muscular coat assists, to more n a very small degree, in propelling the onward current of blood.

## The Pulse.

The most characteristic feature, then, of the arterial flow, is its in- mittency, and this intermittent flow is seen or felt as the Pulse.

The pulse is generally described as an expansion of the artery pro- ced by the wave of blood set in motion by the injection of blood at h ventricular systole into the already full aorta. As the force of the ventricle, however, is not expended in dilating the aorta only, the e of blood passes on, expanding the arteries as it goes, running as it e on the surface of the more slowly travelling blood already con- ned in them, and producing the pulse as it proceeds.



Fig. 180.—Marey's Sphygmograph, modified by Mahomed.

The distention of each artery increases both its length and its diam- . In their elongation, the arteries change their form, the straight s becoming slightly curved, and those already curved becoming more but they recover their previous form as well as their diameter when ventricular contraction ceases, and their elastic walls recoil. The ease of their curves which accompanies the distention of arteries, the succeeding recoil, may be well seen in the prominent temporal ry of an old person. In feeling the pulse, the finger cannot distin- sh the sensation produced by the dilatation from that produced by longation and curving; that which it perceives most plainly, how- is the dilatation, or return, more or less, to the cylindrical form, of tery which has been partially flattened by the finger.

The pulse—due to any given beat of the heart—is not percepti at the same moment in all the arteries of the body. Thus, it can felt in the carotid a very short time before it is perceptible in the artery, and in this vessel again before it occurs in the dorsal artery the foot. The delay in the beat is in proportion to the distance of artery from the heart, but the difference in time between the beat any two arteries probably never exceeds $\frac{1}{6}$ to $\frac{1}{8}$ of a second.

A distinction must be carefully made between the passage of *wave* along the arteries and the arterial flow itself. Both wave current are present; but the rates at which they travel are very differ that of the wave 16.5 to 33 feet per second (5 to 10 metres), being twen or thirty times as great as that of the current.

**The Sphygmograph.**—Much light has been thrown on what be called the form of the pulse wave by the sphygmograph (figs. 1 and 183). · The principle on which it acts will be seen on reference figures.

The small button replaces the finger in the act of taking the pu and is made to rest lightly on the artery, the pulsations of which it desired to investigate. The up-and-down movement of the button communicated to the lever, to the hinder end of which is attached slight spring, which allows the lever to move up, at the same time th



Fig. 181.—Diagram of the lever of the Sphygmograph.

it is just strong enough to resist its making any sudden jerk, and in t interval of the beats also to assist in bringing it back to its origi position. For ordinary purposes the instrument is bound on the w (fig. 182).

It is evident that the beating of the pulse with the reaction of spring will cause an up-and-down movement of the lever, the pen which will write the effect on a smoked card, which is made to move clockwork in the direction of the arrow. Thus a tracing of the p is obtained, and in this way much more delicate effects can be seen t can be felt on the application of the finger.

Two forms of sphygmograph are shown in figs. 180, 183, viz., a modi tion of the original instrument of Marey and Dudgeon's. Marey's instrum and indeed all modifications of it, suffer from the defect that there is no method of measuring the pressure exercised by the button of the instru- pon the artery, and that it is difficult to be certain of the exact position pies over the artery. Dudgeon's sphygmograph, although very conven- use, is, according to Roy and Adami, even less satisfactory, and the s obtained by it are so disfigured by inertia vibrations as to render nore or less worthless. "The mechanical construction of the instrument as to render great inertia vibrations unavoidable." These authors have



Fig. 182.—The Sphygmograph applied to the arm.

ed an instrument called a sphygmometer, in which these defects of the ograph are corrected.



Fig. 183.—Dudgeon's Sphygmograph.

principle of the **sphygmometer** of Roy and Adami is shown in the dia- fig. 184).

apparatus consists of a box (*a*) which is moulded to fit over the end of ius so as to bridge over the radial artery. Within this is a flexible bag d with water, and connected by a T tube with a rubber bag (*h*) and al manometer. The fluid in the box may be raised to any desired , and may then be shut off by tap (*c*). At the upper part of the box is ar opening, and resting upon (*b*) is a flat button (*d*), which by means t light rod (*e*) communicates the movement of (*b*) to the lever (*f*). To of rotation of this lever is a spiral watch-spring (*g*) which can be tight-ened at will, so that the lever can be made to take a vertical position a desired hydrostatic pressure within the box. The movements of the lev recorded upon a piece of blackened glazed paper made to move in a ve direction past it. When in use, the box is fixed upon the end of the radi an appropriate holder, and the pressure is raised to any desired height to w the lever is adapted by tightening or slackening the spring. The tap then closed. The pressure within the box acts in all directions, and is corr indicated by the manometer.



Fig. 184.—Diagrammatic sectional representation of the sphygmometer (Roy and Adam Box in which the portion of the artery is inclosed; *b*, thin-walled india-rubber bag filled with and communicating through tap, *c*, with manometer and thick-walled rubber bag, *h*; *d*, pist nected by rod, *e*, with recording lever, *f*; *g*, spiral spring attached to axis of lever, and by the pressure in *b*, against the piston, *d*, is counterbalanced; *k*, skin and subcutaneous tissue; of radius seen in section; *n*, radial artery seen in section.

The tracing of the pulse **(sphygmogram)**, obtained by the u the sphygmograph, differs somewhat according to the artery upon w it is applied, but its general characters are much the same in all It consists of:—A sudden upstroke (fig. 185, A), which is som



Fig. 185.—Diagram of pulse tracing. A, Up-stroke; B, down-stroke; C, pre-dicrotic wave crotic; E, post-dicrotic wave.

higher and more abrupt in the pulse of the carotid and of other arteries near the heart than in the radial and other arteries more remote; and a gradual decline (B), less abrupt, and therefore taking a longer time than (A). It is seldom, however, that the decline is an uninterrupted fall; it is usually marked about half-way by a distinct notch (C), called the *dicrotic notch*, which is caused by a second more or less marked ascent of the lever at that point and by a second wave called the *dicrotic wave* (D); not unfrequently there is also soon after the commencement of the descent a slight ascent previous to the dicrotic notch: this is called the *pre-dicrotic wave* (C), and in addition there may be one or more slight ascents after the dicrotic, called *post-dicrotic* (E).

The interruptions in the downstroke are called the *katacrotic* waves, to distinguish them from an interruption in the upstroke, the *anacrotic* wave, which is sometimes met with.

The explanation of these tracings presents some difficulties, not, however, as regards the two primary factors, viz., the upstroke and downstroke, because they are universally taken to mean the sudden injection of blood into the already full arteries, and the gradual fall of the lever signifying the recovery of the arteries by their recoil. These points may be demonstrated on a system of elastic tubes, with a syringe to pump in water at regular intervals, just as well as on the radial artery, or on the more complicated system of tubes in which the heart, the arteries, the capillaries and veins are represented, which is known as an *arterial schema*. If we place two or more sphygmographs upon such a system of tubes at increasing distances from the pump, we may demonstrate first, that the rise of the lever commences earliest in that nearest the pump, and secondly, that it is higher and more sudden, while at a longer distance from the pump the wave is less marked, and little later. So in the arteries of the body the wave gradually gets less and less as we approach the periphery of the arterial system, and is lost the capillaries.

The origin of the secondary waves is still a matter of uncertainty.



Fig. 186.—Anacrotic pulse from a case of aortic aneurism.

e *anacrotic* wave occurs when the peripheral resistance is high; that when, for some time during the systole, the flow from the aorta ward the periphery is slower than the flow from the ventricle into the aorta. Thus, it is seen in some cases of nephritis where the arteri rigid and the peripheral resistance high.

The *dicrotic* wave is the most important of the secondary wav has been the subject of much discussion. It is constantly pre pulse-tracings, but varies in height. In point of time the dicroti occurs immediately after the closure of the aortic semilunar valv certain conditions, generally of disease, it becomes so marked a quite plain to the unaided finger. Such a pulse is called *dicrotic*. most generally accepted view of the cause of the dicrotic wave is represents a rebound from the closed aortic valves. During sys the blood is forcibly injected into the aorta, there is as it were a distention of the artery. The systole suddenly ends, the aorta son of its elasticity tends to recover itself, the blood is drive against the semilunar valves, closing them and at the same time rise to a wave—the dicrotic wave—which begins at the heart and onward toward the periphery like the primary wave. According



Fig. 187.—A, Normal pulse-tracing from radial of healthy adult, obtained by the sphyg B, From same artery, with the same extra-arterial pressure, taken during acute nasal c

ter, the conditions favoring the development of dicrotism are highly extensible and elastic arterial wall; (2) a comparatively lo blood pressure, leaving the extensible reaction free scope to act vigorous and rapid stroke of the ventricle, discharging into the considerable quantity of blood.

The other secondary waves are probably due to the elastic r teries, though some of them at least may be due to the inertia of struments used.

the use of the sphygmograph care must be taken as to the careful tion of the pressure. If the pressure be, too great, the characters pulse may be almost entirely obscured, or the artery may be ly obstructed, and no tracing is obtained; and on the other hand, pressure is too slight, a very small part of the characters may be ented on the tracing.

## Blood-Pressure Measurements in Man.

number of instruments have been devised for estimating blood-re in man for clinical purposes. Some of these, though excellent ciple, are too complicated for general use. The first simple and



ig. 188.—Riva-Rocci apparatus (schematic) for determining blood-pressure in man.

mately accurate form of apparatus was that devised by Riva- 1896. This has been modified and improved in minor points ut the principles of the original instrument remain practically e.

rief, the apparatus (fig. 188) consists of the following parts: an ube which can be adjusted about the arm or forearm (fig. 188, *A*); ary manometer (fig. 188, *B*) connected with this tube and also with some form of air-pump (fig. 188, *P*) used for inflating th about the arm and thus exerting pressure upon its blood-vessels. elastic tube is covered by some inelastic tissue, such as a leathe (fig. 188, *C*), in order that the inflation of the tube may cause t increase of pressure to be exerted upon the encased arm. By inf the tube until the pulse at the wrist just disappears and readi height of the column of mercury in the manometer, the maxim systolic pressure is obtained in millimetres of mercury. If no pressure on the arm is reduced until the widest oscillations mercury column are obtained and the lowest position of the m meniscus is read off, the minimum or diastolic blood-pressure i mated.

## The Capillary Flow.

It is in the capillaries that the chief resistance is offered to the ress of the blood; for in them the friction of the blood is grea creased by the enormous multiplication of the surface with whi brought in contact.

When the capillary circulation is examined in any transpare of a full-grown living animal by means of the microscope (fig. 18 blood is seen to flow with a constant equable motion; the red corpuscles moving along, mostly in single file, and bending in ways to accommodate themselves to the tortuous course of the ca but instantly recovering their normal outline on reaching a wider

At the circumference of the stream in the larger capillari sepecially well marked in the small arteries and veins, in conta



Fig. 189.—Capillaries (C.) in the web of the frog's foot connecting a small artery ( small vein V (after Allen Thomson).

the walls of the vessel, and adhering to them, there is a layer of which appears to be motionless. The existence of this still as it is termed, is inferred both from the general fact that one exists in all fine tubes traversed by fluid, and from what seen in watching the movements of the blood-corpuscles. T s occupy the middle of the stream and move with comparative the colorless corpuscles run much more slowly by the walls of l; while next to the wall there is often a transparent space in e fluid appears to be at rest; for if any of the corpuscles hap- forced within it, they move more slowly than before, rolling ng the side of the vessel, and often adhering to its wall. Part ow movement of the colorless corpuscles and their occasional may be due to their having a natural tendency to adhere to of the vessels. Sometimes, indeed, when the motion of the not strong, many of the white corpuscles collect in a capillary d for a time entirely prevent the passage of the red corpuscles. the peripheral resistance is greatly diminished by the dilata- e small arteries and capillaries, so much blood passes on from the arteries into the capillaries at each stroke of the heart, that there is not sufficient remaining in the arteries to distend them. Thus, the intermittent current of the ventricular systole is not converted into a continuous stream by the elasticity of the arteries before the capillaries are reached; and so intermittency of the flow occurs both in capillaries and veins and a pulse is produced. The same phenomenon may occur when the arteries become rigid from disease, and when the beat of the heart is so slow or so feeble that the blood at each cardiac systole has time to pass on to the capillaries before the next stroke occurs; the amount of blood sent at each stroke being insufficient to properly distend the elastic arteries.

A large ca-
the frog's
ight hours
tion had
, showing
of leuco-
ells in the
ersing the
ll; *b*, some
ped.
(Frey.)

It was formerly supposed that the occurrence of any transudation from the interior of the capillaries into the midst of the surrounding tissues was confined, in the absence of injury, strictly to the fluid part of the blood; in other words, that the corpuscles could not escape from the circulating stream, unless the wall of the containing blood-vessel ured. It is true that an English physiologist, Augustus Waller, in 1846, that he had seen blood-corpuscles, both red and white, ly through the wall of the capillary vessel in which they were l (thus confirming what had been stated a short time previously on); and that, as no opening could be seen before their escape, ould be observed afterward—so rapidly was the part healed. observations did not attract much notice until the phenome- cape of the blood-corpuscles from the capillaries and minute rt from mechanical injury, were re-discovered by Cohnheim

Cohnheim's experiment demonstrating the passage of the corp through the wall of the blood-vessel is performed in the following ner. A frog is curarized, that is to say, paralysis is produced by eje under the skin a minute quantity of the poison called **curari**; an abdomen having been opened, a portion of small intestine is draw and its transparent mesentery spread out under a microscope. a variable time, occupied by dilatation, following contraction minute vessels and accompanying quickening of the blood-stream, ensues a retardation of the current, and blood-corpuscles, both re white, begin to make their way through the capillaries and small

The white corpuscles pass through the capillary wall chiefly amœboid movement with which they are endowed. This migrati curs to a limited extent in health, but in inflammatory condit much increased.

The process of **diapedesis** of the red corpuscles, which occurs circumstances of impeded venous circulation, and consequently in blood-pressure, resembles closely the migration of the leucocyte the exception that they are squeezed through the wall of the vess do not, like the leucocytes, work their way through by amœboid ment.

Various explanations of these remarkable phenomena have be gested. Some believe that pseudo-stomata between contiguous thelial cells provide the means of escape for the blood-corpuscles the chief share in the process is probably due to mobility and c tion of the parts concerned—both of the corpuscles and of the ca wall itself.

The circulation through the capillaries must, of necessity, be influenced by that which occurs in the vessels on either side of in the arteries or the veins; their intermediate position causing t feel at once, so to speak, any alteration in the size or rate of the or venous blood-stream. Thus, the apparent contraction of the ries, on the application of certain irritating substances; and durin and their dilatation in blushing may be referred primarily to the of the small arteries.

**Purpose of the Capillaries.**—It is in the capillaries t ultimate function of the blood occurs, for it is here, in these thin vessels, that all exchanges, nutritive and gaseous, between the bl the tissues take place. It is in these vessels also that the velo flow is least, while the pressure is intermediate between that arteries and veins. The physical conditions therefore are such a the exchange between the blood and the tissues.

## The Venous Flow.

The blood-current in the veins is maintained (a) primarily by the vis
rgo of the contraction of the left ventricle; but very effectual assist-
to the flow is afforded (b) by the action of the muscles capable of
sing on the veins with valves, as well as (c) by the suction action of
heart, and (d) aspiration of the thorax.

he effect of muscular pressure upon the circulation may be thus
ined. When pressure is applied to any part of a vein, and the
nt of blood in it is obstructed, the portion behind the seat of press-
ecomes swollen and distended as far back as the next pair of
, which are in consequence closed. Thus, whatever force is exer-
by the pressure of the muscles on the veins, is distributed partly
ssing the blood onward in the proper course of the circulation,
artly in pressing it backward and closing the valves behind.

e circulation might lose as much as it gains by such an action, if
e not for the numerous communications, one with another; for
gh these, the closing up of the venous channel by the backward
re is prevented from being any serious hindrance to the circula-
since the blood, of which the onward course is arrested by the
valves, can at once pass through some anastomosing channel, and
d on its way by another vein. Thus, therefore, the effect of mus-
pressure upon veins which have valves, is turned almost entirely
advantage of the circulation; the pressure of the blood onward
dvantageous, and the pressure of the blood backward is prevented
eing a hindrance by the closure of the valves and the anastomoses
veins.

e venous flow is also assisted by the suction action of the heart,
at some time during every cardiac cycle the intra-auricular and
entricular pressure falls below that of the atmosphere.

e aspiration of the thorax will be considered more fully in the
r on Respiration. In this connection it may be said, however,
he pressure in the great veins falls during inspiration and rises
g expiration.

## The Velocity of the Flow.

e velocity of the blood-current at any given point in the various
ns of the circulatory system is inversely proportional to their sec-
area at that point. If the sectional area of all the branches of a
united were always the same as that of the vessel from which they
nd if the aggregate sectional area of the capillary vessels were
to that of the aorta, the mean rapidity of the blood's motion in the
ries would be the same as in the aorta; and if a similar corre-
nce of capacity existed in the veins and arteries, there would be

an equal correspondence in the rapidity of the circulation in them. But the arterial and venous systems may be represented by two truncated cones with their apices directed toward the heart; the area of their united base (the sectional area of the capillaries) being 400—800 times as great as that of the truncated apex representing the aorta. Thus the velocity of blood in the capillaries is not more than $\frac{1}{400}$ of that in the aorta.

*In the Arteries.*—The velocity of the stream of blood is greater i the arteries than in any other part of the circulatory system, and in the it is greatest in the neighborhood of the heart, and during the ventric lar systole. The rate of movement diminishes during the diastole the ventricles, and in the parts of the arterial system most distant fro the heart. Chauveau has estimated the rapidity of the blood-stream the carotid of the horse at over 20 inches per second during the hear systole, and nearly 6 inches during the diastole (520–150 mm.). ( fig. 179.)

**Estimation of the Velocity.**—Various instruments have been devised measuring the velocity of the blood-stream in the arteries. Ludwig's *Strom* (fig. 191) consists of a U-shaped glass tube dilated at *a* and *a'*, the ends which, *h* and *i*, are of known calibre. The bulbs can be filled by a com opening at *k*. The instrument is so contrived that at *b* and *b'* the glass par firmly fixed into metal cylinders, attached to a ci lar horizontal table, *c c'*, capable of horizontal m ment on a similar table *d d'* about the vertical marked in figure by a dotted line. The opening in when the instrument is in position, as in fig., responds exactly with those in *d d'*; but if *c c*



Fig. 191.



Fig. 192.

Fig. 191.—Ludwig's Stromuhr.

Fig. 192.—Diagram of Chauveau's Instrument. *a.* Brass tube for introduction into the lum the artery, and containing an index needle, which passes through the elastic membrane in its and moves by the impulse of the blood-current. *c.* Graduated scale, for measuring the exte the oscillations of the needle.

turned at right angles to its present position, there is no communication tween *h* and *a*, and *i* and *a'*, but *h* communicates directly with *i*; an turned through two right angles *c'* communicates with *d*, and *c* with *d'*, there is no direct communication between *h* and *i*. The experiment is

ed in the following way :—The artery to be experimented upon is divided
onnected with two canulæ and tubes which fit it accurately with *h* and
he central end, and *i* the peripheral; the bulb *a* is filled with olive oil up
point rather lower than *k*, and *a'* and the remainder of *a* is filled with
inated blood; the tube on *k* is then carefully clamped: the tubes *d* and
also filled with defibrinated blood. When everything is ready, the blood
wed to flow into *a* through *h*, and it pushes before it the oil, and that
ibrinated blood into the artery through *i*, and replaces it in *a'*; when the
reaches the former level of the oil in *a'*, the disc *c c'* is turned rapidly
h two right angles, and the blood flowing through *d* into *a'* again dis-
the oil which is driven into *a*. This is repeated several times, and the
n of the experiment noted. The capacity of *a* and *a'* is known; the
er of the artery is also known by its corresponding with the canulæ of
diameter, and as the number of times *a* has been filled in a given time
vn, the velocity of the current can be calculated.

uveau's instrument, fig. 192, consists of a thin brass tube, *a* in one side
h is a small perforation closed by thin vulcanized india-rubber. Pass-
rough the rubber is a fine lever, one end of which, slightly flattened,
into the *lumen* of the tube, while the other moves over the face of a
The tube is inserted into the interior of an artery, and ligatures applied to
o that the movement of the blood may, in flowing through the tube, be
ed by the movement of the outer extremity of the lever on the face of
l.

*Hæmatochometer* of Vierordt, and the instrument of Lortet, resemble in
le that of Chauveau.

*he Capillaries.*—The observation of Hales, E. H. Weber, and Val-
gree very closely as to the rate of the blood-current in the capil-
f the frog; and the mean of their estimates gives the velocity of
*temic* capillary circulation at about one inch (25 mm.) per min-
The velocity in the capillaries of warm-blooded animals is greater.
dog $\frac{1}{50}$ to $\frac{3}{100}$ inch (.5 to .75 mm.) a second. This may seem
stent with the facts, which show that the whole circulation is
lished in about half a minute. But the whole length of capillary
through which any given portion of blood has to pass, probably
t exceed from $\frac{1}{30}$th to $\frac{1}{50}$th of an inch (.5 mm.); and therefore
e required for each quantity of blood to traverse its own appointed
of the general capillary system will scarcely amount to a second.

*he Veins.*—The velocity of the blood is greater in the veins than
capillaries, but less than in the arteries: this fact depending upon
tive capacities of the arterial and venous systems. If an accurate
e of the proportionate areas of arteries and the veins correspond-
them could be made, we might, from the velocity of the arterial
, calculate that of the venous. A usual estimate is, that the ca-
of the veins is about twice or three times as great as that of the
, and that the velocity of the blood's motion is, therefore, about
r three times as great in the arteries as in the veins, 8 inches
m.) a second. The rate at which the blood moves in the veins
lly increases the nearer it approaches the heart, for the sectional

area of the venous trunks, compared with that of the branches opening into them, becomes gradually less as the trunks advance toward the heart (see fig. 179).

*Of the Circulation as a Whole.*—It would appear that a portion of blood can traverse the entire course of the circulation, in the horse, in half a minute. Of course it would require longer to traverse the vessels of the most distant part of the extremities than to go through those of the neck; but taking an average length of vessels to be traversed, it may be concluded that half a minute represents the average rate. Stewart states that the circulation time in man is probably not less than twelve nor more than fifteen seconds.

Satisfactory data for these estimates are afforded by the results of experiments to ascertain the rapidity with which poisons introduced into the blood are transmitted from one part of the vascular system to another. The time required for the passage of a solution of potassium ferrocyanide, mixed with the blood, from one jugular vein (through the right side of the heart, the pulmonary vessels, the left cavities of the heart, and the general circulation) to the jugular vein of the opposite side, varies from twenty to thirty seconds. The same substance was transmitted from the jugular vein to the great saphena in twenty seconds; from the jugular vein to the masseteric artery in between fifteen and thirty seconds; to the facial artery, in one experiment, in between ten and fifteen seconds; in another experiment in between twenty and twenty-five seconds; in its transit from the jugular vein to the metatarsal artery, it occupied between twenty and thirty seconds, and in one instance more than forty seconds. The result was nearly the same whatever was the rate of the heart's action.

In all these experiments, it is assumed that the substance injected moves with the blood, and at the same rate, and does not move from one part of the organs of circulation to another by diffusing itself through the blood or tissues more quickly than the blood moves. The assumption is sufficiently probable to be considered nearly certain, that the times above mentioned, as occupied in the passage of the injected substances, are those in which the portion of blood, into which each was injected, was carried from one part to another of the vascular system.

Another mode of estimating the general velocity of the circulating blood, is by calculating it from the quantity of blood supposed to be contained in the body, and from the quantity which can pass through the heart in each of its actions. But the conclusions arrived at by this method are less satisfactory. For the total quantity of blood, and the capacity of the cavities of the heart, have as yet been only approximately ascertained. Still the most careful of the estimates thus made accord very nearly with those already mentioned: and it may be assumed that the blood may all pass through the heart in about twenty-five seconds.

## Local Peculiarities of the Circulation.

The most remarkable peculiarities attending the circulation of blood ough different organs are observed in the cases of the *brain,* the *erec- organs,* the *lungs,* the *liver,* and the *kidneys.*

*In the Brain.*—For the due performance of its functions the brain uires a large supply of blood. This object is effected through the mber and size of its arteries, the two internal carotids, and the two rtebrals. It is further necessary that the force with which this blood sent to the brain should be less, or at least should be subject to less riation from external circumstances than it is in other parts, and so e large arteries are very tortuous and anastomose freely in the circle Willis, which thus insures that the supply of blood to the brain is iform, though it may by an accident be diminished, or in some way anged, through one or more of the principal arteries. The transit of e large arteries through bone, especially the carotid canal of the tem- ral bone, may prevent any undue distention; and uniformity of sup- y is further insured by the arrangement of the vessels in the pia ter, in which, previous to their distribution to the substance of the in, the large arteries break up and divide into innumerable minute nches ending in capillaries, which, after frequent communication h one another, enter the brain, and carry into nearly every part of it iform and equable streams of blood. The arteries are also enveloped special lymphatic sheath. The arrangement of the veins within cranium is also peculiar. The large venous trunks or sinuses are med so as to be scarcely capable of change of size; and composed, hey are, of the tough tissue of the dura mater, and, in some instances nded on one side by the bony cranium, they are not compressible by force which the fulness of the arteries might exercise through the stance of the brain; nor do they admit of distention when the flow venous blood from the brain is obstructed.

The general uniformity in the supply of blood to the brain, which hus secured, is well adapted, not only to its functions, but also to its dition as a mass of nearly incompressible substance placed in a cav- with unyielding walls. These conditions of the brain and skull for- rly appeared, indeed, enough to justify the opinion that the quantity blood in the brain must be at all times the same. But it was found t in animals bled to death, without any aperture being made in the nium, the brain became pale and anæmic like other parts. And in th from strangling or drowning, there was congestion of the cerebral sels; while in death by prussic acid, the quantity of blood in the ity of the cranium was determined by the position in which the ani- was placed after death, the cerebral vessels being congested when animal was suspended with its head downward, and comparatively pty when the animal was kept suspended by the ears. Thus, it was concluded, although the total volume of the contents of the cranium i probably nearly always the same, yet the quantity of blood in it is li to variation, its increase or diminution being accompanied by a sim taneous diminution or increase in the quantity of the cerebro-spi fluid, which, by readily admitting of being removed from one part the brain and spinal cord to another, and of being rapidly absorbed, as readily effused, would serve as a kind of supplemental fluid to other contents of the cranium, to keep it uniformly filled in cas variations in their quantity. And there can be no doubt that, althou the arrangements of the blood-vessels, to which reference has been ma insure to the brain an amount of blood which is tolerably uniform, y inasmuch as with every beat of the heart and every act of respirati and under many other circumstances, the quantity of blood in the ca ity of the cranium is constantly varying, it is plain that, were th not provision made for the possible displacement of some of the conte of the unyielding bony case in which the brain is contained. there wo be often alternations of excessive pressure with insufficient supply blood.

*In Erectile Structures.*—The instances of greatest variation in quantity of blood contained, at different times, in the same organs, found in certain structures which, under ordinary circumstances, soft and flaccid, but, at certain times, receive an unusually large qu tity of blood, become distended and swollen by it, and pass into the st which has been termed *erection.* Such structures are the *corpora ca nosa* and *corpus spongiosum* of the penis in the male, and the *clitoris* the female; and, to a less degree, the *nipple* of the mammary gland both sexes. The corpus cavernosum penis, which is the best exa of an erectile structure, has an external fibrous membrane or sheath; from the inner surface of the latter are prolonged numerous fine lame which divide its cavity into small compartments looking like cells wh they are inflated. Within these is situated the plexus of veins up which the peculiar erectile property of the organ mainly depends. consists of short veins which very closely interlace and anastomose wi each other in all directions, and admit of great variations of size, c lapsing in the passive state of the organ, but, for erection, capable of amount of dilatation which exceeds beyond comparison that of arteries and veins which convey the blood to and from them. T strong fibrous tissue lying in the intervals of the venous plexuses, the external fibrous membrane or sheath with which it is connec limit the distention of the vessels, and, during the state of erection, to the penis its condition of tension and firmness. The same gen condition of vessels exists in the corpus spongiosum urethræ, but arou the urethra the fibrous tissue is much weaker than around the body the penis, and around the glans there is none. The venous blood urned from the plexuses by comparatively small veins; those from glans and the fore part of the urethra empty themselves into the rsal veins of the penis; those from the cavernosum pass into deeper ns which issue from the corpora cavernosa at the crura penis; and se from the rest of the urethra and bulb pass more directly into the xus of the veins about the prostate. For all these veins one condi- n is the same; namely, that they are liable to the pressure of muscles hen they leave the penis. The muscles chiefly concerned in this action e the erector penis and accelerator urinæ. Erection results from the stention of the venous plexuses with blood. The principal exciting use in the erection of the penis is nervous irritation, originating in e part itself, or derived from the brain and spinal cord. The nervous fluence is communicated to the penis by the pudic nerves, which ram- y in its vascular tissue; and after their division in the horse the penis no longer capable of erection.

This influx of the blood is the first condition necessary for erection, d through it alone much enlargement and turgescence of the penis ay ensue. But the erection is probably not complete, nor maintained r any time except when, together with this influx, the muscles already ntioned contract, and, by compressing the veins, stop the efflux of od, or prevent it from being as great as the influx.

It appears to be only the most perfect kind of erection that needs e help of muscles to compress the veins; and none such can materially ist the erection of the nipples, or that amount of turgescence, just ling short of erection, of which the spleen and many other parts are able. For such turgescence nothing more seems necessary than a ge plexiform arrangement of the veins, and such arteries as may ad- t, upon occasion, augmented quantities of blood.

*The circulation in the Lungs, Liver, and Kidneys* will be described der their respective heads.

## The Regulation of the Blood-Flow.

The flow of blood is not always the same, but varies:—

(a.) With alterations in the force and frequency of the contractions of the heart; and

(b.) With variations of the peripheral resistance.

It is obvious that the flow of blood may be **increased** under the lowing circumstances:—

(a.) If the force and frequency of the heart's beats be increased, and the peripheral resistance be (1) unchanged, or be (2) diminished.

(b.) If the force and frequency of the heart be unchanged, and the peripheral resistance be diminished.

And may on the other hand be **diminished:—**

(c.) If the force and frequency of the heart's beats be diminis and if the peripheral resistance be (1) unchanged, or be (2) creased.

(d.) If the force and frequency of the heart's beats be unchang and the peripheral resistance be increased.

When the force and frequency of the heart's contractions are creased and at the same time the peripheral resistance is increased, flow may be increased, diminished, or unchanged, according as eithe the two factors, one of which tends to increase the flow, and the ot to diminish it, is more markedly increased, or if they are balanced. complemental proposition is also true, that the flow may be increa diminished, or unchanged, when the force and frequency of the he contractions are diminished, and the peripheral resistance is diminis

The conditions of increased flow and of increase of blood pres are not the same. Indeed, the greatest blood-flow may occur when blood pressure is low, *i.e.*, when the peripheral resistance is dimini and the heart's beat is increased or is unchanged. In fact there is one condition in which increased blood-flow is accompanied by incre blood-pressure, viz., when the heart's beat is increased and the per ral resistance is unchanged.

It will be necessary now to consider (a) *the ways in which the and frequency of the heart's beats are regulated*; and also (b) *the wa which the peripheral resistance is increased or diminished.* We afterward be in a better position to discuss the variations of b pressure produced by different combinations of cardiac and ar alterations.

(*a.*) The **force and frequency of the contractions of the h** may be considered to depend upon:

1. The properties and condition of the heart-muscle itself;
2. The influence of the central nervous system;
3. The amount of the blood passing into the heart's cavities;
4. The amount of pressure to be overcome.
5. The coronary circulation.

Each of these factors must be considered seriatim.

1. *The properties of the heart-muscle.*—It has already been poi out that in structure the muscular fibres of the heart differ from ske muscle on the one hand, and from unstriped muscle on the other, occ ing, as it were, an intermediate position between the two varieties. heart-muscle, however, possesses a property which is not possessed by s tal muscle, or by unstriped muscle to such a degree, namely, the pro of **rhythmical contractility**. The property of rhythmic contra

ɔwn by the action of the heart within the body; its systole is fol-
l by its diastole in regular sequence throughout the life of the
ridual. The force and frequency of the systole may vary from time
me as occasion requires, but there is no interruption to the action
ıe normal heart, or any interference with its rhythmical contrac-
. Further, we find that in an animal rapidly bled to death, the heart
inues to beat for a time, varying in duration with the kind of ani-
experimentally dealt with, and in the entire absence of blood within
ıeart-chambers; and still further, if the heart of an animal be re-
ed from the body, it still, for a varying time, continues its alternate
lic and diastolic movements. Thus we see that the power of
hmic contraction depends neither upon connection with the central



Fig. 193.



Fig. 194.

. 193.—The heart of a frog (Rana esculenta) from the front. *V*, Ventricle; *Ad*, right auricle;
t auricle; *B*, bulbus arteriosus, dividing into right and left aortæ. (Ecker.)
. 194.—The heart of a frog (Rana esculenta) from the back. *s. v.*, Sinus venosus opened; *c. s. s.*,
a cava superior; *c. s. d.*, right vena cava superior; *c. i.*, vena cava inferior; *v. p.*, vena pul-
s; *A. d.*, right auricle; *A. s.*, left auricle; *A. p.*, opening of communication between the right
and the sinus venosus. × 2½–3. (Ecker.)

ıus system, nor yet upon the stimulation produced by the presence
ood within its chambers—it is **automatic**. The cause of this
ımic power has been the subject of much discussion and experi-
al observation. Up to a comparatively short time ago, the remark-
property of the heart to continue its rhythmical contractions after
val from the body was believed to be connected in some way or
with the presence of collections of nerve cells, or ganglia in sev-
arts of its tissue. Although this idea, as we shall presently see, has
been very generally given up, it may be as well to describe shortly
ganglia in this place; they have been studied more particularly

in the heart of the frog, of the tortoise, and of other cold-l animals.

In the frog's heart (fig. 193) these ganglia consist of thre groups. The first group is situated in the wall of the sinus at the junction of the sinus with the right auricle (*Remak's* second group is placed near the junction between the auricles a tricle (*Bidder's*); and the third in the septum between the a (*v. Bezold's*).

The nerve cells of which these ganglia are composed are ge unipolar, and seldom bipolar; sometimes two cells are said to the same envelope, constituting the *twin* cells of Dogiel. Tl are large, and have very large round nuclei and nucleoli (fig Ganglion cells have not been found in the lower part of the ventr

As regards the automatic mov of the heart removed from the b chief knowledge has been derive the study of the hearts of the fr tortoise.



Fig. 195.



Fig. 196.

Fig. 195. Course of the nerves in the auricular partition wall of the heart of a frog. branch; v, ventral branch. (Ecker.)

Fig. 196. Isolated nerve-cells from the frog's heart. I. Usual form. II. Twin cell. C N, nucleus; N', nucleolus; P, process. (From Ecker.)

If removed from the body entire, the frog's heart will cont beat for many hours and even days, and the beat has no apparen ence from the beat of the heart before removal; it will take plac have mentioned, without the presence of blood or other fluid wi chambers. Not only is this the case, but the auricles and ventri be cut off from the sinus, and both parts continue to pulsate, a ther the auricles may be divided from the ventricle with the same If the heart be divided lengthwise, its parts will continue to rhythmically, and the auricles may be cut up into pieces, and th will continue their movements of rhythmical contraction.

It will be thus seen that the rhythmical movements appea more marked in the parts supplied by the ganglia, as the apical the ventricle, in which ganglia have not been found, does not, under inary circumstances, possess the power of automatic movement.

It has, however, been shown by Gaskell that the extreme apex of the tricle of the heart of the tortoise, which contains no ganglia, may der appropriate stimuli be made to contract rhythmically. This ves that the muscular tissue of the heart itself is capable of rhythcal contraction independent of the ganglia. Thus it seems probable at the rhythmic contractility of the heart is a power inherent in the uscular tissue, which is quite independent as far as its commencement, any rate, is concerned of nerve influence.

The heart-muscle exhibits another property which distinguishes it om ordinary skeletal muscle, viz., the way in which it reacts to stimuli. he latter as will be described at greater length in its appropriate place, acts slightly to a slight stimulus above the minimal, and with an inease of the strength of the stimuli will give increasingly ample conactions until the maximum contraction is reached; in the case of the eart-beats this is not so, since the *minimum stimulus which has any fect is followed by the maximum contraction;* in other words the weakt effectual stimulus brings out as great a beat as the strongest. There another great difference between the contraction of the heart and of eletal muscle, viz., the *inability* of the former *to enter into a state of anus* under the influence of stimuli repeated very rapidly. If the art be stimulated by a series of rapid interrupted induction shocks, ere is no summation of the contractions, as there would be supposing ordinary skeletal muscle were stimulated in the same way. This enomenon is said to be due to the following fact, viz., that in order to oduce an extra contraction of the excised frog's heart, the stimulus ust be applied during diastole or period of rest or relaxation, and in at case the next contraction happens at an earlier period than if the mulus were not applied. If applied during the systole, the stimulus s scarcely any effect; the period during which the muscle is refractory stimuli is much longer in the case of the heart than in the case of her muscles. In order to produce a tetanus in skeletal muscle, the cond stimulus must be sent into the muscle before it has had time to cover from the effect of the first stimulus and relax, and so on with e third, fourth, and other stimuli. If, as we may suppose, the same nditions for the production of tetanus are necessary in heart-muscle, e reasons of the impossibility of producing tetanus, *i.e.* that a stimus applied during contraction is ineffectual, are sufficiently obvious. appears, however, that if the stimuli are sufficiently strong and rapy repeated, the refractory period during which the muscle is pracally insensible to stimuli diminishes, and a very rapid repetition of e beats occurs. As a rule the beats are fewer with rapid stimulation.

In connection with the rhythmic contraction of muscle, it is nec sary to allude briefly to what is known as **Stannius' experime** This experiment consisted originally of applying a tight ligature to th heart between the sinus and the right auricle, the effect of which is to the beat of the heart below the ligature, while the sinus and the v leading into it continue to beat. If a second ligature be applied at th junction of the auricles and ventricle, the ventricle may begin to b slowly, while the auricles continue quiescent. In both cases the qui cent parts of the heart may be made to give single contractions i response to mechanical stimulation. A considerable amount of discus has arisen as to the explanation of these phenomena. It was sugge that the action of the ligature is to stimulate some inhibitory nerv mechanism in the sinus, whereby the auricles and ventricle can longer continue to contract, but this suggestion must certainly be giv up if the present theory as to the functions of the nerve ganglia be c rect. It may be that the effect of Stannius' ligature is simply an ex ple of what has been called by Gaskell *blocking*. The explanation this term is as follows:—it appears that under normal conditions th wave of contraction in the heart starts at the sinus and travels dow ward over the auricles to the ventricle, the irritability of the mus and the power of rhythmic contractility being greatest in the sinus, le in the auricles and still less in the ventricle, while under ordinary co ditions the apical portion of the ventricle exhibits very slight irritabilit and still less power of spontaneous contraction. Thus it may be su posed that the wave of contraction beginning at the sinus is more less blocked by a ring of muscle of lower irritability at its junction wit the auricles, and again the wave in the auricles is similarly delayed i its passage over to the ventricle by a ring of lesser irritability, and th the wave of contraction starting at the sinus is broken as it were bo at the auricles and at the ventricle. By an arrangement of ligatures, better, of a system of clamps, one part of the heart may be isolated fro the other portion, and the contraction when stimulated by an inducti shock may be made to stop in the portion of the heart-muscle in whi it begins. It is not unlikely that the contraction of one portion of th heart acts as a stimulus to the next portion, and that the sinus contra tion generally begins first, since the sinus is the most irritable to stimu and possesses the power of rhythmic contractility to the most high developed degree. It must not be thought, however, that the wave contraction is incapable of passing over the heart in any other directi than from the sinus downward: it has been shown that by applicati of appropriate stimuli at appropriate instants, the natural sequence beats may be reversed, and the contraction starting at the arterial p of the ventricle may pass upward to the auricles and then to the si in order.

An exceedingly interesting fact with regard to the passage of the ve in any direction has been made out by partial division of the mus- lar fibres at any point, whereby one part of the wall of the heart is t connected with the other parts by a small portion of undivided uscular tissue, and the wave of contraction then being only able to ss to the next portion of the wall every second or third beat. Thus vision of the muscle has much the same effect as partial clamping it the same position, or of a ligature similarly applied, but not tied ghtly. It may, therefore, be suggested that Stannius' ligature acts as partial or complete block, and prevents the stimulus of the sinus-beat rom passing further down the heart, but that the parts below the liga- ure may be made to contract by stimuli applied to them directly. Nearly all the information to be obtained as to the phenomena of the contraction of heart-muscle apart from the rhythmic action of the organ itself, may be obtained from a heart to which a Stannius' ligature has been applied; indeed, the effect of minimal stimuli, the effect of rapidly repeated shocks, and the refractory period of heart-muscle may all be studied from a heart in this condition.

The velocity of the wave of contraction in frog's heart-muscle has een shown to be $\frac{2}{5}$ to $\frac{3}{5}$ inch, or 10–15 *mm.* a second.

In pointing out the differences between the phenomena of contrac- ion in skeletal and heart-muscle, the similarities between the two are ot to be overlooked; thus it has been shown that the effect of cold, eat, fatigue, and other influences have very much the same effect in oth cases.

2. *The influence of the central nervous system.*

The heart is capable of automatic rhythmic movement, as has been early shown by its behavior when removed from the body, and it has een shown further that there is reason for believing that the power sides in the inherent property of its muscle fibres themselves. While the body, however, the heart's beats are under control of the central ervous system. To this nervous control, we must next direct our at- ntion. The influence which is exerted by the central nervous system ppears to be of two kinds, firstly, *in the direction of slowing or inhibit- g the beats*, and secondly, *in the direction of accelerating or augment- g the beats.* The influence of the first kind is brought to bear upon e heart through the fibres of the vagi nerves, and that of the second ind through the sympathetic fibres.

**Influence of the Vagi.**—It has long been known, indeed ever since e experiments of the Bros. Weber in 1845, that stimulation of one or oth vagi produces slowing of the beats of the heart. It has since been own in all of the vertebrate animals experimented with, that this is e normal action of vagus stimulation. Moreover, section of one nerve, or at any rate of both vagi, produces acceleration of the pulse, and s ulation of the distal or peripheral end of the divided nerve prod normally slowing or stopping of the heart's beats.

It appears that any kind of stimulus produces the same effect, e chemical, mechanical, electrical, or thermal, but that of these the potent is a rapidly interrupted induction current. A certain amou confusion has arisen as to the effect of vagus stimulation in quence of the fact that within the trunk of the nerve is contain some animals, fibres of the sympathetic, and it depends to some upon the exact position of the application of the stimulus, as exact effect produced. Speaking generally, however, excitation part of the trunk of the vagus produces inhibition, the stimulus particularly potent if applied to the termination of the vagi heart itself, where they enter the substance of the organ at the si of the sinus ganglia. The stimulus may be applied to either vag effect, although it is frequently more potent if applied to the n the right side. The effect of the stimulus is not immediately se or more beats may occur before stoppage of the heart takes pla slight stimulation may produce only slowing and not complete s



Fig. 197.—Tracing showing the actions of the vagus on the heart. *Aur.*, Auricular; tricular tracing. The part between perpendicular lines indicates period of vagus stimul indicates that the secondary coil was 8 *cm.* from the primary. The part of tracing shows the regular contractions of moderate height before stimulation. During stimulati some time after, the beats of auricle and ventricle are arrested. After they commence are single at first, but soon acquire a much greater amplitude than before the applicati stimulus. (From Brunton, after Gaskell.)

of the heart. The stoppage may be due either to prolongation diastole, as is usually the case, or to diminution of the systole. stimulation inhibits the spontaneous beats of the heart only, it d do away with the irritability of the heart-muscle, since mechanic ulation may bring out a beat during the still-stand caused b stimulation. The inhibition of the beats varies in duration, bu stimulation be a prolonged one, the beats may reappear before t rent is shut off. When the beats reappear, the first few are feeble, and may be auricular only; after a time the contractions more and more strong, and very soon exceed both in amplitu those which occurred before the application of the stimulus

**ice of the Sympathetic.**—The influence of the sympathetic
nsidered, to a certain extent, as the reverse of that of the
imulation of the sympathetic, even of one side, produces ac-
of the heart-beats, and according to certain observers, section
e nerve produces slowing. The acceleration produced by stim-
the sympathetic fibres is accompanied by increased force, and
on of the nerve is more properly termed *augmentor*. The
he sympathetic differs from that of the vagus in several par-
ides the augmentation which is produced: firstly, the stimulus
produce any effect must be more powerful than is the case
agus stimulation; secondly, a longer time lapses before the
nifest; and thirdly, the augmentation is followed by exhaus-
eats being after a time feeble and less frequent.

**of the cardiac nerve-fibres.**—The fibres of the sympa-
em, which influence the heart-beat in the frog, leave the
l by the anterior root of the third spinal nerve, and pass
the ramus communicans to the third spinal ganglion, thence
nd spinal ganglion, and thence by the annulus of Vieussens



racing showing diminished amplitude and slowing of the pulsations of the auricle
without complete stoppage during irritation of the vagus. (From Brunton, after

subclavian artery) to the first spinal ganglion, and thence in
unk of the sympathetic, to near the exit of the vagus from
n, where it joins that nerve and runs down to the heart within
forming the joint vago-sympathetic trunk.

log, the augmentor fibres leave the cord by the second and
i nerves, and possibly by anterior roots of two or more lower
sing by the rami communicantes to the ganglion stellatum,
racic ganglion, thence by the annulus of Vieussens to the
vical ganglion of the sympathetic fibres from the annulus, or
ferior cervical ganglion proceed to the heart.

e fact that the augmentor fibres are joined to the vagus trunk, it may be understood that the effect of the stimulation of th vagus in the frog is not in all cases purely inhibitory, but may be a mentor, according to the position where the stimulus is applied, th intensity of the stimulus, and the condition of the heart; if it is beatin strongly a slight vagus stimulation will produce immediate inhibition.

The fibres of the vagus which pass to the heart arise in the medu oblongata, in the floor of the fourth ventricle, and in a nucleus of g matter, the exact position of which will be indicated in a future cha ter. It was formerly thought that the inhibitory fibres in the vag trunk were derived from the spinal accessory nerve, but this view h been largely abandoned. The spinal accessory fibres probably supp certain muscles of the larynx. It has been found that stimulation this nucleus, which is called the **cardio-inhibitory centre,** produc inhibition of the heart-beat.

Thus there is no doubt that the vagi nerves are simply the media an inhibitory or restraining influence over the action of the heart, whi is conveyed through them from the centre in the medulla oblonga which is always in operation. The restraining influence of the cent in the medulla may be reflexly *increased* by stimulation of almost a afferent nerve, particularly of the abdominal sympathetic, so as to pr duce slowing or stoppage of the heart, through impulses from it passi down the vagi. As an example of this reflex stimulation, the we known effect on the heart of a violent blow on the epigastrium may referred to. The stoppage of the heart's action in this case is due the conveyance of the stimulus by fibres of the sympathetic (afferen to the medulla oblongata, and its subsequent *reflection* through the va (efferent) to the muscular substance of the heart. It is possible that power of the medullary inhibitory centre may in a similar manner reflexly *lessened* so as to produce accelerated action of the heart.

The course of the augmentor fibres in the spinal cord is not kno but it is thought that in all probability they are connected with an a mentor centre in the medulla. The circulation of venous blood appe to stimulate the inhibitory centre, and of highly oxygenated the a mentor centre.

In addition to direct and reflex stimulation it is almost certain th impulses passing down from the cerebrum may have a similar effect.

*Other Influences Affecting the Heart-Beat.*—**Alteration of temper ture.**—The effect of cold is to slow the heart-beats, and if the heart cooled down to 3° C. (38° F.) it will stop beating. The heart may frozen, and when thawed will continue its spontaneous beats. T effect of heat is to quicken and shorten the heart-beats, but at a mod ate temperature, 20° C. (68° F.), the contractions are increased in for

At or below 40° C. (104° F.) the contrations are so rapid as to pass into heart-rigor; this may be stopped by cooling.

**Poisons and other chemical substances.**—A large number of chemical substances have a distinct effect upon the cardiac contractions. Of these the most important are *atropin* and *muscarin*.

*Atropin* produces considerable augmentation of the heart-beats, and when acting upon the heart prevents the results of vagus stimulation.

*Muscarin* (obtained from various species of poisonous fungi) produces marked slowing of the heart-beats, and, in larger doses, stoppage of the heart. It produces a similar effect to that of prolonged vagus stimulation, and as in that case the effect can be removed by the action of atropin.

*Digitalin* (the active principle of digitalis purpurea), slows the heart and appears to act by stimulating the vagi. Later on the muscle is also more excitable. *Veratrin* and *aconitin* have a similar effect. *Nicotine* prevents the effect of vagus stimulation.

### Methods of investigating the Heart-beat.

(1) The simplest form of an apparatus to be used for recording the contractions of the frog's heart consists of a small closed cylindrical box fixed to a stand. At the bottom of the box are two tubes by means of which water at various temperatures may be made to circulate through it, one tube being the inlet and the other the outlet, and they are connected with india-rubber, suitable for the purpose of conducting water to and from the apparatus. The lever is made of a piece of glass rod which is softened and drawn out in the flame of the blow-pipe a very fine thread, leaving a small piece unaltered to act as a counterpoise. The lever is then passed through a piece of cork and through this cork a fine needle is inserted at right angles to the lever. The needle is made to rest on a support attached above one side of the box in such a way that the lever has free movement up and down. Another small piece of cork is passed along the lever arm and is adjusted and cut so that its point directed downward can rest upon the frog's heart, which is removed from the body and placed upon the top of the box in serum or defibrinated blood. In this way the contractions of the auricles and ventricle are communicated to the lever, and this may be made to write upon a recording cylinder.

(2) The variations of endocardial pressure, which correspond, of course, with the various phases of the cardiac cycle, may be recorded by a modification of the ordinary mercurial manometer. The apparatus is best used with a large frog (*Rana esculenta*), and the heart is exposed in the usual manner, the pericardium opened. A cut is made into the bulb, and by this means a double or *perfusion canula* (fig. 199) is passed into the ventricle, a ligature is passed round the heart, and the canula is tied in tightly. The vessels are then divided beyond the ligature, and the canula, with the heart attached, is removed. To one stem of the canula a tube is attached, communicating with a reservoir of a solution of dried blood in .6 saline solution, and filtered, which is capable of being raised or lowered in temperature by being surrounded by a metal box which contains hot, cold, or iced water. Attached to the other end is a

**similar tube, which communicates by a T piece with a small mercurial m
ometer, provided with a writing style, and also with a vessel into which
serum is received. The apparatus being arranged so that the movement
the mercury can be recorded by the float and the writing style on a slo
revolving drum, and after some serum has been allowed to pass freely thro
the ventricle, both tubes are clipped, the second one beyond the T piece,
the alterations in the pressure are recorded. The effects of fluids at var
temperatures and of poisons may be recorded in the manner indicated abo**

(3) By *Roy's Tonometer* (fig. 200) the alterations in volume which a fr
heart undergoes during contraction are recorded by the following means: A small bell-jar, open above, but provided with a firmly fitting cork, in which is fixed a double canula, is adjustable by a smoothly ground base upon a circular brass plate,





Fig. 199.

Fig. 200.

Fig. 199. Kronecker's Perfusion Canula, for supplying Fluids to the interior of the
Heart. It consists of a double tube, one outside the other; the end view is shown in the engr
The inner tube branches out to the left; thus, when the ventricle is tied to the outer tube of th
ula, a current of liquid can be made to pass into the heart by one tube and out through the ot
Fig. 200.- Roy's Tonometer.

about 2 to 3 inches in diameter. The junction is made complete by g
ing the base with lard. In the plate, which is fixed to a stand adjustab
an upright, are two holes, one in the centre, a large one about one-
of an inch in diameter, to which is fixed below a brass grooved c
about half an inch deep; the other hole is the opening into a pipe prov
with a tap (stopcock). The opening provided with the collar is closed a
lower part with a membrane of animal tissue, which is loosely tied by n
of a ligature around the groove at the lower edge of the collar. To this n
brane a piece of cork is fastened by sealing-wax, from which passes a
which can be attached to a lever, fixed on a stage below the apparatus.

When using the apparatus, the bell-jar is fixed by means of lard, and
jar is filled with olive oil. In the way above described, the heart of a
frog is prepared and the canula fixed in the cork is firmly tied into the h
the tubes of the canula communicating with the reservoir of serum on
one hand, and with a vessel to contain the serum after it has run throu
the other. The canula with heart attached is passed into the oil, an
cork firmly secured. By these means the lever will be found to be adjus

nient elevation. The lever is allowed to write on a moving drum, and is passed through at various temperatures. After a short time the heart op beating; but two wires are arranged, the one in the canula, the rojecting from the plate in such a way that the heart can be moved them by shifting the position of the bell-jar a little. The wires act as es, and can be made to communicate with an induction apparatus, so gle induction shocks can be sent into the heart to produce contractions, need be, by means of the trigger key, at one definite point in the revo- f the recording cylinder.

**ctrical Phenomena of the Heart-beat.**—The phenomena of ural beat of the heart are generally considered to indicate that tolic contraction is a single and not a tetanic one. The electrical s support this view. During the contraction a distinct electrical occurs which is similar to that which happens in skeletal muscle ach contraction. It has been demonstrated that a stanniused art undergoes two changes or phases as regards its electrical con- the first immediately before the contraction, in which the excited ecomes negative to the other parts, contraction following the f excitation, and the second during relaxation, in which the cur-



01.—Capillary electrometer (Ostwald). *C.T.* represents capillary tube containing mercury l sulphuric acid ($H_2SO_4$) in contact at *M*. If a current enters the mercury at *W*, and, tra- e *Hg* and $H_2SO_4$, leaves through the wire *W'*, the mercury meniscus at *M* will move up in B. If the current is reversed the mercury will move in the opposite direction, *i.e.*, toward the In other words, the mercury moves in the direction of the current.

ows in an opposite way. This may be demonstrated by placing art in circuit by means of non-polarizable electrodes with some f current detector, such as the capillary electrometer (fig. 201).

**e Metabolism of the Heart.**—Whatever view may be taken of the nature of the rhythmic cardiac contractions, it will be generally acknowledged that the contractions cannot long be maintained without a due supply of blood or of a similar nutritive fluid. Some very remarkable facts have been made out about this, in the case of the frog's heart. For instance, it has been shown that normal saline solution is insufficient to maintain the contractions, and that in experiments in which it is necessary to maintain the beats for any length of time failing serum or saline solution of dried blood, the solution should contain some serum-albumin, and that there should also be present some potassium chloride, and Dr. Ringer has composed a nutritive fluid which contains chlorides of sodium, potassium, and calcium in small amounts, which is able to maintain the normal beats of the heart. It is therefore very reasonable to suppose that the amount and quality of the blood supplied to the human heart has the greatest influence in maintaining the force and frequency of the rhythmic activity. The view that is taken at present of the action of the heart is one propounded by Gaskell, viz., that in heart muscle as in protoplasm generally, the metabolic processes are those of anabolism or building up, which takes place during the diastole of the heart, that vagus stimulation helps on this process, and of katabolism or discharge, which is manifested in the contraction of the heart, and which is accelerated by stimulation of the sympathetic fibres. That vagus stimulation is therefore ultimately beneficial to the contractions. The electrical currents set up on the stimulation of the vagus and of the sympathetic are in opposite directions, and so if Gaskell's contention is correct that the negative variation of the muscle current occurring on sympathetic stimulation is a sign of katabolism, the result of vagus stimulation, viz., a positive variation of the muscle current, may be supposed to indicate the complementary condition of anabolism.

3. *The Amount of Blood Passing into the Heart's Cavities.*—It is found that in the body, at any rate, the amount of blood which passes into the cavities of the heart distinctly affects the strength of its beat. Thus, if from any cause, the blood is diminished the contractions become much more feeble, although they may possibly be increased in rapidity. Similarly with

4. *The Amount of Pressure to be Overcome.*—If the aortic pressure is too low the muscle contractions of the heart is not so powerful or effective as if the pressure is normal, whereas too great arterial pressure may be sufficient to delay if not to stop altogether the heart's beats, dilatation of its cavities taking place and a condition of *asystolism* (Beau) resulting.

Another condition sometimes forgotten should be added as influencing the potency of the cardiac contraction, viz., the heart must have sufficient room to contract, it must not be unduly pressed upon.

5. *The Coronary Circulation.*—The nutrition of the heart wall has

y investigated by Porter and others. The coronary arteries are
arteries; that is, they do not permit the establishment of a
circulation when one of their branches is blocked. If the
complete, that portion of the heart wall supplied by the branch
ıe immediate effect of the closure of a large branch, in the dog,
ccasional and transient irregularity, or arrest of the ventricular
ons, preceded by irregularities in the force of the contractions
ninution in the amount of work performed. The force, rather



–Plethysmograph. By means of this apparatus, the alteration in volume of the arm,
nclosed in a glass tube, A, filled with fluid, the opening through which it passes being
by a thick gutta-percha band, F, is communicated to the lever, D, and registered by a
pparatus. The fluid in A communicates with that in B, the upper limit of which is
n A. The chief alterations in volume are due to alteration in the blood contained in the
the volume is increased, fluid passes out of the glass cylinder, and the lever, D, also is
vhen a decrease takes place the fluid returns again from B to A. It will therefore be
the apparatus is capable of recording alterations of blood-pressure in the arm. Appa-
d upon the same principle have been used for recording alterations in the volume of
nd kidney.

rate, of the ventricular contractions is closely dependent upon
-supply to the coronary arteries.

ime during which nutrition of the ventricles, through the cor-
hiefly occurs is the diastolic phase, for during the height of
ar contraction the vessels within the cardiac muscles are so
pon that the flow of blood through them is stopped.

**els of Thebesius.**—These vessels, which have been demon-
open both into the auricular and ventricular cavities, must
oked upon, according to the investigations of F. H. Pratt, as
tant source of cardiac nutrition. Through them blood may
ay of connecting branches to the coronary arteries and veins.
ceeded in preserving cardiac contractions for several hours
only source of nutrition was from these vessels. This source
ion may account for the survival of hearts for years where
ed arterio-sclerosis of the coronary arteries has been found
em.

(b.) **The Peripheral Resistance.**—The regulation of the amount of resistance to the passage of blood at the periphery is principally done by the alteration of the calibre of the arterioles. This regulating power is chiefly invested in the nervous system. Its influence is exerted upon the muscular coat of the arteries and not upon the elastic element, which possesses, as must be obvious, rather physical than vital properties. The muscular tissue in the walls of the vessels increases in amount relatively to the other coats as the arteries grow smaller, so that in the arterioles it is developed out of all proportion to the other elements; in fact, in passing from capillary vessels, made up as we have seen of endothelial cells with a ground substance, the first change which occurs as the vessels become larger (on the side of the arteries) is the appearance of muscular fibres. Thus the nervous system is more powerful in regulating the calibre of the smaller than of the larger arteries.

It was long ago shown by Claude Bernard that if the cervical sympathetic nerve is divided in a rabbit, the blood-vessels of the corresponding side of the head and neck become dilated. This effect is best seen in the ear, which if held up to the light is seen to become redder, and the arteries are seen to become larger. The whole ear is distinctly warmer than the opposite one. This effect is produced by removing the arteries from the influence of the central nervous system, which influence normally passes down the divided nerve; for if the peripheral end of the divided nerve (*i.e.*, that farthest from the brain) be stimulated, the arteries which were before dilated return to their natural size, and the parts regain their primitive condition. And, besides this, if the stimulus is very strong or very long continued, the point of normal constriction is passed, and the vessels become much more contracted than normal. The natural condition, which is about midway between extreme contraction and extreme dilatation, is called the natural **tone** of an artery if this is not maintained, the vessel is said to have lost tone, or if it i exaggerated, the tone is said to be too great. The effects described a having been produced by section of the cervical sympathetic and by subsequent stimulation are not peculiar to that nerve, as it has been found that for every part of the body there exists a nerve the division of which produces the same effects, viz., dilatation of the vessels; such may be cited as the case with the sciatic, the splanchnic nerves, and th nerves of the brachial plexus: when these are divided, dilatation of th blood-vessels in the parts supplied by them takes place. It appear therefore, that nerves exist which have a distinct control over the va cular supply of every part of the body. These nerves are called vas *motor.*

Recently Mall has shown that *veins* possess a vaso-motor nerve-suppl as well as arteries.

Vaso-motor nerves may be divided into two classes, according to thei

ction of causing contraction or dilatation of the blood-vessels, into
**so-constrictor** and **vaso-dilator** nerves.

**Vaso-motor Centres.** *Bulbar Centre.*—The bulbar vaso-con-
ctor centre in the rabbit lies in the floor of the fourth ventricle, a
imetre or two caudal to the corpora quadrigemina, and extends
gitudinally over an area of about 3 millimetres. Owsjannikow has
wn that the centre is composed of two halves, each half lying in the
ral column to the side of the median line. This centre is in con-
t action, as is shown by dilatation of the blood-vessels when removed
n its action by section of the spinal cord.

The existence of a vaso-dilator centre in the spinal bulb has not been
ed.

*Spinal Centres.*—Secondary vaso-motor centres are present in the
al cord (Goltz). Under normal conditions they do not act indepen-
ly of the bulbar centre, but when the action of the latter has been
rrupted by section of the cord, certain spinal cells below the section
on central functions and bring about a re-establishment of the lost
ular tone. Moreover, the central functions disappear if the cord
w the section be destroyed.

*Sympathetic Vaso-motor Centres.*—The existence of sympathetic
-motor centres has been proved by the experiments of Goltz and
ald. It was found by these observers that even after destruction of
lower part of the spinal cord, the tone of the vessels of the hind
bs, lost as a result of the operation, was re-established later.

**Vaso-motor Reflexes.**—The secondary vaso-motor centres, when
oved from the influence of the bulbar centre, respond to afferent im-
lses by vaso-motor action. But under normal conditions the bulbar
tre controls vaso-motor reflexes. The afferent impulses which excite
lex vaso-motor action may proceed from the terminations of sensory
rves in general or from the blood-vessels themselves, and the constric-
n or dilatation which follows generally occurs in the area whence the
pulses arise. Yet the reflex may appear elsewhere, *e.g.*, the vessels of
submaxillary gland dilate when the tongue is stimulated—an associa-
n in function. Impulses proceeding to the vaso-motor centre from the
ebrum may cause vaso-dilatation as in *blushing*, or vaso-constriction
in the *pallor* of fear. An important reflex association exists between
vessels of the skin and those of subjacent parts. It is generally an
*erse relation;* that is, when the superficial vessels are dilated the
p are contracted. This reflex is made use of in medical practice
n poultices are applied to the chest in pneumonia, the lung being in
ate of inflammation.

Afferent influence upon the vaso-motor centre is well shown by the

action of a nerve called the **depressor**, the existence of which wa
monstrated by Cyon and Ludwig.

It is a small afferent nerve and passes up from the heart in wh
takes its origin, and in the rabbit goes upward in the sheath of th
perior laryngeal branch of the vagus or with that branch and the
itself, communicating by filaments with the inferior cervical gan
as it proceeds from the heart.

If during a blood-pressure observation in a rabbit this nerve b
vided, and the central end (*i.e.*, that nearest the brain) be stimula
remarkable fall of blood-pressure takes place (fig. 203).

The cause of the fall of blood-pressure is found to proceed fro
dilatation of the vascular district within the abdomen supplied b
splanchnic nerves, in consequence of which the vessels hold a
larger quantity of blood than usual. The engorgement of the spl
nic area very greatly diminishes the amount of blood in the vessels
where, and so materially diminishes the blood-pressure. The fun
of the depressor nerve is that of conveying to the vaso-motor centr
dications of such conditions of the heart as require a diminution o



Fig. 203.—Tracing showing the effect on blood-pressure of stimulating the central end
Depressor nerve in the rabbit. To be read from right to left. T, indicates the rate at wh
recording surface was travelling, the intervals correspond to seconds; C, the moment of entr
current; O, moment at which it was shut off. The effect is some time in developing and las
the current has been taken off. The larger undulations are the respiratory nerves; the pulse
tions are very small. (Foster.)

tension in the blood-vessels; as, for example, that the heart cannot,
sufficient ease, propel blood into the already too full or too tense art
It has been further shown, by Porter and Beyer, that the fall in b
pressure, following stimulation of the depressor nerve, will still d
even if, by simultaneous stimulation of the splanchnics, the abdo
blood-pressure is kept at a constant. It is therefore evident tha
vaso-dilator effect of depressor nerve stimulation is a general on
not confined to the splanchnic area.

The action of the depressor nerve in causing an inhibition of the so-motor centre illustrates the more unusual effect of afferent impulses. a rule, the stimulation of the central end of an afferent nerve pro- ces a reverse or **pressor** effect, and increases the tonic influence of centre, and by causing constriction of the arterioles, either locally or erally, raises the blood-pressure. Thus the effect of stimulating an rent nerve may be either to dilate or to constrict the arteries. Stim- tion of an afferent nerve too may produce a kind of paradoxical effect, sing *general* vascular constriction and so general increase of blood- ssure, but at the same time *local* dilatation which must evidently have immense influence in increasing the flow of blood through the part.

**Course of the Vaso-motor Nerves.**—The cell bodies forming bulbar vaso-motor centre give off neuraxons (axis-cylinder processes), e of which go to the nuclei of certain cranial nerves, while others s down the cord to end at different levels in contact with cells—prob- small cells in the anterior horn and lateral part of the gray matter. se cells constitute the spinal centres. The neuraxons of the spinal s leave the cord in certain cranial nerves and in the anterior roots, end in sympathetic ganglia in contact with their cell bodies. From se latter, neuraxons pass uninterruptedly to their termination in the el wall.

Besides the regulation of the heart beat and of the peripheral resist- e, it must be recollected that other circumstances may affect the blood ssure, of which **changes in the blood** are the chief. First of all—

As regards *quantity*. At first sight it would appear probable that e of the easiest ways to diminish the blood-pressure would be to re- ove blood from the vessels by bleeding. It has been found by experi- ent, however, although the blood-pressure sinks while large abstractions f blood are taking place, that as soon as the bleeding ceases it rises pidly, and speedily becomes normal; that is to say, unless so large an ount of blood has been taken as to be positively dangerous to life, bstraction of blood has little effect upon the blood-pressure. The rapid turn to the normal pressure is due not so much to the withdrawal of mph and other fluids from the body into the blood, as was formerly pposed, as to the regulation of the peripheral resistance by the vaso- otor nerves; in other words, the small arteries contract, and in so do- g maintain pressure on the blood and favor its accumulation in the terial system. This is due to the stimulation of the vaso-motor cen- from diminution of the supply of blood, and therefore of oxygen. e failure of the blood-pressure to return to normal in the too great traction must be taken to indicate a condition of exhaustion of the tre, and consequently of want of regulation of the peripheral resist- e. In the same way it might be thought that injection of blood into the already full vessels would be at once followed by rise in the blood-pressure, and this is indeed the case up to a certain point—the pressure does rise, but there is a limit to the rise. Until the amount of blood injected equals about 2 to 3 per cent of the body-weight, the pressure continues to rise gradually; but if the amount exceed this proportion, the rise does not continue. In this case, therefore, as in the opposite when blood is abstracted, the vaso-motor apparatus must counteract the great increase of pressure, but now by dilating the small vessels, and so diminishing the peripheral resistance, for after each rise there is a partial fall of pressure; and after the limit is reached the whole of the injected blood displaces, as it were, an equal quantity which passes into the small veins, and remains within them. It should be remembered that the veins are capable of holding the whole of the blood of the body.

Further, as we have seen, the amount of blood supplied to the heart, both to its substance and to its chambers, has a marked effect upon the blood-pressure.

*b.* As regards *quality*. The quality of the blood supplied to the heart has a distinct effect upon its contraction, as too watery or too little oxygenated blood must interfere with its action. Thus it appears that blood containing certain substances affects the peripheral resistance by acting upon the muscular fibres of the arterioles, and so directly altering the calibre of the vessels.

## Proofs of the Circulation of the Blood.

It seems hardly necessary at the present time to bring forward the proofs that during life the blood circulates within the body; they are so well known. It is interesting, however, to recount the main arguments by which Harvey in the first instance established the fact of the circulation; they were as follows:—

1. That the heart in half an hour propels more blood than the whole mass of blood in the body;

2. That the blood spurts with great force and in a jerky manner from an opened artery, such as the carotid, with every beat of the heart;

3. That if true, the normal course of the circulation would explain why after death the arteries are commonly found empty and the veins full;

4. That if the large *veins* near the heart be tied in a fish or snake, the heart becomes pale, flaccid, and bloodless; and that on moving the ligature, the blood again flows into the heart. If the *artery* is tied, the heart becomes distended, the distention lasting until the ligature is removed;

5. That if a ligature round a limb be drawn very tight, no blood can

ar the limb, and it becomes pale and cold. If the ligature be some-
t relaxed, blood can enter but cannot leave the limb; hence it be-
es swollen and congested. If the ligature be removed, the limb
n regains its natural appearance;

6. That the valves in the veins only permit the blood to flow toward
heart;

7. That there is general constitutional disturbance resulting from
introduction of a poison at a single point, *e.g.*, snake poison;

To these may now be added many further proofs which have accu-
lated since the time of Harvey, *e.g.*:—

1. That in wounds of arteries and veins; in the former case hemor-
ge may be almost stopped by pressure between the heart and the
nd, in the latter by pressure beyond the seat of injury;

. That the passage of blood-corpuscles from small arteries through
llaries into veins in all transparent vascular parts, as the mesentery,
ue, or web of the frog, the tail or gills of a tadpole, etc., may actu-
be observed under the microscope.

urther, it is obvious that the mere fact of the existence of a hollow
ular organ (the heart) with valves so arranged as to permit the
l to pass only in one direction, of itself suggests the course of the
lation. The only part of the circulation which Harvey could not
w was that through the capillaries, for the simple reason that he
o lenses sufficiently powerful to enable him to see it. Malpighi
) and Leeuwenhoek (1668) demonstrated this in the tail of the tad-
nd lung of the frog.

# CHAPTER VII.

## RESPIRATION.

THE maintenance of animal life necessitates the continual abs
of oxygen and excretion of carbonic acid; the blood being, in
mals which possess a well-developed blood-vascular system, the n
by which these gases are carried. By the blood, oxygen is al
from without and conveyed to all parts of the organism; and,
blood, carbonic acid, which comes from within, is carried to thos
by which it may escape from the body. The two processes,—abs
of oxygen and excretion of carbonic acid, are complementary, an
sum is termed the process of *Respiration*.

In all Vertebrata, and in a large number of Invertebrata, certai
either *lungs or gills*, are specially constructed for bringing th
into proximity with the aërating medium (atmospheric air, or wa
taining air in solution). In some of the lower Vertebrata (fr
other naked Amphibia) the skin is important as a respiratory
and is capable of supplementing, to some extent, the functions
*proper breathing* apparatus; but in all the higher animals, in
man, the respiratory capacity of the skin is so infinitesimal that
be practically disregarded.

Essentially a lung or gill is constructed of a fine transparen
brane, one surface of which is exposed to the air or water, as t
may be, while, on the other, is a network of blood-vessels,—the o
aration between the blood and aërating medium being the thin
the blood-vessels, and the fine membrane on one side of which
are distributed. The difference between the simplest and th
complicated respiratory membrane is one of degree only.

The various complexity of the respiratory membrane, and t
of aërating medium, are not, however, the only conditions whic
a difference in the respiratory capacity of different animals. Th
ber and size of the red blood-corpuscles, the mechanism of the br
apparatus, the presence or absence of a *pulmonary* heart, physiol
distinct from the *systemic*, are, all of them, conditions scarcely
in importance.

It may be as well to state here that the lungs are only the r
for the *exchange*, on the part of the blood, of carbonic acid for
They are not the seat, in any special manner, of those combusti

s of which the production of carbonic acid is the final result. e processes occur in all parts of the body in the substance of the es.

## The Respiratory Apparatus.

he object of respiration being the interchange of gases in the lungs, necessary that the atmospheric air shall pass into them and that hanged air should be expelled from them. The lungs are contained e chest or thorax, which is a closed cavity having no communica-



Fig. 204.



Fig. 205.

g 204.—Outline showing the general form of the larynx, trachea, and bronchi, as seen from h, The great cornu of the hyoid bone; *e*, epiglottis; *t*, superior, and *t′*, inferior cornu of the d cartilage; *c*, middle of the cricoid cartilage; *tr*, the trachea, showing sixteen cartilaginous *b*, the right, and *b′*, the left bronchus. (Allen Thomson.) × ½.
g 205.—Outline showing the general form of the larynx, trachea, and bronchi, as seen from *h*, Great cornu of the hyoid bone; *t*, superior, and *t′*, the inferior cornu of the thyroid ge; *e*, epiglottis; *a*, points to the back of both the arytenoid cartilages, which are sured by the cornicula; *c*, the middle ridge on the back of the cricoid cartilage; *tr*, the posmembranous part of the trachea; *b*, *b′*, right and left bronchi. (Allen Thomson.) × ½.

tion with the outside, except by means of the respiratory passages. Th air enters these passages through the nostrils or through the mout thence it passes through the larynx into the trachea or windpipe, whic about the middle of the chest divides into two tubes, bronchi, one t each (right and left) lung.

The *Larynx* is the upper part of the passage which leads exclusiv to the lung; it is formed by the thyroid, cricoid, and arytenoid cartilag (fig. 204), and contains the *vocal cords*, by the vibration of which th voice is chiefly produced. These vocal cords are ligamentous band attached to certain cartilages capable of movement by muscles. By their approximation the cords can entirely close the entrance into th larynx; but under ordinary conditions, the entrance of the larynx i formed by a more or less triangular chink between them, called th *rima glottidis*. Projecting at an acute angle between the base of th tongue and the larynx, to which it is attached, is a leaf-shaped cartilag with its larger extremity free, called the *epiglottis* (fig. 205, *e*). Th whole of the larynx is lined by mucous membrane, which, however, i extremely thin over the vocal cords. At its lower extremity the laryn joins the trachea.* With the exception of the epiglottis and the s called cornicula laryngis, the cartilages of the larynx are of the hyali variety.

*The Epiglottis.*—The supporting cartilage of the epiglottis is composed of yellow elastic cartilage, inclosed in a fibrous sheath (perichondrium), and covered on both sides with mucous membrane. The anterior surface, which looks toward the back of the tongue, is covered wit mucous membrane, the basis of which is fibrous tissue, elevated towar both surfaces in the form of rudimentary papillæ, and covered wit several layers of squamous epithelium. In it ramify capillary blood-vessels, and in its meshes are a large number of lymphatic channe Under the mucous membrane, in the less dense fibrous tissue of whic it is composed, is a number of tubular glands. The posterior or laryngeal surface of the epiglottis is covered by a mucous membrane, simil in structure to that on the other surface, but its epithelial coat is thinner, the number of strata of cells is less, and the papillæ few and l distinct. The fibrous tissue which constitutes the mucous membrane i in great part of the adenoid variety, and is here and there collected int distinct masses or follicles. The glands of the posterior surface a smaller but more numerous than those of the other surface. In man places the glands which are situated nearest to the perichondrium a directly continuous through apertures in the cartilage with those on th other side, and often the ducts of the glands from one side of the carti

---

* A detailed account of the structure and function of the Larynx will found in a later chapter.

s through and open upon the mucous surface of the other side.
*blets* have been found in the epithelium of the posterior surface
piglottis, and in several other situations in the laryngeal mucous
ne.

*Trachea and Bronchi.*—The trachea extends from the cricoid
e, which is on a level with the fifth cervical vertebra, to a point
the third dorsal vertebra, where it divides into the two bronchi



.—Section of the trachea. *a*, Columnar ciliated epithelium; *b* and *c*, proper structure of
s membrane, containing elastic fibres cut across transversely; *d*, submucuous tissue
mucous glands, *e*, separated from the hyaline cartilage, *g*, by a fine fibrous tissue, *f*; *h*,
vestment of fine fibrous tissue. (S. K. Alcock.)

ach lung (fig. 205). It measures, on an average, four or four-and-
ches in length (12 to 14 cm.), and from three-quarters of an inch
ch in diameter (2 to $2\frac{1}{2}$ cm.), and is essentially a tube of fibro-
embrane, within the layers of which are enclosed a series of car-
us rings, from sixteen to twenty in number. These rings extend
und the front and sides of the trachea (about two-thirds of its
erence), and are deficient behind; the interval between their poste-
emities being bridged over by a continuation of the fibrous mem-

brane in which they are closed (fig. 206). The cartilages of the trachea and bronchial tubes are of the hyaline variety.

Immediately within this tube, at the back, is a layer of unstriped muscular fibres, which extends, *transversely*, between the ends of the cartilaginous rings to which they are attached, and opposite the intervals between them, also; their evident function being to diminish, when required, the calibre of the trachea by approximating the ends of the cartilages. Outside there are a few *longitudinal* bundles of muscular tissue, which, like the preceding, are attached both to the fibrous and cartilaginous framework.

The mucous membrane consists to a great extent of adenoid tissue, separated from the stratified columnar epithelium which lines it by a homogeneous basement membrane. This is penetrated here and there by channels which connect the adenoid tissue of the mucosa with the intercellular substance of the epithelium. The stratified columnar epithelium is formed of several layers, of which the most superficial layer is ciliated, and is often branched downward to join connective tissue corpuscles; while between these branched cells are smaller elongated cells prolonged up toward the surface and down to the basement membrane. Beneath these are one or more layers of more irregularly-shaped cells. Many of the superficial cells are of the goblet variety. In the deeper part of the mucosa are many elastic fibres between which lie connective-tissue corpuscles and capillary blood-vessels.

Numerous mucous glands are situated on the exterior and in the substance of the fibrous framework of the trachea; their ducts perforating the various structures which form the wall of the trachea, and opening through the mucous membrane into the interior.

The two bronchi into which the trachea divides, of which the right is shorter, broader, and more horizontal than the left (fig. 204), resemble the trachea exactly in structure, with the difference that in them there is a distinct layer of unstriped muscle arranged circularly beneath the mucous membrane, forming the *muscularis mucosæ*. On entering the substance of the lungs the cartilaginous rings, although they still form only larger or smaller segments of a circle, are no longer confined to the front and sides of the tubes, but are distributed impartially to all parts of their circumference.

The bronchi divide and subdivide, in the substance of the lungs, into a number of smaller and smaller branches, which penetrate into every part of the organ, until at length they end in the smaller subdivisions of the lungs, called *lobules*.

All the larger branches have walls formed of tough membrane, containing portions of cartilaginous rings, by which they are held open, unstriped muscular fibres, as well as longitudinal bundles of elastic sue. They are lined by mucous membrane, the surface of which, like at of the larynx and trachea, is covered with ciliated epithelium, but e several layers become less and less distinct until the lining consists a single layer of more or less cubical cells covered with cilia (fig. 207). he mucous membrane is abundantly provided with mucous glands.

As the bronchi become smaller and smaller, and their walls thinner, e cartilaginous rings become scarcer and more irregular, until, in the aller bronchial tubes, they are represented only by minute and scatred cartilaginous flakes. And when the bronchi, by successive branches e reduced to about $\frac{1}{40}$ of an inch (.6 mm.) in diameter, they lose their rtilaginous element altogether, and their walls are formed only of a ugh fibrous elastic membrane, with circular muscular fibres; they are ll lined, however, by a thin mucous membrane, with ciliated epitheim, the length of the cells bearing the cilia having become so far minished that the cells are now almost cubical. In the smaller bron-



Fig. 207.—Transverse section of a bronchus, about ⅙ inch in diameter. *e*, Epithelium (ciliated); nediately beneath it is the mucous membrane or internal fibrous layer, of varying thickness; *m*, scular layer; *s. m*, submucous tissue; *f*, fibrous tissue; *c*, cartilage enclosed within the layers fibrous tissue; *g*, mucous gland. (F. E. Schulze.)

i the circular muscular fibres are relatively more abundant than in he larger bronchi, and form a distinct circular coat.

*The Lungs and Pleuræ.*—The Lungs occupy the greater portion of he thorax. They are of a spongy elastic texture, and on section appear o the naked eye as if they were in great part solid organs, except here and there, at certain points, where branches of the bronchi or air-tubes may have been cut across, and show, on the surface of the section, their ubular structure. In fact, however, the lungs are hollow organs, each of which communicates by a separate orifice with a common air-tube, he trachea.

Each lung is enveloped by a serous membrane—the *pleura*, one layer of which adheres closely to its surface, and provides it with its smooth and slippery covering, while the other adheres to the inner surface of he chest-wall. The continuity of the two layers, which form a closed ac, as in the case of other serous membranes, will be best understood y reference to fig. 208. The appearance of a space, however, between the pleura which covers the lung (*visceral* layer), and that which li the inner surface of the chest (*parietal* layer), is inserted in the dr ing only for the sake of distinctness. These layers are, in health, eve where in contact, one with the other; and between them is only jus much fluid as will insure gliding easily, in their expansion and cont tion, on the inner surface of the parietal layer, which lines the ch wall. While considering the subject of normal respiration, we r discard altogether the notion of the existence of any space or cav between the lungs and the wall of the chest.

If, however, an opening be made so as to permit air or fluid to en the pleural sac, the lung, in virtue of its elasticity, recoils, and a con erable space is left between it and the chest-wall. In other words, natural elasticity of the lungs would cause them at all times to contr



Fig. 208.—Transverse section of the chest.

away from the ribs were it not that the contraction is resisted by atr pheric pressure which bears only on the *inner* surface of the air-t and air-cells. On the admission of air into the pleural sac, atmosph pressure bears alike on the inner and outer surfaces of the lung, their elastic recoil is thus no longer prevented.

The pulmonary pleura consists of an outer or denser layer an inner looser tissue. The former or *pleura proper* consists of d fibrous tissue with elastic fibres, covered by endothelium, the cel which are large, flat, hyaline, and transparent when the lung is panded, but become smaller, thicker, and granular when the lung lapses. In the pleura is a lymph-canalicular system; and conne tissue corpuscles are found in the fibrous tissue which forms its gro work. The inner, looser, or sub-pleural tissue contains lamellæ of fib connective tissue and connective-tissue corpuscles between them. merous lymphatics are to be met with, which form a dense plex vessels, many of which contain valves. They are simple endoth es, and take origin in the lymph-canalicular system of the pleura. per. Scattered bundles of unstriped muscular fibre occur in the nonary pleura. They are especially strongly developed on the an- or and internal surfaces of the lungs, the parts which move most



ig. 209.—Ciliary epithelium of the human trachea. *a*, Layer of longitudinally arranged elastic ; *b*, basement membrane ; *c*, deepest cells, circular in form ; *d*, intermediate elongated cells ; ermost layer of cells fully developed and bearing cilia. × 350. (Kölliker.)

ly in respiration: their function is doubtless to aid in expiration. structure of the parietal portion of the pleura is very similar to of the visceral layer.

Each lung is partially subdivided into separate portions called *lobes;* right lung into three lobes, and the left into two. Each of these , again, is composed of a large number of minute parts, called *lob-*



Fig. 210.



Fig. 211.

g. 210.—Terminal branch of a bronchial tube, with its infundibula and air-cells, from the mar- the lung of a monkey, injected with quicksilver. *a*, Terminal bronchial twig; *b b*, infundibula ir-cells. × 10. (F. E. Schulze.)

g. 211.—Two small infundibula or groups of air-cells, *a a*, with air-cells, *b b*, and the ultimate hial tubes, *c c*, with which the air-cells communicate. From a new-born child. (Kölliker.)

. Each pulmonary lobule may be considered to be a lung in minia- , consisting, as it does, of a branch of the bronchial tube, of air-cells, d-vessels, nerves, and lymphatics, with a sparing amount of areolar ie.

On entering a lobule, the small bronchial tube, the structure of which has been just described (*a*, fig. 210), divides and subdivides; its walls at the same time becoming thinner and thinner, until at length they are formed only of a thin membrane of areolar and elastic tissue, lined by a layer of squamous epithelium, not provided with cilia. At the same time, they are altered in shape; each of the minute terminal branches widening out funnel-wise, and its walls being pouched out irregularly into small saccular dilatations, called *air-cells* (fig. 210, *b*). Such a funnel-shaped terminal branch of the bronchial tube, with its group of pouches or air-cells, has been called an *infundibulum* (figs. 210, 211), and the irregular oblong space in its centre, with which the air-cells communicate, an *intercellular passage*.



Fig. 212.—From a section of the lung of a cat, stained with silver nitrate. A. D. Alveolar duct or intercellular passage. S. Alveolar septa. N. Alveoli or air-cells, lined with large flat, nucleated cells, with some smaller polyhedral nucleated cells. M. Unstriped muscular fibres. Circular muscular fibres are seen surrounding the interior of the alveolar duct, and at one part is seen a group of small polyhedral cells continued from the bronchus. (Klein and Noble Smith.)

The air-cells, or air-vesicles, may be placed singly, like recesses from the intercellular passage, but more often they are arranged in groups or even in rows, like minute sacculated tubes; so that a short series of vesicles, all communicating with one another, open by a common orifice into the tube. The vesicles are of various forms, according to the mutual pressure to which they are subject; their walls are nearl contact, and they vary from $\frac{1}{50}$ to $\frac{1}{70}$ of an inch (.5 to .3 mm.) in d eter. Their walls are formed of fine membrane, similar to that o lular passages, and continuous with it, which membrane is folded f so as to form a sharp-edged border at each circular orifice of nication between contiguous air-vesicles, or between the vesicles bronchial passages. Numerous fibres of elastic tissue are spread veen contiguous air-cells, and many of these are attached to the irface of the fine membrane of which each cell is composed, im- to it additional strength, and the power of recoil after disten- The cells are lined by a layer of epithelium (fig. 212), not pro- ith cilia. Outside the cells, a network of pulmonary capillaries d out so densely (fig. 213, that the interspaces or meshes are rrower than the vessels, which are, on an average, $\frac{1}{3000}$ of an ) in diameter. Between the atmospheric air in the cells and d in these vessels, nothing intervenes but the thin walls of the



-Capillary network of the pulmonary blood-vessels in the human lung. × 60. (Kölliker.)

d capillaries; and the exposure of the blood to the air is the omplete, because the folds of membrane between contiguous d often the spaces between the walls of the same, contain only a ayer of capillaries, both sides of which are thus at once exposed ir.

air-vesicles situated nearest to the centre of the lung are smaller ir networks of capillaries are closer than those nearer to the cir- ence. The vesicles of adjacent lobules do not communicate; and the same lobule or proceeding from the same intercellular pas- so as a general rule only near angles of bifurcation; so that, y bronchial tube is closed or obstructed, the supply of air is lost he cells opening into it or its branches.

*d-supply.*—The lungs receive blood from two sources, (*a*) the ary artery, (*b*) the bronchial arteries. The former conveys *venous* the lungs for its *arterialization*, and this blood takes no share in the nutrition of the pulmonary tissues through which it passes. ( The branches of the bronchial arteries ramify for nutrition's sake in t walls of the bronchi, of the larger pulmonary vessels, in the interlob connective tissue, etc.; the blood of the bronchial vessels being retur chiefly through the bronchial and partly through the pulmonary vei

*Lymphatics.*—The lymphatics are arranged in three sets:—1. Irr ular lacunæ in the walls of the alveoli or air-cells. The lymph vessels which lead from these accompany the pulmonary vessels tow the root of the lung. 2. Irregular anastomosing spaces in the walls the bronchi. 3. Lymph-spaces in the pulmonary pleura. The ly phatic vessels from all these irregular sinuses pass in toward the r of the lung to reach the bronchial glands.

*Nerves.*—The nerves of the lung are to be traced from the anter and posterior pulmonary plexuses, which are formed by branches of t vagus and sympathetic. The nerves follow the course of the vessels a bronchi, and in the walls of the latter many small ganglia are situated.

## The Respiratory Mechanism.

Respiration consists of the alternate expansion and contraction the thorax, by means of which air is drawn into or expelled from t lungs. These acts are called *Inspiration* and *Expiration* respectively.

For the inspiration of air into the lungs it is evident that all that necessary is such a movement of the side-walls or floor of the chest, of both, that the capacity of the interior shall be enlarged. By s increase of capacity there will be of course a diminution of the press of the air in the lungs, and a fresh quantity will enter through larynx and trachea to equalize the pressure on the inside and out of the chest.

For the expiration of air, on the other hand, it is also evident t by an opposite movement which shall diminish the capacity of the ch the pressure in the interior will be increased, and air will be expel until the pressure within and without the chest are again equal. In b cases the air passes through the trachea and larynx, whether in enter or leaving the lungs, there being no other communication with the terior of the body; and the lung, for the same reason, remains under the circumstances described closely in contact with the walls and of the chest. To speak of expansion of the chest, is to speak also of pansion of the lung.

We have now to consider the means by which the respiratory m ments are effected.

**Inspiration.**—The enlargement of the chest during inspirati due to muscular action, which brings about an increase in the size of

:avity through the contraction of the inspiratory muscles, the rôle by the lungs being a passive one. The chest cavity is increased rertical, lateral, and antero-posterior diameters. The muscles en- in ordinary inspiration are: the diaphragm, the scaleni, the exter- tercostals, part of the internal intercostals, levatores costarum, ιti lumborum, and the serrati. During forced inspiration nearly nuscle of the trunk is brought into play.

*e vertical diameter.*—Changes in this are due, first, to the contrac- the *diaphragm.* This muscle has the shape of a flattened dome,



Schematic representation of diaphragm. In expiration (I), quiet inspiration (II), and deep inspiration (III). (After Schaeffer.)

hest point being the central tendon. While passive, its lower is are in apposition with the chest walls (fig. 214, I). On contrac- he dome is pulled downward and the lower portions away from est-walls, the downward displacement varying from 6–12 mm. in respiration, and in forced respiration may amount to as much as . The tendency, resulting from its attachments to the lower ribs wer part of the sternum, of pulling these inward is counteracted action of the abdominal viscera, which, when pressed down, tend s also outward. The inward traction is also prevented by the of the *quadrati lumborum*, which by their attachment to the last these and, in case of deep respiration, may even pull them down- The *serrati postici inferiores* aid the above, being attached to ır lower ribs.

anges in the *lateral* and *antero-posterior diameters* are effected by sing of the ribs, the greater number of which are attached very ely to the spine and sternum.

e elevation of the ribs takes place both in front and at the sides

—the hinder ends being prevented from performing any upward mo ment by their attachment to the spine. The movement of the fr extremities of the ribs is of necessity accompanied by an upward forward movement of the sternum to which they are attached, the m ment being greater at the lower end than at the upper end of the la bone.

*The axes of rotation* in these movements are two; one correspond with a line drawn through the two articulations which the rib fo with the spine (*a*, *b*, fig. 215); and the other with a line drawn f



Fig. 215.—Diagram of axes of movement of ribs.

one of these (head of rib) to the sternum (A B, fig. 215); the motio the rib around the latter axis being somewhat after the fashion of rai the handle of a bucket.

The elevation of the ribs is accompanied by a slight opening ou the angle which the bony part forms with its cartilage (fig. 216, and thus an additional means is provided for increasing the an posterior diameter of the chest.

The movements of all the ribs except the twelfth consist of a tion upward, forward, and backward; but, in addition to this, fourth to the ninth have also a movement upward and backward, the tenth and eleventh also rotate backward. The twelfth presents rotation backward and downward.

The muscles involved in these movements of the ribs are the *ext intercostals* and the part of the *internal intercostals* situated betwee costal cartilages. Their action is to widen the intercostal spaces. *scaleni* fix the first and second ribs, thereby making a fixed poi ı for the other muscles involved. The *serrati postici superiores* the above and also raise the third, fourth, and fifth ribs. The *res costarum longi* and *brevi* elevate and evert all the ribs from the ɔ the tenth.

extraordinary or forced inspiration, which may be due either to t exercise or to the interference with the due entrance of air into ngs, all the above muscles act more strongly. The diaphragm de- lower, the scaleni raise the first and second ribs instead of merely them, as in ordinary respiration, as do also the sterno-cleido-



Fig. 216.—Diagram of movement of a rib in inspiration.

ds. These, together with the *erector spinæ*, which straighten the increase the vertical diameter, while the following assist in in- ıg the antero-posterior and lateral diameters: *trapezii* and the *ıidii*, which by fixing the shoulders give a fixed point for the ac- f the *pectorals* and *latissimi dorsi*.

e expansion of the chest during inspiration presents peculiarities 'erent persons. In children of both sexes the principal muscle in- seems to be the diaphragm, and this type of breathing is known *ominal breathing*. In man, the chest and sternum, together with ont wall of the abdomen, are subject to a wide movement; this f breathing is called the *inferior costal*. In women, the movement rs less extensive in the lower and more so in the upper part of the and is called the *superior costal* type.

**xpiration.**—Quiet expiration is a passive act due to the return of orax and its contained lungs to their normal position when the es involved in inspiration relax. This elastic recoil is sufficient in ıry quiet breathing to expel air from the lungs. In forced expira- ıowever, which may occur to a slight degree in speaking, singing, s well as in the case of many involuntary and reflex acts, such as ing, sneezing, etc., certain muscles are involved. Of these the

principal are the abdominal muscles, *obliquus externus* and in
*rectus abdominis*, *transversalis abdominis*, and *pyramidalis*. Th
in several ways, first, by pressing the abdominal viscera agai
diaphragm and thereby forcing it up, their descent into the pelvic
being prevented by the contraction of the *levatores ani*, to whi
name of pelvic diaphragm has been given; secondly, by their
ments to the lower ribs and cartilages, they draw these downwa
inward, thereby lessening the size of the thoracic cavity; lastly, b
contraction, they form a fixed point for the action of that part
*internal* intercostals, not involved in inspiration, to approxima
ribs. In addition to the above the *triangularis sterni* and *internal*
*ossei* also play a certain rôle.

When by the efforts of the expiratory muscles, the chest ha
squeezed to less than its average diameter, it again, on relaxation
muscles, returns to the normal dimensions by virtue of its ela
The construction of the chest-walls, therefore, admirably adapt
for recoiling against and resisting as well undue contraction as
dilatation.

In the natural condition of the parts the lungs can never c
to the utmost, but are always more or less "on the stretch," bein
closely in contact with the inner surface of the walls of the ch
cohesion as well as by atmospheric pressure, and can contract awa
these only when, by some means or other, as by making an openi
the pleural cavity, or by the effusion of fluid there, the pressure
exterior and interior of the lungs becomes equal. Thus, under or
circumstances, the degree of contraction or dilatation of the l
dependent on that of the boundary walls of the chest, the outer
of the one being in close contact with the inner surface of the
and obliged to follow it in all its movements.

### Methods of recording Respiratory Movements.

The movements of respiration may be recorded graphically in sever
The ordinary method is to introduce a tube into the trachea of an anin
to connect this tube by some gutta-percha tubing with a T piece int
into the cork of a large-sized bottle, the other end of the T having att
it a second piece of tubing, which can remain open or can be par
completely closed by means of a screw clamp. Into the cork is inserte
ond piece of glass tubing connected with a Marey's tambour by suitable
This second tube communicates any alteration of the pressure in the l
the tambour, and this may be made to write on a recording surf
173). If the tube attached to the T piece be closed the movements of
tion and expiration are larger than if it were open. The alteratio
pressure within the lungs on inspiration and expiration is shown by th
ment of the column of air in the trachea. By these means a record
respiratory movements may be obtained.

Various instruments for recording the movements of the chest by application of apparatus to the exterior. Such is the **stethometer** of Burton Sander-
n. This consists of a frame formed of two parallel steel bars joined by a
ird at one end. At the free end of the bars is attached a leather strap, by
eans of which the apparatus may be suspended from the neck. Attached to
e inner end of one bar is a tambour and ivory button, to the end of the
her an ivory button. When in use, the apparatus is suspended with the
ansverse bar posteriorly, the button of the tambour is placed on the part of
e chest the movement of which it is desired to record, and the other button



Fig. 217.—Stethograph or Pneumograph. *h*, tambour fixed at right angles to plate of steel *f*;
nd *d*, arms by which instrument is attached to chest by belt *e*. When the chest expands, the
ms are pulled asunder, which bends the steel plate, and the tambour is affected by the pressure
b which is attached to it on the one hand, and to the upright in connection with horizontal screw
(Modified from Marey's instrument.)

made to press upon the corresponding side of the chest, so that the chest is,
it were, held between a pair of calipers. The tambour is connected by
ubing and a T piece with a recording tambour of Marey's, and with a ball,
by means of which air can be squeezed into the cavity of the tympanum.
When in work the tube connected with the air ball is shut off by means of a
screw clamp. The movement of the chest is thus communicated to the recording
tambour.

A simpler form of this apparatus, called a **pneumograph** or **stethograph,**
onsisting of a thick India-rubber bag of elliptical shape about three inches
long, to one end of which a rigid gutta-percha tube is attached. This bag
may be fixed at any required place on the chest by means of a strap and buckle.
By means of the gutta-percha tube the variations of the presssure of air in the
bag produced by the movements of the chest are communicated to a recording
tambour. This apparatus is a simplified form of Marey's pneumograph (fig.
217).

The variations of intrapleural pressure may be recorded by the introducton
of a canula into the pleural or pericardial cavity, which is connected with a
mercurial manometer.

Finally, it has been found possible in various ways to record the dia-
gmatic movements by the insertion of an elastic bar connected with a
our into the abdomen below it (**phrenograph**), by the insertion of needles
different parts of its structure, or by recording the contraction of isolated
rips of the diaphragm.

The acts of expansion and contraction of the chest take up ordinary circumstances a nearly equal time. The act of inspirin however, especially in women and children, is a little shorter tha of expelling it, and there is commonly a very slight pause betwe end of expiration and the beginning of the next inspiration. Th piratory rhythm may be thus expressed:—

| | |
|---|---|
| *Inspiration* . . . . . . . . . . | 6 |
| *Expiration* . . . . . . . . . | 7 or 8 |

A very slight *pause.*

If the ear be placed in contact with the wall of the chest, or b arated from it only by a good conductor of sound or stethoscope, *respiratory murmur* is heard during inspiration. This sound somewhat in different parts—being loudest or coarsest in the nei hood of the trachea and large bronchi (tracheal and bronchial breat and fading off into a faint sighing as the ear is placed at a distanc these (vesicular breathing). It is best heard in children, and in a faint murmur is heard in expiration also. The cause of the ve murmur has received various explanations. Most observers hol the sound is produced in the glottis and larger bronchial tubes, bu it is modified in its passage to the pulmonary alveoli. In dis the lungs the vesicular murmur undergoes various modificatio


Tambour.
Ivory button.
Tube to communicate with recording tambour.
Ball to fill apparatus with air.

Fig. 218.—Stethometer. (Burdon Sanderson.)

ription of which one must consult text-books on physical diag-

*spiratory Movements of the Nostrils and of the Glottis.*—During tion of the muscles which directly draw air into the chest, those guard the opening through which it enters are not passive. In d breathing the instinctive dilatation of the nostrils is well seen, gh under ordinary conditions it may not be noticeable. The g at the upper part of the larynx, however, or rima glottidis, is at each inspiration for the more ready passage of air, and besmaller at each expiration; its condition, therefore, corresponding



219.—Tracing of the normal diaphragm respirations of rabbit. *a*, with quick movement of , with slow movement. J, inspiration, E, expiration. To be read from left to right. ald.)

respiration with that of the walls of the chest. There is a fur-keness between the two acts in that, under ordinary circumstane dilatation of the rima glottidis is a muscular act and its contrac-iefly an elastic recoil; although, under various conditions to be er mentioned, there may be in the latter considerable muscular exercised.

**rms used to express Quantity of Air breathed.**—a. *Breath-tidal air,* is the quantity of air which is habitually and almost nly changed in each act of breathing. In a healthy adult man out 30 cubic inches, or about 500 ccm., or half a litre.

*Complemental air,* is the quantity over and above this which can wn into the lungs in the deepest inspiration; its amount varies, y be reckonded as 100 cubic inches, or about 1,600 ccm.

c. *Reserve air.*—After ordinary expiration, such as that which expe the breathing or tidal air, a certain quantity of air, about 100 cubi inches (1,600 ccm.) remains in the lungs, which may be expelled by a forcible and deeper expiration. This is termed reserve or supplemental air.

d. *Residual air* is the quantity which still remains in the lungs aft the most violent expiratory effort. Its amount depends in great meas- ure on the absolute size of the chest, but may be estimated at about 10 cubic inches, or about 1,600 ccm. to 2,000 ccm.

The total quantity of air which passes into and out of the lungs o an adult, at rest, in 24 hours, is about 686,000 cubic inches. This quan tity, however, is largely increased by exertion; the average amount f a hard-working laborer in the same time being 1,568,390 cubic inches.

e. *Respiratory Capacity.*—The greatest respiratory capacity of th chest is indicated by the quantity of air which a person can expel fro his lungs by a forcible expiration after the deepest inspiration possibl it expresses the power which a person has of breathing in the emerge cies of active exercise, violence, and disease. The average capacity o an adult, at 15.4° C. (60° F.), is about 225 to 250 cubic inches, or 3,5 to 4,000 ccm.

The *respiratory* capacity, or as John Hutchinson called it, *vital* capacit is usually measured by a modified gasometer or *spirometer*, into which t experimenter breathes,—making the most prolonged expiration possible af the deepest possible inspiration. The quantity of air which is thus expell from the lungs is indicated by the height to which the air chamber of t spirometer rises; and by means of a scale placed in connection with this, t number of cubic inches is read off.

In healthy men, the respiratory capacity varies chiefly with t stature, weight, and age.

It was found by Hutchinson, from whom most of our informati on this subject is derived, that at a temperature of 15.4° C. (60° F 225 cubic inches is the average *vital* or respiratory capacity of a healt person, five feet seven inches in height.

*Circumstances affecting the amount of respiratory capacity.*—For every i of height above this standard the capacity is increased, on an average, by ei inches; and for every inch below, it is diminished by the same amount.

The influence of *weight* on the capacity of respiration is less manifest a considerable than that of height: and it is difficult to arrive at any defi conclusions on this point, because the natural average weight of a heal man in relation to stature has not yet been determined. As a general st ment, however, it may be said that the capacity of respiration is not affect by weights under 161 pounds, or 11½ stones; but that, above this point, it diminished at the rate of one cubic inch for every additional pound up to pounds or 14 stones.

By *age*, the capacity appears to be increased from about the fifteenth to thirty-fifth year, at the rate of five cubic inches per year; from thirty-five

r-five it diminishes at the rate of about one and a half cubic inch per year;
at the capacity of respiration of a man of sixty years old would be about
ibic inches less than that of a man of forty years old, of the same height
weight. (John Hutchinson.)

he *number* of respirations in a healthy adult person usually ranges
14 to 18 per minute. It is greater in infancy and childhood. It
s also much according to different circumstances, such as exercise
st, health, or disease, etc. Variations in the number of respirations
spond ordinarily with similar variations in the pulsations of the
t. In health the proportion is about 1 to 4, or 1 to 5, and when the
lity of the heart's action is increased, that of the chest movement is
monly increased also; but not in every case in equal proportion. It
ens occasionally in disease, especially of the lungs or air-passages,
the number of *respiratory* acts increases in quicker proportion than
beats of the *pulse;* and, in other affections, much more commonly,
the number of the pulses is greater in proportion than that of the
irations.

*he Force of Inspiratory and Expiratory Muscles.*—The force with
h the inspiratory muscles are capable of acting is greatest in indi-
als of the height of from five feet seven inches to five feet eight
es, and will elevate a column of three inches of mercury. Above
height the force decreases as the stature increases; so that the aver-
of men of six feet can elevate only about two and a half inches of
cury. The force manifested in the strongest expiratory acts is, on
average, one-third greater than that exercised in inspiration. But
difference is in great measure due to the power exerted by the
ic reaction of the walls of the chest; and it is also much influenced
he disproportionate strength which the expiratory muscles attain,
their being called into use for other purposes than that of simple
ration. The force of the inspiratory act is, therefore, better adapted
that of the expiratory for testing the muscular strength of the
. (John Hutchinson.)

ouglas Powell has shown that within the limits of ordinary tran-
respiration the elastic resilience of the walls of the chest favors in-
tion; and that it is only in deep inspiration that the ribs and rib-
lages offer an opposing force to their dilatation. In other words,
lastic resilience of the lungs, at the end of an act of ordinary
hing, has drawn the chest-walls within the limits of their normal
e of expansion. Under all circumstances, of course, the elastic
of the lungs opposes inspiration and favors expiration.

is possible that the contractile power which the bronchial tubes
ir-vesicles possess, by means of their *muscular fibres* may (1) assist
piration; but it is more likely that its chief purpose is (2) to regu-
nd adapt, in some measure, the quantity of air admitted to the

lungs, and to each part of them, according to the supply of blood the muscular tissue contracts upon and gradually expels collectio mucus, which may have accumulated within the tubes, and which ca be ejected by forced expiratory efforts, owing to collapse or other bid conditions of the portion of lung connected with the obstr tubes (Gairdner). (4) Apart from any of the before-mentioned i tions, the presence of muscular fibre in the walls of a hollow vi such as a lung, is only what might be expected from analogy with organs. Subject as the lungs are to such great variation in si might be anticipated that the elastic tissue, which enters so largely their composition, would be supplemented by the presence of muscular fibre also.

## Respiratory Changes in the Air Breathed.

*Composition of the Atmosphere.*—The atmosphere we breathe ha every situation in which it has been examined in its natural sta nearly uniform composition. It is a mixture of oxygen, nitrogen, bon dioxide, argon, and watery vapor, with, commonly, traces of o gases, as ammonia, sulphuretted hydrogen, etc. Of every 100 vol of pure atmospheric air, 79 volumes (on an average) consist of nitro the remaining 21 of oxygen. By weight the proportion is N. 77, O. The proportion of carbon dioxide is extremely small; 10,000 volum atmospheric air contain only about 4 or 5 of that gas.

The quantity of watery vapor varies greatly according to the tem ature and other circumstances, but the atmosphere is never wit some. In this country, the average quantity of watery vapor in th mosphere is 1.40 per cent.

*Composition of Air which has been breathed.*—The changes effe by respiration in the atmospheric air are: 1, an increase of temperat 2, an increase in the quantity of carbonic acid; 3, a diminution in quantity of oxygen; 4, a diminution of volume; 5, an increase in amount of watery vapor; 6, the addition of a minute amount of or matter and of free ammonia.

1. *The expired air,* heated by its contact with the interior o lungs, *is* (at least in most climates) *hotter* than the inspired air. temperature varies between 36°—37.5° C. (97° and 99.5° F.), the temperature being observed when the air has remained but a short in the lungs. Whatever may be the temperature of the air whe haled, it acquires nearly that of the blood before it is expelled fro chest.

2. *The Carbonic dioxide is increased;* but the quantity exhaled given time is subject to change from various circumstances. every volume of air inspired, from 4 to 5 per cent of oxygen is abstra

hile a rather smaller quantity, 4.0 of carbon dioxide is added in its ace: the expired air will contain, therefore, 400 vols. of carbon dioxide 10,000. The quantity of carbon dioxide exhaled into the air breathed a healthy adult man, calculating that 20 ccm. of the 500 ccm. of the r breathed out at each expiration consists of carbon dioxide, and that e rate of respiration is on an average 16, the total amount would be out 460 litres in the 24 hours. From actual experiment this amount ems to be too high, since from the average of many investigations the tal amount of carbon dioxide excreted per diem has been found to be out 400 litres, weighing 800 grms., consisting of 218 grms. of C., and 2 grms. of O. From this has to be deducted about 10 grms. excreted in y other way than by the lungs, it leaves about 215 grms. as the amount C. excreted by the average healthy man by respiration each day and ght, that is about 7 oz., about half a pound. These quantities must considered approximate only, inasmuch as various circumstances, even health, influence the amount of carbon dioxide excreted, and, correla- ely, the amount of oxygen absorbed.

*Circumstances influencing the amount of carbon dioxide excreted.*—*a. Age d Sex.*—The quantity of carbon dioxide exhaled into the air breathed by les, regularly increases from 8 to 30 years of age; from 30 to 50 the quantity, er remaining stationary for a while, gradually diminishes, and from 50 to treme age it goes on diminishing, till it scarcely exceeds the quantity ex- led at ten years old. In females (in whom the quantity exhaled is always s than in males of the same age) the same regular increase in quantity goes from the 8th year to the age of puberty, when the quantity abruptly ceases increase, and remains stationary so long as they continue to menstruate. hen menstruation has ceased, it soon decreases at the same rate as it does in l men.

*b. Respiratory Movements.*—The quicker the respirations, the smaller is the oportionate quantity of carbon dioxide contained in each volume of the expired r. Although the proportionate quantity of carbon dioxide is thus diminished, e absolute amount exhaled within a given time is increased thereby, owing to e larger quantity of air which is breathed in the time. The last half of a vol- ne of expired air contains more carbonic acid than the half first expired; a rcumstance which is explained by the one portion of air coming from the mote part of the lungs, where it has been in more immediate and prolonged ntact with the blood than the other has, which comes chiefly from the larger onchial tubes.

*c. External temperature.*—The observation made by Vierordt at various mperatures between 3.4°—23.8° C. (38° F. and 75° F.) show, for warm-blooded imals, that within this range, every rise equal to 5.5° C. (10° F.) causes a minution of about 33 ccm. (2 cubic inches) in the quantity of carbonic acid haled per minute.

*d. Season of the Year.*—The season of the year, independently of tempera- re, materially influences the respiratory phenomena; spring being the season the greatest, and autumn of the least activity of the respiratory and other nctions.

*e. Purity of the Respired Air.*—The average quantity of carbon dioxide given out by the lungs constitutes about 4.3 per cent. of the expired air; if the air which is breathed be previously impregnated with carbon dio (as is the case when the same air is frequently respired), then the quanti carbon dioxide exhaled becomes relatively much less.

*f. Hygrometric State of Atmosphere.*—The amount of carbon dioxide ex is considerably influenced by the degree of moisture of the atmosphere, more being given off when the air is moist than when it is dry.

*g. Period of the Day.*—The respiratory quotient, *i.e.*, the ratio betwee bon dioxide eliminated and oxygen absorbed, is greater during the day during the night. In the day, therefore, the $CO_2$ exhaled, in relation to t absorbed, is increased and diminished during the night. This is probabl to the increased production of $CO_2$ as a result of increased tissue activity d the day, and, consequently, the breaking down or katabolism of more substa one of whose end-products is $CO_2$. Furthermore, all of the $CO_2$ eliminated i dependent for its formation upon the oxygen absorbed, but is, in part, the r of the katabolism of carbohydrates in which carbon and oxygen are pres the proportion to form $CO_2$.

*h. Food and Drink.*—By the use of food the quantity is increased, w by fasting it is diminished; it is greater when animals are fed on farina food than when fed on meat. The effects produced by spirituous drinks pend much on the kind of drink taken. Pure alcohol tends rather to inc than to lessen respiratory changes, and the amount therefore of carbon dio expired; rum, ale, and porter, also sherry, have very similar effects. On other hand, brandy, whiskey, and gin, particularly the latter, almost al lessened the respiratory changes, and consequently the amount of the exhaled.

*i. Exercise.*—Bodily exercise, in moderation, increases the quantity to a ⅓ more than it is during rest: and for about an hour after exercise the vol of the air expired in the minute is increased nearly 2,000 ccm., or 118 c inches: and the quantity of carbon dioxide about 125 ccm., or 7.8 cubic in per minute. Violent exercise, such as full labor on the tread-wheel, still ther increases the amount of the acid exhaled.

A larger quantity is exhaled when the barometer is low than when high.

3. *The oxygen is diminished.* Pettenkofer and Voit have found t the mean consumption of oxygen during 24 hours, by a man weigh 70 kilos, is about 700 grms., or 490 litres. The quantity of oxygen sorbed increases with muscular exercise, and falls during rest. In g eral terms the quantity absorbed varies with the activity of the metab processes.

4. *The volume of air is diminished* (allowance being made for the pansion in heating), the loss being due to the fact that a portion of oxygen absorbed is not returned in the form of carbon dioxide. Si the oxygen of a given volume of carbon dioxide would have the s volume as the carbon dioxide itself at a given temperature and press a portion of the oxygen absorbed must be used for other purposes t the formation of carbon dioxide. In fact, some of it is used in formation of urea, some in the formation of water, etc. The oxyge

The carbon dioxide exhaled, divided by the oxygen absorbed, gives what is known as the **respiratory quotient**; thus

$$\frac{CO_2 \text{ exhaled}}{O_2 \text{ absorbed}}.$$

Normally in man on a mixed diet the respiratory quotient is

$$\frac{4.0\text{–}4.5}{5} = 0.8\text{–}0.9.$$

But it is subject to variation through several causes; for example, through variation in diet. On a carbohydrate diet the respiratory quotient may rise above 0.9, since carbohydrates contain enough oxygen to oxidize the carbon in their molecule. On a diet containing much fat it is lowest, since oxygen is needed to completely oxidize it. And the same is true, but to a less degree, in the case of proteids. Muscular exertion raises the respiratory quotient, because in its performance carbohydrates re used up.

5. *The watery vapor is increased.*—The quantity emitted is, as a eneral rule, sufficient to saturate the expired air, or very nearly so. ts absolute amount is, therefore, influenced by the following circumstances, (1), by the quantity of air respired; for the greater this is, the reater also will be the quantity of moisture exhaled; (2), by the quantity of watery vapor contained in the air previous to its being inspired; ecause the greater this is, the less will be the amount to complete the turation of the air; (3), by the temperature of the expired air; for e higher this is, the greater will be the quantity of watery vapor required to saturate the air; (4), by the length of time which each volume f inspired air is allowed to remain in the lungs; for although, during rdinary respiration, the expired air is always saturated with watery por, yet when respiration is performed very rapidly the air has scarcely me to be raised to the highest temperature, or be fully charged with oisture ere it is expelled.

The quantity of water exhaled from the lungs in twenty-four hours nges (according to the various modifying circumstances already mentioned) from about 6 to 27 ounces, the ordinary quantity being about 9 10 ounces. Some of this is probably formed by the chemical combination of oxygen with hydrogen in the system; but the far larger oportion of it is water which has been absorbed, as such, into the ood from the alimentary canal, and which is exhaled from the surface the air-passages and cells, as it is from the free surfaces of all moist imal membranes, particularly at the high temperature of warm-blooded imals.

6. *A small quantity of ammonia is added* to the ordinary constitu-ts of expired air. It seems probable, however, both from the fact that

this substance cannot be always detected, and from its minute when present, that the whole of it may be derived from de ing particles of food left in the mouth, or from carious teeth like; and that it is, therefore, only an accidental constituent of air.

7. *The quantity of organic matter in the breath is increased.* formerly supposed that this organic matter was injurious and g to the unpleasant symptoms which come on in badly ventilated But this has been proved erroneous.

*Method of Experiment.*—The experiments are conducted in such a ma comparative analyses may be made between the air inspired and that Generally an animal is placed in a chamber, called the respiratory chambe but two openings—one for the entrance of the inspired air, the other for t of expired air. Some form of pump is used for renewing the air in the Both the inspired and expired air is made to pass through agents which wi the contained carbon dioxide, such as baryta water or soda lime, and in turn agents which will absorb the watery vapor. When the experiment is c the differences between the two are determined. The difference in oxyge be calculated, and is open to error. The famous respiratory chamber o kofer is large enough to perform such experiments on man, and is of very construction.

*How the Changes in the Air are effected.*—The method b fresh air is inhaled and expelled from the lungs has been ex It remains to consider how it is that the blood absorbs oxyge and gives up carbonic acid to, the air of the alveoli. In the fir it must be remembered that the tidal air only amounts to abou cubic inches (about 500 ccm.) at each inspiration, and that t course insufficient to fill the lungs, but it mixes with the statio by *diffusion*, and so supplies to it new oxygen. The amount of in expired air, which may be taken as the average compositio mixed air in the lungs, is about 16 to 17 per cent; in the pu alveoli it may be rather less than this. From this air the veno has to take up oxygen in the proportion of 8 to 12 vols. per blood, as the difference between the amount of oxygen in arte venous blood is no less. It seems therefore somewhat difficult t stand how this can be accomplished at the low partial pressure of in the pulmonary air. But as was pointed out in a previous (V.), the oxygen is not simply dissolved in the blood, but is to extent chemically combined with the hæmoglobin of the red cor and when a fluid contains a body which enters into loose chemi bination in this way with a gas, the tension of the gas in the not directly proportional to the total quantity of the gas take the fluid, but to the excess above the total quantity which the su dissolved in the fluid is capable of taking up (a known quantit case of hæmoglobin, viz., 1.59 cm. for 1 grm. hæmoglobin).

hand, if the substance be not saturated, *i.e.*, if it be not combined
as much of the gas as it is capable of taking up, further combina-
eads to no increase of its tension. However, there is a point at
the hæmoglobin gives up its oxygen when it is exposed to a
artial pressure of oxygen, and there is also a point at which it
er takes up nor gives out oxygen; in the case of arterial blood of
og, this is found to be when the oxygen tension of the atmosphere
al to 3.9 per cent (or 29.6 mm. of mercury), which is equivalent
ing that the oxygen tension of arterial blood is 3.9 per cent; venous
, in a similar manner, has been found to have an oxygen tension of
r cent. At a higher temperature, the tension is raised, as there is
ter tendency at a high temperature for the chemical compound to
go dissociation. It is therefore easy to see that the oxygen tension
air of the pulmonary alveoli is quite sufficient, even supposing it
less than that of the expired air, to enable the venous blood to
up oxygen, and what is more, it will take it up until the hæmo-
is very nearly saturated with the gas.

regards the elimination of carbon dioxide from the blood, there
dence to show that it is given up by a process of simple diffusion,
nly condition necessary for the process being that the tension of
rbonic acid of the air in the pulmonary alveoli should be less than
nsion of the carbonic acid in venous blood. The carbonic acid
n of the alveolar air probably does not exceed (in the dog) 3 or 4
nt, while that of the venous blood is 5.4 per cent, or equal to 41
f mercury.

## Respiratory Changes in the Blood.

*rculation of Blood in the Respiratory Organs.*—To be exposed to
r thus alternately moved into and out of the air-cells and minute
hial tubes, the blood is propelled from the right ventricle through
lmonary capillaries in steady streams, and slowly enough to per-
ery minute portion of it to be for a few seconds exposed to the
ith only the thin walls of the capillary vessels and the air-cells
ening. The pulmonary circulation is of the simplest kind: for
lmonary artery branches regularly; its successive branches run in
ht lines, and do not anastomose: the capillary plexus is uniformly
over the air-cells and intercellular passages; and the veins de-
from it proceed in a course as simple and uniform as that of the
es, their branches converging but not anastomosing. The veins
o valves, or only small imperfect ones prolonged from their angles
ction, and incapable of closing the orifice of either of the veins
en which they are placed. The pulmonary circulation also is un-
ed by changes of atmospheric pressure, and is not exposed to the

influence of the pressure of muscles: the force by which it is accom plished, and the course of the blood are alike simple.

*Changes in the Blood.*—The most obvious change which the blood the pulmonary artery undergoes in its passage through the lungs is l that of *color,* the dark crimson of venous blood being exchanged for t bright scarlet of arterial blood. The cause of this has been alrea shown to be that the arterial blood contains a greater quantity of scarl or oxyhæmoglobin; *2d,* and in connection with the preceding change *gains oxygen ; 3d,* it *loses carbon dioxide.* It was incidentally mentio in the Chapter on the Blood that the carbon dioxide which is carri by the blood to be eliminated by the lungs is not simply dissolved the plasma. It is combined with some substance in the blood, when it is carried to the lungs this substance must undergo decomp tion. What is the nature of the compound it forms is not known, it appears most likely that the gas is combined in the plasma with t sodium carbonate which it contains. It has also been suggested that the carbon dioxide of the entire blood is more easily given up to t vacuum of a mercurial air-pump than is the gas of the serum correspo ing to the blood taken, that the corpuscles of the blood exercise so power in promoting the decomposition of the substance with which t gas is combined in the plasma. The plasma or serum will not give the whole of its carbon dioxide until the addition of an acid, when t last portion, 2 to 5 per cent, comes off, the entire blood gives up t whole of its carbon dioxide to the action of the mercurial pump, does not require the action of an acid. It may be mentioned that, cording to some, the carbon dioxide is combined with proteid, either the plasma or in the red blood-corpuscles; *4th,* it becomes *slight cooler; 5th,* it *coagulates sooner and more firmly,* apparently containin more fibrin. The oxygen absorbed into the blood from the atmospheri air in the lungs is combined chemically with the hæmoglobin of t red blood-corpuscles. In this condition it is carried in the arterial blo to the various parts of the body, and brought into near relation or co tact with the tissues. In these tissues, a certain portion of the oxyg which the arterial blood contains, disappears, and a proportionate qu tity of carbon dioxide and water is formed. The venous blood, contai ing the new-formed carbon dioxide, returns to the lungs, where a porti of the carbon dioxide is exhaled, and a fresh supply of oxygen is taken

In what way these changes are brought about will be next discus

## Respiratory Changes in the Tissues.

The changes which occur in the composition of the blood during circulation are believed to take place in the tissues, and particularly the muscles. The changes are, as we have just mentioned, chiefly

oval of oxygen from and the addition of carbon dioxide to the blood.
se changes are sometimes spoken of as internal respiration. The
gen carried by the corpuscles of the blood in the form of oxyhæmo-
in is given up to the tissues, as the tension of the gas within them
ry small. The gas thus set free is apparently seized upon by the
oplasm of the tissues and built up into its molecule, and thus assists
he process of anabolism, possibly uniting with some compound
ewhat in the same manner but more firmly than it does with hæmo-
in. The low oxygen pressure of the tissues thus allows a constant
raction of the gas from the blood. The process of katabolism, or
king down, is always associated with the evolution of carbon diox-
so that as the blood passes through the tissues containing little of
gas, the high tension of the gas in the tissues permits of its passage
the blood. It has been proved that the process of the evolution of
on dioxide from living muscle will go on for a time in the absence
supply of free oxygen, and so it is clear that the former gas is not
ed directly from the combustion of the carbon in the presence of
atter gas. It was at one time believed that the carbon dioxide of
us blood resulted from the oxidation of substances in the blood
f. It has, however, been shown that the blood itself has very slight
izing powers, and that in the frog the whole of the blood may be
ced by saline solution without producing any marked effect upon
netabolism of the body. It is obviously unlikely that any but very
t oxidation could go on in such a medium. It has moreover been
nstrated that the tension of carbon dioxide in the tissues is con-
ably greater in the tissues than it is in the venous blood.

## Special Respiratory Acts.

t will be well here, perhaps, to explain certain special respiratory
which appear at first sight somewhat complicated, but cease to be
hen the mechanism by which they are performed is clearly under-
l. The diagram (fig. 220) shows that the cavity of the chest is sep-
d from that of the abdomen by the diaphragm, which, when acting,
lessen its curve, and thus descending, will push *downward and*
*ard* the abdominal viscera; while the abdominal muscles have the
site effect, and in acting will push the viscera *upward and back-*
, and with them the diaphragm, supposing its ascent to be not
any cause interfered with. It will also be seen that the lungs
nunicate with the exterior of the body through the trachea and
x, and further on through the mouth and nostrils—through either
em separately, or through both at the same time, according to the
ion of the soft palate. The stomach communicates with the ex-
r of the body through the œsophagus, pharynx, and mouth; while

below the rectum opens at the anus, and the bladder through the thra. All these openings, through which the hollow viscera comm cate with the exterior of the body, are guarded by muscles, c sphincters, which can act independently of each other.

*Sighing.*—In sighing there is a somewhat prolonged inspiration; air almost noiselessly passing in through the glottis, and by the el recoil of the lungs and chest-walls, and probably also of the abdon walls, being suddenly expelled.

In the first, or *inspiratory* part of this act, the descent of the phragm presses the abdominal viscera downward, and of course pressure tends to evacuate the contents of such of them as commun with the exterior of the body. Inasmuch, however, as their va openings are guarded by sphincters, in a state of constant tonic con tion, there is no escape of their contents, and the air simply enter lungs. In the second, or *expiratory* part of the act, pressure is made on the abdominal viscera in the opposite direction, by the r of the abdominal walls; but the pressure is relieved by the escape o through the open glottis, and the relaxed diaphragm is pushed up t into its original position. The sphincters of the stomach, rectum, bladder, act in the same manner as before.

*Hiccough* resembles sighing in that it is an inspiratory act: bu inspiration is sudden instead of gradual, the diaphragm acting sud and spasmodically; and the air, rushing through the unprepared glottidis, is suddenly arrested and produces the peculiar sound.

*Coughing.*—In the act of coughing there is most often first of deep inspiration, followed by an expiration; but the latter, instea being easy and uninterrupted, as in normal breathing, is obstructe glottis being momentarily closed by the approximation of the cords. The abdominal muscles, then strongly acting, push up viscera against the diaphragm, and thus make pressure on the air i lungs until its tension is sufficient to noisily open the vocal cords w oppose its outward passage. In this way considerable force is exer and mucus or any other matter that may need expulsion from th passages is quickly and sharply expelled by the outstreaming curre air. It will be evident on reference to fig. 220, that pressure exer by the abdominal muscles in the act of coughing, acts as forcibly o abdominal viscera as on the lungs, inasmuch as the viscera form medium by which the upward pressure on the diaphragm is made, there is of necessity quite as great a tendency to the expulsion of t contents as of the air in the lungs. The instinctive and if neces voluntarily increased contraction of the sphincters, however, prev any escape at the openings guarded by them, and the pressure is e tive at one part only, at the rima glottidis.

*neezing.*—The same remarks that apply to coughing, are almost ly applicable to the act of sneezing; but in this instance the blast ', on escaping from the lungs, is directed by a reflex contraction of illars of the fauces, and descent of the soft palate, chiefly through ose, and any offending matter is thence expelled.

*peaking.*—In speaking, there is a voluntary expulsion of air through lottis by means of the expiratory muscles. The vocal cords, by the



Fig. 220.

es of the larynx, are put in a proper position and state of tension brating as the air passes over them, and sound is produced. The is moulded into articulate speech by the tongue, teeth, lips, etc. vocal cords producing the sound only, and having nothing to do *articulation.*

*nging.*—Singing resembles speaking in the manner of its produc- the laryngeal muscles, by variously altering the position and de- f tension of the vocal cords, producing the different notes. Words in the act of singing are of course framed, as in speaking, by the e, teeth, lips, etc.

*iffing.*—Sniffing is produced by a rapidly repeated but incomplete action of the diaphragm and other inspiratory muscles. The mouth is closed, and the whole stream of air is made to enter the air-passages through the nostrils. The alæ nasi are commonly at the same time reflexly dilated.

*Sobbing.*—Sobbing consists of a series of convulsive inspirations, at the moment of which the glottis is usually more or less closed.

*Laughing.*—Laughing is made up of a series of short and rapid expirations.

*Yawning.*—Yawning is an act of inspiration but is unlike most of the preceding actions as it is always more or less involuntary. It is attended by a stretching of various muscles about the palate and lower jaw, which is probably analogous to the stretching of the muscles of the limbs in which a weary man finds relief, as a voluntary act, when they have been some time out of action. The involuntary and reflex character of yawning probably depends on the fact that the muscles concerned are themselves at all times more or less used involuntarily, and require, therefore, something beyond the exercise of the will to set them in action. For the same reason, yawning, like sneezing, cannot be well performed voluntarily.

*Sucking.*—Sucking is not properly a respiratory act, but it may be most conveniently considered in this place. It is caused chiefly by the depressor muscles of the os hyoides. These, by drawing downward and backward the tongue and floor of the mouth, produce a partial vacuum in the latter: and the weight of the atmosphere then acting on all sides tends to produce equilibrium on the inside and outside of the mouth as best it may. The communication between the mouth and pharynx is completely shut off by the contraction of the pillars of the soft palate and descent of the latter so as to touch the back of the tongue; and the equilibrium, therefore, can be restored only by the entrance of something through the mouth. The action, indeed, of the tongue and floor of the mouth in sucking may be compared to that of the piston in a syringe, and the muscles which pull down the os hyoides and tongue, to the power which draws the handle.

## The Nervous Apparatus of Respiration.

Like all other functions of the body, the discharge of which is necessary to life, respiration is essentially an involuntary act. Unless this were the case, life would be in constant danger, and would cease on the loss of consciousness for a few moments, as in sleep. It is, however, also necessary that respiration should be to some extent under the control of the will. For were it not so, it would be impossible to perform those respiratory acts which have been just discussed, such as speaking, singing, and the like.

It has been known for centuries that there exists a district of the central nervous system on the destruction of which both respiration and life cease. All attempts to localize this district, however, before those of Flourens were unsuccessful. Flourens, after many series of experiments as to the exact position of what he called the "knot of life" (nœud vital), placed it in the fourth ventricle, at the point of the V in the gray matter at the lower end of the calamus scriptorius; a district of considerable size, viz., 5 mm., on both sides of the middle line. Observers subsequent to Flourens have attempted to show that the chief respiratory centre on the one hand is situated higher up in the nervous system, *e.g.*, in the floor of the third ventricle (Christiani), or in the corpora quadrigemina (Martin and Booker, Christiani, and Stanier), or on the other hand, lower down in the spinal cord, and that the medullary centres, if they exist, are either accessory or subservient to such centres. The balance of experimental evidence, however, is to prove that the sole centres for respiration is a limited district in the medulla oblongata in close connection with the vagus nucleus on each side, with which they re probably identical. The destruction of this district stops respira- ion forever; whereas, if it be left in connection with the muscles of respiration by their nerves, although the remainder of the central nervous ystem be separated from it, respiration continues. It may be considered lmost certain that the medullary centre is the only true respiratory entre, and that the observations of Langendorff, that in newly-born nimals in which the medulla has been cut immediately or a few millimetres below the point of the calamus scriptorius respiration continues or some time as in normal animals cannot be received. We are indebted o Marckwald for much information on this subject, and he has come to he conclusion that normal respiration does not occur after division of he bulb from the cord, and that the so-called respiratory movements oticed by Langendorff are merely tetanic contractions of the respira- ory muscles with which often enough other muscles take part.

The action of the medullary centre is to send out impulses during nspiration, which cause respiratory movements of the muscles—(*a*) of he nostrils, and jaws through the facial and inferior division of the fth nerves; (*b*) of the glottis, chiefly through the inferior laryngeal ranches of the vagi; (*c*) of the intercostal and other muscles which roduce raising of the ribs, chiefly through the intercostal nerves, and *d*) of the diaphragm through the phrenic nerves.

If any one of these sets of nerves be divided, respiratory movements f the corresponding part cease.

Similarly it may be supposed that the centre sends out impulses dur- ng expiration to certain other muscles. It has been suggested, however, hat the centre consists of two parts, or is double, and that it is made p of an inspiratory centre, which is constantly in action, and of an expiratory centre, which acts less generally, inasmuch as ordinary tranquil expiration is seldom more than an elastic recoil, and not a muscular act to any marked degree.

Assuming this view of the double centres to be correct, of their exa mode of action there is some difference of opinion; it is now thought th they may act automatically, but normally are influenced by afferent im pulses from the periphery, as well as by impulses passing down fro the cerebrum. The centre is, in other words, both **automatic** and re **flex.** It will be simplest to discuss its reflex function first of all.

*Action of Afferent Stimuli.*—(*a*) **Action of the vagi.**—If both va be divided in the neck, the respirations become much slower and deeper this may be the case, but to a less marked degree, if one of the nerv is divided instead of both. If the central end of the divided nerve i stimulated with a weak interrupted current, the most constant effect that the respirations are quickened, and if the stimuli are properly r ulated, the normal rhythm of respiration may be resumed. If the stim be repeated with sufficient quickness, after a while the breathing brought to a stand-still at the height of inspiration by tetanus of th diaphragm. Sometimes, however, stimulation of the central end of th divided vagi produces still greater slowing than that which follo the division, so that if it be continued, the respirations cease, with th diaphragm in a condition of complete relaxation. Marckwald consid that the differences in the effects of vagus stimulation are due to th stimulus being applied to the nerve at different periods in the respi tory cycle, and that the action of the vagus may be to call forth eith inspiration or expiration—the impulses passing up the vagi being nec sary to the production of the normal respiratory rhythm. The fib of the vagus are used under the following circumstances, those fibr which tend to inhibit expiration and to stimulate inspiration are stim ulated at their distribution in the lung when the lung is empty and i a condition of expiration, and the fibres which tend to inhibit inspi tion and to promote expiration are stimulated when the lung is fully e panded. The afferent impulses are the results of mere mechani stimulation, and do not depend upon the chemical nature of the ga within the pulmonary alveoli. The vagus always acts upon the cent as a stimulator of discharge, or exciter of katabolism.

(*b*) **Action of the superior laryngeal nerves.**—If the superi laryngeal branch of the vagus be divided, which usually produces apparent effect, and the central end be stimulated, the effect is ve constant, respirations are slowed, but there is a tendency toward ex ration, as is shown by the contraction of the abdominal muscles. Th if the vagus contains fibres which stimulate inspiration and inhib expiration, as well as other fibres which have the reverse effect, the su perior laryngeal fibres inhibit inspiration and stimulate expiration.

The superior laryngeal nerves are true expiratory nerves, and may set in action when the mucous membrane of the larynx is irritated. hey are not constantly in action like the vagi.

(*c*) **Action of the glosso-pharyngeal nerves.**—It has been as- rtained, chiefly by the researches of Marckwald, that while division of he glosso-pharyngeal nerves produces no effect upon respiration, stim- lation of them causes inhibition of inspiration for a short period. This ction accounts for the very necessary cessation of breathing during wallowing. The effect of the stimulation is only temporary, and is llowed by normal breathing movements.

(*d*) **Action of other sensory nerves.**—The respiratory centres re as a rule stimulated to produce respiration by impressions conveyed y sensory nerves, *e.g.*, the nerves of the skin; cold water applied to e surface is almost invariably followed by a deep inspiration. Stimu- tion of the splanchnics and of the abdominal branches of the vagi oduce expiration. The fifth nerves, as well as the glosso-pharyngeal d the superior laryngeal, inhibit inspiration, but they tend to produce gradual slowing and not an absolute inhibition, as do the glosso- aryngeal.

It must be remembered that although many sensory nerves may on imulation be made to produce an effect upon the respiratory centres, ere is no evidence to show that any one of them, except the vagi, is nstantly in action. The vagi indeed are, as far as we know, the only rmal regulators of respiration.

*Automatic Action of the Respiratory Centres.*—Although it has been ry definitely proved that the respiratory centres may be affected by ferent stimuli, and particularly by those reaching them through the gi, there is reason for believing that the centres are capable of sending t efferent impulses to the respiratory muscles without the action of y afferent stimuli. Thus, if the brain be removed above the bulb, spiration continues. If the spinal cord be divided below the bulb, the cial and laryngeal respiratory movements continue, although no affer- t impulses can reach the centres except through the cranial sensory rves, and these, as we have seen, are not always in action, and indeed ay be divided without producing any effect, when the bulb and cord e intact. As has been shown, too, respiration continues when the vagi e divided. All of these experiments render it highly probable that ferent impulses are not required in order that the respiratory centres ould send out efferent impulses of some kind to the respiratory mus- es; these centres, then, are automatic. How they act in the absence afferent stimuli has been demonstrated by Marckwald. He has shown (*a*) firstly, that if the bulb be separated from the brain, and the vagi then cut, there is, first of all, inspiratory spasm followed by irregular asm of muscles both of inspiration and expiration, and death; (*b*) secondly, that if the vagi are divided, the respirations, although altered in character, are regular, but that if then the brain is separated from the medulla, the same respiratory spasms occur. From these experiments it is concluded that the automatic action of the centres consists in the liberation of respiratory *spasms* only, and not of regular rhythmic movements; but that impressions reaching the centres either from the cerebrum or through the vagi, prevent the gathering tension in the centres from becoming too great, and convert the spasms which would otherwise arise into regular movements. The chief difference between the action of the vagi and of the cerebral tracts, is that the former are always in action, whilst the latter are not. When the vagi are in action and the higher centres are not, periodic respiration takes place, that is to say, respirations occurring in groups, each such group being followed by a pause; a type of respiration known as *Cheyne-Stokes breathing,* to which we shall return presently. It will be thus seen that even the ordinary action of the respiratory centres is to a large extent reflex, and dependent upon vagus or cerebral stimulation.

*Method of Stimulation of the Respiratory Centres.*—Apart then from afferent impulses, the respiratory centres are capable of working automatically, and this fact has been explained by the supposition that they are stimulated to action by the condition of the blood circulating through them, since when the blood becomes more and more venous the action of the centres becomes more and more energetic, and if the air is prevented from entering the chest, the respiration in a short time becomes very labored. Any obstruction to the entrance of air indeed, whether partial or complete, is followed by an abnormal rapidity of the inspiratory acts. The condition caused by any interference with the free exchange of gases in the lungs, or by any circumstance in consequence of which the oxygen of the blood is used up in an abnormally quick manner, is known as *dyspnœa.* If the aëration of the blood is much interfered with, not only are the ordinary respiratory muscles employed, but also those muscles of extraordinary inspiration and expiration which have been previously enumerated. Thus as the blood becomes more and more venous, the action of the medullary centres becomes more and more active. The question has been much debated as to what quality of the venous blood it is which causes this increased activity; whether it is its deficiency of oxygen or its excess of carbonic acid. It has been answered to some extent by the experiments, which show on the one hand that dyspnœa occurs when there is no obstruction to the exit of carbonic acid as when an animal is placed in an atmosphere of nitrogen, and that it cannot therefore be due to the accumulation of carbonic acid; and on the other, that if plenty of oxygen is supplied, true dys
does not occur, although the carbonic acid of the blood is in exces
is highly probable, therefore, that the respiratory centres may be s

ted to action by the absence of sufficient oxygen in the blood circulat-
g in it, and not by the presence of an excess of carbonic acid.

But this is not all, since it has been proved by Marckwald that the
edullary centres are capable of acting for some time in the absence
f any circulation, and after excessive bleeding. The view taken by
his author with regard to the action of the centres is as follows: the
espiratory centres are set to act by the condition of their metabolism,
uch in the same way as the heart is set to beat rhythmically. When
nabolism is completed, katabolism or discharge occurs, and this alter-
ate but crude and spasmodic action will occur without a definite blood-
upply, as long as the centres are properly nourished and stimulated by
heir own intercellular fluid. The afferent impulses brought by the vagi,
consequence of the stimulation of their terminal fibres in the lungs,
ave a tendency to bring about katabolism, and to convert crude respi-
atory spasms into regular and rhythmic discharges. In the absence of
he vagus stimulation, the impulses from the cerebrum may be effectual
r the same purpose.

It is unreasonable to think, however, that the respiratory centres are
dependent of the character of the blood-supply either as regards quan-
ty or quality. This must have a great influence upon their irritability;
is certain, for example, that venous blood greatly increases the respi-
tory movements, first of all both of inspiration and of expiration, and
en of the latter to a greater degree. It may be that the diminution
oxygen in the blood acts as a stimulator of katabolism, in both in-
iratory and expiratory centres, but particularly in the latter, in a
anner similar to but not identical with, that of the vagus. It has also
en shown that the presence of the products of great muscular metabo-
m in the blood will greatly increase the irritability of the respiratory
ntres, even if the blood itself be not particularly venous in character.

It appears that the inspiratory and expiratory respiratory centres are
lateral, and that each pair may act independently, since the bulb may
divided longitudinally, and then if one vagus be divided, the respi-
tory rhythm on the two sides of the body becomes unequal, the move-
ents of the side upon which the vagus is divided being slower than on
e other side, while stimulation of the divided nerve acts only upon
e movements of its own side.

**Apnœa.**—When we take several deep inspirations in rapid succes-
n by voluntary effort, we find that we can do without breathing for a
ch longer time than usual; in other words, several rapid respirations
em to inhibit for a time normal respiratory movements. It was
ought that the reason for this partial cessation of respiration, which
s called *apnœa*, is that by taking several deep breaths we overcharge
r blood with oxygen, and that as the respiratory centre can only be
mulated by blood in which the standard of oxygen is below a certain

level, no respiratory impulses can occur until the oxygen tension of
blood reach that level. This idea must now be modified, if not give
in face of the experiments, *e.g.*, those of Hering, on cats' blood du
apnœa, which have shown that animals in a condition of apnœa
have less and not more oxygen in their blood than in a normal s
although the carbonic anhydride is less. One view now taken of
cause of apnœa is that by rapid inflations of the lungs impulses pa
by the vagi, by means of which inspiration is after a while inhib
another view is that by the repeated stimulation of the centre by v
impulses which result in rapid respiratory movements, anabolism
last arrested. Apnœa is with difficulty produced, if at all, when
vagi are divided.

**Effects of Vitiated Air.—Ventilation.**—As the air expired
the lungs contains a large proportion of carbon dioxide and a mi
amount of organic putrescible matter, it is obvious that if the sam
be breathed again and again, the proportion of carbonic dioxide
organic matter in it will constantly increase till it becomes un
breathe; long before this point is reached however, uneasy sensa
occur, such as headache, languor, and a sense of oppression. It is
markable fact, however, that the organism after a time adapts itse
a very vitiated atmosphere, and that a person soon comes to bre
without sensible inconvenience, an atmosphere which, when he firs
ters it, feels intolerable. Such an adaptation, however can only
place at the expense of a depression of all the vital functions, w
must be injurious if long continued or often repeated.

This power of adaptation is well illustrated by the experimen
Claude Bernard. A sparrow is placed under a bell-glass of such
that it will live for three hours. If now at the end of the second
(when it could have survived another hour) it be taken out and a
healthy sparrow introduced, the latter will perish instantly.

It must be evident that provision for a constant and plentiful su
of fresh air, and the removal of that which is vitiated, is of far gr
importance than the actual cubic space per head of occupants.
less than 2,000 cubic feet per head should be allowed in sleeping a
ments (barracks, hospitals, etc.), and with this allowance the air can
be maintained at the proper standard of purity by such a system of
tilation as provides for the supply of 1,500 to 2,000 cubic feet of
air per head per hour. (Parkes.)

## The Effect of Respiration on the Circulation.

As the heart, the aorta, and pulmonary vessels are situated in
air-tight thorax, they are exposed to a certain alteration of pres
when the capacity of the latter is increased in inspiration; for altho
the expansion of the lungs tends to counter-balance this increase of

er does so entirely, since part of the pressure of the air which is into the lungs through the trachea is expended in overcoming elasticity. The amount thus used up increases as the lungs e more and more expanded, so that the pressure inside the thorax g inspiration, as far as the heart and great vessels are concerned, quite equals that outside, and at the conclusion of inspiration is lerably less than the atmospheric pressure. It has been ascertained he amount of the pressure used up in the way above described, from 5 or 7 mm. of mercury during the pause, to 30 mm. of ry when the lungs are expanded at the end of a deep inspiration, t it will be understood that the pressure to which the heart and vessels are subjected diminishes as inspiration progresses, and at



221.—Diagram of an apparatus illustrating the effect of inspiration upon the heart and ssels within the thorax. I, the thorax at rest; II, during inspiration; D, represents the gm when relaxed; D′, when contracted (it must be remembered that this position is a mere ), *i.e.*, when the capacity of the thorax is enlarged; H, the heart; V, the veins entering it, e aorta; Rl, Ll, the right and left lung; T, the trachea; M, mercurial manometer in con- with pleura. The increase in the capacity of the box representing the thorax is seen to e heart as well as the lungs, and so to pump in blood through V, whereas the valve prevents rough A. The position of the mercury in M shows also the suction which is taking place. )

nimum is less by 30 mm., than the normal pressure, 760 mm. of ry. It will be understood from the accompanying diagram how, there were no lungs in the chest, if its capacity were increased, fect of the increase would be expended in pumping blood into the from the veins. With the lungs placed as they are, during in- ion the pressure outside the heart and great vessels is diminished, ey have therefore a tendency to expand and to diminish the intra- ar pressure. The diminution of pressure within the veins passing right auricle and within the right auricle, itself, will draw the into the thorax, and so assist the circulation. This suction action pendent of the suction power of the diastole of the auricle about we have previously spoken. The effect of sucking more blood into the right auricle will, *cæteris paribus*, increase the amount pass through the right ventricle, which also exerts a similar suction act and through the lungs into the left auricle and ventricle, and thus i the aorta. This all tends to increase the blood-pressure. The effec the diminished pressure upon the pulmonary vessels will also l toward the same end, *i.e.*, an increased flow through the lungs, so t as far as the heart and its veins are concerned, inspiration increases blood-pressure in the arteries. The effect of inspiration upon the a and its branches within the thorax would be, however, contrary; fo the pressure outside is diminished the vessels would tend to expand, thus to diminish the tension of the blood within them, but inasmucl the large arteries are capable of little expansion beyond their nat calibre, the diminution of the arterial tension caused by this me



Fig. 222.—Comparison of blood-pressure curve with curve of intra-thoracic pressure. (To be from left to right.) *a* is the curve of blood-pressure with its respiratory undulations, the sl beats on the descent being very marked; *b* is the curve of intra-thoracic pressure obtained by necting one limb of a manometer with the plural cavity. Inspiration begins at *i* and expirati *e*. The intra-thoracic pressure rises very rapidly after the cessation of the inspiratory effort, then slowly falls as the air issues from the chest; at the beginning of the inspiratory effort the becomes more rapid. (M. Foster.)

would be insufficient to counteract the increase of blood-pressure p duced by the effect of inspiration upon the veins of the chest, and balance of the whole action would be in favor of an increase of blo pressure during the inspiratory period. But if a blood-pressure trac be taken at the same time that the respiratory movements are be recorded, it will be found that, although speaking generally, the arte tension is increased during inspiration, the maximum of arterial tens does not correspond with the acme of inspiration (fig. 222). In fact the beginning of inspiration the pressure continues to fall, then gradu rises until the end of inspiration, and continues to do so for some ti after expiration has commenced.

As regards the effect of *expiration*, the capacity of the chest diminished, and the intra-thoracic pressure returns to the normal, wh is not exactly equal to the atmospheric pressure. The effect of this veins is to increase their extra-vascular and so their intra-vascular sure, and to diminish the flow of blood into the left side of the t, and with it the general blood-pressure, but this is almost exactly nced by the necessary increase of arterial tension caused by the ease of the extra-vascular pressure of the aorta and large arteries, so the arterial tension is not much affected during expiration either . Thus, ordinary expiration does not produce a distinct obstruction he circulation, as even when the expiration is at an end the intra- acic pressure is less than the extra-thoracic.

The effect of violent expiratory efforts, however, has a distinct action bstructing the current of blood through the lungs, as seen in the ness of the face from congestion in straining, this condition being uced by pressure on the small pulmonary vessels.

We may summarize this mechanical effect of respiration on the blood-sure therefore, and say that inspiration aids the circulation and so ases the arterial tension, and that although expiration does not rially aid the circulation, yet under ordinary conditions neither does struct it. Under extraordinary conditions, however, as in violent ration, the circulation is decidedly obstructed.

We have seen, however, that there is no exact correspondence between oint of highest blood-pressure and the end of inspiration, and we suppose that there are other mechanical factors, such, for example, e effect of the abdominal movements, both in inspiration and in ation, upon the arteries and veins within the abdomen and of the extremities, and the influence of the varying intrathoracic pres- upon the pulmonary vessels, both of which ought to be taken into deration. As regards the first of these, the effect during inspira- —as the cavity of the abdomen is diminished by the descent of the ragm—should be two-fold: on the one hand, blood would be sent rd into the chest by compression of the vena cava inferior; on the hand, the passage of blood downward from the chest in the minal aorta, and upward in the veins of the lower extremity, would a certain extent obstructed. In ordinary expiration all this would versed, but if the abdominal muscles are violently contracted, as in ordinary expiration, the same effect would be produced as by in- tion. The effect of the varying intrathoracic pressure, which occurs g inspiration upon the pulmonary vessels is to produce an initial tion of both artery and veins, and this delays for a short time the ge of blood toward the left side of the heart, and the arterial ure falls, but the fall of blood-pressure is soon followed by a steady since the flow is increased by the initial dilatation of the vessels: onverse is the case with expiration. As, however, the pulmonary are more easily dilatable than the pulmonary artery, their greater sibility increases the flow of blood as inspiration proceeds, while

during expiration, except at its beginning, this property of theirs a
the opposite direction, and diminishes the flow. Thus, at the begi
of inspiration the diminution of blood-pressure, which commenced d
expiration, is continued, but after a time the diminution is succeed
a steady rise; the reverse is the case with expiration—at first a ris
then a fall.

The effect of the **nervous system** in producing rhythmical al
tions quite independent of the mechanically caused undulations o



Fig. 223.—Traube-Hering's curves. (To be read from left to right.) The curves 1, 2, 3, 4
are portions selected from one continuous tracing forming the record of a prolonged obser
so that the several curves represent successive stages of the same experiment. Each curve is
in its proper position relative to the base line, which is omitted; the blood-pressure rises in
from 1 to 2, 3, and 4, but falls again in stage 5. Curve 1 is taken from a period when artifici
piration was being kept up, but the vagi having been divided, the pulsations on the ascent a
scent of the undulations do not differ; when artificial respiration ceased these undulations
while disappeared, and the blood-pressure rose steadily while the heart-beats became slower.
as at 2, new undulations appeared; a little later, the blood-pressure was still rising, the hear
still slower, but the undulations still more obvious (3); still later (4), the pressure was still
but the heart-beats were quicker, and the undulations flatter, the pressure then began to fall
(5), and continued to fall until some time after artificial respiration was resumed. (M. Fost

blood-pressure is two-fold. In the first place the *cardio-inhibitory* c
is stimulated during the fall of blood-pressure, and produces a sl
rate of heart-beat, which will be noticed in the tracing (fig. 223).
undulations during the decline of blood-pressure are therefore lo
but less frequent. This effect disappears when, by section of the
the effect of the centre is cut off from the heart. In the second p
the *vaso-motor centre* sends out rhythmical impulses, by which un
tions of blood-pressure are produced, quite independent of the so-c

y undulations. The action of this centre in producing such
ns is thus demonstrated. In an animal under the influence
a record of whose blood-pressure is being taken, and where
respiration has been stopped, and both vagi cut, the blood-
curve rises at first almost in a straight line, but after a time
al undulations occur (called *Traube's* or *Traube-Hering's*
here may be upward of ten of the respiratory undulations in
be-Hering curve. They continue as long as the blood-pressure
to rise, and only cease when the vaso-motor centre and the
exhausted, when the pressure falls. The undulations cannot
pon anything but the vaso-motor centre, as the mechanical
respiration have been eliminated by the curari and by the
of artificial respiration, and the effect of the cardio-inhibitory
s been removed, by the division of the vagi. The rhythmic
od-pressure is most likely due to a rhythmic constriction of
oles followed by a rhythmic fall of pressure and relaxation,
g due to the action of the vaso-motor centre. The vaso-motor
erefore, as well as the cardio-inhibitory, is capable of produc-
mical undulations of blood-pressure.

*e-Stokes' breathing* is a rhythmical irregularity in respirations
been observed in various diseases, and is especially connected
degeneration of the heart. Respirations occur in groups, at
ning of each group the inspirations are very shallow, but each
breath is deeper than the preceding, until a climax is reached,
h the inspirations become less and less deep, until they cease
for a time, after which the cycle is repeated. This phenome-
rs to be due to the want of action of some of the usual cerebral
which pass down to and regulate the discharges of the respira-
es.

ver is the exact quality of the venous blood which excites the
y centre to produce normal respirations, there can be no doubt
e blood becomes more and more venous from obstruction to
ce of air into the lung, or from the blood not taking up from
usual supply of oxygen, the respiratory centre becomes more
excitable, and a condition ensues, which passes rapidly from
*a* (excessive breathing) to the state of *Dyspnœa* (difficult
), and afterward to *Asphyxia ;* and the latter, unless relieved,
ds in death.

ays by which this condition of **asphyxia** may be produced are
rous:—As, for example, by the prevention of the due entry
into the blood, either by direct obstruction of the trachea or
t of the respiratory passages, or by introducing instead of
ir a gas devoid of oxygen, or, by interference with the due in-
of gases between the air and the blood.

mptoms of asphyxia may be divided into three groups, which correspond with the stages of the condition which are usually recognized, these are (1), the stage of exaggerated breathing; (2), the stage of convulsions; (3), the stage of exhaustion.

In the *first stage* the breathing becomes more rapid and at the same time more deep than usual, the inspirations at first being especially exaggerated and prolonged. The muscles of extraordinary inspiration are called into action, and the effort to respire is labored and painful. This is soon followed by a similar increase in the expiratory efforts, which become excessively prolonged, being aided by all the muscles of extraordinary expiration. During this stage, which lasts a varying time from a minute upward, according as the deprivation of oxygen is sudden or gradual, the lips become blue, the eyes are prominent, and the expression intensely anxious. The prolonged respirations are accompanied by a distinctly audible sound; the muscles attached to the chest stand out as distinct cords. This stage includes the two conditions hyperpnœa and dyspnœa already spoken of. It is due to the increasingly powerful stimulation of the respiratory centres by the increasingly venous blood.

In the *second stage*, which is not marked out by any distinct line of demarcation from the first, the violent expiratory efforts become convulsive, and then give way, in men and other warm-blooded animals at any rate, to general convulsions, which arise from the further stimulation of the centres. The spasms of the muscles of the body in general occur, and not of the respiratory muscles only. The convulsive stage is a short one, and lasts less than a minute.

The *third stage* or stage of *exhaustion*. In it, the respirations all but cease, the spasms give way to flaccidity of the muscles, there is insensibility, the conjunctivæ are insensitive and the pupils are widely dilated. Every now and then a prolonged sighing inspiration takes place, at longer and longer intervals until they cease altogether, and death ensues. During this stage the pulse is scarcely to be felt, but the heart may beat for some seconds after respirations have quite ceased. The condition is due to the gradual paralysis of the respiratory centre by the prolonged action of the increasingly venous blood.

As with the first stage, the duration of the second and third stages depends whether the manner of the deprivation of oxygen is sudden or gradual. The convulsive stage is short, lasting, it may be, only one minute. The third stage may last three minutes and upward.

The *conditions of the vascular system* in asphyxia are:—(1) More or less interference with the passage of the blood through the systemic and the pulmonary blood-vessels; (2) Accumulation of blood in the right side of the heart and in the systemic veins; (3) Circulation of impure (non-aërated) blood in all parts of the body.

After death from asphyxia it is found in the great majority of that the right side of the heart, the pulmonary arteries, and the system

gorged with dark, almost black blood, and the left side of the
pulmonary veins, and the arteries are empty. The explana-
ese appearances may be thus summarized: when respiration
, venous blood at first passes freely through the lungs to the
and so to the great arteries. When it reaches the arterioles
its direct action upon their muscular tissue, or more probably
he medium of the vaso-motor centres, the arterioles contract,
ly those of the splanchnic area, the blood-pressure rises and
de of the heart becomes distended. This latter effect may be
xtra action of the right heart, but is more probably due to
sed peripheral resistance, and its slower beat. Although the
are contracted, a little blood is allowed to pass through them,
ighly venous blood, favored by the labored respiratory move-
ives at the right side of the heart. When it reaches the pul-
terioles it gives rise to the same contraction in them as it did
stemic vessels. This obstruction to the circulation through
causes a distended condition of the right heart and the pul-
tery, and on the other hand, produces a greatly diminished
through the pulmonary veins and to the left side of the heart,
fter a time in practical emptiness. So that in the third stage
a it is stated by some observers that the left heart gets into
ion in which it is found after death. Others think that the
dition of the left heart is a post-mortem phenomenon. In
nd second stages of the condition the blood-pressure continu-
until it reaches a point far above the normal. The veins are
gorged, so that when pricked they may eject the blood for
nce. Both sides of the heart and the pulmonary vessels are
with blood, at any rate during the greater portion of these
l at the third stage blood-pressure falls rapidly.

*f death.*—The causes of these conditions and the manner in
y act, so as to be incompatible with life, may be here briefly
l.

e obstruction to the passage of blood through the lungs occurs
the later stages of asphyxia, the obstruction being chiefly in
oles, which contract under the influence of the vaso-motor
possibly of a special part of it, which governs the action of
nary blood-vessels.

cumulation of blood, with consequent distention of the right
heart and of the systemic veins, is the direct result, at least
the obstruction to the pulmonary circulation just referred to.
ses, however, are in operation. (*a*) The vaso-motor centres
by blood deficient in oxygen, cause contraction of all the
ries with increase of arterial tension, and as an immediate

consequence the filling of the systemic veins. (*b*) The increased arterial tension is followed by inhibition of the action of the heart, and the heart, contracting less frequently, and also gradually enfeebled by deficient supply of oxygen, becomes over-distended with blood which it cannot expel. At this stage the left as well as the right cavities are over-distended.

The ill effects of these conditions are to be looked for partly in the heart, the muscular fibres of which, like those of the urinary bladder or any other hollow muscular organ, may be paralyzed by over-stretching; and partly in the venous congestion, and consequent interference with the function of the higher nerve-centres, especially the medulla oblongata.

(3) The passage of non-aërated blood through the lungs and its distribution over the body are events incompatible with life in one of the higher animals for more than a few minutes; the rapidity with which death ensues in asphyxia being due, more particularly, to the effect of non-oxygenized blood on the medulla oblongata, and, through the coronary arteries, on the muscular substance of the heart. The excitability of both nervous and muscular tissue is dependent on a constant and large supply of oxygen, and, when this is interfered with, excitability is rapidly lost.

*Effects of breathing gases other than the atmosphere.*—The diminution of oxygen has a more direct influence in the production of the usual symptoms of asphyxia than the increased amount of carbon dioxide. Indeed, the fatal effect of a gradual accumulation of **carbon dioxide** in the blood, when a due supply of oxygen is maintained, resembles rather the action of a narcotic poison than it does asphyxia.

Then again we must carefully distinguish the asphyxiating effect of an insufficient supply of oxygen from the directly poisonous action of such gases as **carbonic oxide**, which is contained to a considerable amount in common coal-gas. The fatal effects often produced by this gas (as in accidents from burning charcoal stoves in small, close rooms) are due to its entering into combination with the hæmoglobin of the blood-corpuscles and thus preventing its combination with oxygen. The partial pressure of oxygen in the atmosphere may be considerably increased without much effect. **Hydrogen** may take the place of nitrogen if the oxygen is in the usual proportion with no marked ill effect. **Sulphuretted hydrogen** destroys the hæmoglobin of blood. **Nitrous oxide** acts directly on the nervous system as a narcotic, and may also form a stable compound with hæmoglobin. Certain gases, such as **carbon dioxide** in more than a certain proportion; **sulphurous and other acid gases, ammonia,** and **chlorine** produce spasmodic closure of the glottis, and are irrespirable.

As conditions causing asphyxia in addition to the obstruction to the

rachea or elsewhere, and the prevention of the meeting of the blood
nd the air in the lung tissue by the blocking of one or more branches
f the pulmonary artery, may be mentioned the following:

*Alteration in the atmospheric pressure.*—The normal condition of
reathing is that the oxygen of the air breathed should be at the pres-
ure of $\frac{1}{5}$ of the atmosphere, viz., $\frac{1}{5}$ of 760 mm. of mercury, or 152 mm.,
ut it is found that life may be carried on by gradual diminution of
he oyxgen pressure to considerably less than one half of this, viz., to
6 mm., or $\frac{1}{10}$ partial pressure, which is reached at an altitude above
5,000 feet.* Any pressure less than this may begin to produce altera-
ions in the relations of the gases in the blood, and if an animal is sub-
ected suddenly to a marked decrease of barometric pressure, and so of
xygen pressure (below 7 per cent), it is thrown into convulsions, and it
found that the gases are set free in the blood-vessels, no doubt carbon
ioxide and oyxgen as well as nitrogen, although the latter is the only
ne of the three gases the presence of which in the vessels in death
om this condition of affairs has been proved; the others are said to
e reabsorbed. Other derangements may precede this, *e.g.*, bleeding
om the nose, dyspnœa, and vascular derangement. On the other hand,
e oygxen may be gradually increased to a considerable extent without
arked effect, even to the extent of 8 or 10 atmospheres, but when the
ygen pressure is increased up to 20 atmospheres the animals experi-
ented upon by Paul Bert died with severe tetanic convulsions. The
eration of pressure above or below a certain average affects primarily
e gaseous interchange in the lungs, and then that in the tissues gene-
lly, but signs of dyspnœa may be produced as well either by *cutting*
*the supply of blood to the medullary centres*, or by *warming the blood*
*the carotid* arteries which supply them. The cause in the former
se being the deprivation of oxygen and the accumulation of the car-
n dioxide, and of the latter, the increased metabolism of the centre
up by the warmed blood.

---

* For an interesting account of the symptoms produced by diminished atmos-
eric pressure in those mounting to very high altitudes, Whymper's "Travels
ongst the Andes of the Equator" may be consulted.

# CHAPTER VIII.

## SECRETION.

It is the function of gland cells to produce by the metabolism of th protoplasm certain substances called secretions. These materials are two kinds; viz., those which are employed for the purpose of servi some ulterior office in the economy, and those which are discharged fr the body as useless or injurious. In the former case, the separat materials are termed *true secretions;* in the latter they are termed exc *tions.*

The secretions as a rule consist of substances which do not pre-ex in the same form in the blood, but require special cells and a proc of elaboration for their formation, *e.g.*, the liver cells for the for tion of bile, the mammary gland-cells for the formation of milk. T excretions, on the other hand, commonly consist of substances whi exist ready-formed in the blood, and are merely abstracted therefr If from any cause, such as extensive disease or extirpation of an ex tory organ, the separation of an excretion is prevented, and an accu lation of it in the blood ensues, it frequently escapes through ot organs, and may be detected in various fluids of the body. But thi never the case with secretions; at least with those that are most ela rated; for after the removal of the special organ by which each of th is manufactured, the secretion is no longer formed. Cases someti occur in which the secretion continues to be formed by the nat organ, but not being able to escape toward the exterior, on accoun some obstruction, is re-absorbed into the blood, and afterward dischar from it by exudation in other ways; but these are not instances of t vicarious secretions, and must not be so regarded.

The circumstances of their formation, and their final destination, however, the only particulars in which secretions and excretions ca distinguished; for, in general, the structure of the parts engaged eliminating excretions is as complex as that of the parts concerned in formation of secretions. And since the differences of the two proc of separation, corresponding with those in the several purposes and tinations of the fluids, are not yet ascertained, it will be sufficien speak in general terms of the process.

Every secreting apparatus possesses, as essential parts of its structure, a simple and almost textureless membrane, named the *primary* or *basement-membrane;* certain *cells;* and *blood-vessels.* These three structural elements are arranged together in various ways; but all the varieties may be classed under one or other of two principal divisions, namely, *membranes* and *glands.*

## Organs and Tissues of Secretion.

The principal secreting organs are the following:—(1) the serous and synovial membranes; (2) the mucous membranes with their special glands, *e.g.*, the buccal, gastric, and intestinal glands; (3) the salivary glands and pancreas; (4) the mammary glands; (5) the liver; (6) the lachrymal gland; (7) the kidney and skin; and (8) the testes and ovaries.

The structure and functions of the glands secreting materials used in digestion will be considered when we study the alimentary tract. The functions of the kidney and skin will be described in a future chapter.

The lachrymal gland will be considered with the rest of the optic apparatus and the testes in the Chapter on Generation. There remain, then, the serous and mucous membranes and the mammary gland to be here described.

(1.) **Serous and Synovial Membranes.**—Serous membranes are of two principal kinds: *1st.* Those which line visceral cavities,—the *arachnoid, pericardium, pleuræ, peritoneum,* and *tunicæ vaginales. 2d.* The *synovial membranes* lining the joints, and the sheaths of tendons and ligaments, with which, also, are usually included the *synovial bursæ,* or *bursæ mucosæ,* whether these be subcutaneous, or situated beneath tendons and glide over bones.

The serous membranes form closed sacs, and exist wherever the free surfaces of viscera come into contact with each other or lie in cavities unattached to surrounding parts. The viscera invested by a serous membrane are, as it were, pressed into the shut sac which it forms, carrying before them a portion of the membrane, which serves as their investment. To the law that serous membranes form shut sacs, there s, in the human subject, one exception, viz.: the opening of the Fal-opian tubes into the abdominal cavity,—an arrangement which exists n man and all Vertebrata, with the exception of a few fishes.

The serous membranes are especially distinguished by the characters f the endothelium covering their free surface: it always consists of a ingle layer of polygonal cells. The ground substance of most serous membranes consists of connective-tissue corpuscles of various forms ying in the branching spaces which constitute the *lymph canalicular ystem,* and interwoven with bundles of white fibrous tissue, and numerous delicate elastic fibrillæ, together with blood-vessels, nerves, and lymphatics. In relation to the process of secretion, the layer of connective tissue serves as a groundwork for the ramification of blood-vessels, nerves, and lymphatics. But in its usual form it is absent in some instances, as in the arachnoid covering the dura mater, and in the interior of the ventricles of the brain. The primary membrane and epithelium are always present, and are concerned in 'the formation of the fluid by which the free surface of the membrane is moistened.



Fig. 224.—Section of synovial membrane. *a*, Endothelial covering of the elevations of the membrane; *b*, subserous tissue containing fat and blood-vessels; *c*, ligament covered by the synovial membrane. (Cadiat.)

*Functions.*—The principal purpose of the serous and synovial membranes is to furnish a smooth, moist surface, to facilitate the movements of the invested organ, and to prevent the injurious effects of friction. This purpose is especially manifested in joints, in which free and extensive movements take place; and in the stomach and intestines, which, from the varying quantity and movements of their contents, are in almost constant motion upon one another and the walls of the abdomen.

*Fluid.*—The fluid secreted from the free surface of the serous membranes is, in health, rarely more than sufficient to ensure the maintenance of their moisture. The opposed surfaces of each serous sac are at every point in contact with each other. After death, a larger quantity of fluid is usually found in each serous sac; but this, if not the product of manifest disease, is probably such as has transuded after death, o the last hours of life. An excess of such fluid in any serous sac co tutes dropsy of the sac.

The fluid naturally secreted by the serous membranes appears to be entical, in general and chemical characters, with very dilute blood rum. It is of a pale-yellow or straw-color, slightly viscid, alkaline, and account of the presence of albumen, coagulable by heat. This simi- rity of the serous fluid to the liquid part of blood, and to the fluid with hich most animal tissues are moistened, formerly led to the belief that was a simple transudation; but Heidenhain has concluded from experi- ents that the process of separation is one of secretion, dependent upon he selective activity of the endothelial cells. There is reason for sup- osing that the fluids of the cerebral ventricles and of the arachnoid sac re likewise secretions; for they differ from the fluids of the other serous acs not only in being pellucid, colorless, and of much less specific grav- ity, but in that they seldom receive the tinge of bile when present in the blood, and are not colored by madder, or other similar substances intro- luced abundantly into the blood.

It is also probable that the formation of *synovial fluid* is a process f genuine and elaborate secretion, by means of the epithelial cells on he surface of the membrane, and especially of those which are accumu- ated on the edge and processes of the synovial fringes; for, in its pecu- ar density, viscidity, and abundance of albumen, synovia differs alike rom the serum of blood and from the fluid of any of the serous cavities.

(2.) **Mucous Membranes.**—The *mucous membranes* line all those assages by which internal parts communicate with the exterior, and y which either matters are eliminated from the body or foreign sub- ances taken into it. They are soft and velvety, and extremely vascu- ar. The external surfaces of mucous membranes are attached to various ther tissues; in the tongue, for example, to muscle; on cartilaginous arts, to perichondrium; in the cells of the ethmoid bone, in the rontal and sphenoidal sinuses, as well as in the tympanum, to perios- um; in the intestinal canal, it is connected with a firm submucous embrane, which on its exterior gives attachment to the fibres of the uscular coat. The mucous membranes line certain principal tracts—*astro-pulmonary* and *Genito-urinary;* the former being subdivided into he *Digestive* and *Respiratory* tracts.

1. The Digestive tract commences in the cavity of the mouth, from hich prolongations pass into the ducts of the salivary glands. From he mouth it passes through the fauces, pharynx, and œsophagus, to the omach, and is thence continued along the whole tract of the intestinal anal to the termination of the rectum, being in its course arranged in e various folds and depressions already described, and prolonged into e ducts of the intestinal glands, the pancreas and liver, and into the ll-bladder.

2. The Respiratory tract includes the mucous membrane lining th cavity of the nose, and the various sinuses communicating with it, th lachrymal canal and sac, the conjunctiva of the eye and eyelids, and th prolongation which passes along the Eustachian tubes and lines the tym panum and the inner surface of the membrana tympani. Crossing th pharynx, and lining that part of it which is above the soft palate, th respiratory tract leads into the glottis, whence it is continued, throug the larynx and trachea, to the bronchi and their divisions, which i lines as far as the branches of about $\frac{1}{50}$ of an inch ($\frac{1}{2}$ mm.) in diamete and continuous with it is a layer of delicate epithelial membrane whic extends into the pulmonary cells.

3. The Genito-urinary tract, which lines the whole of the urinary p sages, from their external orifice to the termination of the tubuli urinif of the kidneys, extends also into the organs of generation in both sex and into the ducts of the glands connected with them: and in the fem becomes continuous with the serous membrane of the abdomen at th fimbriæ of the Fallopian tubes.

*Structure.*—These mucous tracts, and different portions of each them, present certain structural peculiarities, adapted to the functio which each part has to discharge; yet in some essential characters th mucous membrane is the same, from whatever part it is obtained. I all the principal and larger parts of the several tracts, it presents, just remarked, an external layer of epithelium, situated upon a *basemen membrane*, and beneath this, a stratum of vascular tissue of variab thickness, containing lymphatic vessels and nerves. The vascul stratum, together with the basement membrane and epithelium, in diffe ent cases, is elevated into minute papillæ and villi, or depressed in involutions in the form of glands. But in the prolongations of th tracts, where they pass into gland-ducts, these constituents are reduc in the finest branches of the ducts to the epithelium, the primary or bas ment-membrane, and the capillary blood-vessels spread over the out surface of the latter in a single layer.

The primary or basement membrane is a thin transparent layer, si ple, homogeneous, or composed of endothelial cells. In the minut divisions of the mucous membranes, and in the ducts of glands, it is th layer continuous and correspondent with this basement-membrane th forms the proper walls of the tubes. The cells also, which, lining th larger and coarser mucous membranes, constitute their epithelium, continuous with and often similar to those which, lining the gland-duc are called *gland-cells*. No certain distinction can be drawn between th epithelium-cells of mucous membranes and gland-cells.

*Mucous Fluid: Mucus.*—From all mucous membranes there is secret either from the surface or from certain special glands, or from both, ore or less viscid, grayish, or semi-transparent fluid, of alkaline reac-on and high specific gravity, named *mucus*. It mixes imperfectly ith water, but, rapidly absorbing liquid, it swells considerably when ater is added. Under the microscope it is found to contain epithelium nd leucocytes. It is found to be made up, chemically, of mucin, hich forms its chief bulk, of a little albumen, of salts chiefly chlorides nd phosphates, and water with traces of fats and extractives.

## SECRETING GLANDS.

The secreting glands present, amid manifold diversities of form and composition, a general plan of structure; all contain, and appear constructed with particular regard to the arrangement of the cells, which, as already expressed, both line their tubes or cavities as an epithelium, and elaborate, as secreting cells, the substances to be discharged from them.

*Types of Secreting Glands.*—Secreting glands may be classified according to certain types, which are the following:—1. The *simple tubular* gland (A, fig. 225), examples of which are furnished by the follicles of Lieberkühn, and the tubular glands of the stomach. They are simple tubular depressions of the mucous membrane, the wall of which is formed of primary membrane and is lined with secreting cells arranged as an epithelium. To the same class may be referred the elongated and tortuous *sudoriferous glands.*

2. The *compound tubular* glands (D, fig. 225) form another division. These consist of main gland-tubes, which divide and subdivide. Each gland may be made up of the subdivisions of one or more main tubes. The ultimate subdivisions of the tubes are generally highly convoluted. They are formed of a basement-membrane, lined by epithelium of various forms. The larger tubes may have an outside coating of fibrous, areolar, or muscular tissue. The *kidney*, *testes*, *salivary glands*, *pancreas*, *Brunner's glands*, with *the lachrymal and mammary glands*, *and some mucous glands* are examples of this type but present more or less marked variations among themselves.

3. The *aggregate* or *racemose* glands, in which a number of vesicles or *acini* are arranged in groups or globules (C, fig. 225). The *meibomian follicles* are examples of this kind of gland. There seem to be glands of mixed character, combining some of the characters of the tubular with others of the racemose type; these are called *tubulo-racemose* or *tubulo-acinous* glands. These glands differ from each other only in secondary points of structure: such as, chiefly, the arrangement of their excretory ducts, the grouping of the *acini* and lobules, their connection by areolar tissue, and supply of blood-vessels. The acini commonly appear to be formed by a kind of fusion of the walls of several vesicles, which thus

combine to form one cavity lined or filled with secreting cells which also occupy recesses from the main cavity. The smallest branches of the gland-ducts sometimes open into the centres of these cavities; sometimes the acini are clustered round the extremities, or by the sides of the ducts: but, whatever secondary arrangement there may be, all have the same essential character of rounded groups of vesicles containing



Fig. 225.—Plans of extension of secreting membrane by inversion or recession in form of cavities. A, Simple glands, viz., *g*, straight tube; *h*, sac; *i*, coiled tube. B, Multilocular crypts; *k*, of tubular form; *l*, saccular. C, Racemose, or saccular compound gland; *m*, entire gland, showing branched duct and lobular structure; *n*, a lobule, detached with *o*, branch of duct proceeding from it. D, Compound tubular gland (Sharpey).

gland-cells, and opening by a common central cavity into minute ducts, which ducts in the large glands converge and unite to form larger and larger branches, and at length by one common trunk open on a free surface of membrane.

Among these varieties of structure, all the secreting glands are alike in some essential points, besides those which they have in common with

I truly secreting structures. They agree in presenting a large extent
secreting surface within a comparatively small space; in the circum-
ance that while one end of the gland-duct opens on a free surface, the
posite end is always closed, having no direct communication with
ood-vessels, or any other canal; and in a uniform arrangement of
pillary blood-vessels, ramifying and forming a network around the
alls and in the interstices of the ducts and acini.

*Process of Secretion.*—It is generally conceded that the process of se-
etion is dependent upon the selective activity of the secreting cells.
is probable, however, in the case of the water and salts, that the phys-
al processes of filtration and diffusion may play a part.

The chemical processes constitute the process of *secretion*, properly so
alled, as distinguished from mere transudation spoken of above. In
he chemical process of secretion, various materials which do not exist as
uch in the blood are manufactured by the agency of the gland-cells from
the blood, or, to speak more accurately, from the plasma which exudes
from the blood-vessels into the interstices of the gland-textures.

The best evidence in favor of this view is: 1st. That cells and nuclei
re constituents of all glands, however diverse their outer forms and other
haracters, and that they are in all glands placed on the surface or in
he cavity whence the secretion is poured. 2d. That certain materials
f secretions are visible with the microscope in the gland cells before
hey are discharged. Thus, granules probably representing the fer-
ents of the pancreas may be discerned in the cells of that gland;
permatozoids in the cells of the tubules of the testicles; granules of
ric acid in those of the kidneys (of fish); fatty particles, like those of
ilk, in the cells of the mammary gland.

Secreting cells, like the cells of other organs, appear to develop, grow,
nd attain their individual perfection by appropriating nutriment from
he fluid exuded by adjacent blood-vessels and building it up, so that
t shall form part of their own substance. In this perfected state the
ells subsist for some brief time, and when that period is over they
ppear to dissolve, wholly or in part, and yield their contents to the
eculiar material of the secretion. And this appears to be the case in
very part of the gland that contains the appropriate gland-cells; there-
ore not in the extremities of the ducts or in the acini alone, but in great
art of their length.

We will describe elsewhere the changes which have been noticed from
ctual experiment in the cells of the salivary glands, pancreas, and peptic
lands.

*Discharge of secretions* from glands may either take place as soon as
ey are formed; or the secretion may be long retained within the

gland or its ducts. The former is the case with the sweat glands. But the secretions of those glands whose activity of function is only occasional are usually retained in the cells in an undeveloped form during the periods of the gland's inaction. There are glands which are like both these classes, such as the lachrymal, which constantly secrete small portions of fluid, and on occasions of greater excitement discharge it more abundantly.

When discharged into the ducts, the further course of secretions is affected (1) partly by the pressure from behind; the fresh quantities of secretion propelling those that were formed before. In the larger ducts, its propulsion is (2) assisted by the contraction of their walls. All the larger ducts, such as the ureter and common bile-duct, possess in their coats plain muscular fibres; they contract when irritated, and sometimes manifest peristaltic movements. Rhythmic contractions in the pancreatic and bile-ducts have been observed, and also in the ureters and vasa deferentia. It is probable that the contractile power extends along the ducts to a considerable distance within the substance of the glands whose secretions can be rapidly expelled. Saliva and milk, for instance, are sometimes ejected with much force.

*Circumstances Influencing Secretion.*—The principal conditions which influence secretion are (1) variations in the quantity of blood, (2) variations in the quantity of the peculiar materials for any secretion that the blood may contain, and (3) variations in nerve impulses passing to the gland cells over secretory nerve fibres.

(1.) *An increase in the quantity of blood traversing a gland*, as in nearly all the instances before quoted, coincides generally with an augmentation of its secretion. Thus the mucous membrane of the stomach becomes florid when, on the introduction of food, its glands begin to secrete; the mammary gland becomes much more vascular during lactation; and all circumstances which give rise to an increase in the quantity of material secreted by an organ produce, coincidently, an increased supply of blood; but we have seen that a discharge of saliva may occur under extraordinary circumstances, without increase of blood-supply, and so it may be inferred that this condition of increased blood-supply is not absolutely essential.

(2.) *An increase in the amount of the materials which the glands are designed to separate or elaborate, contained in the blood supplied to them*, increases the amount of any secretion. Thus, when an excess of nitrogenous waste is in the blood, from destruction of one kidney or whatever cause, a healthy kidney will excrete more urea than it did before.

(3.) *Influence of the Nervous System on Secretion.*—The process of secretion is largely influenced through the nervous system. The exact ode in which the influence is exhibited must still be regarded as mewhat obscure. In part, it exerts its influence by increasing or minishing the quantity of blood supplied to the secreting gland, virtue of the power which it exercises over the contractility of the aller blood-vessels; while it also has a more direct influence, as is scribed at length in the case of the submaxillary gland, upon the reting cells themselves; this may be called *trophic* influence. Its fluence over secretion, as well as over other functions of the body, y be excited by causes acting directly upon the nervous centres, upon e nerves going to the secreting organ, or upon the nerves of other rts. In the latter case, a reflex action is produced: thus the impres- n produced upon the nervous centres by the contact of food in the uth is reflected upon the nerves supplying the salivary glands, and duces, through these, a more abundant secretion of the saliva.

Through the nerves, various conditions of the brain also influence the retions. Thus, the thought of food may be sufficient to excite an undant flow of saliva. And, probably, it is the mental state which ites the abundant secretion of urine in hysterical paroxysms, as well the perspirations, and occasionally diarrhœa, which ensue under the luence of terror, and the tears excited by sorrow or excess of joy. e quality of a secretion may also be affected by mental conditions, as the cases in which, through grief or passion, the secretion of milk is red, and is sometimes so changed as to produce irritation in the nentary canal of the child, or even death.

*Relations between the Secretions.*—The secretions of some of the glands m to bear a certain relation or antagonism to each other, by which increased activity of one is usually followed by diminished activity of or more of the others; and a deranged condition of one is apt to ail a disordered state in the others. Such relations appear to exist ong the various mucous membranes; and the close relation between secretion of the kidney and that of the skin is a subject of constant ervation.

## The Mammary Glands.

*Structure.*—The mammary glands are composed of large divisions or es, and these are again divisible into lobules—the lobules being com- ed of the convoluted and dilated subdivisions of the main ducts eoli) held together by connective tissue. The lobes and lobules too bound together by areolar tissue; penetrating between the lobes and ering the general surface of the gland, with the exception of the ple, is a considerable quantity of yellow fat, itself lobulated by aths and processes of tough areolar tissue (fig. 226) connected both the skin in front and the gland behind; the same bond of connection extending also from the under surface of the gland to the sheathing connective tissue of the great pectoral muscle on which it lies. The main ducts of the gland, fifteen to twenty in number, called the *lactiferous* or *galactophorous* ducts, are formed by the union of the smaller (lobular) ducts, and open by small separate orifices through the nipple. At the points of junction of lobular ducts to form lactiferous ducts, and just before these enter the base of the nipple, the ducts are dilated (fig. 226); and, during lactation, the period of active secretion by the gland, the dilatations form reservoirs for the milk, which collects in and distends them. The walls of the gland-ducts are formed of areolar with some unstriped muscular tissue, and are lined internally by short columnar and near the nipple by squamous epithelium. The alveoli consist of a membrana propria of flattened endothelial cells lined by low columnar epithelium, and are filled with fat globules.



Fig. 226.—Dissection of the lower half of the female mamma, during the period of lactation. ⅔.—In the left-hand side of the dissected part the glandular lobes are exposed and partially unravelled; and on the right-hand side, the glandular substance has been removed to show the reticular loculi of the connective tissue in which the glandular lobules are placed: 1, Upper part of the mamilla or nipple; 2, areola; 3, subcutaneous masses of fat; 4, reticular loculi of the connective tissue which support the glandular substance and contain the fatty masses; 5, one of three lactiferous ducts shown passing toward the mamilla where they open; 6, one of the sinus lactei or reservoirs; 7, some of the glandular lobules which have been unravelled; 7′, others massed together (Luschka).

The nipple, which contains the terminations of the lactiferous ducts, is composed also of areolar tissue, and contains unstriped muscular fibres. Blood-vessels are also freely supplied to it, so as to give it a species of erectile structure. On its surface are very sensitive papillæ; and around is a small area or *areola* of pink or dark-tinted skin, on which are to e seen small projections formed by minute secreting glands.

Blood-vessels, nerves, and lymphatics are plentifully supplied to the mammary glands; the calibre of the blood-vessels, as well as the size of the glands, varying very greatly under certain conditions, especially those of pregnancy and lactation.

The alveoli of the glands during the secreting periods are found to be lined with very short columnar cells, with nuclei situated toward the centre. The edges of the cells toward the lumen may be irregular and jagged, and the remainder of the alveolus is filled up with the materials of the milk. During the intervals between the acts of discharge, the cells of the alveoli elongate toward the lumen, their nuclei divide, and in the part of the cells toward the lumen a collection of oil globules and probably of other materials takes place.



Fig. 227.—Section of mammary gland of bitch, showing acini, lined with epithelial cells of a polyhedral or short columnar form. × 200. (V. D. Harris.)

The next stage is that the cells divide and the part of each toward the lumen containing a nucleus and the materials of the secretion is, as it were, broken off from the outer part and goes to form the solid part of the milk. The cells also secrete, from the blood supplied to them, the water, salts, and probably sugar. In addition to the actual casting off parts of the cells containing fat and the other materials, oil globules appear to pass out from the cells with the other materials into the lumen of the alveoli. The cast-off parts of the cells disintegrate or break down, undergoing a kind of solution in the more fluid part of the secretion.

In the earlier days of lactation, epithelial cells partially transformed are discharged in the secretion: these are termed *colostrum corpuscles*, but later on the cells are completely transformed into fat before the secretion is discharged.

After the end of lactation, the mamma gradually returns to its original *nvolution*). The acini, in the early stages of involution, are lined cells in all degrees of vacuolation. As involution proceeds the diminish considerably in size, and at length, instead of a mosaic of lining epithelial cells (twenty to thirty in each acinus), we ha or six nuclei (some with no surrounding protoplasm) lying in an i lar heap within the acinus. During the later stages of involution, yellow granular cells are to be seen. As the acini diminish in si connective tissue and fatty matter between them increase, and in animals, when the gland is completely inactive, it is found to con a thin film of glandular tissue overlying a thick cushion of fat. of the products of waste are carried off by the lymphatics.

During pregnancy the mammary glands undergo changes (*evol* which are readily observable. They enlarge, become harder and distinctly lobulated: the veins on the surface become more prom The areola becomes enlarged and dusky, with projecting papill nipple too becomes more prominent, and milk can be squeezed fr orifices of the ducts. This is a very gradual process, which com about the time of conception, and progresses steadily during the period of gestation. In the gland itself solid columns of cells from the old alveoli to form new alveoli. But these solid column a while are converted into tubes by the central cells becoming fat being discharged as the colostrum corpuscles above mentioned.

## Milk.

The mammary secretion, or milk, is a bluish-white, opaque flu a pleasant, sweet taste, of specific gravity of 1028–1034. It is



Fig. 228.—Globules and molecules of cow's milk. × 400.

emulsion. Under the microscope, it is found to contain a num globules of various sizes (fig. 228), the majority about $\frac{1}{10000}$ of a (2.5 $\mu$) in diameter. They are composed of oily matter, and are *milk-globules*, but the old view that they had an investing memb albuminous material is now generally discarded. Accompanying are numerous minute particles, both oily and albuminous, which e ordinary molecular movements. The milk which is secreted in t days after parturition is called the *colostrum*. This contains the ular colostrum corpuscles, which are four or five times the size of globules, and differs from ordinary milk in containing a larger tity of solid matter, and in being deep yellow, less sweet, but far alkaline, and in having a specific gravity of 1040–1046.

Composition of Colostrum (Pfeiffer).

| | |
|---|---|
| Proteids | 5.71 |
| Fat | 2.04 |
| Sugar | 3.74 |
| Salts | 0.28 |
| Water | 88.23 |
| | 100.00 |

*hemical Composition of Milk.*—In addition to the oil existing in erless little globules floating in a large quantity of water, milk ins certain *proteids*, *milk-sugar* (lactose), and several varieties of Its percentage composition has been already mentioned, but may re repeated. Its reaction is slightly alkaline.

Chemical Composition of Milk. (After Foster, Harrington, *et al.*)

| | Human. | Cow. | Mare. | Bitch. |
|---|---|---|---|---|
| Water | 87.30 | 87 | 90 | 76 |
| Solids | 12.70 | 13 | 10 | 24 |
| Fats | 4.00 | 4 | 2 | 10 |
| Proteids | 1.50 | 4 | 2.5 | 10 |
| Sugar | 7 | 4.3 | 5 | 3.5 |
| Salts | .20 | .7 | .5 | .5 |

## Constituents of Milk.

.) *Water.*—The amount of water varies in different animals, and e same animal from time to time. This is seen from the varying fic gravity; that of cow's milk, on the average, varies from 1028 to in unskimmed milk, and from 1033 to 1037 in skimmed milk. amount secreted by a woman is from 10 to 16 oz. at the end of the week of lactation, and increases to from 30 to 40 oz. by the eighth nth month. A cow under favorable circumstances secretes at least uarts a day.

.) *Proteids.*—These are of two kinds at least, viz., *caseinogen* and *lbumin.* Caseinogen may be obtained from milk either by the ion of an acid, *e.g.*, acetic, or by saturation with crystallized magm sulphate or sodium chloride in the way already indicated. Casen, as already pointed out, belongs to the class of nucleo-albumins . 119).

*oagulation of Milk.*—The clotting of caseinogen is seen when the ic ferment rennin, or when similar ferments from the pancreas or tinal juice are added to milk; it will take place when the milk is neutral or alkaline. By the clotting, caseinogen is converted i coagulated proteid, *casein*, and a proteid residue called whey-pr Casein carries down with it the fat, and the two materials form c As in the case of blood, coagulation cannot occur except in the pr of calcium salts. When caseinogen is acted on by rennin, it is sp hydrolytic cleavage into two parts, paracasein and whey-proteid. casein combines with the calcium salts to form the insoluble com casein; the whey-proteid remains behind in solution in the whey. reference to the coagulation of the blood, the similarity of the two esses will be seen. Caseinogen is also precipitated from milk i presence of an excess of acid. When milk curdles after "souring," due to the formation of lactic acid from the milk-sugar by n organisms.

*Lact-albumin* differs in some of its reactions from serum-albumi 115); it coagulates when milk is boiled, but this scum is also partl to the drying up of the caseinogen on the surface of the milk.

*Lactoglobulin*, another proteid of milk, is similar to the paraglo of the blood.

(3.) *Fats.*—The fats of milk are those usually found in anima sues, viz., olein, stearin, and palmatin (p. 128). There are also o especially that of butyric acid in combination with glycerin. Le and cholesterin and a lipochrome may also be present. The fat, up into minute particles, which are lighter than the remainder constituents, rises to the surface when the milk stands, forming c and cream, when its fatty molecules have run together, forms butt

(4.) *Lactose.*—This sugar, the reactions of which are mentio p. 130, is apt to undergo lactic-acid fermentation if the milk be e to the air, from the action of the organized ferment, the bact lactis. When this occurs milk becomes sour and the caseino thrown down.

(5.) *Salts.*—The chief salt of milk is calcium phosphate. W its presence caseinogen cannot form casein. The gases are dioxide and nitrogen.

SALTS IN WOMAN'S MILK (Rotch).

| | |
|---|---|
| Calcium phosphate | 23.87 |
| Calcium silicate | 1.27 |
| Calcium sulphate | 2.25 |
| Calcium carbonate | 2.85 |
| Magnesium carbonate | 3.77 |
| Potassium carbonate | 23.47 |
| Potassium sulphate | 8.33 |
| Potassium chloride | 12.05 |
| Sodium chloride | 21.77 |
| Iron oxide and alumina | 0.37 |
| | 100.00 |

## The Ductless Glands

### AND INTERNAL SECRETIONS.

The discovery of the remarkable and sometimes fatal effects of the moval of certain of the ductless glands has given a marked impetus to e study of these organs, so that at the present time they occupy a place importance in physiology formerly unthought of. The converse ef- cts of removing certain of these glands and of injections of extracts queous and others) of them into healthy animals or those operated upon, ve led to the belief that they elaborate in the course of their metabolic tivity some substance or substances which are of use to the body. nce the parenchyma cells of these glands belong morphologically to e secretory type, and since active constituents may be extracted from e glands, it is assumed that they produce a secretion. But this secre- on, whatever its quantity may be, passes either into the blood stream rectly (supra-renal) or indirectly by way of the lymphatics (thyroid), stead of discharging through a duct upon a free surface, as in the se of the salivary glands and others. Hence the term *internal secretion* s come into popular use by way of distinction.

It must be borne in mind, however, that both anabolic and katabolic products are formed by all tissues and are absorbed to a greater or less xtent into the circulation. But the term internal secretion does not pply to these. It is confined to such products as are formed by organs f a distinctly glandular type.

The glands which are known certainly to form internal secretions are the thyroid, the supra-renal capsules, the pancreas, and possibly the pituitary body. Howell has called attention to the fact that to be consistent the glycogen formed by the liver from dextrose (and proteid) should be regarded as an internal secretion. Thus the liver forms both an internal and external secretion, as in the case of the pancreas.

The spleen has been included in this chapter for convenience. It as not been proved to form an internal secretion.

**The Thyroid.**—The thyroid gland is situated in the neck. It con- ists of two lobes, one on each side of the trachea, extending upward to he thyroid cartilage, covering its inferior cornu and part of its body; ese lobes are connected across the middle line by a middle lobe or thmus. The thyroid is covered by the muscles of the neck. It is ighly vascular, and varies in size in different individuals.

*Structures.*—The gland is encased in a thin transparent layer of dense eolar tissue, free from fat, containing elastic fibres. This capsule sends strong fibrous trabeculæ, which inclose the thyroid *vesicles*—which are unded or oblong irregular sacs, consisting of a wall of thin hyaline embrane lined by a single layer of short cylindrical or cubical cells.

These vesicles are filled with transparent nucleo-albuminous coll material. The colloid substance increases with age, and the cavit appear to coalesce. In the interstitial connective tissue is a rou meshed capillary plexus, and a large number of lymphatics. The ner adhere closely to the vessels.



Fig. 229.—Part of a section of the human thyroid. *a*, Fibrous capsule; *b*, thyroid vesicles with, *e*, colloid substance; *c*, supporting fibrous tissue; *d*, short columnar cells lining vesicl arteries; *g*, veins filled with blood; *h*, lymphatic vessel filled with colloid substance. × ( Alcock.)

In the vesicles there are in addition to the yellowish glassy col material, epithelium cells, colorless blood-corpuscles, and also col corpuscles undergoing disintegration.

*Accessory Thyroids.*—These are small bodies possessing the struc of the thyroid and apparently performing the same function. They found in the neck and in the mediastinum as far as the heart. The cessory thyroids undergo hypertrophy when the thyroid has been remo

*Parathyroids.*—In addition to the accessory thyroids, parathyr are found in the neck, lying behind or to the side of the thyroid even within its substance (in the rat). They are small bodies, diffe from the thyroid in structure in that they consist of solid columr cells, not of acini; yet they seem capable of performing the functio the thyroid when that body is removed. They frequently exist pairs, but there may be more than two, lying along the carotid in gion of the thyroid. The parathyroids are thought, by some, to be mature thyroids. By others, they are considered to have a separate nction, distinct from that of the thyroids. According to Gley, re- oval of the thyroid body will not, of itself, result fatally, providing at one or all of the parathyroids remain; while removal of the para- yroids, even though the thyroids are undisturbed, is followed rapidly death.

*Functions of the Thyroid.*—The colloid material which is formed thin the thyroid vesicles, and is believed to be their secretion, finally ptures through their walls into the lymph channels and thus gains en- nce to the circulation. The secretion of the thyroid falls into the ass known as internal secretions, and exerts a profound influence upon e metabolic processes of the body, probably through the agency of the ntral nervous system. Complete extirpation of the thyroid, at least in me animals, produces death, preceded by a group of characteristic mptoms. In man and the monkey, the symptoms after removal com n slowly and resemble the disease known in man as *myxœdema*.

This disease is known definitely to be due to disease of the thyroid, whereby its function is interfered with. Moreover, if a piece of thyroid of sufficient size be grafted into an animal from which the glands have been removed, and the graft takes, the symptoms of thyroid removal are lessened in intensity or disappear altogether. And, likewise, thyroid feeding or the administration of thyroid extracts relieves the symptoms of the disease myxœdema.

The above facts show that the thyroid gland must perform some important function in the animal economy, and it is believed that this is accomplished by virtue of its internal secretion. The colloid material of the gland has been submitted to much chemical study, and a substance called *iodothyrin* has been isolated as its active principle. Baumann and Roos state that iodothyrin exists in the gland in combination with proteid bodies. Iodothyrin relieves the symptoms of thyroid removal much to the same extent as thyroid feeding. It is a very resistant substance, and is not injured by the action of the gastric juice or by boiling with 10 per cent sulphuric acid for a long time.

**The Supra-renal Capsules or Adrenals.**—These are two flattened, more or less triangular or cocked-hat shaped bodies, resting by their lower border upon the upper border of the kidneys.

*Structure.*—The gland is surrounded by an outer sheath of connective tissue, which sometimes consists of two layers, sending in exceedingly fine prolongations forming the framework of the gland. The gland tissue proper consists of an outside firmer cortical portion, and an inside soft dark medullary portion.

The finer structure of the supra-renal capsules is incompletely known.

(1.) The *cortical portion* is divided into (fig. 230) an external narrow ayer of small rounded or oval spaces, the *zona glomerulosa*, made by the fibrous trabeculæ, containing polyhedral cells (*b*). The second layer of cells is arranged in columns radiating from the medulla, the *zona fasciculata* (*c*), and separated from each other by fibrous septa. The third layer, that next the medulla, is called from its arrangement the *zona reticularis* (not shown in fig. 230). The individual cells are polyhedral in shape, each possessing a well-defined nucleus. In man, the protoplasm of the cells is especially rich in fat globules, and oftentimes contains in addition larger or smaller granules of a yellowish pigment. The blood-vessels are confined to the septa, and do not penetrate into the cell groups.



Fig. 230.—Vertical section through part of the cortical portion of supra-renal of guinea-pig. *a*, Capsule; *b*, zona glomerulosa; *c*, zona fasciculata; *d*, connective tissue supporting the columns of the cells of the latter, and also indicating the positions of the blood-vessels. × (S. K. Alcock.)

(2.) The *medullary substance* consists of a coarse rounded or irregular meshwork of fibrous tissue, in the alveoli of which are masses of multinucleated protoplasm (fig. 231); numerous blood-vessels; and an abundance of nervous elements. The cells are very irregular in shape and size, poor in fat, and occasionally branched; the nerves run through the cortical substance, and anastomose over the medullary portion.

*Nerves.*—The adrenals are very abundantly supplied with nerves, chiefly composed of medullated fibres. These fibres are derived from the solar and renal plexuses, vagi and phrenics. Nerve-cells are also numerous in connection with these fibres. The fibres enter the hilum of the gland, but the method of their termination is unknown.

*Composition.*—In addition to the ordinary extractives, benzoic ac uric acid, and taurin have been found, and also inosite, as well as a liar pigmentary substance, soluble in water, becoming red on ex- e to light, and giving with ferric chloride a green or blue color. ochromogen has been found by McMunn. Neurin, apparently the nervous elements, has also been shown.

*unction.*—Though formerly unknown, a vast amount of light has thrown upon the function of the supra-renal capsules within the last ears by the researches of Schäfer and Oliver, Zyboulski, Abel, and s. Brown-Séquard, it is true, showed by experiment as early as that removal of the supra-renal capsules is followed by the death of nimal, but his experiments were repeated by others who did not n the same results; and it was concluded that the supra-renal cap- had no function, or at least that their function was not known. h was preceded in the case of Brown-Séquard's animals by symptoms



231.—Section through a portion of the medullary part of the supra-renal of guinea-pig. ssels are very numerous, and the fibrous stroma more distinct than in the cortex, and is er reticulated. The cells are irregular and larger, clean, and free from oil globules. × Alcock.)

vhat analogous to those of the disease of man known as Addison's e. The failures to produce symptoms after attempted removal of lands have probably resulted from incomplete removal or the pres- of accessory bodies. Accessory supra-renal capsules are commonly at in some animals and are sometimes found in man. Further, if land is removed, the other hypertrophies. The experiments of all observers confirm the original experiments of Brown-Séquard. resence of the supra-renal capsules is essential to life. Thus the -renal capsules are proved to have a very important function, and perform this function through the agency of an *internal secretion.* häfer and Oliver found that injections of supra-renal extract pro- marked effects upon the muscular layer of the arteries, the mus- tissue of the heart, and the skeletal muscles. The muscular layer of the arteries is markedly contracted, causing a rise of blood-pressure. When the heart is freed from nervous control its contractions are increased both in force and frequency, still further raising blood-pressure. The contraction of the skeletal muscles in response to a single stimulu is much prolonged.

Very small doses of supra-renal extract are sufficient to produce marked effects. Thus Schäfer states that less than $\frac{1}{13000}$ gramme ( grain) of the desiccated gland is sufficient to produce an effect upon th heart and arteries of an adult man.

It is a curious fact that only extracts of the *medullary portion* of th gland are active. It has been further shown, by Christiani and oth that if only small portions of the medulla remain, the animal opera upon survives; while if all medullary substance be removed, ev though large portions of the cortex remain, the animal invariably di

Abel has succeeded in separating the blood-pressure-raising constitu ent of the extract, and calls it *epinephrin*. By nature it is related t the alkaloid group.

Destruction of the supra-renal capsules through disease in man re sults in the production of a group of symptoms known as Addison's di ease. The administration of supra-renal extract to these cases someti results beneficially, but not so uniformly as thyroid feeding does in my œdema.

On the whole, the assumption that the supra-renal capsules prod an internal secretion, which is essential to life, is warranted.

**The Pituitary Body.**—This body is a small reddish-gray ma occupying the sella turcica of the sphenoid bone.

*Structure.*—It consists of two lobes—a small posterior one, consi ing of nervous tissue; an anterior larger one, resembling the thyroid structure. A canal lined with flattened or with ciliated epitheli passes through the anterior lobe; it is connected with the infundi ulum. The gland spaces are oval, nearly round at the periphe spherical toward the centre of the organ; they are filled with nucleat cells of various sizes and shapes not unlike ganglion cells, collected t gether into rounded masses, filling the vesicles, and contained in a sem fluid granular substance. The vesicles are inclosed by connective tis rich in capillaries.

*Function.*—The function of the pituitary body has not yet been e tablished. Some observers have found that its removal causes deat preceded by symptoms resembling those of thyroid removal. Hence has been supposed that the pituitary body has a function identical wi or analogous to that of the thyroid. On the other hand, tumors o other disease of the pituitary body have been found after death in ass ciation with a disease known as acromegaly, in which the bones and s rts undergo great hypertrophy. In this connection it must be remem- red that the two lobes of the pituitary body are morphologically and nbryologically distinct.

## Internal Secretion of the Pancreas.

Minkowski and von Mering have shown that total extirpation of the ncreas is followed in all cases in the course of a few hours by the ap- earance of sugar in the urine. The amount of sugar which appears is nsiderable—from 5–10 per cent. This experimental disease (diabetes ellitus) is accompanied by an increase in the quantity of urine and by normal thirst and appetite, and proves fatal in 15 days or less. These sults are obtained only when the entire gland or more than nine-tenths it have been removed. If one-tenth of the gland be left behind, gar appears in the urine when carbohydrates are eaten, but not other- ise. Nor is it necessary that the remaining portion of the gland be in s normal situation. Successful grafts under the skin of the abdomen elsewhere will prevent the appearance of sugar in the urine and the her symptoms. If, however, the graft be subsequently removed, the gar in the urine and the other symptoms reappear, and the experi- ental disease proceeds to a rapidly fatal issue.

The symptoms produced by total extirpation of the pancreas do not pend upon the loss of the pancreatic juice proper to the organism. his secretion may be diverted from the intestine through a pancreatic tula without the production of diabetes. Moreover, Hédon and Thiro- ix have rendered the acini of the gland functionally inactive, and ul- imately destroyed them, by the injection of paraffin or other substances nto the duct of Wirsung, without the supervention of diabetes. These xperiments have led to the conviction that the little groups of epithelial- ike cells situated in the connective-tissue stroma of the pancreas (*islands f Langerhans*) secrete something which is absorbed into the circulation nd constitutes its *internal secretion*. Lépine and Boulud have recently xtracted from the urine of patients suffering from diabetes or pneumonia a crystalline substance which produces glycosuria when injected under he skin or into the jugular vein of animals. This substance loses its ower if passed in the blood through the vessels of a living pancreas. hey conclude, therefore, that the pancreas, possibly through its internal ecretion, has an antitoxic function and favors glycolysis in the tissues y destroying the substance which inhibits the conversion of glucose into lycogen or fat.

## Internal Secretion of the Liver.

This subject will be considered at length when we come to study the rmation of glycogen (see p. 449).

**The Spleen** is the largest of these so-called vascular glands; it is situated to the left of the stomach, between it and the diaphragm. It is of a deep red color, of a variable shape, generally oval, somewhat concavo-convex. Vessels enter and leave the gland at the inner side or hilus.

*Structure.*—The spleen is covered externally almost completely by a serous coat derived from the peritoneum, while within this is the proper fibrous coat or capsule of the organ. The latter, composed of connective tissue, with a large preponderance of elastic fibres, and a certain proportion of unstriated muscular tissue, forms the immediate investment of the spleen. Prolonged from its inner surface are fibrous processes or ***trabeculæ***, containing much unstriated muscle, which enter the interior of the organ, and, dividing and anastomosing in all parts, form a kind of supporting framework or *stroma*, in the interstices of which the proper substance of the spleen (*spleen-pulp*) is contained (fig. 233). At the hilus of the spleen, the blood-vessels, nerves, and lymphatics enter, and the fibrous coat is prolonged into the spleen-substance in the form of investing sheaths for the arteries and veins, which sheaths again continuous with the trabeculæ before referred to.



Fig. 232.—Section of injected dog's spleen; *c*, capsule; *tr*, trabeculæ; *m*, two Malpighian bodies with numerous small arteries and capillaries; *a*, artery; *l*, lymphoid tissue, consisting of closely-packed lymphoid cells supported by very delicate retiform tissue; a light space unoccupied by cells is seen all round the trabeculæ, which corresponds to the "lymph path" in lymphatic glands. (Schofield.)

Mall has recently described the spleen as consisting of lobules, rmed by the trabeculæ and contained masses of spleen-pulp.

The *spleen-pulp*, which is of a dark red or reddish-brown color, is mposed chiefly of cells, imbedded in a matrix of fibres formed of the anching of large flattened nucleated endothelioid cells. The spaces of e network only partially occupied by cells form a freely communicat- g system. Of the cells some are granular corpuscles resembling the mph-corpuscles, more or less connected with the cells of the meshwork, th in general appearance and in being able to perform amœboid



**Fig. 233.—Reticulum of the spleen of a cat, shown by injection with gelatine. (Cadiat.)**

vements; others are red blood-corpuscles of normal appearance or riously changed; while there are also large cells containing either a gment allied to the coloring matter of the blood, or rounded corpuscles e red corpuscles.

The splenic artery, after entering the spleen by its concave surface, ivides and subdivides, with but little anastomosis between its branches; t the same time its branches are sheathed by the prolongations of the ibrous coat, which they, so to speak, carry into the spleen with them. The arteries then pass into the spleen-pulp, their fibrous coat being re- placed by lymphoid tissue, and end in capillaries, which communi- cate with the lacunar spaces in the spleen-pulp, from which veins arise.

The walls of the smaller veins are more or less incomplete, and read- ly allow lymphoid corpuscles to be swept into the blood-current. The lood from the arterial capillaries is emptied into a system of interme- iate passages, which are directly bounded by the cells and fibres of the etwork of the pulp, and from which the smallest venous radicles with heir cribriform walls take origin. The veins are large and distensible: he whole tissue of the spleen is highly vascular and becomes readily ngorged with blood: the amount of distention is, however, limited by he fibrous and muscular tissue of its capsule and trabeculæ, which forms n investment and support for the pulpy mass within.

On the face of a section of the spleen can be usually seen readily with he naked eye, minute, scattered rounded or oval whitish spots, mostly om $\frac{1}{80}$ to $\frac{1}{60}$ inch ($\frac{1}{3}$ to $\frac{2}{5}$ *mm.*) in diameter. These are the *Malpi-*

*ghian corpuscles* of the spleen, and are situated on the sheaths of the minute splenic arteries, of which, indeed, they may be said to be outgrowths (fig. 234). For while the sheaths of the larger arteries are constructed of ordinary connective tissue, this has become modified where it forms an investment for the smaller vessels, so as to be composed of adenoid tissue, with abundance of corpuscles, like lymph-corpuscles, contained in its meshes, and the Malpighian corpuscles are but small outgrowths of this *cytogenous* or cell-bearing connective tissue. They are composed of cylindrical masses of corpuscles, intersected in all parts by a delicate fibrillar tissue, which, though it invests the Malpighian bodies, does not form a complete capsule. Blood-capillaries traverse the Malpighian corpuscles and form a plexus in their interior. The structure of a Malpighian corpuscle of the spleen is, therefore, very similar to that of lymphatic-gland substance.



Fig. 234.—Section of spleen of cat. *a*, *a′*, Malpighian corpuscles, in case of *a′*, in connecti with small artery, *b*; *b*, *b′*, small arteries; *c*, section of trabeculæ.

*Functions.*—With respect to the office of the spleen, we have the following data: (1.) The large size which it gradually acquires toward the termination of the digestive process, and the great increase observed about this period in the amount of the finely-granular albuminous plasma within its parenchyma, and the subsequent gradual decrease of is material, seem to indicate that this organ is concerned in storing up me of the changed and absorbed proteid food, to be gradually intro- uced into the blood according to the demands of the general system.

(2.) It seems probable that the spleen, like the lymphatic glands, is gaged in *the formation of blood-corpuscles.* For it is quite certain at the blood of the splenic vein contains an unusually large amount of ite corpuscles; and in the disease termed leucocythæmia, in which e pale corpuscles of the blood are remarkably increased in number, ere is almost always found an hypertrophied state of the spleen or of e lymphatic glands. In Kölliker's opinion, the development of color- ss and also colored corpuscles of the blood is one of the essential func- ons of the spleen, into the veins of which the new-formed corpuscles ss, and are thus conveyed into the general current of the circulation.

(3.) *The formation of red corpuscles.* The spleen is concerned in the rmation of red corpuscles during fœtal life and shortly after birth, and some animals during their whole existence. For, if the spleen be moved from such animals, the red marrow undergoes hypertrophy. oreover, in these animals the cells previously described as hæmatoblasts ay be found in the spleen.

It was formerly believed that the spleen exercised the function of de- oying red corpuscles that had lived out their allotted time. The evi- nce of this, however, is not convincing, and the theory has been actically abandoned. It rested chiefly upon the fact that large nu- ated cells were found in the spleen, with whole or partially disinte- ated red cells in their interior. But the phenomenon is probably of *st-mortem* occurrence. When the circulation ceases, the red cells me to rest, and, lying alongside these large cells, are probably then gested.

(4.) From the almost constant presence of uric acid, in larger quan- ities than in other organs, as well as of the nitrogenous bodies, xanthin, hypoxanthin, and leucin, in the spleen, some *special nitrogenous meta- bolism* may be fairly inferred to occur in it. One of the features of the chemical composition of the spleen is the presence of a special proteid, of the nature of alkali-albumin, containing iron. The salts of the spleen consist chiefly of sodium phosphates.

(5.) Besides these, its supposed direct offices, the spleen is believed to ulfil some purpose in regard to the portal circulation, with which it is n close connection. From the readiness with which it admits of being istended, and from the fact that it is generally small while gastric igestion is going on, and enlarges when that act is concluded, it is sup- osed to act as a kind of vascular reservoir, or diverticulum to the portal stem, or more particularly to the vessels of the stomach. That it may rve such a purpose is also made probable by the enlargement which it undergoes in certain affections of the heart and liver, attended with obstruction to the passage of blood through the latter organ, and by its diminution when the congestion of the portal system is relieved by discharges from the bowels, or by the effusion of blood into the stomach. This mechanical influence on the circulation, however, can hardly be supposed to be more than a very subordinate function.

The spleen may be removed without any obvious ill effect.

*Influence of the Nervous System upon the Spleen.*—When the spleen is enlarged after digestion, its enlargement is probably due to two causes, (1) a relaxation of the muscular tissue which forms so large a part of its framework; (2) a dilatation of the vessels. Both these phenomena are doubtless under control of the nervous system. It has been found by experiment that when the splenic nerves are cut the spleen enlarges, and that contraction can be brought about (1) by stimulation of the spinal cord (or of the divided nerves); (2) reflexly by stimulation of the central stumps of certain divided nerves, *e.g.*, vagus and sciatic; (3) by local stimulation by an electric current; (4) *the exhibition of quinine and some other drugs.* It has been shown by the oncometer of Roy (fig. 311), that the spleen undergoes rhythmical contractions and dilatations, due no doubt to the contraction and relaxation of the muscular tissue in its capsule and trabeculæ. It also shows the rhythmical alteration of the general blood pressure, but to a less extent than the kidney.



Fig. 235.



Fig. 236.

Fig. 235.—Transverse section of a lobule of an injected infantile thymus gland. *a*, Capsule of connective-tissue surrounding the lobule; *b*, membrane of the glandular vesicles; *c*, cavity of the lobule, from which the larger blood-vessels are seen to extend toward and ramify in the spheroidal masses of the lobule. × 30. (Kölliker.)

Fig. 236.—Thymus of a calf. *a*, Cortex of follicle; *b*, medulla; *c*, interfollicular tissue, magnified about twelve times. (Watney.)

**The Thymus.**—This gland must be looked upon as a temporary an, as it attains its greatest size soon after birth, and after the ond year gradually diminishes, until, in adult life, hardly a vestige aains. At its greatest development it is a long, narrow body, situated the front of the chest behind the sternum and partly in the lower part the neck. It is of a reddish or grayish color, distinctly lobulated.

*Structure.*—The gland is surrounded by a fibrous capsule, which sends processes, forming trabeculæ, which divide the glands into lobes, and ry the blood and lymph-vessels. The large trabeculæ branch into ll ones, which divide the lobes into lobules. The lobules are further divided into follicles by fine connective tissue. A follicle (fig. 232) een on section to be more or less polyhedral in shape, and consists of tical and medullary portions, both of which are composed of adenoid ue, but in the medullary portion the matrix is coarser, and is not so d up with lymphoid corpuscles as in the cortex. The adenoid tissue he cortex, and to a less marked extent that of the medulla, consists he two elements, one with small meshes formed of fine fibres with kened nodal points, and the other enclosed within the first, com- d of branched connective-tissue corpuscles (Watney). Scattered in adenoid tissue of the medulla are the *concentric corpuscles of Hassall*, ch are protoplasmic masses of various sizes, consisting of a nucleated ular centre, surrounded by flattened nucleated epithelial cells. he reticulum, especially of the medulla, are large transparent giant . In the thymus of the dog and of other animals are to be found , probably derived from the concentric corpuscles, some of which ined with ciliated epithelium, and others with short columnar cells. arteries radiate from the centre of the gland. Lymph sinuses may en occasionally surrounding a greater or smaller portion of the hery of the follicles (Klein). The nerves are very minute.



Fig. 237.



Fig. 238.

ig. 237.—From a horizontal section through superficial part of the thymus of a calf, slightly ified. Showing in the centre a follicle of polygonal shape with similarly shaped follicles d it. (Klein and Noble Smith.)

ig. 238.—The reticulum of the Thymus. *a*, Epithelial elements; *b*, corpuscles of Hassall. iat.)

From the thymus various substances may be extracted, many of the similar to those obtained from the spleen, *e.g.*, xanthin, hypoxanthi, and leucin, as well as certain proteids, especially nucleo-proteid (foun in all protoplasm), which on injection into the veins of an animal pro duces intra-vascular clotting.

*Function.*—Beard has recently concluded from some experiments o the smooth skate that the important function of the thymus is the form tion of the colorless corpuscles—that the thymus, in fact, is the par source from which all the colorless corpuscles are derived. The first developed from the thymus cells, and from them all the others arise.

Respecting the thymus gland in the hybernating animals, in which exists throughout life, as each successive period of hybernation approac the thymus greatly enlarges and becomes laden with fat, which accumul in it and in fat glands connected with it, in even larger proportions th it does in the ordinary seats of adipose tissue. Hence it appears serve for the storing up of materials which, being re-absorbed in inacti of the hybernating period, may maintain the respiration and the t perature of the body in the reduced state to which they fall during th time. It is also believed to be a source of the red blood-corpuscles, any rate in early life.

**The Pineal Gland.**—This gland, which is a small reddish body, placed beneath the back part of the corpus callosum, and rests upon th corpora quadrigemina.

*Structure.*—It contains a central cavity lined with ciliated epitheliu The gland substance proper is divisible into—(1.) An outer corti layer, analogous in structure to the anterior lobe of the pituitary body and (2.) An inner central layer, wholly nervous. The cortical lay consists of a number of close follicles, containing (*a*) cells of varia shape, rounded, elongated, or stellate; (*b*) fusiform cells. There is a present a gritty matter (*acervulus cerebri*), consisting of round partic aggregated into small masses. The central substance consists of wh and gray matter. The blood-vessels are small, and form a very delic capillary plexus.

The pineal gland is a vestigial structure, being the atrophied th eye which was situated in the median line. It is found in a better veloped condition in certain lizards, though it is functionless.

**The Coccygeal and Carotid Glands.**—These so-called glands situated, the one in front of the tip of the coccyx, and the other at t point of bifurcation of the common carotid artery on each side. Th are made up of a plexus of small arteries, are inclosed and supported a capsule of fibrous tissue, which contains connective-tissue corpusc The blood-vessels are surrounded by one or more layers of cells l secreting cells, which are said to be modified plasma cells of the conn tive tissue. The function of these bodies is unknown.

# CHAPTER IX.

## FOOD AND DIGESTION.

THE object of digestion is to bring the materials of the food into ch a condition that they may be taken up by the blood and lymphatic sels, and so rendered available for the wants of the system. It makes e foods soluble and diffusible, and also converts bodies already soluble d diffusible into forms which can be utilized, *e.g.*, cane sugar, al-ough soluble and diffusible, cannot be used by the body until it has en split into two molecules of monosaccharide. Very few of these aterials are fit for this purpose when taken into the body, and the ajority would therefore be to all intents and purposes quite useless less digested.

We find, then, that foods may be divided into classes corresponding sely to those employed to describe the chief substances of which the imal body consists. This classification may be recapitulated as fol-ws:—

RGANIC.

- I. Foods primarily containing **Nitrogenous substances**, consisting of *Proteids*, *e.g.*, albumen, casein, myosin, gluten, legumin and their allies; and *Albuminoids*, *e.g.*, gelatin, elastin, and chondrin.
- II. Food primarily containing **Non-Nitrogenous substances**, comprising:
  - (1.) *Amyloid or saccharine bodies*, chemically known as carbo-hydrates; *e.g.*, starches and sugars.
  - (2.) *Oils and fats.*—These substances contain carbon, hydrogen, and oxygen, but the oxygen is less in amount than in the amyloids and saccharine bodies.

ORGANIC.

- I. Foods which supply **Mineral and saline matter.**
- II. Liquid food containing chiefly **Water.**

Man requires that the chief part of his food should be *cooked.* Very organic substances can be properly digested without previous ex-re to heat and to other manipulations which constitute the process oking.

### Organic nitrogenous foods.

.—The *Flesh of Animals, e.g.*, of the ox (beef, veal), sheep (mutton, ), pig (pork, bacon, ham).

f these, beef is richest in nitrogenous matters, containing about 20 cent, whereas mutton contains about 18 per cent, veal 16.5, and

**pork, 10; beef is also firmer, more satisfying, and is supposed to more strengthening than mutton, whereas the latter is more digesti The flesh of young animals, such as lamb and veal, is less digestible less nutritious. Pork is comparatively indigestible, and contain large amount of fat.**

**Flesh contains:—(1) Nitrogenous bodies; chiefly *myosin*, and on more *globulins; serum-albumin, gelatin* (from the interstitial fib connective tissue); *elastin* (from the elastic tissue), as well as hæ *globin.* (2) Fatty matters, including *lecithin* and *cholesterin.* (3) tractive matters, some of which are agreeable to the palate, *e.g. osmaz* and others, which are weakly stimulating, *e.g., creatin.* Besides, th are *sarcolactic* and *inositic acids, taurin, xanthin,* and others. (4) Sa chiefly of potassium, calcium, and magnesium. (5) Water, the amo of which varies from 15 per cent in dried bacon to 39 in pork, 51 to in fat beef and mutton, to 72 per cent in lean beef and mutton. (6 certain amount of carbo-hydrate material is found in the flesh of so animals, in the form of *inosite, dextrin, grape sugar,* and (in yo animals) *glycogen.***

TABLE OF PERCENTAGE COMPOSITION OF BEEF, MUTTON, PORK, AND VEA (LETHEBY.)

| | Water. | Proteid. | Fats. | Salts. |
|---|---|---|---|---|
| *Beef.—Lean* | 72 | 19.3 | 3.6 | 5.1 |
| " *Fat* | 51 | 14.8 | 29.8 | 4.4 |
| *Mutton.—Lean* | 72 | 18.3 | 4.9 | 4.8 |
| " *Fat* | 53 | 12.4 | 31.1 | 3.5 |
| *Veal* | 63 | 16.5 | 15.8 | 4.7 |
| *Pork.—Fat* | 39 | 9.8 | 48.9 | 2.3 |

Together with the flesh of the above-mentioned animals, that of *deer, hare, rabbit,* and *birds,* constituting *venison, game,* and *poul* should be added as taking part in the supply of nitrogenous substan and also *fish*—salmon, eels, etc., and *shell-fish, e.g.,* lobster, crab, mus oysters, shrimps, scollops, cockles, etc.

TABLE OF PERCENTAGE COMPOSITION OF POULTRY AND FISH.—(LETHEBY

| | Water. | Proteid. | Fats. | Salts. |
|---|---|---|---|---|
| Poultry | 74 | 21 | 3.8 | 1.2 |

(Singularly devoid of fat, and is therefore generally eaten with b or pork.)

| | Water. | Proteid. | Fats. | Salts. |
|---|---|---|---|---|
| White Fish | 78 | 18.1 | 2.9 | 1. |
| Salmon | 77 | 16.1 | 5.5 | 1.4 |
| Eels (very rich in fat) | 75 | 9.9 | 13.8 | 1.3 |
| Oysters | 75.74 | 11.72 | 2.42 | 2.73 |

**(7.39 consist of non-nitrogenous matter and loss.) (Payen.)**

**Even now the list of fleshy foods is not complete, as the fle nearly all animals has been occasionally eaten, and we may pre**

hat except for difference of flavor, etc., the average composition is early the same in every case.

*b. Milk.**—Is intended as the entire food of young animals, and as uch contains, when pure, all the elements of a typical diet. (1) Albuminous substances in the form of *caseinogen,* and *serum* or *lact-albumin.* 2) Fats in the cream. (3) Carbo-hydrates in the form of *lactose* or milk ugar. (4) Salts, chiefly *calcium phosphate;* and (5) Water. From it we btain (*a*) *cheese,* which is the clotted caseinogen or casein precipitated ith more or less of fat according as the cheese is made of skim milk skim cheese), of fresh milk with its cream (Cheddar and Cheshire), or of resh milk plus cream (Stilton and double Gloucester). The precipiated casein is allowed to ripen, by which process some of the alumin is further split up, with formation of fat. (*β*) *Cream,* consists of he fatty globules encased in caseinogen and serum-albumin, and which eing of low specific gravity float to the surface. (*γ*) *Butter,* or the atty matter deprived of its proteid envelope by the process of churning. ) *Buttermilk,* or the fluid obtained from cream after butter has been ormed; very rich therefore in nitrogen. (*ε*) *Whey,* or the fluid which emains after the precipitation of casein; it contains sugar, salt, and a mall quantity of albumin.

ABLE OF COMPOSITION OF MILK, BUTTER-MILK, CREAM, AND CHEESE.—(LETHEBY AND PAYEN.)

| | Nitrogenous matters. | Fats. | Lactose. | Salts. | Water. |
|---|---|---|---|---|---|
| *Milk (Cow)* | 4.1 | 3.9 | 5.2 | .8 | 86 |
| *Buttermilk* | 4.1 | .7 | 6.4 | .8 | 88 |
| *Cream* | 2.7 | 26.7 | 2.8 | 1.8 | 66 |
| *Cheese.—Skim* | 44.8 | 6.3 | — | 4.9 | 44 |
| *Cheese.—Cheddar* | 28.4 | 31.1 | — | 4.5 | 36 |
| | | | Non-nitrogenous matter and loss. | | |
| *Cheese.—Neufchatel (Fresh).* | 8. | 40.71 | 36.58 | .51 | 36.58 |

*c. Eggs.*—The yolk and albumen of eggs are in the same relation as ood for the embryos of oviparous animals that milk is to the young of ammalia, and afford another example of the natural admixture of he various alimentary principles. The proteids of eggs are *egg-albumin* and globulins, of which the *vitellin* of the yolk is most important; *uclein* in combination with iron is also found. In addition to the hree common fats there is a yellow fatty pigment, *lutein* (lipochrome), small quantity of *grape sugar; lecithin,* and *cholesterin* and *inorganic alts,* chiefly potassium chloride and phosphates.

TABLE OF THE PERCENTAGE COMPOSITION OF FOWLS' EGGS.

| | Nitrogenous substances. | Fats. | Salts. | Water. |
|---|---|---|---|---|
| *White* | 20.4 | — | 1.6 | 78 |
| *Yolk* | 16. | 30.7 | 1.3 | 52 |

---

The details of the composition of milk have been discussed in the chapter on etion.

*d. Leguminous fruits* are used by vegetarians, as the chief source the nitrogen of the food. Those chiefly used are *peas, beans, lentil* etc., they contain a nitrogenous substance called *legumin*, allied albumen. They contain about 25.30 per cent of this nitrogenous body and twice as much nitrogen as wheat.

## Organic non-nitrogenous foods.

*I. Carbo-hydrates.—a. Bread,* made from the ground grain obtain from various so-called cereals, viz., wheat, rye, maize, barley, rice, etc., is the direct form in which the carbo-hydrate is supplied in ordinary diet. It contains starch, dextrin, and a little sugar. It al besides these, contains *gluten*, composed of several vegetable proteid and a small amount of fat.

TABLE OF PERCENTAGE COMPOSITION OF BREAD AND FLOUR.

| | Nitrogenous matters. | Carbo-hydrates. | Fats. | Salts. | Water. |
|---|---|---|---|---|---|
| *Bread* . . . . | 8.1 | 51. | 1.6 | 2.3 | 37 |
| *Flour* . . . . | 10.8 | 70.85 | 2. | 1.7 | 15 |

Various articles of course besides bread are made from flour, sago, macaroni, biscuits, etc. There is dextrine and a small amount dextrose in bread, particularly in the crust.

*b. Vegetables,* especially potatoes. They contain starch and sug In cabbage, turnips, etc., the salts of potassium are abundant.

*c. Fruits* contain sugar, and organic acids, tartaric, malic, citri and others.

*d. Sugar,* chiefly saccharose, used pure or in various sweetmeats.

*II. Oils and fats.*—The substances supplying the oils and fats of th food are chiefly *butter, bacon and lard* (pig's fat), *suet* (beef and mutt fat), and vegetable oils. These contain olein, stearin, and palmit Butter contains others in addition, while vegetable oils, as a rule, con tain no stearin.

## Mineral or Inorganic Foods.

*The salts of the food.*—Nearly all the foregoing substances in th preceding classes, contain a greater or less amount of the salts requir in food, but green vegetables and fruit supply certain salts, chie potassium, without which the normal health of the body cannot maintained.

Sodium chloride is an essential food; it is contained in nearly solids, but so much is required that it has also to be taken as a con ment. Potassium salts are supplied in muscle, nerve, in meats generall and in potatoes. Calcium salts are supplied in eggs, blood of meat, wh and vegetables. Iron is contained in hæmoglobin, in milk, eggs,

etables. It is derived in all cases, so it is supposed, by organic
npounds, into which it is built up during plant life, or during the life
other animals (hæmatogens).

## Liquid Foods.

Although water is essential to life, and from two to two and a half
ts a day must be consumed in addition to that taken in mixed with solid
d, yet it can hardly be regarded as a food. Of the non-alcoholic
stances which may be added to it for flavoring purposes, such as tea,
ee, cocoa, etc., the last can alone be considered to have a certain
l value, as it contains fats, albuminous material, and starch, the
er constituents of such substances being a volatile oil, an alkaloid
ine, caffeine), and tannic acid. Regarding the food value of alcoholic
erages, which has long been a subject of controversy, it is now gene-
y agreed that their food value is but slight. Beer, wines, and spirits
tain ethyl alcohol, the amount varying from 1–2 per cent in beer to
0 per cent in spirits.

**The effect of cooking.**—In general terms this may be said to
ler food more easily digestible, both directly and indirectly, through
eased palatability. Subjecting food to sufficiently high degrees of
also serves to kill parasites, such as trichinæ and the various tape-
ms, which may be present and alive in raw meats. In the case of
ts, various methods of cooking are employed, such as roasting, where
t in bulk is subjected, in an oven, to a high temperature, at first
a short time, and then to a somewhat lower temperature until the
ing is completed. This causes a coagulation of the outer layers of
min so that the juices of the meat are retained. The same end is
ined in boiling, by first immersing the meat in boiling water for a
and then continuing the cooking at a lower temperature. If a
h is to be made, the extractives may be obtained by heating in water
a long period at a temperature below the coagulation point of
min. Such a broth contains the flavoring extracts of the meat, but
f only slight nutritive value. For small pieces of meat, *broiling*
tically serves the same purpose as does roasting for larger pieces.
ing, as usually employed, is the least serviceable method of prepara-
, since the fat or other oily material used so permeates the food as to
ler it difficult of penetration by the digestive juices.

Upon vegetables, the cooking produces the necessary effect of render-
them softer, so that they can be more readily broken up in the mouth;
lso causes the starch grains to swell up and burst, and so aids the
stive fluids in penetrating into their substance. The albuminous

matters are coagulated, and the gummy, saccharine and saline matt are removed. The conversion of flour into dough is effected by mixing with water, and adding a little salt and a certain amount of yeast. Ye consists of the cells of an organized ferment (*Torula cerevisiæ*), and it i by the growth of this plant, changing by ferment action the sugar pr duced from the starch of the flour, that a quantity of carbonic acid g and alcohol is formed. By means of the former the *dough* rises. An other method of making dough consists in mixing the flour with wa containing a large quantity of carbonic acid gas in solution.

By the action of heat during baking (*d*) the dough continues to e pand, and the gluten being coagulated, the bread sets as a permane vesiculated mass.

## Digestion.

**The Enzymes,** or unorganized ferments, are the essential fact in digestion, and their predominant action is one of hydrolytic cleav that is, the substance acted upon takes up water and then splits into tw different substances, usually of the same class. Their chemical nat is as yet undetermined because of the inability of getting absolutely p specimens, but it is generally admitted that they contain nitrogen, a they are usually classed as proteids. Practically all are secreted in t glands as *zymogens*, which bear the same relation to enzymes as fibrino does to fibrin; they are transformed to enzymes by the proper stimulus b never exist as such in the glands. Some of them pass into the urine, b most are excreted with the fæces.

Each enzyme has a special point of temperature at which it acts be and any change in the temperature retards its action; the action is su pended at a definite point of low temperature, but the enzyme is not d stroyed by cold; the action is also suspended at higher temperatures, a at a still higher point the enzyme is destroyed. Some enzymes act o in an alkaline medium, being destroyed in an acid medium, and vice ver others act in either alkaline, neutral or acid media. Enzymes are hi dered in their action by the accumulation of the products of their activit Most of them cease acting altogether when these products reach a certa concentration, but will begin acting again on the removal of these pro ucts or if the mixture be simply diluted.

The quantity of the enzyme determines the rapidity of the action b not the amount; a small quantity will digest as much as a large quant but will take longer. The enzymes are not used up in the course of th ctivity, as far as can be seen, and do not seem to undergo any change in heir composition. They are classified either according to the chemical ature of their action, or according to the class of substances on which hey act; the former classification is more logical, but the latter is more onvenient and more generally used.

The food is first of all received into the *mouth*, and is subjected to the tion of the *teeth* and *tongue*, being at the same time mixed with the first f the digestive juices—the *saliva*. It is then swallowed, and, passing rough the *pharynx* and *œsophagus* into the *stomach*, is subjected to the tion of the *gastric juice*—the second digestive juice. Thence it passes to the *intestines*, where it meets with the *bile*, the *pancreatic juice*, and e *intestinal juices*, all of which exercise an influence upon the portion the food not already absorbed from the stomach. By this time most the food is digested, and the residue of undigested matter leaves the dy in the form of *fæces* by the external opening of the bowel.

**The Mouth** is the cavity contained between the jaws and inclosed the cheeks laterally, the lips anteriorly; behind, it opens into the arynx by the *fauces*, and is separated from the nasal cavity above, by e hard palate in front, and the soft palate behind, which forms its roof. e tongue forms the lower part or floor. In the jaws are contained the eth, and when the mouth is closed these form its anterior boundaries. e whole of the cavity of the mouth is lined with stratified epithelium, which the superficial layers are squamous. This epithelium is continus at the lips with that of the skin anteriorly, and posteriorly with at of the pharynx. The mucous membrane itself, varying in thickness various parts, and consisting of a fine areolar connective tissue, in ich is found adenoid tissue in considerable amount, is provided with merous small tubular glands lined with columnar epithelium, and sembling in structure the mucous salivary glands, to be presently scribed. Into the buccal cavity open the ducts of the salivary glands, ich are three in number on either side.

In the mouth, then, the food is subjected to the action of the teeth, is masticated, and is mixed with saliva. These processes of mastican and insalivation must be considered more in detail.

**Mastication.**—The act of chewing, or mastication, is performed by biting and grinding movement of the lower range of teeth against the per. The simultaneous movements of the tongue and cheeks assist tly by crushing the softer portions of the food against the hard palate d gums, and thus supplementing the action of the teeth, and partly by urning the morsels of food to the action of the teeth, again and again, they are squeezed out from between them, until they have been suffintly chewed.

*Muscles.*—The simple up and down, or *biting* movements of the lower jaw, are performed by the *temporal, masseter,* and *internal pterygoid* muscles, the action of which in closing the jaws alternates with that of the *digastric* and other muscles passing from the os hyoides to the lower jaw, which open them. The *grinding* or side to side movements of the lower jaw are performed mainly by the *external pterygoid* muscles, the muscle of one side acting alternately with the other. When both external pterygoids act together, the lower jaw is pulled directly forward, so that the lower incisor teeth are brought in front of the level of the upper.

*Temporo-maxillary Fibro-cartilage.*—The function of the inter-articulo-fibro-cartilage of the temporo-maxillary joint in mastication is to serve:—(1) As an elastic pad to distribute the pressure caused by the exceedingly powerful action of the masticatory muscles. (2) As a joint-surface or socket for the condyle of the lower jaw when the latter has been partially drawn forward out of the glenoid cavity of the temporal bone by the external pterygoid muscle, some of the fibres of the latter being attached to its front surface, and consequently drawing it forward with the condyle which moves on it.

*Nervous Mechanism.*—The act of mastication is partly voluntary and partly reflex and involuntary. The consideration of such nervous actions will come hereafter. It will suffice here to state that the afferent nerves chiefly concerned are the sensory branches of the fifth and the tenth or glosso-pharyngeal, and the efferent are the motor branches of the fifth and the twelfth (hypoglossal) cerebral nerves. The nerve-centre through which the reflex action occurs, and by which the movements of the various muscles are harmonized, is situated in the medulla oblongata. In so far as mastication is voluntary or mentally perceived, it is under the influence of the cerebral hemispheres.

**Insalivation.**—The act of mastication is much assisted by the saliv which is secreted by the salivary glands in largely increased amount du ing the process, and the intimate incorporation of which with the foo as it is being chewed, is termed *insalivation.*

## The Salivary Glands.

The glands which secrete the saliva in the human subject are the sal ivary glands proper, viz., the *parotid,* the *sub-maxillary,* and the *sub-li gual,* and numerous smaller bodies of similar structure, and with sep rate ducts, which are scattered thickly beneath the mucous membrane the lips, cheeks, soft palate, and root of the tongue.

*Structure.*—The salivary glands are compound tubular or tubulo-rac mose glands. They are made up of lobules. Each lobule consists of th ranchings of a subdivision of the main duct of the gland, which is genrally more or less convoluted toward its extremities, and sometimes, acording to some observers, sacculated or pouched. The convoluted or ouched portions form the *alveoli*, or proper secreting parts of the gland. The alveoli are composed of a basement membrane of flattened cells oined together by processes to produce a fenestrated membrane, the paces of which are occupied by a homogeneous ground-substance. With-n, upon this membrane, which forms the tube, the nucleated salivary ecreting cells, of cubical or columnar form, are arranged parallel to one nother enclosing a central canal. The granular appearance frequently een in the salivary cells is due to the numerous zymogen granules which ey contain. When isolated, the cells not infrequently are found to be ranched. Connecting the alveoli into lobules is a considerable amount



. 239.—Section of sub-maxillary gland of dog. Showing gland cells, *b*, and a duct, *a*, in section. (Kölliker.)

fibrous connective tissue, which contains both flattened and granular toplasmic cells, lymph corpuscles, and in some cases fat cells. The ules are connected to form larger lobules (lobes), in a similar manner. e alveoli pass into the intralobular ducts by a narrowed portion (inter-lary), lined with flattened epithelium with elongated nuclei. The in-calary ducts pass into the intralobular ducts by a narrowed neck, lined th cubical cells with small nuclei. The intralobular duct is larger in e, and is lined with large columnar nucleated cells, the parts of which, ard the lumen of the tube, present a fine longtitudinal striation, due the arrangement of the cell network. It is most marked in the sub-xillary gland. The intralobular ducts pass into the larger ducts, and se into the main duct of the gland. As these ducts become larger y acquire an outside coating of connective tissue, and later on some triped muscular fibres. The lining of the larger ducts consist of one more layers of columnar epithelium, the cells of which contain an racellular network of fibres arranged longitudinally.

*Varieties.*—Certain differences in the structure of salivary gland
be observed according as the glands secrete pure saliva, or saliva
with mucus, or pure mucus, and therefore the glands have been cla
as:—

(1) *True salivary glands* (called most unfortunately by some,
glands), *e.g.*, the parotid of man and other animals, and the sub
lary of the rabbit and guinea-pig (fig. 240). In this kind the al
lumen is small, and the cells lining the tubule are short granular c
nar cells, with nuclei presenting the intranuclear network. Durin
the cells become larger, highly granular, with obscured nuclei, a
lumen becomes smaller. During activity, and after stimulation
sympathetic, the cells become smaller and their contents more o
the granules first of all disappearing from the outer part of the cell



Fig. 240.—From a section through a true salivary gland. *a*, The gland alveoli, lined with
ous "salivary cells;" *b*, intralobular duct cut transversely. (Klein and Noble Smit

then being found only at the extreme inner part and contiguous
of the cell. The nuclei reappear, as does also the lumen.

(2) In the *true mucus-secreting glands*, as the sublingual of m
other animals, and in the submaxillary of the dog, the tubes are
contain a larger lumen, and also have larger cells lining them. Th
are of two kinds, (*a*) *mucous or central* cells, which are trans
columnar cells with irregular or flattened nuclei near the basemen
brane. The cell substance is made up of a fine network, which
resting state contains a transparent substance called *mucigen*,
which the cell does not stain well with logwood (fig. 241). Wh
gland is secreting, as well as on stimulation of the nerve, *mucigen*
verted into *mucin*, and the cells swell up, appear more transpare
stain deeply in logwood (fig. 242). After stimulation, the cells
smaller, more granular, and more easily stained, from having disc
their contents. The nuclei appear more distinct. (*b*) *Crescents*
*nuzzi*, sometimes called the *Demilunes of Heidenhain* (fig. 241),
are crescentic masses of granular parietal cells found here and th

ıe basement membrane and the central cells. The cells compos-
mass are small, and have a very dense reticulum, the nuclei are
l, and increase in size during secretion. In the mucous gland
e some large tubes, lined with large transparent central cells, and
esides a few granular parietal cells; other small tubes are lined
all granular parietal cells alone; and a third variety are lined
with each kind of cell.

In the *muco-salivary or mixed glands*, as the human submaxillary



Fig. 241.



Fig. 242.

1.—Section of the submaxillary gland of a dog, during rest. Most of the alveolar cells
and clear, being filled with the material for secretion (in this case, mucigen) which
ıeir protoplasm; some of the c-lls, however, are small and protoplasmic, forming the
een in most of the alveoli. (Ranvier.)
2.—Section of a similar gland after a period of activity. The mucigen has been dis-
om the mucin-secreting cells, which consequently appear shrunken and less clear.
lls and the alveoli are much smaller, and the protoplasm of the cells is more apparent.
nts of Gianuzzi are enlarged. (Ranvier.)
cent cells; *g*, mucus-secreting cells; *l*, lumen of alveolus.

art of the gland presents the structure of the mucous gland,
e remainder has that of the salivary glands proper.

*es and Blood-vessels.*—Nerves of large size are found in the sali-
nds; they are principally contained in the connective tissue of
oli, and in certain glands, especially in the dog, are provided
ıglia. Some nerves have special endings in Pacinian corpuscles,
pply the blood-vessels, and others penetrate the basement mem-
the alveoli and end upon, but not in, the salivary cells.

blood-vessels form a dense capillary network around the ducts of
li, being carried in by the fibrous trabeculæ between the alveoli,
also begin the lymphatics by lacunar spaces.

so-called mucous glands of the mouth and tongue present in some
structures of mucous, in others of serous glands.

## Saliva.

Saliva, as it commonly flows from the mouth, is the mixed secretion of the salivary glands proper and of the glands of the buccal mucous membrane and tongue; it is often mixed with air, which, being retained by its viscidity, makes it frothy. When obtained from the parotid ducts, and free from mucus, saliva is a transparent watery fluid, the specific gravity of which varies from 1004 to 1008, and in which, when examined with the microscope, are found floating a number of minute particles, derived from the secreting ducts and vesicles of the glands. In the impure or mixed saliva are found, besides these particles, numerous epithelial scales separated from the surface of the mucous membrane of the mouth and tongue, and the so-called salivary corpuscles, discharged probably from the mucous glands of the mouth and the tonsils, which, when the saliva is collected in a deep vessel, and left at rest, subside in the form of a white opaque matter, leaving the supernatant salivary fluid transparent and colorless, or with a pale bluish-gray tint. It also contains various kinds of micro-organisms (bacteria). In *reaction*, the saliva, when first secreted, appears to be always alkaline: the alkalinity is about equal to .08 or .10 per cent of sodium carbonate and is due to the presence of disodium hydrogen phosphate $Na_2HPO_4$. During fasting, the saliva, although secreted alkaline, shortly becomes neutral; especially when it is secreted slowly and is allowed to mix with the acid mucus of the mouth, by which its alkaline reaction is neutralized.

CHEMICAL COMPOSITION OF HUMAN SALIVA (HAMMERBACHER).

| | In 1,000 parts. |
|---|---|
| Water | 994.2 |
| Solids | 5.8 |
| Mucus and epithelium | 2.2 |
| Soluble organic matter (ptyalin) | 1.4 |
| Potassium sulpho-cyanide | 0.04 |
| Salts | 2.20 |

The mucin is the largest representative of the organic nitrogenou class of bodies in the saliva; it may be thrown down by addition of ace tic acid, if sodium chloride be absent. It gives the three chief protei reactions, and may easily be split up by the action of a dilute mineral aci into globulin and a carbohydrate whose exact character has not yet bee established, though it resembles a sugar in reducing copper sulphate solu tions.

The presence of *potassium sulphocyanide* (CNKS) in saliva, may b shown by the blood-red coloration which the fluid gives with a solutio of ferric chloride ($Fe_2Cl_6$), and which is bleached on the addition of solution of mercuric chloride ($HgCl_2$), but not by hydrochloric acid.

*Rate of Secretion and Quantity.*—The rate at which saliva is secreted is subject to considerable variation. When the tongue and muscles concerned in mastication are at rest, and the nerves of the mouth are subject to no unusual stimulus, the quantity secreted is not more than sufficient, with the mucus, to keep the mouth moist. During actual secretion the flow is much accelerated.

The *quantity* secreted in twenty-four hours varies, but is at least 2 pints (1 litre).

*Uses of Saliva.*—The purposes served by saliva are (*a*) mechanical and (*b*) chemical.

(*a*). *Mechanical.*—(1) It keeps the mouth in a due condition of moisture, facilitating the movements of the tongue in speaking, and the mastication of food. (2) It serves also in dissolving sapid substances, and rendering them capable of exciting the nerves of taste. But the principal mechanical purpose of the saliva is, (3) that by mixing with the food during mastication, it makes it a soft pulpy mass, such as may be easily swallowed. To this purpose the saliva is adapted both by quantity and quality. For, speaking generally, the quantity secreted during feeding is in direct proportion to the dryness and hardness of the food. The quality of saliva is equally adapted to this end. It is easy to see how much more readily it mixes with most kinds of food than water alone does; and the saliva from the parotid, labial, and other small glands, being more aqueous than the rest, is that which is chiefly *braided* and mixed with the food in mastication; while the more viscid mucous secretion of the submaxillary, palatine, and tonsillitic glands is spread over the surface of the softened mass, to enable it to slide more easily through the fauces and œsophagus.

(*b*) *Chemical.*—The chemical action which the saliva exerts upon the food in the mouth is to convert the starchy materials which it contains into soluble starch and then, partially, into sugar. This power the saliva owes to one of its constituents, *ptyalin*, which is one of the enzymes, or unorganized ferments. Certain investigators have of late asserted that saliva contains another enzyme, known as *glucase*, which has the power of splitting the disaccharides into monosaccharides, or maltose into dextrose. The action of this ferment is certainly very limited. The conversion of the starch under the influence of the ferment into sugar takes place in several stages, and in order to understand it, a knowledge of the structure and composition of starch granules is necessary. A starch granule consists of two parts: an envelope of *cellulose*, which does not give a blue color with iodine except on addition of sulphuric acid, and of *granulose*, which is contained within, and which gives a blue with iodine alone. Brücke states that a third body is contained in the granule, which gives a red with iodine, viz., *erythro-granulose*. On boiling, the granulose swells up, bursts the envelope, and the whole granule is more or less completely converted into a paste or gruel, which is called gelatinous starch.

When ptyalin acts upon boiled starch, it first changes the latter (by hydrolysis) into soluble starch, or *amidulin;* this is more limpid and more like a true solution, though it still gives the blue coloration on the addition of iodine. This stage is very brief, only thirty seconds being sometimes required in laboratory experiments, to render a stiff starch paste completely fluid when a few drops of saliva are added at body temperature. This rapidity of action is of great importance, as under proper conditions of mastication practically all the boiled starch of the food ought to enter the stomach as soluble starch. When the starch has not been previously boiled, the envelope of cellulose retards the action of the ptyalin to a very marked degree.

The further stages of hydrolytic cleavage result in the formation of variable mixture of maltose and iso-maltose with dextrins, but never re- sult (in laboratory experiments) in the complete conversion of the dex- trins into sugars. Gradually, as the starch is converted, the blue color- ation with iodine is replaced by a purplish-red and finally by a distinct red color: the latter color is produced by *erythro-dextrin* (so-called fro the color), a hypothetical substance which has never been isolated. I the later stages no coloration is obtained with iodine, and for this reason the dextrins formed are known as *achroö-dextrins;* there are probably several of these, but they have not yet been sufficiently isolated. As sugar appears very early in the process, even at the stage of erythro-dex- trin, and gradually increases in amount, it is generally concluded that maltose is formed early in the decomposition of the starch molecule: the process is usually represented schematically as follows:



The sugars formed are maltose ($C_{12}H_{22}O_{11}$) and a closely allied sug known as iso-maltose. A small percentage of dextrose has been found by some observers, and this may be due to the action of *glucase.* Maltose i allied to saccharose or cane-sugar more nearly than to glucose; it is crys- talline; its solution has the property of polarizing light to the right to greater degree than solutions of glucose (3 to 1); it is not so sweet, an reduces copper sulphate less easily. It can be converted into glucose boiling with dilute acids.

cording to Brown and Heron the reactions may be represented thus:—
olecule of gelatinous starch is converted by the action of an amylolytic ferment into *n* molecules of soluble starch.
molecule of soluble starch $= 10\,(C_{12}H_{20}O_{10}) + 8\,(H_2O)$, which is further converted by the ferment into
1. Erythro-dextrin (giving red with iodine) + Maltose.
$9\,(C_{12}H_{20}O_{10})$ $(C_{12}H_{22}O_{11})$
then into 2. Erythro-dextrin (giving yellow with iodine) + Maltose.
$8\,(C_{12}H_{20}O_{10})$ $2\,(C_{12}H_{22}O_{11})$
next into 3. Achroö-dextrin + Maltose.
$7\,(C_{12}H_{20}O_{10})$ $3\,(C_{12}H_{22}O_{11})$
so on; the resultant being:—

$$\underset{\text{Soluble starch}}{10\,(C_{12}H_{20}O_{10})} + \underset{\text{Water}}{8\,(H_2O)} = \underset{\text{Maltose}}{8\,(C_{12}H_{22}O_{11})} + \underset{\text{Achroö-dextrin.}}{2\,(C_{12}H_{20}O_{10})}$$

any observers, however, deny that the maltose simultaneously presith erythro-dextrin is actually split off from the starch molecule in ormation of erythro-dextrin; they claim that it is rather the product ore advanced hydrolysis in other starch molecules, and point out that ch a chemical reaction of considerable time duration, it is improbable all the starch molecules are attacked at the same rate or are, at any moment, equally advanced in cleavage. Their theory is that a of more and more simple dextrins are formed which give rise finally disaccharides.

*est for Sugar.*—In such an experiment the presence of sugar is at discovered by the application of Trommer's test, which consists in ddition of a drop or two of a solution of copper sulphate, followed larger quantity of caustic potash. When the liquid is boiled, an e-red precipitate of copper suboxide indicates the presence of sugar. *he action of saliva on starch is facilitated by:* (*a*) Moderate heat, 37.8° C. (100° F.). (*b*) A neutral medium. (*c*) Removal of the ed material from time to time. Its action *is retarded by:* (*a*) Cold; perature of 0° C. (32° F.) stops it for a time, but does not destroy it, as a high temperature above 60° C. (140° F.) destroys it. (*b*) Acids ong alkalies either delay or stop the action altogether; the action intly alkaline medium is nearly as vigorous as in a neutral medium. esence of too great a percentage of the changed material. Ptyalin, t it converts starch into sugar, is an *amylolytic* or diastasic ferment. arch appears to be the only principle of food upon which saliva acts cally: the secretion has no apparent influence on any of the other y principles, such as sugar, gum, cellulose, or on fat, and seems to ally destitute of power over albuminous and gelatinous substances. liva from the parotid is less viscid; less alkaline, the first few drops rged in secretion being even acid in reaction; clearer, although it ecome cloudy on standing from the precipitation of calcium carbonom escape of carbon dioxide; and more watery than that from the xillary. It has moreover a less powerful action on starch. Subl saliva is the most viscid, and contains more solids than either of her two, but has little diastasic action.

The salivary glands of children do not become functionally ac the age of 4 to 6 months, and hence the bad effect of feeding them this age on starchy food, corn-flour, etc., which they are unable t soluble and capable of absorption. The salivas of the dog, cat, be pig are almost inactive, whereas that of monkeys, rabbits, mice, sq and guinea-pigs, are strongly diastasic.

*Salivary Digestion in the Stomach.*—Under proper conditions s digestion may continue for some time after the food has entered th ach. In laboratory experiments it is found that while the add even .05 per cent. of hydrochloric acid will inhibit the action of pty a solution of starch, if any proteids be present in the solution more acid must be added before the action of the ptyalin is s The explanation of the latter fact is that the acid unites with the p in some loose chemical combination, forming "combined acid" wh little effect, comparatively, on ptyalin. This "combined acid" red color with litmus, but is distinguished from free acid by g brownish instead of a bluish color with Congo red.

When food enters an empty stomach, as happens at the begin a meal, the acid first secreted combines with the proteid food-stu so does not affect the ptyalin. It usually requires at least 15 to utes before the acid is secreted in sufficient quantity to be in ex free acid, of the amount which can combine with the proteids, and this time salivary digestion may continue. Of course the action alin on food taken later in a meal is promptly stopped when it rea stomach because of the presence of free acid.

## The Nervous Mechanism of the Secretion of Saliv

The secretion of saliva is under the control of the nervous syst is a reflex action. Under ordinary conditions it is excited by the lation of the peripheral branches of two nerves, viz., the *gusta lingual* branch of the inferior maxillary division of the fifth ner the *glosso-pharyngeal* part of the eighth pair of nerves, which are uted to the mucous membrane of the tongue and pharynx con The stimulation occurs on the introduction of sapid substances i mouth, and the secretion is brought about in the following way: the terminations of the above-mentioned sensory nerves distributed mucous membrane an impression is conveyed upward (afferent) special nerve centre situated in the medulla-oblongata which c the process, and by it is reflected to certain nerves supplied salivary glands, which will be presently indicated. In other the centre, stimulated to action by the sensory impressions to it, sends out impulses along efferent or secretory nerves s to the salivary glands, which cause the saliva to be secreted by a arged from the gland cells. Other stimuli, however, besides that of e food, and other sensory nerves besides those mentioned, may proce reflexly the same effects. For example, saliva may be caused to w by irritation of the mucous membrane of the mouth with mechanil, chemical, electrical, or thermal stimuli, also by the irritation of the ucous membrane of the stomach in some way, as in nausea, which ecedes vomiting, when some of the peripheral fibres of the *vagi* are itated. Stimulation of the *olfactory* nerves by smell of food, of the *ic* nerves by the sight of it, and of the *auditory* nerves by the sounds ich are known by experience to accompany the preparation of a meal, y also, in the hungry, stimulate the nerve centre to action. In addin to these, as a secretion of saliva follows the movement of the muss of mastication, it may be assumed that this movement stimulates the reting nerve fibres of the gland, direct or reflexly. From the fact t the flow of saliva may be increased or diminished by mental emons, it is evident that impressions from the cerebrum also are capable timulating the centre to action or of inhibiting its action.

Salivary secretion may also be excited by direct stimulation of the tre in the medulla.

*On the Submaxillary Gland.*—The submaxillary gland has been the nd chiefly employed for the purpose of experimentally demonstrating influence of the nervous system upon the secretion of saliva, because he comparative facility with which, with its blood-vessels and nerves, ay be exposed to view in the dog, rabbit, and other animals. The f nerves supplied to the gland are (1) the *chorda tympani*, a branch n off from the *facial* (or *portio dura* of the seventh pair of nerves), he canal through which it passes in the temporal bone, in its passage n the interior of the skull to the face; and (2) branches of the *symetic* nerve from the plexus around the facial artery and its branches he gland. The chorda (fig. 243, *ch. t.*), after quitting the temporal e, passes downward and forward, under cover of the external pterymuscle, and joins at an acute angle the lingual or gustatory nerve, eeds with it for a short distance, and then passes along the submaxy gland duct (fig. 243, *sm. d.*), to which it is distributed, giving ches to the submaxillary ganglion (fig. 243, *sm. gl.*), and sending others rminate in the superficial muscles of the tongue. It consists of fine ullated fibres which lose their medulla in the gland. If this nerve xposed and divided anywhere in its course from its exit from the skull he gland, no immediate result will follow, nor will stimulation er of the lingual or of the glosso-pharyngeal produce a flow of saliva. if the peripheral end of the divided nerve be stimulated, an abundant etion of saliva ensues, and the blood supply is enormously increased, arteries being dilated. The veins even pulsate, and the blood coned within them is more arterial than venous in character.

When, on the other hand, the stimulus is applied to the *sympat* filaments (mere division producing no apparent effect), the arteries tract, and the blood stream is in consequence much diminished: from the veins, when opened, there escapes only a sluggish strea dark blood. The saliva, instead of being abundant and watery, bec scanty and tenacious. If both chorda tympani and sympathetic bran be divided, the gland, released from nervous control, may secrete tinuously and abundantly (*paralytic* secretion).

The abundant secretion of saliva, which follows stimulation of chorda tympani, is not merely the result of a filtration of fluid



**Fig. 243.**—Diagrammatic representation of the sub-maxillary gland of the dog with its nerv blood-vessels. (This is not intended to illustrate the exact anatomical relations of the several tures.) *sm. gld.*, the sub-maxillary gland into the duct (*sm. d.*) of which a canula has bee The sublingual gland and duct are not shown. *n. l.*, *n. l'.*, the lingual or gustatory nerve ; *ch. t'.*, the chorda tympani proceeding from the facial nerve, becoming conjoined with the li at *n. l'.*, and afterward diverging and passing to the gland along the duct ; *sm. gl.*, sub-max ganglion with its roots; *n. l.*, the lingual nerve proceeding to the tongue ; *a. car.*, the carotid a two branches of which, *a. sm. a.* and *r. sm. p.*, pass to the anterior and posterior parts of the g *v. sm.*, the anterior and posterior veins from the gland ending in *v. j.*, the jugular vein ; *v. sym* conjoined vagus and sympathetic trunks ; *gl. cer. s.*, the superior-cervical ganglion, two bra of which forming a plexus, *a. f.*, over the facial artery are distributed (*n. sym. sm.*) along th glandular arteries to the anterior and posterior portion of the gland. The arrows indicat direction taken by the nervous impulses ; during reflex stimulations of the gland they ascend brain by the lingual and descend by the chorda tympani. (M. Foster.)

the blood-vessels, in consequence of the largely increased circula through them. This is proved by the fact that, when the main du obstructed, the pressure within may considerably exceed the blood- sure in the arteries, and also that when into the veins of the an experimented upon some *atropin* has been previously injected, stim tion of the peripheral end of the divided chorda produces all the va lar effects as before, without any secretion of saliva accompanying t Again, if an animal's head be cut off, and the chorda be rapidly exp and stimulated with an interrupted current, a secretion of saliva ensue a short time, although the blood supply is necessarily absent. T xperiments serve to prove that the chorda contains two sets of nerve bres, one set (*vaso-dilator*) which, when stimulated, act upon a local aso-motor centre for regulating the blood supply, inhibiting its action, nd causing the vessels to dilate, and so producing an increased supply of lood to the gland; while another set, which are paralyzed by injection f atropin, directly stimulate the cells themselves to activity, whereby hey secrete and discharge the constituents of the saliva which they roduce. These latter fibres very possibly terminate on the salivary cells hemselves. If, on the other hand, the sympathetic fibres be divided, timulation of the tongue by sapid substances, or of the trunk of the ngual, or of the glosso-pharyngeal, continues to produce a flow of saliva. rom these experiments it is evident that the chorda tympani nerve is he principal nerve through which efferent impulses proceed from the entre to excite the secretion of this gland.

The sympathetic nerve also contains two sets of fibres, vaso-constrictor nd secretory. But the flow of saliva, upon stimulating the sympathetic, scanty, and the saliva itself viscid. At the same time the vessels of he gland are constricted. The secretory fibres may be paralyzed by the dministration of atropine.

*On the Parotid Gland.*—The nerves which influence secretion in the arotid gland are branches of the facial (lesser superficial petrosal) and the sympathetic. The former nerve, after passing through the otic nglion, joins the auriculo-temporal branch of the fifth cerebral nerve, d, with it, is distributed to the gland. The nerves by which the imulus ordinarily exciting secretion is conveyed to the medulla ob- ngata, are, as in the case of the submaxillary gland, the fifth, and the osso-pharyngeal. The pneumogastric nerves convey a further stimu- s to the secretion of saliva, when food has entered the stomach; the rve centre is the same as in the case of the submaxillary gland.

*Changes in the Gland Cells.*—The method by which the salivary cells oduce the secretion of saliva appears to be divided into two stages, ich differ somewhat according to the class to which the gland belongs, ., whether to (1) the true salivary, or (2) to the mucous type. In the rmer case, it has been noticed, as has been already described, that ring the rest which follows an active secretion the lumen of the alveo- becomes smaller, the gland cells larger and very granular. During retion the alveoli and their cells become smaller, and the granular pearance in the latter to a considerable extent disappears, and at the d of secretion the granules are confined to the inner part of the cell rest to the lumen, which is now quite distinct (fig. 244).

It is supposed from these appearances that the first stage in the act secretion consists in the protoplasm of the salivary cell taking up m the lymph certain materials from which it manufactures the elements of its own secretion, and which are stored up in the form granules in the cell during rest, the second stage consisting of the actu discharge of these granules, with or without previous change. T granules are zymogen granules, and represent the chief substance of t salivary secretion, *i.e.*, ptyalin. In the case of the submaxillary gland the dog, at any rate, the sympathetic nerve-fibres appear to have to with the first stage of the process, and when stimulated the protoplasm extremely active in manufacturing the granules, whereas the chor tympani is concerned in the production of the second act, the actual di charge of the materials of secretion, together with a considerable amou of fluid, the latter being an actual secretion by the protoplasm, as ceases to occur when atropin has been subcutaneously injected.

In the mucus-secreting gland, the changes in the cells during secr tion have been already spoken of. They consist in the gradual secr



Fig. 244.—Alveoli of true salivary gland. A, at rest; B, in the first stage of secretion; C, after p longed secretion. (Langley.)

tion by the protoplasm of the cell of a substance called *mucigen*, whi is converted into *mucin*, and discharged on secretion into the canal the alveoli. The mucigen is, for the most part, collected into the inn part of the cells during rest, pressing the nucleus and the small portic of the protoplasm which remains, against the limiting membrane of t alveoli.

The process of secretion in the salivary glands is identical with th of glands in general; the cells which line the ultimate branches of th ducts being the agents by which the special constituents of the sali are formed. The materials which they have incorporated with them selves are almost at once given up again, in the form of a fluid (secr tion), which escapes from the ducts of the gland; and the cells, them selves, undergo disintegration—again to be renewed, in the intervals the active exercise of the functions. The source whence the cells obtai the materials of their secretion is the blood, or, to speak more accu rately, the plasma, which is filtered off from the circulating blood int the interstices of the glands as of all living textures.

## THE TONGUE.

*Structure.*—The tongue is a muscular organ covered by mucous membrane. The muscles, which form the greater part of the substance of the tongue (*intrinsic* muscles) are termed *linguales;* and by these,



Fig. 245.—Papillar surface of the tongue, with the fauces and tonsils. 1, 1, circumvallate pa llæ, in front of 2, the foramen cæcum; 3, fungiform papillæ ; 4, filiform and conical papillæ ; 5, ansverse and oblique rugæ ; 6, mucous glands at the base of the tongue and in the fauces; 7, tonsils; part of the epiglottis ; 9, median glosso-epiglottidean fold (frænum epiglottidis). (From Sappey.)

hich are attached to the mucous membrane chiefly, its smaller and ore delicate movements are chiefly performed.

By other muscles (*extrinsic* muscles), as the genio-hyoglossus, the yloglossus, etc., the tongue is fixed to surrounding parts, and by this oup of muscles its larger movements are performed.

The mucous membrane of the tongue resembles other mucous membranes in essential points of structure, but contains *papillæ*, more o less peculiar to itself; peculiar, however, in details of structure and ar rangement, not in their nature. The tongue is beset with numerou mucous follicles and glands.

The larger *papillæ* of the tongue are thickly set over the anteri two-thirds of its upper surface, or *dorsum* (fig. 245), and give to it i characteristic roughness. In carnivorous animals, especially those the cat tribe, the papillæ attain a large size, and are developed in sharp recurved horny spines. Such papil cannot be regarded as sensitive, but they able the tongue to play the part of a m efficient rasp, as in scraping bones, or o comb in cleaning fur. Their greater pro inence than those of the skin is due to th interspaces not being filled up with epit lium, as the interspaces of the papillæ the skin are. The papillæ of the ton present several diversities of form;



Fig. 246.



Fig. 247.

Fig. 246.—Section of a mucous gland from the tongue. A, opening of the duct on the fre face; C, basement membrane with nuclei; B, flattened epithelial cells lining duct. The duct di into several branches, which are convoluted and end blindly, being lined throughout by colu epithelium. D, lumen of one of the tubuli of the gland. × 90. (Klein and Noble Smith.)

Fig. 247.—Vertical section of a circumvallate papilla of the calf. 1 and 3, epithelial l covering it; 2, taste goblets; 4 and 4′, duct of serous gland opening out into the pit in which p is situated; 5 and 6, nerves ramifying within the papilla. (Engelmann.)

three principal varieties, differing both in seat and general charact may usually be distinguished, namely, the (1) *circumvallate*, the *fungiform*, and the (3) *filiform* papillæ. Essentially these have al them the same structure, that is to say, they are all formed by a pro tion of the mucous membrane, and contain special branches of bl vessels and nerves. In details of structure, however, they differ con erably one from another.

The surface of each kind is studded by minute conical processe mucous membrane, which thus form secondary papillæ.

(1.) *Circumvallate.*—These papillæ (fig. 247), eight or ten in n are situate in two V-shaped lines at the base of the tongue (1, 1, 45). They are circular elevations from $\frac{1}{20}$th to $\frac{1}{12}$th of an inch , (1 to 2 mm.), each with a central depression, and surrounded by cular fissure, at the outside of which again is a slightly elevated both the central elevation and the ring being formed of close-set le papillæ.

.) *Fungiform.*—The fungiform papillæ (3, fig. 245) are scattered y over the sides and tip, and sparingly over the middle of the dor- of the tongue; their name is derived from their being usually nar- r at their base than at their summit. They also consist of groups mple papillæ (A. fig. 248), each of which contains in its interior a of capillary blood-vessels (B.), and a nerve-fibre.

.) *Conical or Filiform.*—These, which are the most abundant pa- , are scattered over the whole surface of the tongue, but especially



. 248.—Surface and section of the fungiform papillæ. A, the surface of a fungiform papilla, y denuded of its epithelium; *p*, secondary papillæ; *e*, epithelium. B, section of a fungiform with the blood-vessels injected ; *a*, artery ; *v*, vein; *c*, capillary loops of similar papillæ in hboring structure of the tongue; *d*, capillary loops of the secondary papillæ; *e*, epithelium. Kölliker, after Todd and Bowman.)

he middle of the dorsum. They vary in shape somewhat, but for ost part are conical or filiform, and covered by a thick layer of rmis, which is arranged over them, either in an imbricated manner, prolonged from their surface in the form of fine stiff projections, ike in appearance, and in some instances in structure also (fig. From their peculiar structure, it seems likely that these papillæ mechanical function, or one allied to that of touch rather than te; the latter sense being probably seated especially in the other arieties of papillæ, the *circumvallate* and the *fungiform.*

e *epithelium* of the tongue is stratified with the upper layers of uamous kind. It covers every part of the surface; but over the form papillæ forms a thinner layer than elsewhere. The epithelium ng the filiform papillæ is extremely dense and thick, and, as before oned, projects from their sides and summits in the form of long, air-like processes (fig. 249). Many of these processes bear a close blance to hairs. Blood-vessels and nerves are supplied freely to

the papillæ. The nerves in the fungiform and circumvallate p
form a kind of plexus, spreading out brushwise (fig. 249), but the
mode of termination of the nerve-filaments is not certainly know

In the circumvallate papillæ of the tongue of man peculiar
tures known as *gustatory buds* or *taste goblets*, have been disc
They are of an oval shape, and consist of a number of closely p
very narrow and fusifor
(*gustatory cells*). This
core of gustatory cells
closed in a single la
broader fusiform cells
*ing cells*). The gustato
terminate in fine spi
unlike cilia, which pro
the free surface (fig. 25

These bodies also occ
by side in considerable



Fig. 249.



Fig. 250.

Fig. 249.—Two filiform papillæ, one with epithelium, the other without. $\frac{35}{1}$.—*d*, the su
the papillæ dividing at their upper extremities into secondary papillæ; *a*, artery, an
dividing into capillary loops; *e*, epithelial covering, laminated between the papillæ, but
into hair-like processes, *f*, from the extremities of the secondary papillæ. (From Köll
Todd and Bowman.)

Fig. 250.—Taste-goblet from dog's epiglottis (laryngeal surface near the base), precis
in structure to those found in the tongue. *a*, depression in epithelium over goblet; below
are seen the fine hair-like processes in which the cells terminate; *c*, two nuclei of the ax
tory) cells. The more superficial nuclei belong to the superficial (incasing) cells; the c
lines indicate the fusiform shape of the incasing cells. × 400. (Schofield.)

bers in the epithelium of the papilla foliata, which is situated n
root of the tongue in the rabbit, and also in man. Similar taste-
have been observed on the posterior (laryngeal) surface of the epi

## THE PHARYNX.

The portion of the alimentary canal which intervenes betw
mouth and the œsophagus is termed the *Pharynx*. It will suff
to mention that it is constructed of a series of three muscles wi

ted fibres (*constrictors*), which are covered by a thin fascia externally, nd are lined internally by a strong fascia (pharyngeal aponeurosis), on he inner aspect of which is areolar (submucous) tissue and mucous membrane, continuous with that of the mouth, and, as regards the part oncerned in swallowing, is identical with it in general structure. The pithelium of this part of the pharynx, like that of the mouth, is stratiied and squamous.

The pharynx is well supplied with mucous glands (fig. 246).

Between the anterior and posterior arches of the soft palate are situated the *Tonsils,* one on each side. A tonsil consists of an elevation f the mucous membrane representing 12 to 15 orifices, which lead into



Fig. 251.



Fig. 252.

Fig. 251.—Lingual follicle or crypt. *a*, involution of mucous membrane with its papillæ; *b*, mphoid tissues, with several lymphoid sacs. (Frey.)

Fig. 252.—Vertical section through a crypt of the human tonsil. 1, entrance to the crypt; 2 and he framework or adenoid tissue; 4, the inclosing fibrous tissue; *a* and *b*, lymphatic follicles; 5 d 6, blood-vessels. (Stöhr.)

ypts or recesses, in the walls of which are placed nodules of adenoid lymphoid tissue (fig. 252). These nodules are enveloped in a less nse adenoid tissue which reaches the mucous surface. The surface covered with stratified squamous epithelium, and the subepithelial or ucous membrane proper may present rudimentary papillæ formed of enoid tissue. The tonsil is bounded by a fibrous capsule (fig. 252, 4). to the crypts open the ducts of numerous mucous glands.

The viscid secretion which exudes from the tonsils serves to lubrie the bolus of food as it passes them in the second part of the act of glutition.

## THE ŒSOPHAGUS OR GULLET.

The Œsophagus or Gullet, the narrowest portion of the alimentary canal, is a muscular and mucous tube, nine or ten inches in length, which extends from the lower end of the pharynx to the cardiac orifice of the stomach.

*Structure.*—The œsophagus is made up of three coats—viz., the outer, *muscular;* the middle, *submucous;* and the inner, *mucous.* The *muscular* coat is covered externally by a varying amount of loose fibrous tissue. It is composed of two layers of fibres, the outer being arranged longitudinally, and the inner circularly. At the upper part of the œsophagus this coat is made up principally of striated muscle fibres, as they are continuous with the constrictor muscles of the pharynx; but lower down the unstriated fibres become more and more numerous, and toward the end of the tube form the entire coat. The muscular coat is connected with the mucous coat by a more or less developed layer of areolar tissue, which forms the *submucous* coat (fig. 253, *f*), in which is contained in the lower half or third of the tube many mucous glands, ducts of which, passing through the mucous membrane, open on its s face. Separating this coat from the mucous membrane proper is a w



Fig. 253.—Transverse section of the human œsophagus. *a*, Fibrous covering; *b*, longitudinal muscular fibres; *c*, transverse muscular fibres; *d*, areolor or submucous coat; *e*, muscularis mucosæ; *f*, mucous membrane, with part of a lymphoid nodule; *g*, stratified epithelial lining; *h*, mucous gland; *i*, gland duct; *m'*, striated muscle fibres. (V. Horsley.)

eveloped layer of longitudinal, unstriated muscle, called the *muscularis* *ucosæ*. The mucous membrane is composed of a closely felted mesh-ork of fine connective tissue, which, toward the surface, is elevated into udimentary papillæ. It is covered with a stratified epithelium, of hich the most superficial layers are squamous. The epithelium is ar-nged upon a basement membrane.

In newly-born children the mucous membrane exhibits, in many rts, the structure of lymphoid tissue (Klein).

Blood- and lymph-vessels, and nerves, are distributed in the walls of e œsophagus. Between the outer and inner layers of the muscular at, *nerve-ganglia* of Auerbach are also found (fig. 259).

## DEGLUTITION.

When properly masticated, the food is transmitted in successive por-ns to the stomach by the act of deglutition or swallowing. The fol-ing account of deglutition is based upon the researches of Kronecker d Meltzer, whose experiments seem to disprove the earlier theory of gendie:

The mouth is closed, and the food is rolled after thorough mixing h the saliva into a bolus on the dorsum of the tongue. The tip of tongue is pressed upward and forward against the hard palate, thus tting off the anterior part of the mouth cavity. The mylo-hyoid scles then suddenly contract, the bolus of food is put under great ssure, and shot backward and downward through the pharynx and phagus to the cardiac orifice of the stomach. Coincidently with the traction of the mylo-hyoid muscles, the hyoglossi are thrown into ion, drawing the tongue backward and downward, not only increasing pressure upon the food, but forcing the epiglottis over the glottis thus closing the larynx. The interval of time between the com-ncement of the act of deglutition and the arrival of the food at the diac orifice of the stomach is not more than 0.1 second. Usually the d remains at the cardiac orifice without entering the stomach until first part of the act of swallowing is reinforced by the subsequent traction of the constrictors of the pharynx and the passage of a peri-ltic wave down the œsophagus. This wave, reaching the cardiac ori- about 6 seconds after the commencement of the act of deglutition, ces the food into the stomach, the sphincter having previously re-ed. In some cases, however, the food is not stopped at the cardiac fice, but is sent through the relaxed sphincter by the original force of mylo-hyoid contraction.

In man the œsophagus contracts in three separate segments—the segment lying in the neck and being about 6 centimetres long, the second being the next 10 centimetres of the tube, and the third the remaining portion to the stomach.

The act of swallowing consists, then, of the contraction in sequenc of five muscle-segments: the mylo-hyoids, the constrictors of the pharynx, and the three segments of the œsophagus. The computed time o contraction is as follows:

| | Second |
|---|---|
| Contraction of mylo-hyoids and constrictors of the pharynx | 0 |
| Contraction of the first part of the œsophagus | 0 |
| Contraction of the second part of the œsophagus | 1 |
| Contraction of the third part of the œsophagus | 3 |
| | 6 |

If a second attempt at swallowing be made before the first has bee completed (that is, before 6 seconds have elapsed), the remaining portio of the first act is inhibited, and the contraction wave reaches the stomac 6 seconds after the commencement of the second act.

In addition to the above, the following facts must be noted:

During the act of deglutition the posterior nares are closed throug the action of the levator palati and tensor palati muscles, which rais the velum; the palato-pharyngei, drawing the posterior pillars of th fauces together; and the azygos uvulæ, which raises the uvula—thu forming a complete curtain. Otherwise the food would pass into th nose, as happens in the case of cleft palate. At the same time the larynx is closed by the adductor muscles of the vocal cords and the descen of the epiglottis, the larynx being drawn upward as a whole through th action of the mylo-hyoid, genio-hyoid, thyro-hyoid, and digastric muscles. The presence of the epiglottis is not necessary for the completion of the act of deglutition.

*Nervous Mechanism.*—The nerves engaged in the reflex act of deglutition are:—*sensory*, branches of the fifth cerebral supplying the soft palate; glosso-pharyngeal, supplying the tongue and pharynx; the superior laryngeal branch of the vagus, supplying the epiglottis and the glottis while the *motor* fibres concerned are:—branches of the fifth, supplyin part of the digastric and mylo-hyoid muscles, and the muscles of mastication; the facial, supplying the levator palati; the glosso-pharyngeal supplying the muscles of the pharynx; the vagus, supplying the muscle of the larynx through the inferior laryngeal branch, and the hypoglossal, the muscles of the tongue. The nerve-centre by which the muscle are harmonized in their action, is situate in the medulla oblongata. I the movements of the œsophagus, the ganglia contained in its wall with the pneumo-gastrics, are the nerve-structures chiefly concerned.

It is important to note that the swallowing both of food and drink a muscular act, and can, therefore, take place in opposition to the forc of gravity. Thus, horses and many other animals habitually drink u hill, and the same feat can be performed by jugglers.

## The Stomach.

an and those Mammalia which are provided with a single stom-
onsists of a dilatation of the alimentary canal placed between
inuous with the œsophagus,
nters its larger or cardiac
he one hand, and the small
, which commences at its
l end or pylorus, on the
It varies in shape and size
g to its state of distention.

*ture.*—The stomach is com-
four coats, called respec-
1) an external or peritoneal,
cular, (3) submucous, and
ous coat; with blood-vessels,
ics, and nerves distributed
etween them.

The *peritoneal* coat has the
of serous membranes in
as has been described. (2)
*cular* coat consists of three
layers or sets of fibre, which,
g to their several directions,
d the longitudinal, circular,
que. The *longitudinal* set
most superficial: they are
us with the longitudinal
the œsophagus and spread
diverging manner over the
end and sides of the stom-
hey extend as far as the py-
eing especially distinct at
r or upper curvature of the
, along which they pass in
trong bands. The next set
*ircular* or *transverse* fibres,
ore or less completely en-
parts of the stomach; they
abundant at the middle and in the pyloric portion of the or-
form the chief part of the thick projecting ring of the pylorus.
res are not simple circles, but form double or figure-of-8 loops,
s intersecting very obliquely. The next, and consequently



Fig. 254.—From a vertical section through the mucous membrane of the cardiac end of stomach. Two peptic glands are shown with a duct common to both, one gland only in part. *a*, duct with columnar epithelium becoming shorter as the cells are traced downward; *n*, neck of gland tubes, with central and parietal or so-called peptic cells; *b*, fundus with curved cæcal extremity—the parietal cells are not so numerous here. × 400. (Klein and Noble Smith.)

deepest set of fibres, are the *oblique*, continuous with the circula
cular fibres of the œsophagus, and having the same double-loop
rangement that prevails in the preceding layer: they are compar
few in number, and are placed only at the cardiac orifice and por
the stomach, over both surfaces of which they are spread, some
obliquely from left to right, others from right to left, around the
orifice, to which, by their interlacing, they form a kind of sph
continuous with that around the lower end of the œsophagus.
muscular fibres of the stomach and of the intestinal canal are *uns*
being composed of elongated, spindle-shaped fibre-cells.

(3) and (4) The *mucous membrane* of the stomach, which res
a layer of loose cellular membrane, or *submucous tissue*, is
level, soft, and velvety; of a pale pink color during life, and in t
tracted state thrown into numerous, chiefly longitudinal, folds o
which disappear when the organ is distended.

The basis of the mucous membrane is a fine connective tissue



Fig. 255.—Transverse section through lower part of peptic glands of a cat. *a*, peptic cell spheroidal or cubical cells; *c*, transverse section of capillaries. (Frey.)

approaches closely in structure to adenoid tissue; this tissue s
the tubular glands of which the superficial and chief part of the
membrane is composed, and passing up between them assists in
them together. Here and there are to be found in this coat, i
ately underneath the glands, masses of adenoid tissue suff
marked to be termed by some lymphoid follicles. The glands a
rated from the rest of the mucous membrane by a very fine hom
ous basement membrane.

At the deepest part of the mucous membrane are two layers
lar and longitudinal) of unstriped muscular fibres, called the *mus*
*mucosæ*, which separate the mucous membrane from the scan
mucous tissue.

When examined with a lens, the internal or free surface of th
ach presents a peculiar honeycomb appearance, produced by
polygonal depressions, the diameter of which varies generally fro
to $\frac{1}{350}$th of an inch (about 125$\mu$); but near the pylorus is as
$\frac{1}{100}$th of an inch (250$\mu$). They are separated by slightly
ridges, which sometimes, especially in certain morbid states of th
ch, bear minute, narrow vascular processes, which look like vi

have given rise to the erroneous supposition that the stomach has absorbing villi, like those of the small intestines. In the bottom of these little pits, and to some extent between them, minute openings are visible, which are the orifices of the ducts of perpendicularly arranged tubular glands (fig. 254), imbedded side by side in sets or bundles, on the surface of the mucous membrane, and composing nearly the whole structure.

The glands of the mucous membrane are of two varieties, (*a*) Cardiac, (*b*) Pyloric.

(*a*) *Cardiac* glands are found throughout the whole of the cardiac end of the stomach. They are arranged in groups of four or five, which are separated by a fine connective tissue. Two or three tubes often open into one duct, hich forms about a third of the whole length of the tube and opens on e surface. The ducts are lined with columnar epithelium. Of the and tube proper, *i.e.*, the part of the gland below the duct, the upper ird is the *neck* and the rest the *body*. The neck is narrower than the dy, and is lined with granular cubical cells which are continuous with e columnar cells of the duct. Between these cells and the membrana ria of the tubes, are large oval or spherical cells, opaque or granular pearance, with clear oval nuclei, bulging out the membrana pro- these cells are called *oxyntic or parietal cells*. They do not form tinuous layer. The body, which is broader than the neck and ter-



Fig. 256.



Fig. 257.

Fig. 256.—Section showing the pyloric glands. *s*, free surface; *d*, ducts of pyloric glands; *n*, k of same; *m*, the gland alveoli; *mm*, muscularis mucosæ. (Klein and Noble Smith.)

Fig. 257.—Plan of the blood-vessels of the stomach, as they would be seen in a vertical section. arteries, passing up from the vessels of submucous coat; *b*, capillaries branching between and nd the tubes; c, superficial plexus of capillaries occupying the ridges of the mucous membrane; ein formed by the union of veins which, having collected the blood of the superficial capillary xus, are seen passing down between the tubes. (Brinton.)

minutes in a blind extremity or ***fundus*** near the muscularis mucosæ, i lined by cells continuous with the cubical or central cells of the neck, but longer, more columnar and more transparent. In this part are few parietal cells of the same kind as in the neck (fig. 254).

As the pylorus is approached the gland ducts become longer a the tube proper becomes shorter, and occasionally branched at t fundus.

(*b*) *Pyloric Glands.*—These glands (fig. 256) have much longer duc than the peptic glands. Into each duct two or three tubes open b very short and narrow necks, and the body of each tube is branched, wavy, and convoluted. The lumen is very large. The ducts are lin with columnar epithelium, and the neck and body with shorter an more granular cubical cells, which correspond with the central cells o the cardiac glands. Moreover, the parietal cells which are present i the cardiac glands, are absent in the pyloric. During secretion the cel become, as in the case of the cardiac glands, larger and the granul restricted to the inner zone of the cell. As they approach the duoden the pyloric glands become larger, more convoluted and more dee situated. They are directly continuous with Brunner's glands in t duodenum. (Watney.)

*Changes in the gland cells during secretion.*—The chief or cubi cells of the cardiac glands, and the corresponding cells of the pylo glands during the early stage of digestion, if hardened in alcohol, appe swollen and granular, and stain readily. At a later stage the cells b come smaller and less granular, and stain even more readily. T parietal cells swell up, but are otherwise not altered during digesti The granules, however, in the alcohol-hardened specimen, are believ not to exist in the living cells, but to have been precipitated by t hardening reagent; for if examined during life they appear to be co fined to the inner zone of the cells, and the outer zone is free fr granules, whereas during rest the cell is granular throughout. Th granules are thought to be pepsin, or the substance from which pep is formed, *pepsinogen*, which is during rest stored chiefly in the in zone of the cells and discharged into the lumen of the tube duri secretion. (Langley.)

*Lymphatics.*—Lymphatic vessels surround the gland tubes to greater or less extent. Toward the fundus of the peptic glands found masses of lymphoid tissue which may appear as distinct follic somewhat like the solitary glands of the small intestine.

*Blood-vessels.*—The blood-vessels of the stomach, which first bre up in the sub-mucous tissue, send branches upward between the clo packed glandular tubes, anastomosing around them by means of a capillary network, with oblong meshes. Continuous with this dee plexus, or prolonged upward from it, so to speak, is a more superfic etwork of larger capillaries, which branch densely around the orifices f the tubes, and form the framework on which are moulded the small levated ridges of mucous membrane bounding the minute, polygonal pits efore referred to. From this *superficial* network the veins chiefly take heir origin. Thence passing down between the tubes, with no very free onnection with the deeper *inter-tubular* capillary plexus, they open nally into the venous network in the submucous tissue.

*Nerves.*—The nerves of the stomach are derived from the pneumogas- ric and sympathetic, and form a plexus in the sub-mucous and muscular oats containing many ganglia (Remak, Meissner).

## Gastric Juice.

The functions of the stomach are, (a) to afford storage for the food ntil it can be taken up for digestion and absorption by the intestines; (*b*) o secrete a digestive fluid, the gastric juice, to the action of which the ood is subjected after it has entered the cavity of the stomach from the sophagus; (c) to thoroughly incorporate the fluid with the food by eans of its muscular movements; and (d) to absorb such substances as re ready for absorption. It is not essential to life as has been shown by ccessful removal of the stomach; but in such cases food has to be given small quantities frequently until a secondary dilatation of the intestine as formed and can act as a place of storage. While the stomach con- ins no food, and is inactive, no gastric fluid is secreted; and mucus, hich is either neutral or slightly alkaline, covers its surface. But im- ediately on the introduction of food or other substance, the mucous embrane, previously quite pale, becomes slightly turgid and reddened th the influx of a larger quantity of blood; the gastric glands com- ence secreting actively, and an acid fluid is poured out in minute drops, hich gradually run together and flow down the walls of the stomach, or ak into the substances within it.

*Chemical Composition.*—The first accurate analysis of gastric juice as made by Prout: but it does not appear to have been collected in any ge quantity, or pure and separate from food, until the time when Beau- nt was enabled, by a fortunate circumstance, to obtain it from the stom- h of a man named St. Martin, in whom there existed, as the result of unshot wound, an opening leading directly into the stomach, near the per extremity of the great curvature, and three inches from the cardiac fice. The introduction of any mechanical irritant, such as the bulb of mometer, into the stomach, through this artificial opening, excited e the secretion of gastric fluid. This was drawn off, and was often ed to the extent of nearly an ounce. The introduction of alimen- ubstances caused a much more rapid and abundant secretion than did other mechanical irritants. No increase of temperature could be de tected during the most active secretion; the thermometer introduced i the stomach always stood at 37.8° C. (100° F.) except during musc exertion, when the temperature of the stomach, like that of other p of the body, rose one or two degrees higher.

The chemical composition of human gastric juice has been also inve tigated by Schmidt. The fluid in this case was obtained by means of accidental gastric fistula, which existed for several years below the l mammary region of a patient between the cartilages of the ninth and te ribs. The mucous membrane was excited to action by the introduction some hard matter, such as dry peas, and the secretion was removed means of an elastic tube. The fluid thus obtained was found to be aci limpid, odorless, with a mawkish taste—with a specific gravity of 10 to 1010. It contained a few cells, seen with the microscope, and so fine granular matter. The analysis of the fluid obtained in this way given below. Essentially it is a weakly acid fluid containing hy chloric acid and two enzymes, pepsin and rennin, with possibly a th (glucase). The gastric juice of dogs and other animals obtained by introduction into the stomach of a clean sponge through an artifici made gastric fistula, shows a decided difference in composition, but p sibly this is due, at least in part, to admixture with food.

CHEMICAL COMPOSITION OF GASTRIC JUICE.

| | Dogs. | Human. |
|---|---|---|
| Water | 971.17 | 994.4 |
| Solids | 28.82 | 5.60 |
| Solids— | | |
| Ferment—Pepsin | 17.5 | 3.19 |
| Hydrochloric acid (free) | 2.7 | .2 |
| Salts— | | |
| Calcium, sodium, and potassium, chlorides; and calcium, magnesium, and iron, phosphates | 8.57 | 2.19 |

The *quantity* of gastric juice secreted daily has been variously e mated; but the average for a healthy adult may be assumed to ra from five to ten pints in the twenty-four hours. The acidity of fluid is due to free *hydrochloric* acid, although other acids, *e.g.*, *lac* *acetic*, *butyric*, are not infrequently to be found therein as products gastric digestion or abnormal fermentation. In healthy gastric juice amount of free hydrochloric acid is usually about 0.2 per cent, but be as much as 0.3 per cent. In pathological conditions it may be tirely absent, or may amount to 0.5 per cent, or even more.

There is but little doubt that hydrochloric acid is the proper acid healthy gastric juice, and various tests have been used to prove th most of these depend upon changes produced in aniline colors by ion of hydrochloric acid, even in minute traces, whereas lactic and er organic acids have no such action. Pepsin will act with phos- oric, lactic, and oxalic acids, as proven by laboratory experiments, but e best results are obtained with hydrochloric acid. Of these tests the llowing may be mentioned.

An aqueous alkaline solution of 00 *tropæolin*, a bright yellow dye, is rned red on the addition of a minute trace of hydrochloric acid; and queous solutions of methyl violet and gentian violet are turned blue un- er the same circumstances. The lactic acid sometimes present in the ntents of the stomach is derived partly from the sarcolactic acid of uscle, and partly from lactic acid fermentation of carbohydrates. Lactic id ($C_3H_6O_3$), if present, gives the following test. A solution of 10 cc. f a 4 per cent aqueous solution of carbolic acid, 20 cc. of water, and one op of liquor ferri perchloridi is made, forming a blue-colored mixture; mere trace of free lactic acid added to such a solution causes it to come yellow, whereas hydrochloric acid even in large amount only leaches it.

The proteid matter in the food combines with part of the hydro- hloric acid, which is then known as *combined acid* and does not redden tmus paper. As this combination is immediate, it follows that no free cid is found in the gastric contents until the amount secreted is more han enough to saturate the various albuminous affinities. It is for this eason that, as already mentioned, salivary digestion may continue in e stomach for some time after the commencement of gastric digestion. ccording to Ehrlich the amount necessary to saturate the affinities of 00 grammes of various articles of diet is as follows:

| | | |
|---|---|---|
| Beef (boiled) | 2.0 | grammes of pure HCl. |
| Mutton (boiled) | 1.9 | " " " |
| Veal (boiled) | 2.2 | " " " |
| Pork (boiled) | 1.6 | " " " |
| Ham (boiled) | 1.8 | " " " |
| Sweatbread (boiled) | 0.9 | " " " |
| Wheat bread | 0 3 | " " " |
| Rye bread | 0.5 | " " " |
| Swiss cheese | 2.6 | " " " |
| Milk (100 cc.) | 0.32–0.42 | " " " |

As regards the formation of pepsin and acid, the former is produced the central or chief cells of the cardiac glands, and also most likely the similar cells in the pyloric glands; the acid is chiefly found at the rface of the mucous membrane, but is in all probability formed by the rietal cells of the cardiac glands, hence called oxyntic, as no acid is rmed by the pyloric glands in which this variety of cell is absent.

he acid is probably formed from materials in the blood and results a combination of common salt with monosodic orthophosphate

($NaH_2PO_4 + NaCl = Na_2HPO_4 + HCl$); the disodic orthophosphate i then reconverted by the action of carbonic acid and water ($Na_2HPO_4 + CO_2 + H_2O = NaH_2PO_4 + NaHCO_3$): all these salts are found in the blood.

The ferment *Pepsin* can be procured by digesting portions of the mucous mem- brane of the stomach in cold water, after they have been macerated for some tim in water at a temperature 27°—37.8° C. (80°—100° F.). The warm water dissolves various substances as well as some of the pepsin, but the cold water takes up littl else than pepsin, which is contained in a grayish-brown viscid fluid, on evaporatin the cold solution. The addition of alcohol throws down the pepsin in grayish-whi flocculi. Glycerine also has the property of dissolving out the ferment: and if th mucous membrane be finely minced, and dehydrated by absolute alcohol, a powe ful extract may be obtained by macerating it in glycerine.

*Functions.*—The chief function of gastric juice is such alteration proteid food-stuffs as will lead to their ready absorption and such modi cation as will favor their further digestion (as far as necessary) in th intestines; gastric digestion is thus both a complete and a prelimin process. Less important functions are the antiseptic action, coagulati of milk, and inversion of disaccharides into monosaccharides. The chi digestive power of the gastric juice depends on the pepsin and acid co tained in it, both of which are, under ordinary circumstances, neces for the process.

The general effect of digestion in the stomach is the conversion of th food into *chyme*, a substance of varying composition according to th nature of the food, yet always presenting a characteristic thick, pult ceous, grumous consistence, with the undigested portions of the fo mixed in a more fluid substance, and a strong, disagreeable acid odor a taste.

This action on proteids may be shown by adding a little gastric jui (natural or artificial) to some diluted egg-albumin, and keeping the mi ture at a temperature of about 37.8° C. (100° F.); it is soon found th the albumin cannot be precipitated on boiling, but that if the solution neutralized with an alkali, a precipitate of acid-albumin is thrown dow After a while the acid-albumin disappears, so that no precipitate resul on neutralization, and proper analysis will show that all the albumin h been converted into other proteid substances, viz., *proteoses* and *pepto* The process, as is the case in salivary digestion, is never complete a the final result is always a mixture of peptones with proteoses which ca not be further peptonized: the relative proportions, of course, depend o the duration of the process. A side product is found (as an insolub residue) in artificial gastric digestion which gives practically all the pr teid reactions and is soluble in dilute alkali, though insoluble in wate sodium chloride, or dilute acid. This is known as *anti-albumid* and m changed into peptone by prolonged digestion; it does not occur in ysiological gastric digestion. The commonest proteose is the one med from albumin and is known as albumose: the class name, howr, is proteose, and this name is used in the subsequent descriptions of digestive processes.

*Characteristics of Peptones.*—Peptones have a certain characteristic ich distinguishes them from other proteids. They are *diffusible, i.e.,* y possess the property of passing through animal membranes.

In their diffusibility peptones differ remarkably from egg-albumin, and this diffusibility depends one of their chief uses. Egg-albumin as h, even in a state of solution, would be of little service as food, inasch as its indiffusibility would effectually prevent its passing by absorp into the blood-vessels of the stomach and intestinal canal. When pletely changed by the action of the gastric juice into peptones, albuous matters *diffuse* readily, and are thus quickly absorbed.

Peptones are not found in the blood, even of the vessels immediately cerned in absorption from the stomach and intestines. After their orption, therefore, by the epithelial cells, they must, probably, ergo a synthetic change, appearing in the blood as albumins and bulins, which are not readily diffusible and which occupy the same e as the proteids from which the peptones were derived.

*Products of Gastric Digestion.*—The proteid is first changed into synn, or acid proteid, by the combined action of the pepsin and acid. ugh the acid alone is capable of accomplishing this, the fact that it not do so physiologically is proven by the great length of time reed, in laboratory experiments, for the change. The next change is conversion of the syntonin into proteoses which, according to Neuter, occurs in two successive stages. The first of these stages is the ersion of syntonin into the primary proteoses, *i.e.,* proto-proteose and ro-proteose; the second is the conversion of both proto-proteose and ro-proteose into the secondary proteoses, *i.e.,* deutero-proteose. last change is the conversion of the deutero-proteose into peptone; change does not occur to any great extent physiologically and the oses always predominate. Schematically the changes in the proteids be represented as follows:



The action of pepsin is one of hydrolysis and the products are hyd forms of proteid. The acid is not only essential to the action of pe but it also aids digestion by causing the proteids to swell. That th tion is important is proven, in laboratory experiments, by the inc length of time required for digestion when fibrin has been wrapped thread and thus prevented from swelling.

*Reactions of Proteoses.*—The proteoses cannot be coagulated by All are soluble in salt solution. All are precipitated by picric acid saturation (after neutralizing) with ammonium sulphate. All giv Biuret test, copper sulphate producing a precipitate which redissol the addition of caustic potash and forms a rose red solution. Th mary proteoses are precipitated by strong nitric acid, also by aceti and potassium ferrocyanide, and by saturation with sodium chlorid magnesium sulphate. The secondary proteoses are not precipitat these reactions just mentioned but are characterized by the fact that precipitates, when formed, disappear on warming and reappear on ing. Proto-proteose is distinguished by being soluble in water hetero-proteose is not.

*Peptone* reacts to the same test as deutero-proteose, but is not pr tated on saturation with ammonium sulphate.

*Circumstances favoring Gastric Digestion.*—1. A temperature of 37.8° C. (100° F.); at 0° C. (32° F.) it is delayed, and by boiling together stopped. 2. An acid medium is necessary. Hydrochloric best acid for the purpose. Excess of acid or neutralization stops the ess. 3. The removal of the products of digestion. Excess of pe delays the action.

*a. Fibrin* is first dissolved, forming a solution of globulins. T termediate products of the digestion of globulins are called globu of vitellin, vitelloses; of casein, caseinoses; of myosin, myosi These are practically the same as albumoses, and are included und term proteoses.

*b. Proteids.*—All proteids are converted by the gastric juice int teoses and peptones, and, therefore, whether they be taken into the in meat, eggs, milk, bread, or other foods, proteoses and peptone ar the resultant.

*c. Milk* is curdled, the casein being precipitated, and then disso The curdling is due to a special ferment of the gastric juice, and i due to the action of the free acid only. The effect of rennet, whic decoction of the fourth stomach of a calf in brine (rennet), has long known, as it is used extensively to cause precipitation of casein in c manufacture. The ferment which produces this curdling action i tinct from pepsin, and is called *rennin.*

*d.* Upon pure *oleaginous* principles the gastric juice has no action. In e case of adipose tissue, its effect is to dissolve the areolar tissue, albunous cell-walls, etc., which enter into its composition, by which means e fat is able to mingle more uniformly with the other constituents of e *chyme*.

The gastric fluid acts as a general solvent for some of the *saline* contuents of the food, as, for example, particles of common salt, which y happen to have escaped solution in the saliva; while its acid may ible it to dissolve some other salts which are insoluble in the latter or water.

*e.* Upon starches the gastric juice has no action, but by the aid of its drochloric acid it inverts the disaccharides into monosaccharides to a tain extent, changing cane sugar into dextrose; the ferment glucase (if stent) may have a similar, though unimportant and slight, action.

*g.* The action of the gastric juice in preventing and checking putretion has been often directly demonstrated. Indeed, that the secretion ich the food meets with in the stomach is *antiseptic* in its action, is at might be anticipated from the proneness to decomposition of organic tters, such as those used as food, especially under the influence of mth and moisture. It is due to the antiseptic action of the gastric e that disease-germs are often destroyed in the stomach, and the peris saved from an attack of illness.

*Time occupied in Gastric Digestion.*—Under ordinary conditions, from e to four hours may be taken as the average time occupied by the estion of a meal in the stomach. But many circumstances will modify rate of gastric digestion. The chief are: the *nature* of the food taken its *quantity* (the stomach should be fairly filled—not distended); the e that has elapsed since the last meal, which should be at least enough the stomach to be quite clear of food; the amount of exercise previous subsequent to a meal (gentle exercise being favorable, over-exertion rious to digestion); the state of mind (tranquillity of temper being ntial, in most cases, to a quick and due digestion), and the bodily lth.

*Movements of the Stomach.*—The gastric fluid is assisted in accomhing its share in digestion by the movements of the stomach. In ivorous birds, for example, the contraction of the strong muscular ard affords a necessary aid to digestion, by grinding and triturating hard seeds which constitute part of the food. But in the stomachs of and other Mammalia, the movements of the muscular coat are too le to exercise any such mechanical force on the food; neither are needed, for mastication has already done the mechanical work gizzard; and experiments have demonstrated that substances are digested even inclosed in perforated tubes, and consequently protected from mechanical influence.

The normal actions of the muscular fibres of the human stomach appear to have a three-fold purpose: (1) to adapt the stomach to the quantity of food in it, so that its walls may be in contact with the food on all sides, and, at the same time, may exercise a certain amount of compression upon it; (2) to keep the orifices of the stomach closed until the food is digested; and (3) to perform certain peristaltic movements, whereby the food, as it becomes chymified, is gradually propelled toward, and ultimately through, the pylorus. In accomplishing this latter end, the movements without doubt materially contribute toward effecting a thorough intermingling of the food and the gastric fluid.

When digestion is not going on, the stomach is uniformly contracted, its orifices not more firmly than the rest of its walls; but, if examined shortly after the introduction of food, it is found closely encircling its contents, and its orifices are firmly closed like sphincters. The cardiac orifice, every time food is swallowed, opens to admit its passage to the stomach, and immediately again closes. The pyloric orifice, during the first part of gastric digestion, is usually so completely closed, that even when the stomach is separated from the intestines, none of its contents escape. But toward the termination of the digestive process, the pylorus seems to offer less resistance to the passage of substances from the stomach; first it yields to allow the successively digested portions go through it; and then it allows the transit of even undigested substances. It appears that food, so soon as it enters the stomach, is subjected to a kind of peristaltic action of the muscular coat, whereby the digested portions are gradually moved toward the pylorus. The movements are observed to increase in rapidity as the process of chymification advances, and are continued until it is completed.

The contraction of the fibres situated toward the pyloric end of the stomach seems to be more energetic and more decidedly peristaltic than those of the cardiac portion. Thus, it was found in the case of St. Martin, that when the bulb of the thermometer was placed about three inches from the pylorus, through the gastric fistula, it was tightly embraced from time to time, and drawn toward the pyloric orifice for a distance three or four inches. The object of this movement appears to be, just said, to carry the food toward the pylorus as fast as it is formed in chyme, and to propel the chyme into the duodenum; the undigest portions of food being kept back until they are also reduced into chym or until all that is digestible has passed out. The action of these fib is often seen in the contracted state of the pyloric portion of the sto ach after death, when it alone is contracted and firm, while the cardi portion forms a dilated sac. Sometimes, by a predominant action strong circular fibres placed between the cardia and pylorus, the two po or ends as they are called, of the stomach, are partially separated ach other by a kind of hour-glass contraction. By means of the ltic action of the muscular coats of the stomach, not merely is ied food gradually propelled through the pylorus, but a kind of current is continually kept up among the contents of the stomach, cumferential parts of the mass being gradually moved onward the pylorus by the contraction of the muscular fibres, while the portions are propelled in the opposite direction, namely toward rdiac orifice; in this way is kept up a constant circulation of the ts of the viscus, highly conducive to their free mixture with the fluid and to their ready digestion.

movements of the stomach have been recently studied by Cannon by the he Roentgen ray and an opaque substance, bismuth subnitrate, mixed with ric contents. His results, in the main, confirm those of previous observers.

**luence of the Nervous System.**—The normal movements of mach during gastric digestion do not appear to be so closely con-



58.—Very diagrammatic representation of the nerves of the alimentary canal. Oe to Rct, is parts of the alimentary canal from œsophagus to rectum; L. V, left vagus, ending on stomach; rl, recurrent laryngeal nerve, supplying upper part of œsophagus; R.V, right ning left vagus in œsophageal plexus; œ.pl, supplying the posterior part of stomach, and as R'V' to join the solar plexus, here represented by a single ganglion, and connected with or mesenteric ganglion m.gl.; a, branches from the solar plexus to stomach and small and from the mesenteric ganglia to the large intestine; Spl.maj., large splanchnic nerve, om the thoracic ganglia and rami communicantes; r.c, belonging to dorsal nerves from the 9th (or 10th); Spl.min., small splanchnic nerve similarly from the 10th and 11th dorsal These both join the solar plexus, and thence make their way to the alimentary canal; c.r., om the ganglia, etc., belonging to 11th and 12th dorsal and 1st and 2d lumbar nerves, g to the inferior mesenteric ganglia (or plexus), m.gl., and thence by the hypogastric yp., and the hypogastric nerve, n.hyp., and the hypogastric plexus, pl.hyp., to the circular f the rectum; l.r., nerves from the 2d and 3d sacral nerves, S.2, S.3 (nervi erigentes) g by the hypogastric plexus to the longitudinal muscles of the rectum. (M. Foster.)

with the plexuses of nerves and ganglia contained in its walls as merly supposed. The action, however, appears to be set up by the presence of food within it. The stomach is, moreover, directly connected with the higher nerve-centres by means of branches of the vagi and of the splanchnic nerves through the solar plexus.

First as to the function of the vagi in connection with the gastric movements. Irritation of these nerves produces contraction of the stomach, including the sphincter pylori. The vagi, then, are the motor nerves to the stomach.

Secondly as to the other nerve-fibres, which reach the stomach and intestines through the solar plexus. These fibres pass from the spinal cord in the anterior roots of the nerves from the sixth to the twelfth dorsal, passing in the splanchnic nerves to the solar plexus, and thence to the stomach. Stimulation of the splanchnics causes stoppage of the muscular movements as well as relaxation of the sphincter pylori.

It seems probable that automatic peristaltic contraction is inherent in the muscular coat of the stomach, and that the central nervous system is only employed to regulate it by impulses passing down by the vagi or splanchnic nerves.

Next as to the influence of the nerves on the secretion of the gastric juice. It has been known for a long time that the secretion of gastric juice could be reflexly stimulated. For example, Bidder and Schmidt observed in a dog with a gastric fistula that the mere sight of food was sufficient to cause a flow of gastric juice. Quite recently, Pawlow has proved that secretory fibres are carried to the gastric glands in the vagus trunk. His experiment consisted in establishing a gastric fistula, and some days later in dividing the œsophagus in the neck in such a manner that any food swallowed would be diverted to the exterior through the cut end. "Fictitious meals" could then be given to the animal, and the effect upon the stomach noted. As long as the vagi were intact, certain foods (meats) caused a flow of gastric juice, though none of the food reached the stomach. When the vagi had been cut, no secretion occurred. Moreover, he found that direct stimulation of the vagus produced a flow of gastric juice.

The subject has been still further elucidated by some experiments of Heidenhain, relative to the normal mechanism of secretion. He cut out a portion of the fundic end of the stomach, converting it into a blind pouch opening to the exterior, while the continuity of the stomach itself was established by sutures. Food given to the animal caused a secretion in the cul-de-sac as well as in the stomach. From the experiments he concludes that normally there occur a primary secretion due to the mechanical stimulation of the mucous membrane and confined to isolated spots, and a secondary secretion due to the absorption of the products of digestion, which comes from the whole mucous membrane.

Khigine has carried these experiments still further and obtained very complete results. He has investigated the effects of various chemical substances upon the flow of secretion, and has found that *peptone* is the best of all stimuli. How it acts is unknown. Khigine believes that it acts upon the afferent nerve-filaments in the stomach, and that the effect is reflex.

The influence of the higher nerve-centres on gastric digestion, as in the case of mental emotion, is too well known to need more than a reference.

*Digestion of the Stomach after Death.*—If an animal die during the process of gastric digestion, and when, therefore, a quantity of gastric juice is present in the interior of the stomach, the walls of this organ itself are frequently themselves acted on by their own secretion, and to such an extent that a perforation of considerable size may be produced, and the



Fig. 259.—Auerbach's nerve-plexus in small intestine. The plexus consists of fibrillated substance, and is made up of trabeculæ of various thicknesses. Nucleus-like elements and ganglion-cells are imbedded in the plexus, the whole of which is inclosed in a nucleated sheath. (Klein.)

ontents of the stomach may in part escape into the cavity of the abdomen. This phenomenon is not infrequently observed in *post-mortem* exminations of the human body. If a rabbit be killed during a period f digestion, and afterward exposed to artificial warmth to prevent its emperature from falling, not only the stomach, but many of the surounding parts will be found to have been dissolved (Pavy).

From these facts, it becomes an interesting question why, during fe, the stomach is free from liability to injury from a secretion, which, fter death, is capable of such destructive effects.

It is only necessary to refer to the idea of Bernard, that the living omach finds protection from its secretion in the presence of epithelium nd mucus, which are constantly renewed in the same degree that they e constantly dissolved, in order to remark that although the gastric mucus is probably protective, this theory, so far as the *epithelium* is concerned, has been disproved by experiments of Pavy's, in which the mucous membrane of the stomachs of dogs was dissected off for a small space, and, on killing the animals some days afterward, no sign of digestion of the stomach was visible. "Upon one occasion, after removing the mucous membrane, and exposing the muscular fibres over a space of about an inch and a half in diameter, the animal was allowed to live for ten days. It ate food every day, and seemed scarcely affected by the operation. Life was destroyed while digestion was being carried on, and the lesion in the stomach was found very nearly repaired; new matter had been deposited in the place of what had been removed, and the denuded spot had contracted to much less than its original dimensions."

Pavy believes that the natural alkalinity of the blood, which circulates so freely during life in the walls of the stomach, is sufficient to neutralize the acidity of the gastric juice; and as may be gathered from what has been previously said, the neutralization of the acidity of the gastric secretion is quite sufficient to destroy its digestive powers; but the experiments adduced in favor of this theory are open to many objections, and afford only a negative support to the conclusions they are intended to prove. Again, the pancreatic secretion acts best on proteids in an *alkaline* medium; but it has no digestive action on the living intestine. No satisfactory theory of the reason why the stomach does not digest itself has yet been suggested.

## VOMITING.

The expulsion of the contents of the stomach in vomiting, like that of mucus or other matter from the lungs in *coughing*, is preceded by an inspiration; the glottis is then closed, and immediately afterward the abdominal muscles strongly act; but here occurs the difference in the two actions. Instead of the vocal cords yielding to the action of the abdominal muscles, they remain tightly closed. Thus the diaphragm being unable to go up, forms an unyielding surface against which the stomach can be pressed. In this way, as well as by its own contraction, the diaphragm is *fixed*, to use a technical phrase. At the same time the *cardiac* sphincter-muscle being relaxed, and the orifice which it naturally guards being actively dilated, while the *pylorus* is closed, and the stomach itself also contracting, the action of the abdominal muscles, by these means assisted, expels the contents of the organ through the œsophagus, pharynx, and mouth. The reversed peristaltic action of the œsophagus probably increases the effect.

It has been frequently stated that the stomach itself is quite passive during vomiting, and that the expulsion of its contents is effected solely by the pressure exerted upon it when the capacity of the abdomen is diminished by the contraction of the diaphragm, and subsequently of the inal muscles. The experiments and observations, however, which pposed to confirm this statement, only show that the contraction abdominal muscles alone is sufficient to expel matters from an sting bag through the œsophagus; and that, under very abnormal stances, the stomach, by itself, cannot expel its contents. They means show that in ordinary vomiting the stomach is passive; the other hand, there are good reasons for believing the contrary. s true that facts are wanting to demonstrate with certainty this of the stomach in vomiting; but some of the cases of fistulous g into the organ appear to support the belief that it does take and the analogy of the case of the stomach with that of the other viscera, as the rectum and bladder, may be also cited in confirm-

e *muscles* concerned in the act of vomiting, are chiefly and pri- *those of the abdomen;* the *diaphragm* also acts, but usually not as uscles of the abdominal walls do. They contract and compress mach more and more toward the diaphragm; and the diaphragm is usually drawn down in the deep inspiration that precedes each vomiting) is fixed, and presents an unyielding surface against the stomach may be pressed. The diaphragm is, therefore, as a ssive, during the actual expulsion of the contents of the stomach. ere are grounds for believing that sometimes this muscle actively cts, so that the stomach is, so to speak, squeezed between the de- ng diaphragm and the retracting abdominal walls.

ne persons possess the power of *vomiting at will,* without applying due irritation to the stomach, but simply by a voluntary effort. s also that this power may be acquired by those who do not nat- possess it, and by continual practice may become a habit. There es also of rare occurrence in which persons habitually swallow od hastily, and nearly unmasticated, and then at their leisure re- te it, piece by piece, into their mouth, remasticate, and again it, like members of the ruminant order of Mammalia.

e various *nerve-actions* concerned in vomiting are governed by a entre situated in the medulla oblongata.

sensory nerves are the fifth, glosso-pharyngeal and vagus prin- ; but, as well, vomiting may occur from stimulation of sensory from many organs, *e.g.*, kidney, testicle, etc. The centre may stimulated by impressions from the cerebrum and cerebellum, d *central* vomiting occurring in disease of those parts. The impulses are carried by the phrenics and other spinal nerves.

## THE INTESTINES.

Intestinal canal is divided into two chief portions, named from ifferences in diameter, the *small* and *large* intestine (fig. 220).

These are continuous with each other, and communicate by means of an opening guarded by a valve, the *ileocæcal* valve, which allows the passage of the products of digestion from the small into the large bowel, but not, under ordinary circumstances, in the opposite direction.

**The Small Intestine.**—The Small Intestine, the average length of which in an adult is about twenty feet, has been divided, for convenience of description, into three portions, viz., the *duodenum*, which extends for eight or ten inches beyond the pylorus; the *jejunum*, which forms two-fifths, and the *ileum*, which forms three-fifths of the rest of the canal.

*Structure.*—The small intestine, like the stomach, is constructed of four principal coats, viz., the serous, muscular, sub-mucous, and mucous.



Fig. 260.



Fig. 261.

Fig. 260.—Horizontal section of a small fragment of the mucous membrane, including one entire crypt of Lieberkühn and parts of several others.

Fig. 261.—Piece of small intestine (previously distended and hardened by alcohol), laid open to show the normal position of the valvulæ conniventes.

(1.) The *serous* coat is formed by the visceral layer of the peritoneum, and has the structure of serous membranes in general.

(2.) The *muscular* coats consist of an internal circular and an external longitudinal layer: the former is usually considerably the thicker. Both alike consist of bundles of unstriped muscle supported by connective tissue. They are well provided with lymphatic vessels, which form a set distinct from those of the mucous membrane.

Between the two muscular coats is a nerve plexus (Auerbach's plexus) (fig. 259), similar in structure to Meissner's (in the submucous tissue), but with more numerous ganglia.

(3.) Between the mucous and muscular coats is the *submucous* coat, which consists of connective tissue, in which numerous blood-vessels and lymphatics ramify. A fine plexus, consisting mainly of non-medul

**ated nerve-fibres,** ***Meissner's plexus,*** **with ganglion cells at its nodes,** ccurs in the submucous tissue from the stomach to the anus.

(4.) The *mucous membrane* is the most important coat in relation to he function of digestion. The following structures, which enter into ts composition, may now be successively described:—the *valvulæ conni- ventes;* the *villi;* and the *glands.* The general structure of the mucous membrane of the intestines resembles that of the stomach (p. 360), and, ike it, is lined on its inner surface by columnar epithelium. Adenoid issue (fig. 260) enters largely into its construction; and on its deep urface is the *muscularis mucosæ* (*mm*, fig. 265), the fibres of which are rranged in two layers: the outer longitudinal and the inner circular.

*Valvulæ Conniventes.*—The valvulæ conniventes (fig. 261) commence n the duodenum, about one or two inches beyond the pylorus, and



Fig. 262.



Fig. 263.

Fig. 262.—Transverse section through four crypts of Lieberkühn from the large intestine of the They are lined by columnar epithelial cells, the nuclei being placed in the outer part of the The divisions between the cells are seen as lines radiating from L, the lumen of the crypt; G, thelial cells, which have become transformed into goblet cells. × 350. (Klein and Noble Smith.)
Fig. 263.—A gland of Lieberkühn in longitudinal section. (Brinton.)

ecoming larger and more numerous immediately beyond the entrance the bile duct, continue thickly arranged and well developed through- t the jejunum; then, gradually diminishing in size and number, they ase near the middle of the ileum. They are formed by a doubling ward of the mucous membrane; the crescentic, nearly circular, folds us formed being arranged transversely to the axis of the intestine, and ch individual fold seldom extending around more than ½ or ⅔ of the wel's circumference. Unlike the rugæ in the œsopnagus and stom- h, they do not disappear on distention of the canal. Only an imper- ct notion of their natural position and function can be obtained by oking at them after the intestine has been laid open in the usual anner. To understand them aright, a piece of gut should be distended ther with air or alcohol, and not opened until the tissues have become rdened. On then making a section it will be seen that, instead of disappearing, they stand out at right angles to the general surface of the mucous membrane (fig. 261). Their functions are (1) to afford a largely increased surface for secretion and absorption, and (2) to prevent the too rapid passage of the very liquid products of gastric digestion, immediately after their escape from the stomach, and (3) to assist in the more perfect mingling of the latter with the secretions poured out to act on them, by their projection, and consequent interference with an uniform and untroubled current of the intestinal contents.

*Glands.*—The glands are of three principal kinds:—viz., those of (1) Lieberkühn, (2) Brunner, and (3) Peyer.

(1.) The *glands* or *crypts of Lieberkühn* are simple tubular depressions of the intestinal mucous membrane, thickly distributed over the whole surface both of the large and small intestines. In the small intestine they are visible only with the aid of a lens; and their orifices appear as minute dots scattered between the villi. They are larger in the large intestine, and increase in size the nearer they approach the anal end of the intestinal tube; and in the rectum their orifices may be visible to the naked eye. In length they vary from $\frac{1}{180}$ to $\frac{1}{60}$ of an inch. Each tubule (fig. 263) is constructed of the same essential parts as the intestinal mucous membrane, viz., of a fine *membrana propria*, or basement membrane, a layer of columnar epithelium lining it, many of which are goblet cells, and capillary blood-vessels covering its exterior, the free surface of the columnar cells presenting a striated appearance.



Fig. 264.—Transverse section of injected Peyer's glands (from Kölliker). The drawing was taken from a preparation made by Frey: it represents the fine capillary-looped network spreading from the surrounding blood-vessels into the interior of three of Peyer's capsules from the intestine of the rabbit.

*3runner's glands* (fig. 265) are confined to the duodenum; they bundant and thickly set at its commencement and diminish as the duodenum advances. They are situated beneath the mucosæ, imbedded in the submucous tissue; each gland is a and convoluted tube, lined with columnar epithelium. As , in structure they are very similar to the pyloric glands of :h, and their epithelium undergoes a similar change during but they are more branched and end their ducts are longer. The duct of each gland passes e muscularis mucosæ, and opens face of the mucous membrane.

ne *glands of Peyer* occur chiefly clusively in the *small* intestine. found in greatest abundance wer part of the ileum near the valve. They are met with in tions, viz., either scattered sin-ich case they are termed *glandulæ* or aggregated in groups varying to three inches in length, and -an-inch in width, chiefly of an their long axis parallel with that estine. In this state, they are *ndulæ agminatæ*, the groups be-only called *Peyer's patches* (fig. almost always placed opposite ment of the mesentery. In and in function, there is no lifference between the solitary the individual bodies of which p or patch is made up. They single or aggregated masses of sue forming lymph-follicles. In ion in which they have been most commonly examined, each ars as a circular opaque-white rounded body, from $\frac{1}{24}$ to $\frac{1}{12}$ inch 1.) in diameter, according to the degree in which it is devel-ey are principally contained in the submucous coat, but some-ect through the *muscularis mucosæ* into the mucous mem-the agminate glands, each follicle reaches the free surface of ne, and is covered with columnar epithelium. Each gland is l by the openings of Lieberkühn's follicles.



Fig. 265.—Vertical section of duodenum, showing *a*, villi; *b*, crypts of Lieberkühn, and *c*, Brunner's glands in the submucosa *s*, with ducts, *d*; muscularis mucosæ, *m*; and circular muscular coat, *f*. (Schofield.)

jacent glands of a Peyer's patch are connected together by ue. Sometimes the lymphoid tissue reaches the free surface, replacing the epithelium, as is also the case with some of the lymp follicles of the tonsil.

Peyer's glands are surrounded by lymphatic sinuses which do penetrate into their interior; the interior is, however, traversed very rich blood capillary plexus. If the vermiform appendix of a bit, which consists largely of Peyer's glands, be injected with blu pressing the point of a fine syringe into one of the lymphatic sin the Peyer's glands will appear as grayish white spaces surrounde blue; if now the arteries of the same be injected with red, the gra patches will change to red, thus proving that they are surrounde lymphatic spaces but penetrated by blood-vessels. The lacteals pas out of the villi communicate with the lymph sinuses round Pe glands. It is to be noted that Peyer's patches are largest and prominent in children and young persons.



Fig. 266.—Agminate follicles, or Peyer's patch, in the state of distention. × 5. (Boehm.)

*Villi.*—The Villi (figs. 265, 267, and 268) are confined exclusivel the mucous membrane of the small intestine. They are minute vasc processes, measuring $\frac{1}{48}$ to $\frac{1}{8}$ of an inch (.5 to 3 mm.) in length, co ing the surface of the mucous membrane, and giving it a pecu velvety, fleecy appearance. Krause estimates their number at two three hundred per square millimetre in the upper part of the sm intestine, and somewhat less in the lower part. They vary in form e in the same animal, and differ according as the lymphatic vessels *lacteals* which they contain are empty or full; being usually, in former case, flat and pointed at their summits, in the latter cylindr or clavate.

Each villus consists of a small projection of mucous membrane; interior is supported throughout by fine adenoid tissue, which forms framework or stroma in which the other constituents are contained.

The surface of the villus is clothed by columnar epithelium, wh rests on a fine basement membrane; while within this are found, ning from without inward, blood-vessels, fibres of the *muscularis mu-osæ*, and a single lymphatic or lacteal vessel rarely looped or branched ig. 268).

The epithelium is continuous with that lining the other parts of the ucous membrane. The cells are arranged with their long axes radiat-ng from the surface of the villus (fig. 265), and their smaller ends esting on the basement membrane. The free surface of the epithelial ells of the villi, like that of the cells which cover the general surface f the mucous membrane, is covered by a fine border which exhibits very elicate striations, whence it derives its name, *striated basilar border.*

Beneath the basement or limiting membrane there is a rich supply of *ood-vessels.* Two or more minute arteries are distributed within each illus; and from their capillaries, which form a dense network, proceed ne or two small veins, which pass out at the base of the villus.

The layer of the *muscularis mucosæ* in the villus forms a kind of in hollow cone immediately around the central lacteal, and is, there-re, situated beneath the blood-vessels. It is without doubt instru-ntal in the propulsion of chyle along the lacteal.



Fig. 267.—Vertical section of a villus of the small intestine of a cat. *a*, striated basilar border he epithelium; *b*, columnar epithelium; *c*, goblet cells; *d*, central lymph-vessel; *e*, smooth mus-ar fibres; *f*, adenoid stroma of the villus in which lymph corpuscles lie. (Klein.)

The *lacteal vessel* in each villus is the form of commencement of the nphatic system of vessels* in the intestines. It begins almost at the of the villus commonly by a dilated extremity. In the larger villi re may be two small lacteal vessels which join (fig. 268), or the teals may form a kind of network in the villus. The last method is ely or never seen in the human subject, although common in some of lower animals (A, fig. 268).

**The Large Intestine.**—The Large Intestine, which in an adult rom about 4 to 6 feet long, is subdivided for descriptive purposes o three portions, viz.:—the *cæcum*, a short wide pouch, communi-ing with the lower end of the small intestine through an opening, arded by the *ileo-cæcal* valve; the *colon*, continuous with the cæcum, which forms the principal part of the large intestine, and is d into ascending, transverse, and descending portions; and the r which, after dilating at its lower part, again contracts, and im ately afterward opens externally through the *anus*. Attached cæcum is the small *appendix vermiformis*.

---

* For an account of the Lymphatic System, see Chapter IX.

*Structure.*—Like the small intestine, the large intestine is structed of four principal coats, viz., the serous, muscular, sub-m and mucous. The *serous* coat need not be here particularly desc Connected with it are the small processes of peritoneum conta fat, called *appendices epiploicæ*. The fibres of the *muscular* coat, like of the small intestine, are arranged in two layers—the outer longitu the inner circular. In the cæcum and colon, the longitudinal fibre sides being, as in the small intestine, thinly disposed in all parts of th of the bowel, are collected, for the most part, into three strong b which, being shorter, from end to end, than the other coats of t testine, hold the canal in folds, bounding intermediate sacculi. O division of these bands, the intestine can be drawn out to its full le



Fig. 268.—A. *Villus of sheep.* B. *Villi of man.* (Slightly altered from Teichmann.)

and it then assumes, of course, an uniformly cylindrical form. I rectum, the fasciculi of these longitudinal bands spread out and m with the other longitudinal fibres, forming with them a thicker la fibres than exists on any other part of the intestinal canal. The ar muscular fibres are spread over the whole surface of the bowe somewhat more marked in the intervals between the sacculi. Toward e lower end of the rectum they become more numerous, and at the us they form a strong band called the *internal sphincter* muscle.

The *mucous membrane* of the large, like that of the small intestine, lined throughout by columnar epithelium, but, unlike it, is quite des- ute of villi, and is not projected in the form of *valvulæ conniventes.* general microscopic structure resembles that of the small intestine: d it is bounded below by the *muscularis mucosæ.*

The general arrangement of ganglia and nerve-fibres in the large testine resembles that in the small.

*Glands.*—The glands with which the large intestine is provided are two kinds, (1) the *tubular* and (2) the *lymphoid.*

(1.) The *tubular* glands, or glands of Lieberkühn, resemble those the small intestine, but are somewhat larger and more numerous. ey also contain many goblet cells.

(2.) Follicles of *adenoid* or *lymphoid* tissue are most numerous in cæcum and vermiform appendix. They resemble in shape and ucture, almost exactly, the solitary glands of the small intestine. er's patches are not found in the large intestine.

*Ileo-cæcal Valve.*—The ileo-cæcal valve is situate at the place of ction of the small with the large intestine, and guards against any ux of the contents of the latter into the ileum. It is composed of semilunar folds of mucous membrane. Each fold is formed by a bling inward of the mucous membrane, and is strengthened on the side by some of the circular muscular fibres of the intestine, which contained between the outer surfaces of the two layers of which each is composed. While the circular muscular fibres, however, of the el at the junction of the ileum with the cæcum are contained be- n the outer opposed surfaces of the folds of mucous membrane h form the valve, the longitudinal muscular fibres and the peri- um of the small and large intestine respectively are continuous each other, without dipping in to follow the circular fibres and the ous membrane. In this manner, therefore, the folding inward of two last-named structures is preserved, while on the other hand, ividing the longitudinal muscular fibres and the peritoneum, the can be made to disappear, just as the constrictions between the li of the large intestine can be made to disappear by performing a ar operation. The inner surface of the folds is smooth; the ous membrane of the ileum being continuous with that of the cæcum. surface of each fold which looks toward the small intestine is ed with villi, while that which looks to the cæcum has none. n the cæcum is distended, the margin of the folds are stretched, thus are brought into firm apposition one with the other.

## DIGESTION IN THE INTESTINES.

After the food has been duly acted upon by the gastric juice, such of it as has not been absorbed passes into the duodenum, and is there subjected to the action of the secretions of the pancreas and liver which enter that portion of the small intestine, as well as to the secretion (succus entericus) which is poured out into the intestines from the glands lining them. Mixed with products of gastric digestion is found a certain amount of proteid matter which has not been acted upon at all: the fats are also included and such carbohydrates as have not been acted upon by salivary digestion together with products of this digestion.



Fig. 269.—Section of the pancreas of a dog during digestion. *a*, alveoli lined with cells, the outer zone of which is well stained with hæmatoxylin; *d*, intermediary duct lined with squamous epithelium. × 350. (Klein and Noble Smith.)

## THE PANCREAS, AND ITS SECRETION.

The **Pancreas** is situated within the curve formed by the duodenum; and its main duct opens into that part of the small intestine, through a small opening, or through a duct common to it and to the liver, about two and a half inches from the pylorus.

*Structure.*—In structure the pancreas bears some resemblance to the salivary glands. Its capsule and septa, as well as the blood-vessels and lymphatics, are similarly distributed. It is, however, looser and softer, the lobes and lobules being less compactly arranged. The main duct divides into branches (lobar ducts), one for each lobe, and these branches subdivide into intra-lobular ducts, and these again by their division and branching form the gland tissue proper. The intralobar ducts correspond to a lobule, while between them and the secreting tubes of *veoli* are longer or shorter *intermediary* ducts. The larger ducts ossess a very distinct lumen and a membrana propria lined with lumnar epithelium, the cells of which are longitudinally striated, but e shorter than those found in the ducts of the salivary glands. In the tralobular ducts the epithelium is short and the lumen is smaller. he intermediary ducts opening into the alveoli possess a distinct lumen, ith a membrana propria lined with a single layer of flattened elongated lls. The alveoli are branched and convoluted tubes, with a membrana opria lined with a single layer of columnar cells. They have a stinct lumen, though spindle-shaped cells are often seen in the ntre of the acini. Heidenhain has observed that the alveolar lls in the pancreas of a fasting dog consist of two zones, an inner or ntral zone which is finely granular, and which stains feebly, and a



270.—Section of the pancreas of armadillo, showing the two kinds of gland-structure. (V. D. Harris.)

aller parietal zone of finely striated protoplasm which stains easily. e nucleus is partly in one, partly in the other zone. During digestion, is found that the outer zone increases in size, and the central zone minishes; the cell itself becoming smaller from the discharge of the retion. At the end of digestion the first condition again appears, the er zone enlarging at the expense of the outer. It appears that the anules are formed by and stored up in the protoplasm of the cells, from terial supplied to it by the blood. The granules are thought to sist of material from which, under certain conditions, the ferments the gland are developed, and which is therefore called *Zymogen*. In ition to the ordinary alveoli of the pancreas there are found distrited irregularly in the gland other collections of cells of a different aracter (*Islands of Langerhans*). They are considerably smaller, eir protoplasm is more granular, and is less easily stained with hæmaxylin, and their nuclei are small and deeply staining, being situated so more toward the centre of the cells. The collections of cells vary in size and shape, and sometimes seem to be mere masses of protoplasm with nuclei undifferentiated into cells. These nests of cells are sometimes seen to consist of distinct columns of cells. No distinct basement membrane, however, can be made out as bounding these columns. The special form of nerve terminations, called *Pacinian corpuscles*, are often found in the pancreas.

**The Pancreatic Juice.**—The secretion of the pancreas has been obtained for purposes of experiment from the lower animals, especially the dog, by opening the abdomen and exposing the duct of the gland, which is then made to communicate with the exterior. A pancreatic fistula is thus established.

An extract of pancreas made from the gland which has been removed from an animal killed during digestion possesses the active properties of pancreatic secretion. It is made by first dehydrating the gland, cut up into small pieces, by keeping it for some days in absolute alcohol, and then, after the entire removal of the alcohol, by pounding up these pieces into a pulpy mass and placing it in strong glycerin. A glycerin extract is thus obtained. It is a remarkable fact, however, that the amount of the ferment *trypsin* greatly increases if the gland be exposed to the air for twenty-four hours before placing in alcohol; indeed, a glycerin extract made from the gland immediately upon the removal from the body often appears to contain none of the ferments. This seems to indicate that the conversion of zymogen in the gland into the ferment only takes place during the act of secretion, and that the gland, although it always contains in its cells the materials (trypsinogen) out of which trypsin is formed, yet the conversion of the one into the other only takes place by degrees. Dilute acid appears to assist and accelerate the conversion, and if a recent pancreas be rubbed up with dilute acid before dehydration, a glycerin extract made afterward, even though the gland may have been only recently removed from the body, is very active.

Trypsinogen is also converted into trypsin through the action of the intestinal juice. Schepowalnikow, who discovered this action, found that the secretion of the duodenal end was considerably more active than that of the lower end of the intestine. This action was destroyed by boiling. It was probably, therefore, the action of a ferment. Hence, it has been called by Pawlow, *entérokinase.* Entérokinase also assists to some extent in the activation of the fat-splitting and amylolytic enzymes.

*Properties.*—Pancreatic juice is colorless, transparent, and slightly viscid, alkaline in reaction. It varies in specific gravity from 1010 to 1030, according as it is obtained from a permanent fistula—then more watery—or from a newly-opened duct. The solids vary in a temporary fistula from 80 to 100 parts per thousand, and in a permanent one from 16 to 50 per thousand. It is characterized by having three distinct an tant enzymes known as trypsin, amylopsin, and steapsin, whose is, respectively, proteolytic, amylolytic, and lipolytic (fat-split- there is also a fourth distinct, though less important, one known case, which inverts the disaccharides.

CHEMICAL COMPOSITION OF PANCREATIC JUICE (C. SCHMIDT).

| a dog. | Recent fistula. | Permanent fistula. |
|---|---|---|
| ater | 900.76 | 980.45 |
| lids | 99.24 | 19.55 |
| Organic substances | 90.44 | 12.71 |
| Ash | 8.80 | 6.84 |
| Sodium carbonate | 0.58 | 3.31 |
| Sodium chloride | 7.35 | 2.50 |
| Calcium, magnesium, and sodium phosphates | 0.53 | 0.08 |

*unctions.*—(1.) By the aid of its proteolytic or proteid-splitting ne, *trypsin*, it converts *proteids into proteoses and peptones*, but the s is both more rapid and more complete than in gastric digestion, t, in the final result, the peptones are greatly in excess of the pro- The proteids pass through the same preliminary stages as in c digestion, being split at first into alkali-albumin, then into ry proteoses, both proto-proteose and hetero-proteose, and then eutero-proteose; but the first stages are so transient that it is lt to detect either the alkali-albumin or primary proteose. For ason some investigators deny the existence of either alkali-albumin mary proteose in pancreatic digestion. The deutero-albumoses sily demonstrated in the earlier stages, but become very scanty Anti-albumid is found as a side product in artificial digestion, not present in normal digestion. Trypsin also has the power of ng a certain proportion of peptones into simpler bodies, such as or amido-caproic acid, *tyrosin* or paroxyphenyl-amido-propionic *ysin*, *lysatinin*, *tryptophan*, and some other bodies. Leucin and have been found in the intestinal contents, so that this destruc- hemipeptone must take place to a certain extent within the body as in artificial tryptic digestion.

laboratory experiments only about one-half of the peptones can nged in this way. The more stable portion which cannot be d is usually known as *antipeptone*, though it is as yet undecided r this term represents a single chemical substance or a complex of s bodies; recent experiments, however, tend to show that it repre- a mixture of much simpler substances than peptone. There are theories as to the reason or use of this change into leucin, tyrosin, One of the most plausible is that it saves the body from needless when too much proteid food has been taken; the breaking down in the intestine of bodies only slightly removed from urea relieves the liver and other glandular organs from the strain of converting an excess of absorbed proteid material into a form in which it can be excreted. Another theory is that leucin, tyrosin, etc., are essential for the physiological working of the body, in some unknown way, just as the products of the thyroid gland are.

The formation of the decomposition products indol and skatol is caused by the action of bacteria on proteids, and will be spoken of under another heading.

The albuminous or proteid substances which have not been converted into peptone and absorbed in the stomach, and the partially changed substances, *i.e.*, the proteoses, are converted into peptone by the pancreatic juice, and then in part into leucin and tyrosin.

The ferment trypsin acts best in an alkaline medium, but will act also in a neutral medium, or in the presence of a small amount of combined acid; it will not work in the presence of free acid. It therefore differs from pepsin in being able to act without the aid of any other substance than water. In the process of tryptic digestion, proteid matter does not swell up at first but seems to be corroded.

(2.) *Starch is converted into maltose* in an exactly similar manner to that which happens with saliva, erythro-dextrine and one or more achroödextrines being the intermediate products. The amylolytic enzyme of the pancreatic juice, which cannot be distinguished from ptyalin, is called *amylopsin*. The maltose thus formed is converted to dextrose either just before or during its absorption, in which form it passes into the blood. This conversion is in part due to the action of the enzyme *glucase*.

(3.) Pancreatic juice possesses *the property of curdling milk*, containing a special (rennet) ferment for that purpose. The ferment is distinct from trypsin, and will act in the presence of an acid (W. Roberts). It is best extracted by brine. The milk-curdling ferment of the pancreas is, in some pancreatic extracts, extremely powerful, insomuch that 1 cc. of a brine extract will coagulate 50 cc. of milk in a minute or two.

(4.) *Oils and fats are emulsified and saponified* by pancreatic secretion. The terms *emulsification* and *saponification* may need a little explanation. The former is used to signify an important mechanical change in oils or fats, whereby they are made into an emulsion, or in other words are minutely subdivided into small particles. If a small drop of an emulsion be looked at under the microscope it will be seen to be made up of an immense number of minute rounded particles of oil or fat, of varying sizes. The more complete the emulsion the smaller are these particles. An emulsion is formed at once if oil or fat, which when old is slightly acid from the presence of free fatty acid, is mixed ith an alkaline solution. Saponification signifies a distinct chemical hange in the composition of oils and fats. An oil or a fat being made p chemically of *glycerin*, a triatomic alcohol, and one or more fatty cid radicles, when an alkali is added to it, and heat is applied, two hanges take place: firstly, the oil or fat is split up into glycerin, and s corresponding fatty acid; secondly, the fatty acid combines with the lkali, to form a soap which is chemically known as stearate, oleate, or almitate of potassium or sodium. Thus saponification means a chem- al splitting up of oils or fats into new compounds, and emulsification eans merely a mechanical splitting of them up into minute particles. he pancreatic juice has been for many years credited with the posses- on of a special ferment, which was called by Claude Bernard *steapsin*, d which is a *lipolytic* or fat-splitting ferment. This ferment has not een isolated, but its presence may be demonstrated by adding portions the fresh pancreas to butter or other fat and maintaining the proper mperature. Its action is made manifest by the liberation of butyric id, which smells like rancid butter.

The generally accepted theory is that only a small portion of the t which is eaten is thus changed into soap, and that the function of the ponified fat is to assist in the emulsification of the major part, a proc- s which is favorably influenced by the bile. The proper emulsifica- on of fat is a necessary preliminary to its absorption, for when in sease the entrance of the pancreatic juice or the bile to the intestine interfered with, the fæces contains a great excess of fat.

Some recent experiments, however, tend to invalidate the emulsion theory and prove that the entire fat of the food is changed in the intestine into fatty acids d glycerine; that the fatty acids are entirely, or in part, changed to soaps; and t these soaps, or the mixture of soaps and free fatty acids, are absorbed in solu- n. The chief facts favoring this view are that: (1) The action of steapsin is suf- ently rapid to allow the saponification of a full fatty meal within the ordinary iod of digestion; (2) histological examination has never shown that fat particles pass into a columnar cell, and none have ever been found in the broad striated der of the cell; (3) the fat globules found in columnar cells after a fatty meal w steadily larger as the period of absorption progresses, indicating that they are osited from solution; (4) the fatty acids are easily soluble in bile solutions, and solubility of the soaps is greatly increased by the presence of bile. The fat con- uents, according to this theory, are recombined in the columnar cells to form tral fats.

*Conditions favorable to the Action.*—The secretion of the pancreatic ce appears to be, at any rate in some animals, *e.g.*, the rabbit and g, almost continuous; the flow, however, is not uniform, the amount reases immediately after taking food, and the maximum is reached in m one to one and a half hours, then the amount falls to about one- f, after which a conspicuous rise occurs, and this is followed by a gradual fall to the base line. To the work of Pawlow and his pupil owe our more exact knowledge of many of the factors involved in t production of the pancreatic secretion. According to them, the flow pancreatic juice begins after some of the acid chyme from gastric gestion has entered the duodenum, but is not excited by the mere p ence of food in the stomach. The acidity of the chyme is the import factor, since an equally abundant flow of pancreatic juice may be brou about by the introduction of acid (HCl), alone, into the stom whence it rapidly passes into the duodenum, or by introducing an directly into the duodenum itself. Furthermore, the character of pancreatic secretion varies with the nature of the food ingested; carbohydrate foods, alone, the juice has a high amylolytic power, a poor in other enzymes and changes in a similar manner for proteid fats. All of these phenomena Pawlow ascribes to reflex action, an found, in fact, that, with proper precautions, a pancreatic secretion be brought about by vagus stimulation, and to some extent by st lating the splanchnic nerves. The secretion still occurs, however, both vagi and splanchnics are divided. This has been explained b action of peripheral reflexes involving the sympathetic ganglia w the pancreas and walls of the intestine itself.

Recent investigations by Bayliss and Starling and by subse workers tend to show that the normal stimulus to pancreatic secret probably a chemical one. They have shown that the introduction acid into an isolated loop of small intestines, connected with the viscera only by its blood-vessels and having all nerve communic severed, is still able to excite an abundant secretion of pancreatic Furthermore, an extract of the mucous membrane of such a loop, the introduction of the acid and not before, when injected into th culation is followed, likewise, by an abundant secretion from the creas. From the intestinal mucosa, treated in the above mann substance, whose exact nature is not yet definitely known, has isolated, for which the name *secretin* has been suggested. Its curser, in the mucous membrane, is termed prosecretin.

The amount of secretion per diem is not definitely known, b approximately estimated to be about half a litre.

## THE LIVER.

The **Liver**, the largest gland in the body, situated in the abd on the right side chiefly, is an extremely vascular organ, and rec its supply of blood from two distinct sources, viz., from the *porta* and from the *hepatic artery*, while the blood is returned from it int va inferior by the *hepatic veins.* Its secretion, the *bile*, is con-rom it by the *hepatic duct*, either directly into the intestine, or, igestion is not going on, into the *cystic* duct, and thence into -bladder, where it accumulates until required. The portal vein, artery, and hepatic duct branch together throughout the liver, e hepatic veins and their tributaries run by themselves.

he outside, the liver has an incomplete covering of peritoneum, eath this is a very fine coat of areolar tissue, continuous over e surface of the organ. It is thickest where the peritoneum is nd is continuous on the general surface of the liver with the in the human subject, almost imperceptible areolar tissue in-he lobules. At the transverse fissure it is merged in the areolar nt called Glisson's capsule, which, surrounding the portal vein, rtery, and hepatic duct, as they enter at this part, accompanies their branches through the substance of the liver.

*ture.*—The liver is made up of small roundish or oval portions *bules*, each of which is about $\frac{1}{20}$ of an inch (about 1 mm.) in , and composed of the minute branches of the portal vein, he-ery, hepatic duct, and hepatic vein; while the interstices of these



—The liver from below and behind. *L S.*, Spigelian lobe; *L.C.*, caudate lobe; *L.Q.*, be: *R.L.*, right lobe; *L.L.*, left lobe; *g.bl.*, gall-bladder; *v.c.i.*, inferior vena cava; cal fissure; *f.d.v.*, fissure of the ductus venosus; *p*, portal fissure with portal vein, ry and bile-duct. (Wesley, from a His model.)

e filled by the liver cells. The hepatic cells (fig. 259), which glandular or secreting part of the liver, are of a spheroidal newhat polygonal from mutual pressure about $\frac{1}{800}$ to $\frac{1}{1000}$ inch to $\frac{1}{40}$ mm.) in diameter, possessing one, sometimes two nuclei. substance contains numerous fatty molecules, and possibly some of bile-pigment, as well as a variable amount of glycogen. sometimes exhibit slow amœboid movements. They are held by a very delicate sustentacular tissue, continuous with the lar connective tissue.

derstand the distribution of the blood-vessels in the liver, it will be well to trace, first, the two blood-vessels and the duct whic the organ on the under surface at the transverse fissure, viz., the vein, hepatic artery, and hepatic duct. As before remarked, all run in company, and their appearance in longitudinal section is shown in fig. 273. Running together through the substance of the liver, they are contained in small channels called *portal canals*, their immediate investment being a sheath of areolar tissue continuous with Glisson's capsule.



Fig. 272.



Fig. 273.

Fig. 272.—A. Liver-cells. B. Ditto, containing various-sized particles of fat.

Fig. 273.—Longitudinal section of a portal canal, containing a portal vein, hepatic a hepatic duct, from the pig. P, branch of vena portæ, situate in a portal canal formed a lobules of the liver, *l*, *l*, and giving off vaginal branches; there are also seen within the la vein numerous orifices of the smallest interlobular veins arising directly from it; *a*, hepatic a hepatic duct. × 5. (Kiernan.)

To take the distribution of the portal vein first:—In its course th the liver this vessel gives off small branches which divide and sub *between* the lobules surrounding them and limiting them, and fro circumstance called *inter*-lobular veins. From these small ves dense capillary network is prolonged into the substance of the l



Fig. 274.—Capillary network of the lobules of the rabbit's liver. The figure is taken fro successful injection of the hepatic veins, made by Harting: it shows nearly the whole of bules, and parts of three others; *p*, portal branches running in the interlobular spaces; *h*, veins penetrating and radiating from the centre of the lobules. × 45. (Kölliker.)

is network gradually gathering itself up, so to speak, into larger converges finally to a single small vein, occupying the centre of ule, and hence called *intra*-lobular. This arrangement is well fig. 274, which represents a transverse section of a lobule.

small *intra*-lobular veins discharge their contents into veins *sub*-lobular (*h h h*, fig. 275), while these again, by their union, e main branches of the *hepatic* veins, which leave the posterior of the liver to end by two or three principal trunks in the infe- a cava, just before its passage through the diaphragm. The ular and *hepatic veins*, unlike the *portal* vein and its companions, ttle or no areolar tissue around them, and their coats being very ey form little more than mere channels in the liver substance losely surrounds them.

manner in which the lobules are connected with the ***sublobular*** means of the small ***intralobular*** **veins has been likened to a** twig **leaves without footstalks—the lobules representing the leaves,** ***sublobular*** **vein the small branch from which it springs.**



Fig. 275.



Fig. 276.

5.—Section of a portion of liver passing longitudinally through a considerable hepatic the pig. H, hepatic venous trunk, against which the sides of the lobules (*l*) are applied; lobular hepatic veins, on which the bases of the lobules rest, and through the coats of are seen as polygonal figures; *i*, mouth of the intralobular veins, opening into the sub- ns; *i'*, intralobular veins shown passing up the centre of some divided lobules; *l*, *l*, cut the liver; *c*, *c*, walls of the hepatic venous canal, formed by the polygonal bases of the 5. (Kiernan.)

.—Portion of a lobule of liver. *a*, bile capillaries between liver-cells, the network in ell seen; *b*, blood capillaries. × 350. (Klein and Noble Smith.)

hepatic artery, the chief function of which is to distribute blood ition to Glisson's capsule, the walls of the ducts and blood-ves- other parts of the liver, is distributed in a very similar manner to the portal vein, its blood being returned by small branches into the ramifications of the portal vein, or into the capillary ple the lobules which connect the *inter-* and *intra-*lobular veins.

The hepatic duct divides and subdivides in a manner very lik



Fig. 277.—Hepatic cells and bile capillaries, from the liver of a child three months' ol figures represent fragments of a section carried through the periphery of a lobule. The puscles of the blood are recognized by their circular contour; *vp*, corresponds to an inte vein in immediate proximity with which are the epithelial cells of the biliary ducts, to whic lower part of the figures, the much larger hepatic cells suddenly succeed. (E. Hering.)

of the portal vein and hepatic artery, the larger branches being by *cylindrical*, and the smaller by small *polygonal* epithelium.

The bile-capillaries commence between the hepatic cells, a bounded by a delicate membranous wall of their own. They ap be always bounded by hepatic cells on all sides, and are thus se from the nearest blood-capillary by at least the breadth of one ce 276 and 277).

## THE GALL-BLADDER.

The **Gall-bladder** (*g.bl.* fig. 271) is a pyriform bag, attached under surface of the liver, and supported also by the peritoneum, passes below it. The larger end, or *fundus*, projects beyond th margin of the liver; while the smaller end contracts into the cysti

*Structure.*—The walls of the gall-bladder are constructed o principal coats. (1) Externally (excepting that part which is in with the liver) is the *serous* coat, which has the same structure peritoneum, with which it is continuous. Within this is (2) the or areolar coat, constructed of tough fibrous and elastic tissu which is mingled a considerable number of plain muscular fibre longitudinal and circular. (3) Internally the gall-bladder is li mucous membrane, and a layer of columnar epithelium. The of the mucous membrane presents to the naked eye a minutely combed appearance from a number of tiny polygonal depressio intervening ridges, by which its surface is mapped out. In th duct the mucous membrane is raised up in the form of crescenti h together appear like a spiral valve, and which minister to the tion of the gall-bladder in retaining the bile during the interval of ıtion.

'he gall-bladder and all the main biliary ducts are provided with ɔus glands, which open on the internal surface.

### FUNCTIONS OF THE LIVER.

'he function of the liver in connection with digestion is to secrete bile, and may be now considered. The other functions in connec- with the general metabolism of the body, and particularly its gly- ıic function, will be discussed later on. First of all it will be as to take the composition and functions of the bile, and afterward to ss its mode of secretion.

## The Bile.

*'roperties.*—The bile is a somewhat viscid fluid, of a yellow, reddish- w or green color, a strongly bitter taste, and, when fresh, with a ely perceptible odor: it has a neutral or slightly alkaline reaction, ts specific gravity is about 1020. Its color and degree of consist- vary much, quite independent of disease; but, as a rule, bile becomes ıally more deeply colored and thicker as it advances along its ducts, ıen it remains long in the gall-bladder, wherein, at the same time, ɔomes more viscid and ropy, darker, and more bitter, mainly from 'eater degree of concentration, on account of partial absorption of ıter, but also from being mixed with mucus.

CHEMICAL COMPOSITION OF HUMAN BILE. (Frerichs.)

| | | |
|---|---|---|
| Water | | 859.2 |
| Solids—Bile salts | 91.5 | |
| Fat | 9.2 | |
| Cholesterin | 2.6 | |
| Mucus and coloring matters | 29.8 | |
| Salts | 7.7 | |
| | | 140.8 |
| | | 1000.0 |

) *Bile salts,* sometimes termed *Bilin,* can be obtained as colorless, dingly deliquescent crystals, soluble in water, alcohol, and alkaline ons, giving to the watery solution the taste and general characters le. They consist of sodium salts of glycocholic and taurocholic The formula of the former salt being $C_{26}H_{43}NaNO_6$, and of the $C_{26}H_{44}NaNO_7S$.

e bile acids are easily decomposed by the action of dilute acids or alkalies

$$\underset{\text{Glycocholic Acid.}}{C_{26}H_{43}NO_6} + H_2O = \underset{\text{Glycin.}}{C_2H_5NO_2} + \underset{\text{Cholic Acid.}}{C_{24}H_{40}O_5}$$

$$\text{and } \underset{\text{Taurocholic Acid.}}{C_{26}H_{45}NO_7S} + H_2O = \underset{\text{Taurin.}}{C_2H_7NO_3S} + \underset{\text{Cholic Acid.}}{C_{24}H_{40}O_5}$$

Glycin, or glycocin, is amido-acetic acid, *i.e.*, acetic acid $C_2H_4O_2$, wi of the atoms of H replaced by the radical amidogen $NH_2$, $C_2H_3$(N $C_2H_5NO_2$. Taurin likewise is amido-isethionic acid. Isethionic acid phurous acid $H_2SO_3$, in which an atom of H is replaced by the mono radicle oxy-ethylene, $C_2H_4OH$, viz., $H(C_2H_4OH)SO_3$, and in amido-iset acid, the OH hydroxyl in this radicle is replaced by amidogen $NH_2$ $H(C_2H_4NH_2)SO_3 = C_2H_7NSO_3$. The proportion of these two salts in the different animals varies, *e.g.*, in ox bile the glycocholate is in great e whereas the bile of the dog, cat, bear, and other carnivora contains tau late alone; in human bile the glycocholate is in excess (4.8 to 1.5).

*Preparation of Bile Salts.*—Bile salts may be prepared in the foll manner: mix bile which has been evaporated to a quarter of its bulk animal charcoal, and evaporate to perfect dryness in a water bath. Ne tract the mass while still warm with absolute alcohol. Separate the alc extract by filtration, and to it add perfectly anhydrous ether as long as cipitate is thrown down. The solution and precipitate should be set as a closely stoppered bottle for some days, when crystals of the bile salts or will have separated out. The glycocholate may be separated from the cholate by dissolving bilin in water, and adding to it a solution of neutr acetate, and then a little basic lead acetate, when lead glycocholate sep out. Filter and add to the filtrate lead acetate and ammonia, a precipi lead taurocholate will be formed, which may be filtered off. In both cas lead may be got rid of by suspending or dissolving in hot alcohol, hydrogen sulphide, filtering and allowing the acids to separate out by t dition of water.

The *Test* for bile salts is known as Pettenkofer's. If to an aq solution of the salts strong sulphuric acid be added, the bile aci first of all precipitated, but on the further addition of the acid a dissolved. If to the solution a drop of solution of cane sugar be a fine deep cherry red to purple color is developed.

The reaction will also occur on the addition of grape or fruit sugar i of cane sugar, slowly with the first, quickly with the last; and a color s to the above is produced by the action of sulphuric acid and sugar on alb the crystalline lens, nerve tissue, oleic acid, pure ether, cholesterin, m codeia and amylic alcohol. The substance which gives the reaction is *aldehyde*, formed by the action of sulphuric on sugar. Furfur-aldehyd cholalic acid gives the red color.

The spectrum of Pettenkofer's reaction, when the fluid is r ately diluted, shows four bands—the most marked and broadest and a little to the left; another at F; a third between D and E, to D; and the fourth near D.

(*b*) The yellow *coloring matter* of the bile of man and the Car is termed *Bilirubin* or *Bilifulvin* ($C_{16}H_{18}N_2O_3$) crystallizable a soluble in water, soluble in chloroform or carbon disulphide; a g matter, *Biliverdin* ($C_{16}H_{18}N_2O_4$) which always exists in large t in the bile of Herbivora, being formed from bilirubin on expo- the air, or by subjecting the bile to any other oxidizing agency, dding nitrous acid. Biliverdin is soluble in alcohol, glacial acetic nd strong sulphuric acid, but insoluble in water, in chloroform her. It is usually amorphous but may sometimes crystallize in rhombic plates. When the bile has been long in the gall-bladder, pigment, *Biliprasin*, may be also found in small amount.

cases of biliary obstruction, the coloring matter of the bile is re- ed and circulates with the blood, giving to the tissues the yellow aracteristic of jaundice.

e coloring matters of human bile do not appear to give character- sorption spectra; but the bile of the Guinea-pig, rabbit, mouse, ox, and crow do so, the most constant of which appears to be a t F. The bile of the sheep and ox gives three bands in a thick nd four or five bands with a thinner layer, one on each side of near E, and a faint line at F. (McMunn.)

re seems to be a close relationship between the coloring matters blood and of the bile, and it may be added, between these and the urine (*urobilin*), and of the fæces (*stercobilin*) also; it is le they are, all of them, varieties of the same pigment, or derived e same source. Indeed it is maintained that *Urobilin* is identi- *Hydrobilirubin*, a substance which in alkaline solution gives a uorescence with zinc chloride, which is obtained from bilirubin action of sodium amalgam, or by the action of sodium amalgam line hæmatin; both urobilin and hydrobilirubin giving a charac- absorption band between b and F. They are also identical with lin, which is formed in the alimentary canal from bile pigments.



Fig. 278.—Crystalline scales of cholesterin.

*Test* (Gmelin's) for the presence of *bile-pigment* consists of the of a small quantity of nitric acid, yellow with nitrous acid; if resent, a play of colors is produced, beginning with green and through blue and violet to red, and lastly to yellow. The final

yellow substance has been called *choletelin.* The spectrum of Gmel
test gives a black band extending from near b to beyond F.

(*c*) *Fatty substances* are found in variable proportions in the
Besides these saponifiable fats, there is a small quantity of *Cholest*
which is an alcohol, and, with the free fats, is probably held in sol
by the bile salts. It is a body belonging to the class of monatomic
hols ($C_{27}H_{45}OH$, Obermüller), and crystallizes in rhombic plates
278). It is insoluble in water and cold alcohol, but dissolves eas
boiling alcohol or in ether. It gives a red color with strong sulp
acid, and with nitric acid and ammonia; also a play of colors begi
with blood red and ending with green on the addition of sulphuric
and chloroform. *Lecithin* ($C_{42}H_{84}NPO_9$) is also found: it is a com
tion of cholin with glycerophosphoric acid in which two of the hyd
atoms of the glycerine are replaced by radicals of the fatty acids,
oleic and palmitic acids.

(*d*) The *Mucus* in bile is derived from the mucous membra
glands of the gall-bladder, and of the hepatic ducts. It constitu
residue after bile is treated with alcohol. The epithelium with w
is mixed may be detected in the bile with the microscope in the f
cylindrical cells, either scattered or still held together in layer
the presence of the mucus is probably to be ascribed the rapid
position of the bile; for, according to Berzelius, if the mucus b
rated, it will remain unchanged for many days.

(*e*) The *Saline* or *inorganic constituents* of the bile are sin
those found in most other secreted fluids. It is possible that th
bonate and neutral phosphate of sodium and potassium, found
ashes of bile, are formed in the incineration, and do not exist as s
the fluid. Oxide of iron is said to be a common constituent of th
of bile, and copper is generally found in healthy bile, and consta
biliary calculi.

(*f*) *Gas.*—Small amounts of carbonic acid, oxygen, and ni
gases, may be extracted from bile.

*Functions of the Bile.*—Though it is not a true digestive fl
that it has no ferment and digests nothing itself, yet it must be re
as an important aid to digestion for the following reasons: There
doubt that it (*a*) assists in *emulsifying the fats* of the food, ar
rendering them capable of passing into the lacteals by absorption
it has appeared in some experiments in which the common bi
was tied, that, although the process of digestion in the stomach w
affected, chyle was no longer well formed; the contents of the l
consisting of clear, colorless fluid, instead of being opaque and wl
they ordinarily are, after feeding. It is, however, the combined
of the bile with the pancreatic juice to which the emulsification
rather than to that of the bile alone. The bile itself has a very

ulsifying power. If the theory be accepted that fats are absorbed as tty acids and soaps, in solution, the action of the bile becomes very portant because solutions of bile salts have the power of dissolving e fatty acids.

(b) It is probable, also, that the *moistening of the mucous membrane* the intestines by bile facilitates absorption of fatty matters through it.

(c) The bile, like the gastric fluid, has a certain but not very con- erable *antiseptic* power, and may serve to prevent the decomposition food during the time of its sojourn in the intestines. Experiments w that the contents of the intestines are much more fœtid after the mon bile-duct has been tied than at other times: moreover, it is nd that the mixture of bile with a fermenting fluid stops or spoils process of fermentation. This function may, very probably, be ex- ned by its so aiding fat digestion that the fats are absorbed before can decompose.

d) The bile has also been considered to act as a *natural purgative*, romoting an increased secretion of the intestinal glands, and by ulating the intestines to the propulsion of their contents. This view ves support from the constipation which ordinarily exists in jaun- from the diarrhœa which accompanies excessive secretion of bile, rom the purgative properties of ox-gall.

) The bile appears to have the power of *precipitating the gastric oses and peptones, together with the pepsin*, which is mixed up with , as soon as the contents of the stomach meet it in the duodenum. us stops the action of the pepsin. The purpose of this operation is bly both to delay any change in the proteoses until the pancreatic can act upon them, and also to prevent the pepsin from exercising lvent action on the ferments of the pancreatic juice. In some way esence seems also to aid the action of trypsin.

) As an *excrementitious* substance, the bile may serve especially as ium for the separation of certain highly carbonaceous substances the blood; and its adaptation to this purpose is well illustrated by culiarities attending its secretion and disposal in the fœtus. Dur- tra-uterine life, the lungs and the intestinal canal are almost in- ; there is no respiration of open air or digestion of food; these necessary, on account of the supply of well-elaborated nutriment ed by the vessels of the fœtus at the placenta. The liver, during me time, is proportionately larger than it is after birth, and the on of bile is active, although there is no food in the intestinal upon which it can exercise any digestive property. At birth, testinal canal is full of concentrated bile, mixed with intestinal on, and this constitutes the *meconium*, or fæces of the fœtus. fœtus, therefore, the main purpose of the secretion of bile must ectly excretive. Probably all the bile secreted in fœtal life is incorporated in the meconium, and with it discharged, and thus the liver may be said to discharge a function in some sense vicarious of that of the lungs. For, in the fœtus, nearly all the blood coming from the placenta passes through the liver, previous to its distribution to the several organs of the body; and the abstraction of certain substances will purify it, as in extra-uterine life it is purified by the separation of carbon dioxide and water at the lungs.

*Mode of Secretion and Discharge.*—The secretion of bile is continually going on, but is retarded during fasting, and accelerated on taking food. This has been shown by tying the common bile-duct of a dog, and establishing a fistulous opening between the skin and gall-bladder, whereby all the bile secreted was discharged at the surface. It was noticed that when the animal was fasting, sometimes not a drop of bile was discharged for several hours; but that, in about ten minutes after the introduction of food into the stomach, the bile began to flow abundantly, and continued to do so during the whole period of digestion.

The bile is formed in the hepatic cells; thence, being discharged into the minute hepatic ducts, it passes into the larger trunks, and from the main hepatic duct may be carried at once into the duodenum. This probably happens only while digestion is going on, *i.e.*, for 5 to 7 hours after the introduction of food into the stomach; during fasting, it regurgitates from the common bile-duct through the cystic duct, into the gall-bladder, where it accumulates till, in the next period of digestion, it is discharged into the intestine. The gall-bladder thus fulfils its office, that of a reservoir; for its presence enables bile to be constantly secreted, yet insures its employment in the service of digestion, although digestion is periodic, and the secretion of bile constant.

The mechanism by which the bile passes into the gall-bladder is simple. The orifice through which the common bile-duct communicates with the duodenum is narrower than the duct, and appears to be closed, except when there is sufficient pressure behind to force the bile through it. The pressure exercised upon the bile secreted during the intervals of digestion appears insufficient to overcome the force with which the orifice of the duct is closed; and the bile in the common duct, finding no exit in the intestine, traverses the cystic duct, and so passes into the gall-bladder, being probably aided in this retrograde course by the peristaltic action of the ducts. The bile is discharged from the gall-bladder and enters the duodenum on the introduction of food into the small intestine: being pressed on by the contraction of the coats of the gall-bladder, and of the common bile-duct also; for both these organs contain unstriped muscular fibre-cells. Their contraction is excited by the stimulus of the food in the duodenum acting so as to produce a reflex movement, the force of which is sufficient to open the orifice of the common bile-duct, which is closed by a sphincter.

Bile is not pre-formed in the blood. As just observed, it is secreted he hepatic cells, although some of its constituents may be brought hem almost in the condition for immediate secretion. The blood which the liver cells secrete the bile is that supplied to them by the l vein. This is shown by the alterations which occur in the pro- on the alteration of the pressure in the portal system. If the portal be obstructed, the amount of bile secreted diminishes, and is ulti- ly suppressed, death resulting. It has, however, been shown that extraordinary circumstances bile may be secreted by the aid of lood from the hepatic artery, since if a branch of the portal vein d, the part of the liver supplied by it continues to secrete bile, h in diminished quantity. When the discharge of the bile into testine is prevented by an obstruction of some kind, as by a *gall-* blocking the hepatic duct, it is reabsorbed in great excess into ood, and, circulating with it, gives rise to the well-known phenom- f jaundice. This is explained by the fact that the pressure of ion in the ducts although normally very low, not exceeding 15 n the dog, is still higher than that of the portal veins, and if it ds 16 mm. the secretion although formed ceases to be poured out, the opposing force be increased, the bile passes into the blood- s through the lymphatics, and the yellow color appears in the skin n the secretions, and constitutes the condition of jaundice. In ice the fæces are light colored and highly offensive, there is con- ion, the heart beats slowly, and from the presence of bile salts as s bile pigment in the blood, the red blood corpuscles may be in issolved. The latter action results in the presence of hæmoglobin an additional amount of bile pigment in the urine.

*sposal of the Bile.*—The simple excretion of the fœtal bile makes bable that the bile in extra-uterine life is also, at least in part, destined to be discharged as excrementitious. The analysis of the fæces however, that (except when rapidly discharged in purgation) they n very little of the bile secreted, probably not more than one-six- part of its weight, and that this portion includes chiefly its col- matter in the form of stercobilin, and some of its fatty matters ucin, but its salts to only a very slight degree, almost all of which een reabsorbed from the intestines into the blood. The bilirubin art converted into urobilin and is reabsorbed and excreted by the s in the urine.

e elementary composition of bile-salts shows such a preponderance bon and hydrogen that probably, after absorption, they combine xygen, and are excreted in the form of carbonic acid and water. ange after birth, from the direct to the indirect mode of excre- the bile may, with much probability, be connected with a purpose tion to the development of heat. The temperature of the fœtus is largely maintained by that of the parent, but, in extra-uterine life, there is (as one may say) a waste of material for heat when any excretion is discharged unoxidized; the carbon and hydrogen of bilin, therefore, instead of being ejected in the fæces, to a very large extent (viz., $\frac{7}{8}$), are reabsorbed, in order that they may be combined with oxygen, and that in the combination heat may be generated. It appears that taurocholic acid may easily be split up in the intestine into taurin and cholalic acid, and the same is probable of glycocholic acid. Taurin, glycin, and cholalic acid have all been detected in small amounts in the fæces. So that the bile is in part excreted, but in part is reabsorbed from the intestine (chiefly the large), and returned to the liver. What may be the ultimate destination of these altered or unaltered constituents is unknown. Glycin is supposed to go partly to form urea, and taurin is excreted to a slight extent in the urine as tauro-carbamic acid, but it is probable that although part of this may unite to re-form glycocholic or taurocholic acid, the remainder is united with oxygen, and is burnt off in the form of carbonic acid and water.

A substance, contained in the fæces, and named *stercorin*, is closely allied to cholesterin. Ten grains and a half of stercorin are excreted daily (A. Flint).

From the peculiar manner in which the liver is supplied with much of the blood that flows through it, it is probable that this organ is excretory, not only for such hydro-carbonaceous matters as may need expulsion from the blood, but that it serves for the direct purification of the stream which, arriving by the portal vein, has just gathered up various substances in its course through the digestive organs—substances which may need to be expelled almost immediately after their absorption. For it is easily conceivable that many things may be taken up during digestion, which not only are unfit for purposes of nutrition, but which would be positively injurious if allowed to mingle with the general mass of the blood. The liver, therefore, may be supposed placed in the only road by which such matters can pass unchanged into the general current, jealously to guard against their further progress, and turn them back again into an excretory channel. The frequency with which metallic poisons are either excreted by the liver, or intercepted and retained, often for a considerable time, in its own substance, may be adduced as evidence for the probable truth of this supposition.

The secretion of the bile by the hepatic cells is undoubtedly influenced by the amount of blood supplied to them. This is well seen after a meal, when the amount of blood passing through the portal circulation in consequence of the congestion of the secreting organs of the abdomen is greatly increased, and with it the bile secretion. It is, however, prob that the secretion of the cells is in some more direct way under the control of the nervous system, but how this influence is exercised is unknown. The antecedents of the various substances of the bile from which the cells manufacture its chief constituents are not exactly known. It is surmised that the bilirubin is formed from hæmoglobin brought from the spleen either actually dissolved in the plasma of the blood or n such a condition in the corpuscles as to be easily acted upon by the iver cells, by which the iron is separated. The bile salts are, at any ate in part, formed simply by the conjunction of glycin and taurin with holalic acid, all of which may be brought to the liver in the portal blood, but failing this it is probable that the hepatic cells can produce hese substances anew.

## The Intestinal Secretion, or Succus Entericus.

On account of the difficulty in isolating the secretion of the glands n the wall of the intestine (Brunner's and Lieberkühn's) from other ecretions poured into the canal (gastric juice, bile, and pancreatic se-retion), but little is known regarding the composition of the intestinal uice, or *succus entericus.*

It is said to be a yellowish alkaline fluid with a specific gravity of 011, and to contain about 2.5 per cent of solid matters (Thiry).

*Functions.*—The secretion is said to be able to convert proteids into eptones, and to convert starch into sugar, but the evidence in favor of ese actions is insufficient. The chief function of the juice is to act pon sugars. It possesses the power of converting cane into grape gar, and maltose into glucose. It also contains a milk-curdling fer-ent.

The reaction which represents the conversion of cane sugar into grape gar may be represented thus:

$$\underset{\text{Saccharose.}}{2\,C_{12}H_{22}O_{11}} + \underset{\text{Water.}}{2\,H_2O} = \underset{\text{Dextrose.}}{C_{12}H_{24}O_{12}} + \underset{\text{Lævulose.}}{C_{12}H_{24}O_{12}}$$

The conversion is probably effected by means of a hydrolytic ferment, *vertin* (Bernard).

## Summary of the Digestive Changes in the Small Intestine.

In order to understand the changes in the food which occur during passage through the small intestine, it will be well to refer briefly to state in which it leaves the stomach through the pylorus. It has n said before, that the chief office of the stomach is not only to mix o an uniform mass all the varieties of food that reach it through the ophagus, but especially to dissolve the nitrogenous portion by means its secretion. The fatty matters, during their sojourn in the stomach, become more thoroughly mingled with the other constituents of the food taken, but are not yet in a state fit for absorption. The conversion of starch into sugar, which began in the mouth, has been interfered with, if not altogether stopped. The soluble matters—both those which were so from the first, as sugar and saline matter, and the gastric peptones—have begun to disappear by absorption into the blood-vessels, and the same thing has befallen such fluids as may have been swallowed.

The thin pultaceous chyme, therefore, which, during the whole period of gastric digestion, is being constantly squeezed or strained through the pyloric orifice into the duodenum, consists of albuminous matter, broken down, dissolving and half dissolved; fatty matter broken down and melted, but not dissolved at all; starch very slowly in process of conversion into sugar, and as it becomes sugar, also dissolving in the fluids with which it is mixed; while with these are mingled gastric fluid, and fluid that has been swallowed, together with such portions of the food as are not digestible, and will be finally expelled as part of the fæces.

On the entrance of the chyme into the duodenum, it is subjected to the influence of the bile and pancreatic juice, which are then poured out, and also to that of the succus entericus. All these secretions have a more or less alkaline reaction, and by their admixture with the gastric chyme, its acidity becomes less and less until at length, at about the middle of the small intestine, the reaction becomes alkaline and continues so as far as the ileo-cæcal valve.

The special digestive functions of the small intestine may be taken in the following order:—

(1.) One important duty of the small intestine is the alteration of the *fat* in such a manner as to make it fit for absorption; and there is no doubt that this change is chiefly effected in the upper part of the small intestine. What is the exact share of the process, however, allotted respectively to the bile and to the pancreatic secretion, is still uncertain. The fat is changed in two ways. (*a.*) To a slight extent it is chemically decomposed by the alkaline secretions with which it is mingled, and a soap is the result. (*b.*) It is emulsionized, *i.e.*, its particles are minutely subdivided and diffused, so that the mixture assumes the condition of a milky fluid, or emulsion. As will be seen in the next Chapter, most of the fat is absorbed by the lacteals of the intestine, but a small part, which is saponified, is also absorbed by the blood-vessels.

(2.) The *albuminous* substances which have been partly dissolved in the stomach, and have not been absorbed, are subjected chiefly to the action of the pancreatic juice. The pepsin is rendered inert by being precipitated together with the gastric peptones and proteoses, as soon as the chyme meets with bile. By these means the pancreatic ferment trypsin is enabled to proceed with the further conversion of the proteoses into peptones, and part of the peptones (hemipeptone) into leucin and tyrosin. Albuminous substances, which are chemically altered in the process of digestion (peptones) and gelatinous matters similarly changed, are absorbed by the blood-vessels and lymphatics of the intestinal mucous membrane. Albuminous matters, in state of solution, which have not undergone the peptonic change, are probably, from the difficulty with which they *diffuse*, absorbed, if at all, almost solely by the lymphatics.

(3.) The *starchy*, or amyloid portions of the food, the conversion of which into maltose was more or less interrupted during their stay in the stomach, are now acted on briskly by the pancreatic juice and the succus entericus; and the sugar in the form of maltose is dissolved in the intestinal fluids, and is absorbed chiefly by the blood-vessels. During or just prior to its absorption, maltose is converted into dextrose.

(4.) *Saline* and *saccharine* matters, such as common salt, and cane ugar, if not in a state of solution beforehand in the saliva or other fluids which may have been swallowed with them, are at once dissolved in the tomach, and if not here absorbed, are soon taken up in the small intesine; the blood-vessels, as in the last case, being chiefly concerned in the bsorption. Cane sugar is in part or wholly converted into grape sugar efore its absorption. This is accomplished partially in the stomach, but lso by a ferment in the succus entericus.

(5.) The *liquids*, including in this term the ordinary drinks, as water, ine, ale, tea, etc., which may have escaped absorption in the stomach, re absorbed probably very soon after their entrance into the intestine; he fluidity of the contents of the latter being preserved more by the onstant secretion of fluid by the intestinal glands, pancreas, and liver, han by any given portion of fluid whether swallowed or secreted, reaining long unabsorbed. From this fact, therefore, it may be gathered hat there is a kind of circulation constantly proceeding from the intesnes into the blood, and from the blood into the intestines again; for all the fluid—a very large amount—secreted by the intestinal glands, ust come from the blood, the latter would be too much drained, were not that the same fluid after secretion is again reabsorbed into the rrent of blood—going into the blood charged with nutrient products digestion—coming out again by secretion through the glands in a mparatively unchanged condition.

At the lower end of the small intestine, the chyme, still thin and ltaceous, is of a light yellow color, and has a distinctly fæcal odor. his odor depends upon the formation of indol and other substances to again alluded to. In this state it passes through the ileo-cæcal openg into the large intestine.

## Summary of the Digestive Changes in the Large Intestine.

The changes which take place in the chyme in the *large* intestine are probably only the continuation of the same changes that occur in the course of the food's passage through the upper part of the intestinal canal. From the absence of villi, however, we may conclude that absorption, especially of fatty matter, is in great part completed in the small intestine; while, from the still half-liquid, pultaceous consistence of the chyme when it first enters the cæcum, there can be no doubt that the absorption of liquid is not by any means concluded. The peculiar odor, moreover, which is acquired after a short time by the contents of the large bowel, would seem to indicate a further chemical change in the alimentary matters or in the digestive fluids, or both. The acid reaction, which had disappeared in the small bowel, again becomes very manifest in the cæcum—probably from acid fermentation processes in some of the materials of the food.

There seems no reason to conclude that any special secondary digestive process occurs in the cæcum or in any other part of the large intestine. Probably any constituent of the food which has escaped digestion and absorption in the small bowel may be digested in the large intestine; and the power of this part of the intestinal canal to absorb fatty, albuminous, or other matters, may be gathered from the good effects of nutrient enemata, so frequently given when from any cause there is difficulty in introducing food into the stomach. In this connection, however, the possibility of nutrient enemata passing into the small intestine, as shown by the studies of Cannon, must be considered. In ordinary healthy digestion, however, the changes which ensue in the chyme after its passage into the large intestine are mainly the absorption of the more liquid parts; the chief function of the large intestine being to act as a reservoir for the residues of digestion before their expulsion from the body.

## Action of Micro-organisms in the Intestines.

Certain changes take place in the intestinal contents independent of, or at any rate supplemental to, the action of the digestive ferments. These changes are brought about by the action of micro-organisms o bacteria. We have indicated elsewhere that the digestive ferments ar examples of *unorganized* ferments, so bacteria are examples of organi ferments. Organized ferments, of which the yeast plant, *toru* (*saccharomyces*) *cerevisiæ*, may be taken as a typical example, consist o unicellular vegetable organisms, which when introduced into a suitabl culture medium grow with remarkable rapidity, and by their growth produce new substances from those supplied to them as food. Thus for example, when the yeast cell is introduced into a solution of grape sugar, it grows, and on the one hand alcohol, and on the other hand carbon dioxide are produced. These substances are not the direct result of the life of the cell, but probably arise from the formation of some chemical



Fig. 279.—Types of micro-organisms. *a*, micrococci arranged singly; in twos, diplococci—if all e micrococci at *a* were grouped together, they would be called staphylococci—and in fours, sarnæ: *b*, micrococci, in chains streptococci; *c* and *d*, bacilli of various kinds, one is represented ith flagellum; *e*, various forms of spirilla; *f*, spores, either free or in bacilli.

ubstances allied to the unorganized ferments which greatly increase in mount with the multiplication of the original cell. In all such fer-entative processes, organisms analogous to the yeast cell are present, nd it is not strange that if the ferment cell is introduced into a suit-ble medium, it may by its rapid reproduction have power to convert n unlimited amount of one substance into another. Speaking generally special variety of cell is concerned with each ferment action, thus one ariety has to do with alcoholic, another with lactic and another with etous fermentation. A considerable number of species of bacteria xist in the body during life, chiefly in connection with the mucous embranes, particularly of the digestive tract. These bacteria are nicellular organisms, devoid of chlorophyll, sometimes called *fission ngi* or *schizomycetes*. They multiply chiefly by division, but many of em also form spores—whereas the yeast cell multiplies by gemmation. he bacteria are very much smaller than the yeast cells, being only om 1 to $2\mu$ in width. Morphologically they are classified into i. *micro-cci* or globular bacteria, ii. *bacilli* or rod-shaped bacteria, and iii. *irilla* or sinuous bacteria.

Many forms of bacteria have been isolated from the mouth, a few rieties from the stomach, and a very large number from the intestines. is only in the last named locality that their multiplication has much fect from a physiological point of view. The normal (hydrochloric id) acidity of the stomach usually destroys all the micro-organisms ken in with the food, but when the amount of this acid is deficient (and metimes even when it is normal) some of the spores may escape. On reaching the small intestine these spores begin to develop in its alkaline medium, and may increase to such an extent as to stop all pancreatic and intestinal digestion; the point where this occurs varies from day to day. The large intestine always swarms with micro-organisms, though the ileo-cæcal valve, in some unknown way, prevents their passage into the small intestine; as a consequence, both intestinal and pancreatic digestion normally cease at this valve. The bacteria found in the intestine are anaerobic, *i.e.*, they do not exist in the presence of free oxygen.

The changes induced in the intestine by the activity of micro-organisms are of two kinds, fermentation and putrefaction; the former of these results in the breaking down of carbohydrate matter and the latter in that of proteid matter. The process of fermentation is the least complex and probably occurs normally in the small intestine, to a certain extent. The lactic-acid fermentation is the most importa though the butyric-acid fermentation is next; under their influence th carbohydrates are broken down into lactic and butyric acids, and perh into acetic acid also. Carbonic acid gas may be formed at the same ti and cause flatulence. Cellulose and other insoluble carbohydrates a decomposed with the formation of marsh gas and hydrogen, whi escape by the rectum.

In putrefaction the process is nearly the same as in tryptic digestio the proteids being broken down into peptones, leucin, tyrosin, and long row of other substances which have strong odors and belong to t aromatic group. It also results in the production of various gases, suc as carbon dioxide, sulphuretted hydrogen, ammonia, hydrogen a methane (marsh gas), and of a high percentage of the volatile fatty acid valerianic and butyric. Of the aromatic substances the most importa are indol and skatol, though their toxicity has been greatly ove estimated. Some undergo oxidation, indol and skatol forming indo and skatoxyl; they are usually carried off in the fæces, but when t bowel is obstructed they are absorbed and eventually appear in the uri indoxyl and skatoxyl forming respectively indoxyl- and skatoxyl-sulphu acids and their salts. Tyrosin is further broken down into para-ox phenol-proprionic acid, paracresol and phenol; para-oxy-phenol-ac acid is also formed.

### MOVEMENTS OF THE INTESTINES.

Much has been added to our knowledge concerning the moveme of the intestines by the recent studies of W. B. Cannon. He rende the movements of the intestinal contents visible on a fluorescent scre used with the *x*-ray, by mixing bismuth subnitrate, 10 to 33 per c with the food ingested. In the small intestine the most common mo ment is, first, a division of the contents of an intestinal loop int number of equal segments by a series of constriction rings. These segments are then subdivided and forced apart, and then by a new series of constrictions and dilatations of the tube forced together again. At the same time, a slow peristalsis may move the whole segmenting mass gradually along the small intestine toward its lower end. The effect of these rhythmical movements is to mix the food thoroughly with the igestive secretions and facilitate absorption, at the same time emptying he lymphatics and veins in the intestinal wall through compression. n the transverse and ascending colon, the most common movement is n anti- or reverse peristalsis. Food entering the large intestine is first orced by antiperistaltic waves into the cæcum; each succeeding instalent being treated in the same manner until the cæcum is filled; after hich the reverse waves and food-mass, being prevented from passing rther by the blind end of the cæcum, are forced out into the colon. t the same time, the ileo-cæcal valve prevents a regurgitation into the nall intestine. Thus again, in the cæcum, are the processes of absorpon favored by the series of constriction waves passing over its walls and mpressing the food-mass within it. From time to time strong general ntractions, in the cæcum and ascending colon, force some of the food ward.

When material has accumulated in the transverse colon, deep succesve tonic constrictions appear and force its contents into the descending lon. When sufficient material has accumulated here, it is evacuated strong peristalsis combined with compression by the contracting abminal muscles. This process is again repeated for new material ening.

Reverse or antiperistalsis does not commonly occur in the small intine, but large nutrient enemata introduced into the rectum and on may be forced by antiperistaltic waves in the large intestine to d through the ileo-cæcal valve into the small intestine. Here they treated in the same way as food which has been introduced in the mal way.

The intestinal movements are inhibited by strong emotions, such as r, distress, anger, and the like. In the cat, at least, they do not se during sleep or at night.

## nfluence of the Nervous System on Intestinal Digestion.

As in the case of the œsophagus and stomach, the peristaltic movets of the intestines may be directly set up in the muscular fibres by esence of chyme acting as the stimulus. Few or no movements when the intestines are empty. The intestines are connected he central nervous system both by the vagi and by the splanchnic

nerves, as well as by other branches of the sympathetic which co
them from the cœliac and other abdominal plexuses.

The relations of these nerves respectively to the movements
intestine and the secretions are probably the same as in the case
stomach already considered.

*Duration of Intestinal Digestion.*—The time occupied by the j
of a given portion of food from the stomach to the anus varies
erably even in health, and on this account probably it is that su
ferent opinions have been expressed in regard to the subject.
twelve hours are occupied by the journey of an ordinary meal t
the *small* intestine, and twenty-four to thirty-six hours by the
through the *large* bowel.

The contents of the large intestine, as they proceed toward t
tum, become more and more solid, and losing their more liqu
nutrient parts, gradually acquire the odor and consistence charac
of *fæces.* After a sojourn of uncertain duration in the sigmoid
of the colon, or in the rectum, they are finally expelled by the
defæcation.

The average quantity of solid fæcal matter evacuated by the
adult in twenty-four hours is about six or eight ounces (200
grams).

### COMPOSITION OF FÆCES.

The amount of water varies considerably, from 68 to 82 per c
upward. The following table is about an average composition:—

| | |
|---|---|
| Water . . . . . . . . . . . . . . | 73 |
| Solids, comprising: | 26 |
| a. Insoluble residues of the food, uncooked starch, cellulose, woody fibres, cartilage, seldom muscular fibres and other proteids, fat, cholesterin, horny matter, and mucin . . . . . . | |
| b. Certain substances resulting from decomposition of foods, indol, skatol, fatty and other acids, calcium and magnesium soaps . . . | |
| c. Special excrementitious constituents:—Excretin, excretoleic acid (Marcet), and stercorin (Austin Flint) . . . . . . . . . | |
| d. Salts:—Chiefly phosphate of magnesium and phosphate of calcium, with small quantities of iron, soda, lime, and silica . . . . . . | |
| e. Insoluble substances accidentally introduced with the food . . . . . . . . | |
| f. Mucus, epithelium, altered coloring matter of bile, fatty acids, etc. . . . . . . | |
| g. Varying quantities of other constituents of bile, and derivatives from them . . . . . . | |
| | 100 |

*The Gases contained in the Stomach and Intestines.*—Unde
nary circumstances, the alimentary canal contains a considerable

y of gaseous matter. Any one who has had occasion, in a post-mortem
amination, either to lay open the intestines, or to let out the gas
iich they contain, must have been struck by the small space afterward
cupied by the bowels, and by the large degree, therefore, in which the
, which naturally distends them, contributes to fill the cavity of the
lomen. Indeed, the presence of air in the intestines is so constant,
l, within certain limits, the amount in health so uniform, that there
be no doubt that its existence here is not a mere accident, but in-
ded to serve a definite and important purpose, although, probably, a
hanical one.

*Sources.*—The sources of the gas contained in the stomach and bowels
be thus enumerated:—

1. Air introduced in the act of swallowing either food or saliva; 2.
es developed by the decomposition of alimentary matter, or of the
etions and excretions mingled with it in the stomach and intestines;
t is probable that a certain mutual interchange occurs between the
s contained in the alimentary canal, and those present in the blood
hese gastric and intestinal blood-vessels; but the conditions of the
ange are not known, and it is very doubtful whether anything like
ue and definite secretion of gas from the blood into the intestines or
ach ever takes place. There can be no doubt, however, that the
stines may be the proper excretory organs for many odorous and
r substances, either absorbed from the air taken into the lungs in
iration, or absorbed in the upper part of the alimentary canal, again
e excreted at a portion of the same tract lower down—in either case
ming rapidly a gaseous form after their excretion, and in this way,
aps, obtaining a more ready egress from the body. It is probable
, under ordinary circumstances, the gases of the stomach and intes-
are derived chiefly from the second of the sources which have been
nerated.

## Composition of Gases of the Alimentary Canal.

(*Tabulated from various authorities by Brinton.*)

| hence obtained. | Composition by Volume. | | | | | |
|---|---|---|---|---|---|---|
| | Oxygen. | Nitrog. | Carbon. Acid. | Hydrog. | Carburet. Hydrogen. | Sulphuret. Hydrogen. |
| ach . . . | 11 | 71 | 14 | 4 | — | — |
| l Intestines . | — | 32 | 30 | 38 | — | trace. |
| m . . . | — | 67 | 12 | 8 | 13 | |
| . . . | — | 35 | 51 | 6 | 8 | |
| m . . . | — | 46 | 43 | — | 11 | |
| lled *per anum* | — | 22 | 40 | 19 | 19 | ½ |

The above table differs little from the average obtained by man modern observers, but it cmits an important point to which attention should be drawn, viz., that the amounts of the gases vary with the diet. For all practical purposes oxygen and sulphuretted hydrogen may be omitted. An analysis of the intestinal gases (Ruge, copied by Halliburton) in man is as follows:—

| Gases. | Milk Diet. | Meat Diet. | Vegetable Diet. |
|---|---|---|---|
| Carbon dioxide . . . . | 9 to 16 | 8 to 13 | 21 to 34 |
| Hydrogen . . . . | 43 to 54 | 0.7 to 3 | 1.5 to 4 |
| Carburetted hydrogen . . | 0.9 | 26 to 37 | 44 to 55 |
| Nitrogen . . . . . | 36 to 38 | 45 to 64 | 10 to 19 |

*Sources of the Carbon Dioxide.*—From the carbonates and lactates in food; from alcoholic fermentation of sugar; from putrefaction of carbohydrates and proteids; and from butyric acid fermentation.

*Sources of the Hydrogen.*—From butyric acid fermentations of lactic acid—

$$\underset{\text{Lactic Acid.}}{2\,C_3H_6O_3} = \underset{\text{Butyric Acid.}}{C_{11}H_8O_2} + 2\,CO_2 + 2\,H_2$$

*Source of the Carburetted Hydrogen.*—From the decomposition of acetates and lactates and from cellulose ($C_6H_{10}O_5 + H_2O = 3\,CO_2 + 3\,CH_4$).

*Source of the Nitrogen.*—The nitrogen is derived from the swallowed air.

## Defæcation.

The act of the expulsion of fæces is in part due to an increased refle peristaltic action of the lower part of the large intestine, namely o the sigmoid flexure and rectum, and in part to the more or less volun tary action of the abdominal muscles. In the case of active voluntar efforts, there is usually, first an inspiration, as in the case of coughin sneezing, and vomiting; the glottis is then closed, and the diaphrag fixed. The abdominal muscles are contracted as in expiration; but the glottis is closed, the whole of their pressure is exercised on the ab dominal contents. The sphincter of the rectum being relaxed, the ev uation of its contents takes place accordingly; the effect being, of cour increased by the peristaltic action of the intestine. As in the oth actions just referred to, there is as much tendency to the escape of th contents of the lungs or stomach as of the rectum; but the pressure relieved only at the orifice, the sphincter of which instinctively or i voluntarily yields.

*Nervous Mechanism.*—The anal sphincter muscle is normally in state of tonic contraction. The nervous centre which governs this co traction is probably situated in the lumbar region of the spinal cord, smuch as in cases of division of the cord above this region the sphincter egains, after a time, to some extent the tonicity which is lost immeditely after the operation. By an effort of the will, acting through the entre, the contraction may be relaxed or increased. In ordinary cases the apparatus is set in action by the gradual accumulation of fæces in the sigmoid flexure and rectum, pressing by the peristaltic action of these parts of the large intestine against the sphincter, and causing by eflex action its relaxation; this sensory impulse acting through the rain and reflexly through the spinal centre. At the same time that he sphincter is inhibited or relaxed, impulses pass to the muscles of the ower intestine increasing their peristalsis, and, if necessary, to the abominal muscles as well. The action of the centre is therefore double.

# CHAPTER X.

## ABSORPTION.

ABSORPTION takes place not only in the cells covering the external surface of the body and lining those cavities in direct communication with the external world, but, also, from cavities and spaces within the body proper. The former is sometimes spoken of as external absorption and the latter as internal absorption, a distinction which is useful for purposes of description only. In the first class are included the absorption of material from the skin, the lungs, and the alimentary tract, and its introduction into the blood and lymph, by means of which it is carried to the various tissues. In the second class is included the absorption of such circulating material from the blood and lymph by the different tissue-cells which come in contact with them. We may have, as in the case of intestinal absorption, then, two cavities, the intestinal and that of the blood or lymph vessels, separated by two membranes made up of living cells. One layer, in this case, consists of the intestinal epithelium, and the other of the endothelium of the blood or lymph vessels. Where absorption takes place within the body proper, as in the taking up of material by tissue-cells from the lymph spaces, the cell membrane, or ectoplasm where no definite membrane exists, is all that separates the protoplasm of the cell from the material to be absorbed. In the case of absorption from the alimentary canal by the blood or lymph there are actually two processes occurring—one, of absorption proper, or the taking in of material by the cell; and the other of elimination, or extrusion of material from the cell. In some instances the absorbed substances undoubtedly undergo important changes within the absorbing cell's protoplasm; *e.g.*, the probable synthesis of peptones into higher proteids during their passage through the epithelium of the stomach and intestine. In other instances, the absorbed material undergoes no change; *e.g.*, elimination of urea by the kidney epithelial cells.

### Methods of Absorption.

The exact methods by means of which absorption takes place has long been a subject of controversy and of research. This problem is one of the most difficult in physiology, and is yet, in the main, unsolved. Because known physical and chemical laws were inadequate to expl most of the phenomena of living processes, it was believed by the earlier physiologists that in these processes there existed an inexplicable something, a living or vital principle which was beyond our conception. As new facts in physics and chemistry were discovered, a second school of physiologists developed who sought to explain all the processes of life by known chemical and physical principles. Recently, the pendulum has again swung toward the former vitalistic views, but under another name—the selective activity of the cell. In either case, the name is a confession of our ignorance regarding the most important factors concerned in absorption, and such ignorance will continue until more is known about the physics and chemistry of the living cell itself. Some of the known physical factors concerned in absorption and elimination have already been considered in a former chapter (Chap. V., see *osmosis* and *diffusion*). A third factor, *filtration*, consists in the passage of a fluid under pressure through a membrane. These factors undoubtedly play an important rôle in the passage of solutions through the alimentary mucous membrane and walls of the absorbing vessels. The part which the physical factors play is more pronounced in the absorption of water and crystalloids. The nature of the fluid within the vessels, the very feeble power of dialysis which the albuminous blood possesses, determines the direction of the osmotic current, viz., into and not out of the blood-vessels. The current is, of course, aided by the fact of the constant change in the blood presented to the absorbing surface, as it rapidly circulates within the vessels, as well as by the movements of the walls of the stomach and intestines, in the case of alimentary absorption, by means of which the material to be absorbed is brought into intimate contact with the absorbing membrane. As a rule, the current is from the stomach or intestine into the blood; but the reversed action may occur, when, for example, sulphate of magnesia is taken into the stomach, in which case there is a rapid discharge of water from the blood-vessels into the alimentary canal, resulting in purgation.

*Rapidity of Absorption.*—The rapidity with which matters may be absorbed from the stomach, probably by the blood-vessels chiefly, and diffused through the textures of the body, has been found by experiment. It appears that lithium chloride may be diffused into all the vascular textures of the body, and into some of the non-vascular, as the cartilage of the hip-joint, as well as into the aqueous humor of the eye, in a quarter of an hour after being given on an empty stomach. Into the outer part of the crystalline lens it may pass after a time, varying from half an hour to an hour and a half. Lithium carbonate, when taken in five- ten-grain doses on an empty stomach, may be detected in the urine 5 or 10 minutes; or, if the stomach be full at the time of taking the se, in 20 minutes. It may sometimes be detected in the urine, more- er, for six, seven, or eight days.

Some experiments on the absorption of various mineral and ble poisons have brought to light the singular fact that, in some absorption takes place more rapidly from the rectum than from stomach. Strychnia, for example, when in solution, produces its sonous effects much more speedily when introduced into the rect than into the stomach. When introduced in the solid form, howev it is absorbed more rapidly from the stomach than from the rectu doubtless because of the greater solvent property of the secretion of former than of the latter.

*Conditions for Absorption.*—1. The diffusibility of the substanc be absorbed is one of the chief conditions for its absorption—a coll as we have seen, dialyzes very little. It must be also *in the liqui gaseous state.* Mercury may, however, be absorbed even in the met state; and in that state may pass into and remain in the blood-ve or be deposited from them; and such substances as exceedingly fi divided charcoal, when taken into the alimentary canal, have been f in the mesenteric veins. Oil, minutely divided, as in an emulsion, pass slowly into blood-vessels, as it will through a filter moistened water; but it is doubtful if fatty matters find their way into the b vessels as they do into the lymph-vessels of the intestinal canal.

2. The less *dense the fluid to be absorbed, the more speedy*, as a eral rule, is its absorption by the living blood-vessels. Hence the absorption of water from the intestines; also of weak saline solut but with strong solutions, there appears less absorption into, than sion from, the blood-vessels.

3. The absorption is *the less rapid the fuller and tenser the vessels* are; and the tension may be so great as to hinder altogethe entrance of more fluid. Thus, if physiological salt solution is inj into a dog's veins to repletion, poison is absorbed very slowly; but the tension of the vessels is diminished by bleeding, the poison quickly. So, when cupping-glasses are placed over a poisoned wo they retard the absorption of the poison not only by diminishin velocity of the circulation in the part, but by filling all its vessel full to admit more.

4. On the same ground, absorption *is the quicker the more rapi circulation of the blood;* not because the fluid to be absorbed is quickly imbibed into the tissues, or mingled with the blood, but be as fast as it enters the blood, it is carried away from the part, an blood being constantly renewed, is constantly as fit as at the firs the reception of the substance to be absorbed.

These four conditions are physical, but (5) the *vital condition* o absorptive epithelium must not be forgotten. It has been show example, that the absorption by the frog's skin is hastened by al tarded by chloroform. It appears also that absorption is retarded than hastened by removal of the intestinal epithelium.

## The Lymphatic System.

aving now discussed the methods and conditions of absorption in ral, we must next turn to the system of vessels in which, on the and, materials of the food not taken directly into the blood-vessels alimentary canal are received and carried into the blood-stream; n the other, fluid which has exuded from the blood-vessels into the



Fig. 280.—Diagram of the principal groups of Lymphatic vessels (from Quain).

is gathered up and carried back again into the blood. This sys- vessels is called the Lymphatic System, and the vessels themselves ned Lymphatics or Absorbents. They have often been incidentally ned in former chapters.

e principal vessels of the lymphatic system are, in structure and l appearance, like very small and thin-walled veins. They are ed with valves. They commence in fine microscopic *lymph-cap-*

*illaries*, which drain the intercellular or lymph spaces, and they end directly or indirectly in two trunks which open into the large veins near the heart (fig. 280). The fluid which they contain, unlike the blood, passes only in one direction, namely, from the fine branches to the trunk and so to the large veins, on entering which they are mingled with the stream of blood and form part of its constituents. The course of the fluid in the lymphatic vessels is always toward the large veins in the neighborhood of the heart, and in fig. 280 the greater part of the contents of the lym-phatic system of vessels will be seen to pass through a comparatively large trunk called the *thoracic duct*, which finally empties its cont into the blood-stream, at the junction of the internal jugular and clavian veins of the left side. There is a smaller duct on the right The lymphatic vessels of the intestinal canal are called *lacteals*, bec



Fig. 281.



Fig. 282.

Fig. 281.—Superficial lymphatics of right groin and upper part of thigh, $\frac{1}{6}$.—1. Upper inguinal glands. 2, 2′. Lower or inguinal or femoral glands. 3, 3′. Plexus of lymphatics in the course of the long saphenous vein. (Mascagni.)

Fig. 282.—Lymphatic vessels of the head and neck and the upper part of the trunk (Mascagni). $\frac{1}{6}$.—The chest and pericardium have been opened on the left side, and the left mamma detached and thrown outward over the left arm, so as to expose a great part of its deep surface. The principal lymphatic vessels and glands are shown on the side of the head and face, and in the neck, axilla and mediastinum. Between the left internal jugular vein and the common carotid artery, the upper ascending part of the thoracic duct marked 1, and above this, and descending to 2, the arch and last part of the duct. The termination of the upper lymphatics of the diaphragm in the mediastinal glands, as well as the cardiac and the deep mammary lymphatics, is also shown.

gestion the fluid contained in them resembles milk in appear-
l the *lymph* in the lacteals during the period of digestion is
*le.* There is no essential distinction, however, between lacteals
hatics. In some parts of its course the lymph-stream must
pass through *lymphatic glands.*

Lymphatic vessels are distributed in nearly all parts of the body. Their existence, however, has not yet been determined in the placenta, the umbilical cord, the membranes of the ovum, or in any of the so-called non-vascular parts, as the nails, cuticle, hair, and the like.

*Origin of Lymph Capillaries.*—The lymphatic capillaries commence most commonly either (*a*) in closely meshed networks, or (*b*) in irregular lacunar spaces between the various structures of which the different organs are composed. Such irregular spaces, forming what is now termed



283.

Fig. 284.

Superficial lymphatics of the forearm and palm of the hand, $\frac{1}{5}$.—5. Two small glands
f the arm. 6. Radial lymphatic vessels. 7. Ulnar lymphatic vessels. 8, 8. Palmar
hatics. 9, 9′. Outer and inner sets of vessels. *b*. Cephalic vein. *d*. Radial vein.
n. *f*. Ulnar vein. The lymphatics are represented as lying on the deep fascia.

Lymphatics of central tendon of rabbit's diaphragm, stained with silver nitrate. The
nce has been shaded diagrammatically to bring out the lymphatics clearly. *l*. Lym-
by long narrow endothelial cells, and showing *v*, valves at frequent intervals. (Scho-

-canalicular system, have been shown to exist in many tis-
erous membranes such as the omentum and mesentery they
connected system of very irregular branched spaces partly
y connective tissue-corpuscles, and both in these and in many
es are found to communicate freely with regular lymphatic

vessels. In many cases, though they are formed mostly by the chinks and crannies between the blood-vessels, secreting ducts, and other parts which may happen to form the framework of the organ in which they exist, they are lined by a distinct layer of endothelium.

The lacteals offer an illustration of another mode of origin, namely, (*c*) in blind dilated extremities; but there is no essential difference in structure between these and the lymphatic capillaries of other parts.

*Structure of Lymph Capillaries.*—The structure of lymphatic capillaries is very similar to that of blood-capillaries: their walls consist of a single layer of elongated endothelial cells with sinuous outline, which cohere along their edges to form a delicate membrane. They differ from blood capillaries mainly in their larger and very variable calibre, and in their numerous communications with the spaces of the lymph-canalicular system.

*Communications of the Lymphatics.*—The fluid part of the blood constantly exudes from or is strained through the walls of the blood-capillaries, so as to moisten all the surrounding tissues, and occupies the interspaces which exist among their different elements, which form the beginnings of the lymph-capillaries; and the latter, therefore, are the means of collecting the exuded blood plasma, and returning that part which is not directly absorbed by the tissues into the blood-stream. It is not necessary to assume the presence of any special channels between the blood and lymphatic vessels, inasmuch as even blood-corpuscles can pass bodily, without much difficulty, through the walls of the blood-capillaries and small veins, and could pass with still less trouble, probably, through the comparatively ill-defined walls of the capillaries which contain lymph.

It has been already mentioned (p. 31) that in certain parts of the body, *stomata* exist, by which lymphatic capillaries directly communicate with parts hitherto supposed to be closed cavities.

Stomata have been found in the pleura; and as they may be presumed to exist in other serous membranes, it would seem as if the serous cavities, hitherto supposed closed, form but a large lymph-sinus or widening out, so to speak, of the lymph-capillary system with which they directly communicate.

When absorption into the lymphatic system takes place in membranes covered by epithelium or endothelium through the interstitial or intercellular cement-substance, it is said to take place through *pseudo-stomata*, already alluded to (p. 32).

*Demonstration of Lymphatics of Diaphragm.*—The stomata on the peritoneal surface of the diaphragm are the openings of short vertical canals which up into the lymphatics, and are lined by cells like those of germinating e thelium. By introducing a solution of Berlin blue into the peritoneal ca of an animal shortly after death, and suspending it, head downward, ar

tion of the lymphatic vessels of the diaphragm, through the stomata on its
ritoneal surface, may readily be obtained if artificial respiration be carried
for about half an hour. In this way it has been found that in the rabbit
e lymphatics are arranged between the tendon bundles of the centrum ten-
neum; and they are hence termed *interfascicular*. The centrum tendineum
coated by endothelium on its pleural and peritoneal surfaces, and its substance
nsists of tendon bundles arranged in concentric rings toward the pleural
le and in radiating bundles toward the peritoneal side.

The lymphatics of the anterior half of the diaphragm open into those of the
terior mediastinum, while those of the posterior half pass into a lymphatic
ssel in the posterior mediastinum, which soon enters the thoracic duct.
th these sets of vessels, and the glands into which they pass, are readily
jected by the method above described; and there can be little doubt that
ring life the flow of lymph along these channels is chiefly caused by the
tion of the diaphragm during respiration. As it descends in inspiration,
e spaces between the *radiating* tendon bundles dilate, and lymph is sucked
om the peritoneal cavity, through the widely open stomata, into the inter-
scicular lymphatics. During expiration, the spaces between the *concentric*
ndon bundles dilate, and the lymph is squeezed into the lymphatics toward
he pleural surface (Klein). It thus appears probable that during health there
s a continued sucking in of lymph from the peritoneum into the lymphatics
y the "pumping" action of the diaphragm; and there is doubtless an equally
ontinuous exudation of fluid from the general serous surface of the perito-
eum. When this balance of transudation and absorption is disturbed either
y increased transudation or some impediment to absorption, an accumulation
f fluid necessarily takes place (ascites).

*Structure of Lymphatic Vessels.*—The larger vessels as before men-
ioned are very like veins, having an external coat of areolar tissue, with
lastic filaments; within this, a thin layer of areolar tissue, with un-
riped muscular fibres, which have, principally, a circular direction,
d are much more abundant in the small than in the larger vessels;
d again, within this, an inner elastic layer of longitudinal fibres, and
lining of epithelium; and numerous valves. The valves, constructed
ke those of veins, and with the free edges turned toward the heart,
e usually arranged in pairs, and, in the small vessels, are so closely
aced, that when the vessels are full, the valves constricting them
here their edges are attached, give them a peculiar beaded or knotted
pearance.

## The Lymph Flow.

The flow of the lymph toward the point of its discharge into the veins
brought about by several agencies. With the help of the valvular
echanism (1) all occasional pressure on the exterior of the lymphatic
d lacteal vessels propels the lymph onward: thus muscular and other
ternal pressure accelerates the flow of the lymph as it does that of
blood in the veins. The actions of (2) the muscular fibres of the

small intestine, and probably the layer of unstriped muscle present in each intestinal villus, seem to assist in propelling the chyle: for, in the small intestine of a mouse, the chyle has been seen moving with intermittent propulsions that appeared to correspond with the peristaltic movements of the intestine. But for the general propulsion of the lymph and chyle, it is probable that, together with (3) the *vis a tergo* resulting from absorption (as in the ascent of sap in a tree), and from external pressure, some of the force may be derived (4) from the contractility of the vessel's own walls. The respiratory movements, also, (5) favor the current of lymph through the thoracic duct as they do the current of blood in the thoracic veins.

**Lymph-Hearts.**—In reptiles and some birds, an important auxiliary to the movement of the lymph and chyle is supplied in certain muscular sacs, named *lymph-hearts*, and it has been shown that the caudal heart of the eel is a lymph-heart also. The number and position of these organs vary. In frogs and toads there are usually four, two anterior and two posterior; in the frog, the posterior lymph-heart on each side is situated in the ischiatic region, just beneath the skin; the anterior lies deeper, just over the transverse process of the third vertebra. Into each of these cavities several lymphatics open, the orifices of the vessels being guarded by valves, which prevent the retrograde passage of the lymph. From each heart a single vein proceeds, and conveys the lymph directly into the venous system. In the frog, the inferior lymphatic heart, on each side, pours its lymph into a branch of the ischiatic vein; by the superior, the lymph is forced into a branch of the jugular vein, which issues from its anterior surface, and which becomes turgid each time that the sac contracts. Blood is prevented from passing from the vein into the lymphatic heart by a valve at its orifice.

The muscular coat of these hearts is of variable thickness; in some cases it can only be discovered by means of the microscope; but in every case it is composed of striped fibres. The contractions of the hearts are rhythmical, occurring about sixty times in a minute, slowly, and, in comparison with those of the blood-hearts, feebly. The pulsations of the cervical pair are not always synchronous with those of the pair in the ischiatic region, and even the corresponding sacs of opposite sides are not always synchronous in their action.

Unlike the contractions of the blood-heart, those of the lymph-heart appear to be directly dependent upon a certain limited portion of the spinal cord. For Volkmann found that so long as the portion of spinal cord corresponding to the third vertebra of the frog was uninjured, the cervical pair of lymphatic hearts continued pulsating after all the rest of the spinal cord and the brain were destroyed; while destruction of this portion, even though all other parts of the nervous centres were uninjured, instantly arrested the heart's movements. The posterior, or ischiatic, pair of lymph-hearts were found to be governed, in like manner, by the portion of spinal cord corresponding to the eighth vertebra. Division of the posterior spinal roots did not arrest the movements; but division of the anterior roots caused them to cease at once.

**Lymphatic Glands.**—Lymphatic glands are small round or oval compact bodies varying in size from a hemp-seed to a bean, interposed course of the lymphatic vessels, and through which the chief part lymph passes in its course to be discharged into the blood-vessels. re found in great numbers in the mesentery, and along the great of the abdomen, thorax, and neck; in the axilla and groin; a



85.—Section of a mesenteric gland from the ox, slightly magnified. *a*, Hilus; *b* (in the rt of the figure), medullary substance; *c*, cortical substance with indistinct alveoli; *d*, (Kölliker.)

the popliteal space, but not farther down the leg, and in the far as the elbow. Some lymphatics do not, however, pass through before entering the thoracic duct.

*ucture.*—A lymphatic gland is covered externally by a capsule of tive tissue, generally containing some unstriped muscle. At the ide of the gland, which is somewhat concave (*hilus*), (fig. 285, *a*),



86.—Section of medullary substance of an inguinal gland of an ox. *a*, *a*, glandular sub pulp forming rounded cords joining in a continuous net (dark in the figure); *c*, *c*, tra he space, *b*, *b*, between these and the glandular substance is the lymph sinus, washed clear cles and traversed by filaments of retiform connective-tissue. × 90. (Kölliker.)

sule sends inward processes called *trabeculæ* in which the blood- are contained, and these join with other processes prolonged from er surface of the part of the capsule covering the convex or outer the gland; they have a structure similar to that of the capsule, tering the gland from all sides, and freely communicating, form a fibrous supporting *stroma*. The interior of the gland is seen on section, even when examined with the naked eye, to be made up of two parts, an outer or *cortical* (fig. 287, *c*, *c*), which is light colored, and an inner of redder appearance, the *medullary* portion (fig. 285). In the outer or cortical part of the gland (fig. 287) the intervals between the trabeculæ are comparatively large, and form more or less triangular intercommunicating spaces termed *alveoli;* while in the more central or medullary part is a finer meshwork formed by the more free anastomosis of the trabecular process. Within the alveoli of the cortex and in the meshwork formed by the trabeculæ in the medulla, is contained the proper gland structure. In the former it is arranged as follows: occupying the central and chief part of each alveolus is a more or less wedge-shaped mass of adenoid tissue, densely packed with lymph corpuscles; but at the periphery surrounding the central portion and immediately next the capsule and trabeculæ, is a more open meshwork of adenoid tissue constituting the *lymph sinus* or *channel*, and containing fewer lymph-corpuscles. The central mass is inclosed in endothelium, the cells of which join by their processes, the processes of the adenoid framework of the lymph sinus. The trabeculæ are also covered with endothelium. The lining of the central mass does not prevent the passage of fluids and even of corpuscles into the lymph sinus. The framewor adenoid tissue of the lymph sinus is nucleated, that of the central is non-nucleated. At the inner part of the alveolus, the wedge-sha



Fig. 287.—Diagrammatic section of lymphatic gland. *a.l.*, afferent ; *e.l.*, efferent lymphatics; *C*, cortical substance; *l.h.*, reticulating cords of medullary substance; *l.s.*, lymph-sinus; *c.*, fibrous coat sending in trabeculæ ; *t.r.*, into the substance of the gland. (Sharpey.)

entral mass divides into two or more smaller rounded or cord-like asses which joining with those from the other alveoli, form a much loser arrangement of the gland tissue than in the cortex; spaces (fig. 88, *b*), are left within those anastomosing cords, in which are found ortions of the trabecular meshwork and the continuation of the lymph inus.

The essential structure of lymphatic-gland substance resembles that hich was described as existing, in a simple form, in the interior of the litary and agminated intestinal follicles.

The lymph enters the gland by several afferent vessels, which open



Fig. 288.—A small portion of medullary substance from a mesenteric gland of the ox. *d*, *d*, tra-læ; *a*, part of a cord of glandular substances from which all but a few of the lymph-corpuscles been washed out to show its supporting meshwork of retiform tissue and its capillary blood-els (which have been injected, and are dark in the figure); *b*, *b*, lymph-sinus, of which the reti- tissue is represented only at *c*, *c*. × 300. (Kölliker.)

eath the capsule into the lymph-channel or lymph-path; at the same e they lay aside all their coats except the endothelial lining, which continuous with the lining of the lymph-path. The *efferent* vessels gin in the medullary part of the gland, and are continuous with the nph-path here as the afferent vessels were with the cortical portion; endothelium of one is continuous with that of the other.

The efferent vessels leave the gland at the *hilus*, the more or less cave inner side of the gland, and generally either at once or very after join together to form a single vessel.

ood-vessels which enter and leave the gland at the hilus are freely uted to the trabecular tissue and to the gland-pulp.

**Hæmolymph Glands.**—In the prevertebral, retroperitonea of the sheep, ox, and other animals, there are found in large n and in man in small numbers, glands which resemble the ly glands described above, but differing from them, mainly, in po sinuses containing blood instead of lymph. For these structures, ally described by Gibbes, the name *hæmolymph glands* was sugge Russell, and has been adopted by subsequent workers. Warthi has recently made a detailed study of the nature and function o structures, finds two recognizable types, which he has respectivel splenolymph and marrowlymph nodes. Between these two types, tion forms exist. There are also transition forms between the lymph glands and the spleen and lymph glands. New hæm glands may be formed from adipose tissue. This is very marke splenectomy.

The function of these glands is, probably, normally one of hæ and new formation of leucocytes. In disease, where the blood has gone marked changes, they may be concerned in the development blood-cells as well.

## The Lymph and Chyle.

*Lymph* is, under ordinary circumstances, a clear, transpare yellowish fluid, of a specific gravity varying from 1012—1022. devoid of smell, is slightly alkaline, and has a saline taste. As se the microscope in the small transparent vessels of the tail of pole, it usually contains no corpuscles or particles of any kind; only in the larger trunks that any corpuscles are to be found. corpuscles are similar to colorless blood-corpuscles. The fluid i the corpuscles float is albuminous, and contains no fatty partic is liable to variations according to the general state of the blood that of the organ from which the lymph is derived. It may clo posure to the air. As it advances toward the thoracic duct, af ing through the lymphatic glands, it becomes spontaneously co and the number of corpuscles is much increased.

*Chyle*, found in the lacteals after a meal, is an opaque, whitis fluid, neutral or slightly alkaline in reaction. Its whiteness and are due to the presence of innumerable particles of oily or fatty of exceedingly minute though nearly uniform size, measuring average about [illegible] of an inch (0.8[illegible]). These constitute what is the molecular base of chyle. Their number, and consequently t ity of the chyle, are dependent upon the quantity of fatty mat tained in the food. The fatty nature of the molecules is made by their solubility in ether. Each molecule probably consists of let of oil coated over with albumen, in the manner in which rops of oil always become covered in an albuminous solution. This is roved when water or dilute acetic acid is added to chyle, many of the olecules are lost sight of, and oil-drops appear in their place, as the vestments of the molecules have been dissolved, and their oily con- nts have run together.

Except these molecules, the chyle taken from the villi or from lac- als near them, contains no other solid or organized bodies. The fluid which the molecules float is albuminous, and does not spontaneously agulate. But as the chyle passes on toward the thoracic duct, and pecially while traversing one or more of the mesenteric glands, it is aborated. The quantity of molecules and oily particles gradually di- inishes; cells, to which the name of *chyle-corpuscles* is given, appear it; and it acquires the property of coagulating spontaneously. The gher in the thoracic duct the chyle advances, the greater is the num- er of chyle-corpuscles, and the larger and firmer is the clot which forms it when withdrawn and left at rest. Such a clot is like one of blood ithout the red corpuscles, having the chyle-corpuscles entangled in it, d the fatty matter forming a white creamy film on the surface of the rum. But the clot of chyle is softer and moister than that of blood. ike blood, also, the chyle often remains for a long time in its vessels ithout coagulating, but coagulates rapidly on being removed from them. he existence of the materials which, by their union, form fibrin, is, erefore, certain; and their increase appears to be commensurate with at of the corpuscles.

The structure of the chyle-corpuscles was described when speaking the white corpuscles of the blood, with which they are identical. *The nph, in chemical composition, resembles diluted plasma,* and from what been said, it will appear that *perfect chyle and lymph are, in essen- characters, nearly similar, and scarcely differ, except in the prepon- ance of fatty and proteid matter in the chyle.*

CHEMICAL COMPOSITION OF LYMPH AND CHYLE.

| | I. Lymph. (Donkey). | II. Chyle. (Donkey). | III. Mixed Lymph & Chyle (Human). |
|---|---|---|---|
| Water . . . . . . . | 96.536 | 90.237 | 90.48 |
| Solids . . . . . . . | 3.454 | 9.763 | 9.52 |
| lids— | | | |
| Proteids, including Serum-Albumin, Fibrinogen, and Globulin. | 1.320 | 3.886 | 7.08 |
| Extractives, including in (I and II) Sugar, Urea, Leucin and Cholesterin . . . . | 1.559 | 1.565 | 1.08 |
| tty matter and Soaps . . . | a trace | 3.601 | .92 |
| lts . . . . . . . | .585 | .711 | .44 |

*Quantity.*—The quantity which would pass into a cat's blood in nty-four hours has been estimated to be equal to about one-sixth of the weight of the whole body. And, since the estimated weight of the blood in cats is to the weight of their bodies as 1 to 7, the quantity of lymph daily traversing the thoracic duct would appear to be about equal to the quantity of blood at any time contained in the animals. By another series of experiments, the quantity of lymph traversing the thoracic duct of a dog in twenty-four hours was found to be about equal to two-thirds of the blood in the body.

## CHANNELS OF ABSORPTION.

*The Lacteals.*—During the passage of the chyme along the intestinal canal, its completely digested parts are absorbed into the blood and distributed in the mucous membrane. The absorption into both sets of vessels is carried on *most actively but not exclusively, in the villi* of the small intestine; for in them both the capillary blood-vessels and the lacteals are brought almost into contact with the intestinal contents. There seems to be no doubt that absorption of fatty matters during digestion, from the contents of the intestines, is effected chiefly through



Fig, 289.—Section of the villus of a rat killed during fat absorption. *ep*, epithelium; *str*, stri border; *c*, lymph-cells; *c'*, lymph-cells in the epithelium; l, central lacteal containing disintegrat lymph-corpuscles. (E. A. Schäfer.)

the epithelial cells which line the intestinal tract, and especially thos which clothe the surface of the villi. Thence, the fatty particle passed on into the interior of the lacteal vessels, but how they pass, what laws govern their passage, are not at present exactly known. lymph-corpuscles of the villi are however. in some animals. *e.g.*, th and frog, important agents in effecting the passage of fat-particles into the lacteals. These cells take up the fat which has passed through the columnar cells and then, by reason of their amœboid movement, carry it in to the lacteal. When arrived there they break up and set free both fat and proteid matter thereby.

The process of absorption is assisted by the pressure exercised on the contents of the intestines by their contractile walls; and the absorption of fatty particles is also facilitated by the presence of the bile, and the pancreatic and intestinal secretions, which moisten the absorbing surface.

*The Lymphatics.*—The lymph is diluted *liquor sanguinis,* which is always exuding from the blood-capillaries into the interstices of the tissues in which they lie; and as these interstices form in most parts of the body the beginnings of the lymphatics, the source of the lymph is sufficiently obvious. In connection with this may be mentioned the fact that changes in the character of the lymph correspond very closely with changes in the character of either the whole mass of blood, or of that n the vessels of the part from which the lymph is exuded. Thus it appears that the coagulability of the lymph, although always less than, is directly proportionate to that of the blood; and that when fluids are inected into the blood-vessels in sufficient quantity to distend them, the njected substance may be almost directly afterward found in the ymphatics.

Some other matters than those originally contained in the exuded iquor sanguinis may, however, find their way with it into the lymphatic essels. Parts which having entered into the composition of a tissue, nd, having fulfilled their purpose, require to be removed, may not be ltogether excrementitious, but may admit of being reorganized and dapted again for nutrition; and these may be absorbed by the lym-



290.—Mucous membrane of frog's intestine during fat absorption. ep, epithelium; str, striated border; C, lymph corpuscles; *l*, lacteal. (E. A. Schäfer.)

atics, and elaborated with the other contents of the lymph in passing rough the glands.

*The Blood-Vessels.*—In the absorption by the lymphatic or lacteal ssels just described there appears something like the exercise of choice in the materials admitted into them. This is not the case with the blood-vessels; it appears that every substance, whether gaseous, liquid, or a soluble, may be absorbed by the blood-vessels, provided it is capable of permeating their walls, and of mixing with the blood.

## Where Absorption May Take Place.

*In the Alimentary Canal.*—The greatest activity of absorption occurs in the alimentary canal. In it the materials of the duly digested food find their way by means of this process on the one hand into the blood-vessels of the portal circulation, and on the other into the lacteal vessels which are, as we have seen, the commencements of the lymphatic vessels of the intestines.

*In the Stomach.*—Recent experiments have shown that though absorption does take place in the stomach, it is not as active as was formerly supposed, even in the case of water. Von Mering has found that water begins to pass from the stomach into the intestine almost as soon as it is swallowed, and that very little of it is absorbed from the stomach. Of 500 cc. given by mouth to a large dog, only 5 cc. were absorbed in 25 minutes, the rest having passed into the intestine. Peptones and sugars are absorbed in the stomach, but only to a limited extent, and the same is true of salts. Fats are not absorbed at all in the stomach. In all cases absorption from the stomach is much increased by alcohol and condiments, such as pepper and mustard.

*In the Small Intestine.*—All the products of digestion are absorbed in the small intestine, as is abundantly shown by experiments. The absorption of fats has been already described. Recently absorption from the small intestine has been studied in the human subject in the case of a patient who had a fistulous opening in the lower part of the ileum. Eighty-five per cent of the proteid of a test-meal was absorbed before the food reached the fistula. Though water and salts are freely absorbed, the intestinal contents does not lose much in bulk or fluidity because of the quantity of water added in the alimentary secretions. In absorption, sugar is changed either just before or during its passage through the wall of the intestine from maltose into dextrose.

*In the Large Intestine.*—A great deal of absorption takes place in the large intestine. This is evident from the fact that the intestinal contents is very fluid when it enters the large intestine, and almost solid when it leaves it. Its contents pass through the large intestine very slowly, usually occupying about 12 hours. In addition to water and salts, the sugar, proteid, and fats not absorbed in the small intestine are almost entirely absorbed here.

The power of absorption in the large intestine sometimes forms a tant feature in medical practice. When patients cannot swallow or liquid food, or retain what has been swallowed, they may be shed by rectal feeding. The large intestine shows a remarkable in its ability to absorb unchanged albumins, such as white of egg, ll as peptones and proteoses. Some of this may be due to the passf the nutrient enema back into the small intestine past the ileovalve.

the stomach, as well as in both the large and small intestine, the ption of water, salts, proteids, and sugars takes place chiefly into lood-vessels.

*hrough the Skin.*—It has been shown that metallic preparations d into the skin have the same action as when given internally, in a less degree. Mercury applied in this manner exerts its spenfluence upon syphilis, and excites salivation; potassio-tartrate of ony may excite vomiting, or an eruption extending over the whole ; and arsenic may produce poisonous effects. Vegetable matters, if soluble, or already in solution, give rise to their peculiar effects, hartics, narcotics, and the like, when rubbed into the skin. The of rubbing is probably to convey the particles of the matter into rifices of the glands, whence they are more readily absorbed than would be through the epidermis. When simply left in contact he skin, substances, unless in a fluid state, are seldom absorbed.

has long been a contested question whether the skin covered with idermis has the power of absorbing water; and it is a point the difficult to determine because the skin loses water by evaporation. rom the result of many experiments, it may now be regarded as a scertained fact that such absorption really occurs. The absorption er by the surface of the body may take place in the lower animals apidly. Not only frogs, which have a thin skin, but lizards, in the cuticle is thicker than in man, after having lost weight by kept for some time in a dry atmosphere, are found to recover both weight and plumpness very rapidly when immersed in water. merely the tail, posterior extremities, and posterior part of the of the lizard are immersed, the water absorbed is distributed hout the system. And a like absorption through the skin, though ss extent, may take place also in man.

severe cases of dysphagia, when not even fluids can be taken into mach, immersion in a bath of warm water or of milk and water suage the thirst; and it has been found in such cases that the of the body is increased by the immersion. Sailors also, when te of fresh water, find their urgent thirst allayed by soaking their in salt water, and wearing them in that state; but these effects part due to the hindrance to the evaporation of water from the

*Through the Lungs.*—It is a remarkable fact that not only is the epithelium of the pulmonary air vesicles able to allow the passage through it of gases and volatile substances, but that also under certain conditions fluids such as water may also be absorbed, and besides this, the presence of carbon particles in the bronchial glands and elsewhere in connection with the lungs must point to the pulmonary epithelium as the only possible channel of their absorption.

# CHAPTER XI.

## METABOLISM, NUTRITION, AND DIET.

THE term *metabolism* is the English equivalent of the German *Stoffwechsel*, meaning, literally, an exchange of material. In its broadest physiological sense it includes the study of the exchange of material between the tissues of the body and their surrounding media. Strictly speaking, digestion, secretion, and excretion should be included. These subjects are for convenience, however, discussed in detail under separate chapters, and will be considered here only in their essential relation to metabolism in general. This includes the study of the income and outgo of material; the storing of energy in the body; the transfer of this potential energy into kinetic energy; and the nutrition of the various tissues. The building up of absorbed food material into the protoplasm of the cell or of simpler compounds into more complex ones, which may be stored in the tissues, is known as *anabolism*, and the compounds themselves as *anabolites*. The breaking down of these substances into simpler forms, whereby the potential energy of the anabolites is transformed into kinetic energy, is known as *katabolism*, and its products as *katabolites*.

In order to form an estimate of these processes going on in the body, the amount and nature of the ingested material must be known, as well as the amount of refuse or unused material that passes out of the alimentary canal as fæces, and the amount of excreted material from the various excretory organs.

The food is intended to supply the place of the material which has been utilized by the body, and, in a simpler form, eliminated in the excretions. But in the choice of a diet this is not enough; the food should be sufficient to supply such need without waste and without unduly increasing the output of excreta, while at the same time the body should be maintained in health, without increase or loss of weight.

These requisites of a diet scale then allow for wide alterations in the amount of different kinds of foods under different circumstances.

Careful analyses of the excreta, many of which we have already had occasion to call attention to, show that they are made up, besides water, chiefly of the chemical elements carbon, hydrogen, oxygen, and nitrogen, but that they also contain, to a less extent, sulphur, phosphorus, chlorine, ssium, sodium, and certain other of the elements. Since this is the case it must be evident that to balance this waste, foods must be supplied containing all these elements to a certain degree, but some of them, viz., those which take a principal part in forming the excreta, in large amount.

Of the excreta the carbon dioxide and ammonia, which are made up of the elements carbon, oxygen, nitrogen, hydrogen, are given off from the lungs. By the urine many elements are eliminated from the blood, especially nitrogen, hydrogen, and oxygen. In the sweat, the elements chiefly represented are carbon, hydrogen, and oxygen, and these are also those of which the fæces are made. By all the excretions large quantities of water are got rid of daily, but chiefly by the urine.

The relations between the amounts of the chief elements contained in these various excreta in twenty-four hours may be thus summarized:—

| —— | Water. | C. | H. | N. | O. |
|---|---|---|---|---|---|
| By the lungs | 330 | 248.8 | — | ? | 651.15 |
| By the skin | 660 | 2.6 | — | — | 7.2 |
| By the urine | 1700 | 9.8 | 3.3 | 15.8 | 11.1 |
| By the fæces | 128 | 20. | 3. | 3. | 12. |
| Grammes | 2818 | 281.2 | 6.3 | 18.8 | 681.41 |

From this should be subtracted the 296 grms. water, which are produced by the union of hydrogen and oxygen in the body during the process of oxidation (*i. e.*, 33 hydrogen and 262 oxygen). There are 26 grms. of salts got rid of by the urine, and 6 by the fæces; total, 32 grms.

The quantity of carbon daily lost from the body amounts to about 281.2 grms. (nearly 4,500 grains), and of nitrogen 18.8 grms. (nearly 300 grains), and if a man could be fed by these elements, as such, the problem would be a very simple one; a corresponding weight of charcoal and, allowing for the oxygen in it, of atmospheric air, would be al that is necessary. But an animal can live only upon these element when they are arranged in a particular manner with others, in the for of such food-stuffs as we have already enumerated, p. 339 *et seq.*; moreover, the relative proportion of carbon to nitrogen in either of the compounds alone is, by no means, the proportion required in the die of man. Thus, in proteid, the proportion of carbon to nitrog is only as 3.5 to 1. If, therefore, a man took into his body, as food sufficient proteid to supply him with the needful amount of carbon, h would receive more than four times as much nitrogen as he wanted and if he took only sufficient to supply him with nitrogen, he would starved for want of carbon. It is plain, therefore, that he should tal with the albuminous part of his food, which contains so large a relati amount of nitrogen in proportion to the carbon he needs, substances i ich the nitrogen exists in much smaller quantities relatively to the bon.

It is therefore evident that the diet must consist of several substances, t of one alone.

Many valuable observations have been made with a view of ascertain- ; the effect upon the metabolism of a variation in the amount and ture of food. These are of great assistance in the consideration of tetics.

*Effect of a Proteid Diet.*—Experiments have been made, to a consider- le extent upon dogs, which demonstrate the effect of proteid food. ter a period without food, during which the output of nitrogen, as wn by the urea, has diminished to a certain amount, the animal is l with a diet of lean meat which would suffice to produce the amount urea, and so of flesh, which it has been losing during its starvation iod. The effect of this, however, is at once to send up the amount urea excreted to a point above that which it has been previous to the nmencement of its flesh diet, so that again the output of nitrogen uld exceed its income, and the weight of the animal would continue wly to diminish. It is only after a considerable increase of the flesh en that a point is reached where the income and expenditure are al, and at which the animal is not using up quickly or slowly the rogen of his own tissue, and is no longer losing flesh. This condition hich the nitrogen of the egesta equals the nitrogen of the ingesta is wn as *nitrogenous equilibrium.* In the dog, according to Waller, it s not occur until the amount of flesh of the food is over three times reat as would be necessary to supply the nitrogen of the urea during riod of starvation. Thus a dog excretes during a starvation period grms. of urea per kilo of body weight; in order to satisfy this it ld be necessary to administer 1.5 grms. per kilo of meat; this at increases urea excreted to about 0.75 grms. per kilo of body weight, nitrogenous equilibrium is not attained until over three times—viz., ms. per kilo of body weight of meat is given. Foster gives even a er figure. The effect, therefore, of proteid food is largely to increase excretion of urea, which indicates increase of the metabolism of the ies.

It must not be thought however that during nitrogenous equilibrium e is, of necessity, equilibrium of carbon. On the contrary, it is very ible that the carbon, as supplied by the large amount of meat, is not rely eliminated, but may be partially retained in the body. If re- d in the body it is probably retained in the form of fat, although bly it might be retained partially as some carbohydrate, *e.g.*, gly- n; but the amount of glycogen obtained from the body is too small he latter to be appreciable. The animal in nitrogenous equilib- , therefore, may gain weight, although not in the form of flesh.

The converse may also be the case, the animal getting rid of more carbon than the meat supplies, in which case he would lose weight but would not lose flesh.

The proteids of food are described by Voit as having two relations to the proteid metabolism and to outgoing urea; the first part going to maintain the ordinary and quiet metabolism of the tissues, for which purpose it is actually built up into their molecule, and the second part causing a more rapid formation of urea and rapid proteid metabolism, but never forming a part of the actual protoplasmic molecule. The former proteids are called *morphotic* or *tissue* proteids, the latter *circulating* or *floating* proteids. Normally more proteid is eaten than is needed to supply proteid waste. Pflüger has pointed out, however, that the tissues must have an excess of proteid to destroy in order to perform their metabolic processes normally. This use of the proteids to form by their oxidation heat and not to produce tissue was looked upon by the older physiologists as a wasteful use of good material, and was called a *luxus consumption.*

The condition of nitrogenous equilibrium (*i.e.*, the income and output being equal) is one which may be maintained even if the amount of proteid taken as diet far exceeds the necessities of the economy, the urea being excreted in excessive amount, and the wasteful use of proteid food which is so common may not be attended with harmful consequences, so long as the liver is able to do its work in the formation of urea. The body may or may not increase in weight, but if the liver strikes work from any cause, a condition of lithiasis, or of gout, follows.

It has not actually been proved, but it is not unlikely, that even in the condition of lithiasis, the nitrogen of the ingesta may not greatly exceed that of the egesta, but that the mode of elimination is different. It is only in cases of growth or putting on of flesh, as in growing children, that nitrogen is retained in the body, except to a very small amount, in health.

According to calculations which have been made, it appears that the body puts on thirty grammes of flesh for every gramme of nitrogen so retained.

As regards the retention of carbon in the body, it is calculated that one gramme and a half of weight is put on for each gramme by which the ingesta of carbon is greater than the egesta.

*The Effect of an Albuminoid Diet.*—The albuminoid which is eaten in greatest quantity is gelatin. Though gelatin closely resembles the proteid molecule chemically, it cannot replace the proteid of the food. In other words, nitrogenous equilibrium cannot be maintained on a diet consisting of gelatin, carbohydrates, and fats. Proteid food is absolutely essential to the reconstruction of the proteid molecule. Gelatin is one of the proteid substances whose food value is comparable to that carbohydrates and fats, as the following experiments will prove: In e case, when 500 grms. of food, without any gelatin, formed the diet, subject lost 22 grms., but when 200 grms. of gelatin were added, the bject gained 54 grms. In another experiment, when the diet consisted 2,000 grms. of meat without gelatin, the gain was 30 grms., but when 0 grms. of gelatin were added, the gain became 376 grms. The lack real proteid food value is proven by a third experiment in which the t consisted at first of 200 grms. each of meat and of gelatin; here the in was 25 grms., but when the meat was omitted and the gelatin alone en, there was a loss of 118 grms. In these cases gelatin did not take place of proteid in any sense, but rather saved it from work. The oteid was so protected that, instead of being used up, it helped to m tissues and increased the body weight. Gelatin, therefore, saves er material for constructive processes.

*Formation of Urea.*—Having studied the uses of proteids in the body, may next turn our attention to their conversion to urea, the form in ich the used-up proteids chiefly leave the body. The method of forma- n of urea, as well as the place where this occurs, has given rise to great ntroversy, while most of the intermediate products between proteids d urea have not as yet been determined. We can state with certainty t urea is not formed in the kidneys, since it is not only found in the od of the renal artery, but it accumulates in the blood if the kidneys diseased or removed and the separation of the urine is interfered with. us it seems reasonable to assume that the function of the kidneys, far as the more important solid—urea—is concerned, is only one separation. This will be discussed under the heading of the method the secretion of the urine. It remains to consider here the question of origin of the urea which is found in the blood, and its method of mation.

At the present time it is believed that urea is formed in the liver. is conclusion is borne out by a number of experiments. The power of liver cells to form urea is shown by the increase of urea in the blood ving an isolated (and living) liver, through which an artificial circula- n is kept up, when ammonium carbonate, or other ammonium salts, added to the blood. The same change occurs even when liver is pped up and simply mixed with the ammonium compounds in a ker; this shows that the change is due to the metabolic activity of r cells. The reaction is probably as follows:

$$(NH_4)_2CO_3 - 2H_2O = CON_2H_4.$$

If blood from a well-fed animal be circulated through the isolated , there is a distinct increase in the amount of urea it contains. On the other hand, if the blood be from a fasting animal, there is no increase of urea. Evidently, then, the blood from a well-fed animal contains something which the liver cells are capable of transforming to urea. And, finally, if the liver be removed and the animal kept alive, as has been done (Pawlow), there is a marked diminution in the quantity of urea in the urine. The power of the liver to form urea is thus demonstrated, and, moreover, the fact that the liver forms from some antecedent substance the greater part of the urea eliminated.

The question which now presents itself is, What is this antecedent substance or substances?

Urea is the end-product of the oxidation of proteids. It was formerly thought that urea was formed directly from some antecedent among the closely related products of proteid metabolism, such as creatin, creatinin, leucin, tyrosin, xanthin, hypoxanthin, etc. Creatinin at one time seemed the most probable source, because in laboratory experiments it decomposes into urea and sarcosin. Attention was also directed to leucin and tyrosin, which are found in practically all the glandular organs of the body. It was found that when leucin was fed to a dog, the amount of urea in the urine was considerably increased, but that leucin itself did not appear; the same phenomena were noticed with glycin, sarcosin, and the amido acids. It was also known that in acute yellow atrophy of the liver, a disease characterized by degeneration of the liver cells with consequent loss of functional power, the urea of the urine was replaced by leucin and tyrosin. Experimental investigation, however, did not justify any of these theories.

Finally it was found that when ammonia was fed to animals, the nitrogen appeared in the urine in the form of urea. Due investigation of this fact led to the belief that proteids were first broken down to an ammonia stage and then again built up into urea by the liver. For a long time it was thought that this stage was represented by ammonium carbonate, but in view of recent experiments this idea has been given up, and it is now believed that *ammonium carbamate* is the true antecedent.

In these experiments the liver was first shut out of the general circulation by (Eck's fistula) connecting the portal vein with the hepatic artery; the results of this operation are, for all practical purposes, equivalent to actual removal of the liver. When animals survived this operation it was found that they could live if fed very carefully on a mixed diet from which proteids were almost entirely eliminated, but that if the food contained an excess of proteids, convulsions ensued and proved fatal. Further investigation of the composition of the u and blood showed that proteid metabolism was represented in them ammonium carbamate and not by urea. Ammonium carbamate was then ted into the blood of other animals ; when a larger quantity was than the liver could dispose of, death ensued, following convulsions e same nature as those produced by an excess of proteid food in the als which had been operated on.

Ammonium carbamate is thus shown to be, in part at least, the direct cedent of urea; it is also shown to be a toxic substance which may e death by accumulating in excess. The reaction by which the liver nges it to the inert form of urea is as follows:

$$CO < {NH_2 \atop ONH_4} - H_2O = CO < {NH_2 \atop NH_2}.$$

(Ammonium carbamate.) (Urea.)

The manner in which absorbed proteids are changed to ammonium bamate, etc., is as yet undecided. According to one theory, while l in the circulating medium, they are metabolized by direct contact h the living bioplasm of the tissues; according to another, they must be incorporated in the body tissues and then changed. The interiate steps occur chiefly in muscle tissue, and there is great reason to ose that some of the steps are represented by various muscle extrac- such as creatinin, hypoxanthin, etc. These substances probably k down into carbon dioxide, ammonia, and amido-acids, and are built up by synthetic processes into ammonium carbonate, and by dehydration changed to ammonium carbamate. Another possible edent is ammonium lactate; this is derived from the lactic acid h is produced in large quantities in the muscles. Muscular activity ases the elimination of urea, but the increase is very slight, and is no direct relationship between the amount of work done and the nt of nitrogen excreted.

here is experimental evidence to show that while the liver pro- the major part of the urea eliminated, other organs or tissues apable of forming it to a limited degree.

*ormation of Uric Acid.*—Uric acid probably arises much in the way as urea. The relation which uric acid and urea bear to each , as we have seen, is still obscure. The fact that they often exist her in the same urine, makes it seem probable that they have differrigins; but the entire replacement of one by the other, as of urea ic acid in the urine of birds, serpents, and many insects, and of acid by urea, in the urine of the feline tribe of Mammalia, shows close relationship. But although it is true that one molecule of acid is capable of splitting up into two molecules of urea and one es-oxalic acid, this is no evidence that uric acid is an antecedent of in the nitrogenous metabolism of the body.

he intimate relations which exist between several other of the nitrogenous extractives and uric acid will be seen by a reference to th formulæ:—

| | |
|---|---|
| Hypoxanthin or Carnin | $C_5H_4N_4O$. |
| Xanthin | $C_5H_4N_4O_2$. |
| Uric Acid | $C_5H_4N_4O_3$. |

*Formation of Hippuric Acid.*—The source of hippuric acid is not s isfactorily determined; in part it is probably derived from some consti uents of vegetable diet, though man has no hippuric acid in his foo nor, commonly, any benzoic acid that might be converted into it; part from the natural disintegration of tissues, independent of vegetal food, for Weismann constantly found an appreciable quantity, even wh living on an exclusively animal diet.* Hippuric acid arises from t union of benzoic acid with glycin ($C_2H_5NO_2 + C_7H_6O_2 = C_9H_9NO$ $H_2O$), which union probably takes place in the kidneys themselves. It possible that the aromatic radicle in this reaction is obtained from t splitting up of tyrosin, which appears so frequently as a result of t decomposition of proteid, the ammonia radicle with which it is asso ated going to form urea.

The source of the extractives of the urine is probably in chief p metabolism of the nitrogenous tissues, but we are unable to say wheth these nitrogenous bodies are merely accidental, having resisted furth decomposition into urea, or whether they are the representatives of t decomposition of special tissues, or of special forms of metabolism the tissues. There is, however, one exception, and that is in the ca of **kreatinin**; this represents not only the kreatinin which enters t body in ordinary flesh food, but nitrogenous waste as well.

*Effects of Fats and Carbohydrates as Food.*—Experiments illustrati the ill-effects produced by feeding animals upon one or two alimenta substances only have been often performed.

Dogs were fed exclusively on *sugar and distilled water.* During t first seven or eight days they were brisk and active, and took their foo and drink as usual; but in the course of the second week they began get thin, although their appetite continued good, and they took dail between six and eight ounces of sugar. The emaciation increased durin the third week, and they became feeble, and lost their activity and a petite. At the same time an ulcer formed on each cornea, followed b an escape of the humors of the eye: this took place in repeated exper ments. The animals still continued to eat three or four ounces of sug daily; but became at length so feeble as to be incapable of motion, an died on a day varying from the thirty-first to the thirty-fourth. On di section their bodies presented all the appearances produced by death fro starvation; indeed, dogs will live almost the same length of time witho any food at all.

When dogs were fed exclusively on *gum*, results almost similar to th

bove ensued. When they were kept on *olive-oil and water*, all the
henomena produced were the same, except that no ulceration of the
ornea took place; the effects were also the same with butter. The ex-
eriments of Chossat and Letellier prove the same; and in men, the
ame is shown by the various diseases to which those who consume but
ttle nitrogenous food are liable, and especially by the affection of the
ornea which is observed in Hindus feeding almost exclusively on rice.

The nutritive function of fats and carbohydrates in the body is to
rve as a source of energy. They are oxidized, with the ultimate pro-
uction of carbon dioxide and water, and must liberate the same amount
energy as when burned outside the body. A given amount of fat,
wever, furnishes more energy than a corresponding amount of either
oteid or carbohydrate. The stock of fat in the animal body will de-
y the fatal consequences of the deprivation of food. The percentage
ss of fat in a starving animal is given on page 454.

*The Formation of Glycogen* (*Glycogenesis*).—The important fact that
e liver normally forms sugar, or a substance readily convertible into
was discovered by Claude Bernard in the following way: he fed a
g for seven days with food containing a large quantity of sugar and
rch; and, as might be expected, found sugar in both the portal and
patic blood. But when this dog was fed with meat only, to his sur-
se, sugar was still found in the blood of the hepatic veins. Repeated
periments gave invariably the same result; no sugar being found,
ter a meat diet, in the portal vein, if care were taken, by applying a
ture on it at the transverse fissure, to prevent reflux of blood from
hepatic venous system. Bernard found sugar also in the substance
he liver. It thus seemed certain that the liver formed sugar, even
en, from the absence of saccharine and amyloid matters in the food,
e could be brought directly to it from the stomach or intestines.

Bernard found, subsequently to the before-mentioned experiments,
t a liver, removed from the body, and from which all sugar had been
pletely washed away by injecting a stream of water through its
od-vessels, after the lapse of a few hours contained sugar in abun-
ce. This post-mortem production of sugar was a fact which could
y be explained on the supposition that the liver contained a substance
lily convertible into sugar; and this theory was proved correct by the
overy of a substance in the liver allied to starch, and now generally
ned *glycogen*.

We may believe that glycogen is first formed and stored in the liver
s, and that the sugar, when present, is the result of its transformation.

*Source of Glycogen*.—Although, as before mentioned, the greatest
unt of glycogen is produced by the liver upon a diet of starch or
ar, a certain quantity is produced upon a proteid diet. The glyco-
when stored in the liver cells may readily be demonstrated in sec-

**tions of liver containing it by its reaction (red or port-wine color) wit iodine, and moreover, when the hardened sections are so treated tha the glycogen is dissolved out, the protoplasm of the cell is so vacuolat as to appear little more than a framework. There is no doubt that i the liver of a hibernating frog the amount of glycogen stored up in th outer parts of the liver cells is very considerable.**

***Average amount of Glycogen in the Liver of Dogs under Various Di* (Pavy).**

| Diet. | Amount of Glycogen in Li |
|---|---|
| **Animal food . . . . . . . . . .** | **7.19 per cen** |
| **Animal food with sugar (about ¼ lb. of sugar daily)** | **14.5 "** |
| **Vegetable diet (potatoes, with bread or barley-meal)** | **17.23 "** |

**The dependence of the formation of glycogen on the kind of fo taken is also well shown by the following results, obtained by the sa experimenter:**

***Average quantity of Glycogen found in the Liver of Rabbits after F ing, and after a diet of Starch and Sugar respectively.***

| | Average Amount of Glycogen in Li |
|---|---|
| After fasting for three days . . . | **Practically absent.** |
| " diet of starch and grape-sugar . . | 15.4 per cent. |
| " " cane-sugar . . . . . | 16.9 " |

Glycogen is also formed on a gelatin diet, but **fats taken in as food** not increase its amount in the cells. The diet most favorable **to t** production of a large amount of glycogen is a mixed diet **containin** large amount of carbo-hydrate, but with some proteid. Glycerin **inje** into the alimentary canal may also increase the glycogen of the **liver.**

*Destination of Glycogen.*—There are two chief theories **as to the de** nation of hepatic glycogen. (1.) That the glycogen is **converted i** sugar during life by the agency of a ferment (*liver diastase*) **also for** in the liver; and that the sugar is conveyed away by the **blood of** hepatic veins, to undergo combustion in the **tissues.** (2.) **That** conversion into sugar only occurs after death, and that during **life** sugar exists in healthy livers; glycogen not undergoing this **transfor** tion. The chief arguments advanced in support of this **view are,** that scarcely a trace of sugar is found in **blood drawn** during **life f** the right ventricle, or in blood collected from the right side of **the h** *immediately* after an animal has been killed; while if the **examin** be delayed for a very short time after death, sugar in **abundance** be found in such blood; (*b*), that the liver, **like the venous blood in** heart, is, at the moment of death, completely free from sugar, **altho** afterward its tissue speedily becomes saccharine, unless the **formatio** gar be prevented by boiling, or other means calculated to interfere ith the action of a ferment.

Instead of adopting the view that normally, during life, glycogen cts as a store of carbo-hydrate material to be converted, little by little, to sugar as occasion requires, and that it passes as sugar into the he-atic venous blood, to be conveyed to the tissues to be further disposed f, Pavy inclines to the belief that it may represent an intermediate age in the formation of fat from materials absorbed from the alimen-ry canal. There is little evidence in favor of this view, and although is possible that the liver cells may, in some way or other (not at pres-t understood), be able to convert part of its store of glycogen into fat, e consensus of opinion inclines to the belief that most of the glycogen aves the liver as sugar.

Indeed, wherever glycogen is found, in the muscles, in the placenta, elsewhere, it must be looked upon as a store of carbo-hydrate material ich may be oxidized to furnish energy to the body. Whether the cogen which probably reaches the muscles as sugar is reconverted into cogen before it is built up as it were into the protoplasmic molecule not known.

*The relation of glycogen to the cell metabolism.*—It is not exactly known ether the glycogen is formed simply by a process of dehydration of sugar which reaches the cells in the portal blood, or whether cells by their metabolism are usually in the habit of form-glycogen or sugar which, during fasting and other similar conditions, t once discharged into the hepatic blood to be used up by the tissues, which is stored up in the cells as glycogen as long as there is suffic-t sugar in the blood without it, or as long as the tissues are so quiescent not to require more than a small quantity of the total amount of bo-hydrate secreted by the hepatic cells.

**Glycosuria.**—Sugar may be present not only in the hepatic veins, in the systemic blood to excess, and when such is the case, the sugar xcreted by the kidneys, and appears in variable quantities in the e. This condition is known as glycosuria.

*Influence of the Nervous System.*—Glycosuria may be experimentally duced by puncture of the medulla oblongata in the region of the -motor centre. The better fed the animal the larger is the amount gar found in the urine; in the case of a starving animal no sugar ears. It is, therefore, highly probable that the sugar comes from hepatic glycogen, since in the one case glycogen is in excess, and in other it is almost absent. The nature of the influence is uncertain. ay be exercised in dilating the hepatic vessels, or possibly may be ted on the liver cells themselves. The whole course of the nervous stimulus cannot be traced to the liver, but, at any rate, it is not conducted by the vagi or by the splanchnics, but at first it passes from the lower part of the floor of the fourth ventricle and medulla down the spinal cord as far as—in rabbits—the fourth dorsal vertebra, and hence to the first thoracic ganglion. The formation of sugar by the liver is also not a vaso-dilator effect, since it will occur when the vessels are constricted.

Many other circumstances will cause glycosuria. It has been observed after the administration of various drugs—*e.g.*, strychnine (in frogs), phloridzin, a glucoside, and phloretin, a derivative of phloridzin, not a glucoside, morphine, nitrite of amyl, etc.—after the injection of curari, poisoning with carbonic oxide gas, the inhalation of ether, chloroform, etc., the injection of oxygenated blood into the portal venous system. It has been observed in man after injuries to the head, and in the course of various diseases.

In all such cases, at any rate, the glycosuria appears to be due to some abnormal activity of the liver cells themselves set up by the direct action of the secretory nerves upon them.

The well-known disease, *diabetus mellitus*, in which a large quantity of sugar is persistently secreted daily with the urine, has, doubtless, some close relation to the normal functions of the pancreas. The nature of the relationship has not yet been determined, though some recent experiments seem to be pertinent (see p. 331).

*Effect of too much Food.*—All the three classes of food-stuffs mentioned—fats, carbohydrates, and gelatin—have their distinct uses when combined with proteids. A small amount of fat or a larger amount of carbohydrate (starch or sugar) added to some proteid diminishes the amount of proteid required before nitrogenous equilibrium is attained (in a dog to the extent of 50 per cent or more), but if the carbohydrate exceed a certain minimum it is retained in the body as fat.* If the proteid be increased, the metabolism is increased likewise, and so fat may not be deposited, even if the carbohydrate of the diet be excessive. It is even possible that some of the already stored-up fat may be used up, and so loss of weight (fat) might result.

Persistent excess of carbohydrate food produces an accumulation of fat, which may not only be an inconvenience causing obesity, but may interfere with the proper nutrition of muscles, and a feebleness of the action of the heart, with other troubles. Starches when taken in grea

---

* The result of various feeding experiments, *e.g.*, of the milch cow fed upon grass, have proved beyond all doubt that fat is formed by the tissues chiefly from carbohydrate food, but to a less extent from proteids. Fatty foods, even indirectly lead to the deposition of fats, are not as such deposited in the t Fat is everywhere in the body an effect of actual protoplasmic metabolism

s are almost certain to give rise to dyspepsia, with acidity and flat-
e. Excess of starch or of sugar in the food may, however, be got
by the urine in the form of sugar. There is evidently a limit to
bsorption of fat as well as of starch, since if in excessive amount
may appear in the fæces.

hat *salts* are necessary as food is proved by the presence of scurvy
they are not present, and we know that there is a constant excre-
of chlorides, phosphates and sulphates in the urine, so that in order
lance the income and output, these salts in combination with
m, potassium, calcium, etc., must be taken in.

he necessity for the taking in of *water*, in order to balance the ex
on, is sufficiently obvious.

o summarize what has been said:—

*roteid.*—i. If the nitrogen of the income is less than that of the
ut, the animal loses flesh and starves, gradually or quickly, accord-
to the extent of the deficiency.

i. If the nitrogen of the income be evenly balanced, the proteid
only just sufficient, the animal does not lose flesh, but may increase
minish in weight (fat).

i. If the nitrogen of the ingesta exceed that of the egesta, the ex-
s mainly retained in the form of flesh.

. If the proteid be in great excess, although there be a condition
rogenous equilibrium, there may be increase in weight, but also a
ood of gout and similar affections.

*tty and Carbohydrate Foods* are of no use either together or sepa-
without the addition of the other food-stuffs. In moderation,
may diminish the amount of proteid necessary to produce nitro-
s equilibrium. If the quantity of either be increased beyond a
n amount, it is retained in the body in form of fat (and, in the
f the carbohydrate, as glycogen). If in great excess, disorders of
ion occur. Fats have more potential energy than carbohydrates,
e less digestible. Fatty foods need more oxygen than carbohy-
when they are used up in the body.

*latin* will not entirely, but will partly replace the proteid in a diet.
*lts* of sodium, potassium, calcium, etc., are necessary in food, the
des, phosphates and sulphates, and possibly the citrates, being the
important of those required.

*ater* is absolutely essential to life—an animal will not survive
ation for longer than a few days.

*ects of Deprivation of Food.*—The animal body deprived of all food
course of a variable time dies from starvation. The length of
hat any given animal will live in such a condition depends upon
circumstances; the chief may be supposed to be the nature and
y of the metabolism of its tissues.

The effect of *starvation* on the lower animals, as recorded by various experimenters is:—(1.) One of the most notable effects of starvation, as might be expected, is *loss of weight;* the loss being greatest at first, as a rule, but afterward not varying very much, day by day, until death ensues. Chossat found that the ultimate proportional loss was, in different animals experimented on, almost exactly the same; death occurring when the body had lost two-fifths (forty per cent) of its original weight. Different parts of the body lose weight in very different proportions. The following most noteworthy losses are taken, in round numbers, from the table given by Chossat:—

| | | | |
|---|---|---|---|
| Fat . . . | loses 93 per cent. | Liver . . . | loses 52 per cent. |
| Blood . . . . | 75 " | Muscles . . . | 43 " |
| Spleen . . . | 71 " | Nervous tissues . . | 2 " |
| Pancreas . . . | 64 " | | |

These figures are in practical agreement with those of later experi- menters. They show that the chief losses are sustained by the adip tissue, the muscles and glands.

(2.) The effect of starvation on the *temperature* of the various ani- mals experimented on by Chossat was very distinct. For some time th variation in the daily temperature was more marked than its absolut and continuous diminution, the daily fluctuation amounting to 3° C. (5° o 6° F.), instead of 5° to 1° C. (1° or 2° F.), as in health. But a short tim before death, the temperature fell very rapidly, and death ensued when th loss had amounted to about 16.2° C. (30° F.). It has been often said, and with truth, although the statement requires some qualification, th death by starvation is really death from want of heat; for not only has i been found that differences of time with regard to the period of the fatal result are attended by the same ultimate loss of heat, but the effect of the application of external warmth to animals cold and dying from starvation, is more effectual in reviving them than the administration of food.

The *symptoms* produced by starvation in the human subject are hun ger, accompanied, or it may be replaced, by pain, referred to the regi of the stomach; insatiable thirst; sleeplessness; general weakness a emaciation. The exhalations both from the lungs and skin are fœti indicating the tendency to decomposition which belongs to badly nou ished tissues; and death occurs, sometimes after the additional exhausti caused by diarrhœa, often with symptoms of nervous disorder, delir or convulsions.

In the human subject death commonly occurs within six to ten d after total deprivation of food. But this period may be consider prolonged by taking a very small quantity of food, or even water o The cases so frequently related of survival after many days, or even so weeks, of abstinence, have been due either to the last-mentioned circ ces, or to others no less effectual, which prevented the loss of heat moisture. Cases in which life has continued after total abstinence food and drink for many weeks, or months, exist only in the imagion of the vulgar.

(3.) During the starvation period the excreta diminish. The urea, epresenting the nitrogen, falls quickly in amount, reaches a minin and remains constant at this point for several days, and then rises n and finally falls rapidly immediately before death; the sulphates phosphates undergo much the same form of reduction. The carbon ide given out and the oxygen taken in diminish. The fæces diminas well as the bile. It has been concluded as highly probable that greater part of the urea represents the loss of weight of the muscles. The appearances presented after death from starvation are those of eral wasting and bloodlessness, the latter condition being least noticee in the brain. The stomach and intestines are empty and contracted, the walls of the latter appear remarkably thinned and almost transent. The various secretions are scanty or absent, with the exception the bile, which, not being discharged, usually fills the gall-bladder. parts of the body readily decompose.

In starvation, then, we see that the only income consists of the ined oxygen. The whole of the energy of the body given out in the tion of heat and mechanical labor is obtained at the expense of the g up of its own tissues, there being as a result a constant drain of nitrogen and carbon, not to mention the other elements of which are made up. It is obvious that such a condition cannot be end for any length of time.

## Requisites of a Normal Diet.

t will have been understood that it is necessary that a normal diet ld be be made up of various articles, that they should be well cooked, that they should contain about the same amount of carbon and nin as are got rid of by the excreta. No doubt these desiderata may tisfied in many ways, and it would be unreasonable to expect the of every adult to be unvarying. The age, sex, strength, and cirstances of each individual must ultimately determine what he takes od. A dinner of bread and cheese with an onion contains all the isites for a meal, but such diet would be suitable only for those posng strong digestive powers. It is a well-known fact that the diet e continental nations differs from that of our own country, and of cold from that of hot climates, but the same principle underlies all, viz., the replacement of the loss of the excreta in the most enient and economical way possible. Without going into detail in the matter here, it may be said that any one in active work requires more food than one at rest, and that children and women require less food than do adult men.

Of the various diet-scales which have been drawn out with the object of supplying the proximate principles in the required proportions, the foregoing is slightly modified from Moleschott:—

| *Dry Food—* | | | | N. | C. |
|---|---|---|---|---|---|
| Proteid . | 120 grms. | (4.232 oz.) | supplying | 18.88 grms. | 64.18 grms. |
| Fat . . | 90 " | (3.174 oz.) | " | | 70.20 " |
| Carbohydrate | 320 " | (11.64 oz.) | " | | 146.82 " |
| | | | | N. 18.88 | C. 281.2 |
| Salts . . | 30 " | (nearly 1 oz.) | | | |
| *Water* . . | 2800 " | | | | |

Two other diet-scales may be mentioned, which are often quoted, viz:—

RANKE'S DIET-SCALE.

| | |
|---|---|
| Proteid . . . . . . . . . . | 100 grms. |
| Fats . . . . . . . . . . . | 100 " |
| Carbohydrates . . . . . . . . | 250 " |
| Salts . . . . . . . . . . . | 25 " |
| Water . . . . . . . . . . | 2600 " |

PETTENKOFER & VOIT'S DIET-SCALE is as follows:—

| | |
|---|---|
| Proteids . . . . . . . . . . | 118 to 137 grms. |
| Fats . . . . . . . . . . | 56 to 117 " |
| Carbohydrates . . . . . . . | 352 to 500 " |
| Salts . . . . . . . . . . | |
| Water . . . . . . . . . . | 2016 grms. |

The amount of the excreted carbon and nitrogen is not, of course, always the same, it having been unfortunately proved possible, for example, to subsist on 9 or 10 grms. of nitrogen and 200 grms. of carbon per diem (the ordinary diet for needle-women in London, and the average of the cotton operatives in Lancashire during the famine, 1862), the amount of these elements excreted falling to figures corresponding to such an income. Of course, upon such a diet the metabolism is low, and persistent weakness must be the result.

The 9 or 10 grms. of N in such a semi-starvation diet would be equivalent to 58.5 to 65 grms. of proteids, whereas the amount of proteids in some diets may be as high as 150–159 grms. per diem (English navvies), or 165 gms. (Munich brewers' men). The English and Bavarian soldier in time of peace consumes 126 grms. of proteid per diem (4.4 oz.).

Not only the proteids but also the fats may vary; the amount may be as low as 56 grms. and as high as 117 grms. The carbohydrates may vary from 200 grms. to 500 grms. and upward. Sometimes, with a small proportion of fat, the carbohydrate may be correspondingly increased to make up the necessary carbon. A useful table after Pavy

lp to show in what ways it is possible to obtain the requisite
; of nitrogen and carbon from the most common food-stuffs.
100 parts of the following substances the proportion of N and C
:ated:

| | N. | C. | | N. | C. |
|---|---|---|---|---|---|
| ithout bone | 3 | 11 | Oatmeal . . . . | 1.95 | 44 |
| eef . . . | 3.528 | 17.76 | Bread . . . . | 1 | 28 |
| . . . | 1.9 | 13.5 | Potatoes . . . . | .33 | 11 |
| Milk . . . | .66 | 8 | Eels . . . . | 2 | 30 |
| . . . | 2 to 7 | 35 to 71 | Mackerel . . . . | 3.74 | 19.26 |
| . . . | 4.5 | 42 | Sardines in oil . | 6 | 29 |
| . . . | 4.1 | 48 | Butter . . . . | .64 | 83 |

der to obtain the amount of proteid present from the proportion of
a, multiply by 6.5.

m these data it is possible to form various diet-scales which shall
the needs of different conditions. Assuming that the average
t of carbon and nitrogen required is about 300 grms. and 20 grms.
ively, this may be obtained as follows:—

| | | N. | C. |
|---|---|---|---|
| ns. | {12 oz. avoirdupois<br>¾ lb. " } lean uncooked meat* | 10 grms. | 37 grms. |
| | (32 oz. or 2 lbs. avoirdupois) bread . | . 9 " | 252 " |
| | | 19 grms. | 289 grms. |

; this diet is not a usual one; a certain proportion of the carbon
lly supplied as butter, or bacon, and so if 90 grms. (3.1 oz.) of
or bacon be used they would supply about 72 grms. of carbon, and
bohydrate would be diminished nearly one-third; but the nitro-
uld also be diminished from 9 grms. to 6 grms. It would be
ry to supply some extra nitrogenous principle, and this might
e by the addition of eggs, milk, cheese, beans, or of any of the
uffs already enumerated at p. 339 *et seq.*, as supplying nitrogenous
hiefly. For example, 56 grms. (2 oz.) cheese, would supply, on
rage, 3 grms. nitrogen and 20 grms. carbon; or 28 grms. cheese,
ng 1.5 grms. nitrogen and about 10 grms. carbon, and 225
½ lb.) potatoes, and 225 grms. (½ lb.) carrots, supplying together
grm. of nitrogen and 35 grms. of carbon. The diet would then
follows:—

| | | N. | C. |
|---|---|---|---|
| grms. | lean uncooked meat . . . . | 10 grms. | 37 grms. |
| " | Bread . . . . . . | 6 " | 168 " |
| " | Butter . . . . . . . . | .5 " | 72 " |
| " | Cheese . . . . . . | 1.5 " | 10 " |
| "<br>" | Potatoes<br>Carrots } . . . . . . | 1 " | 35 " |
| | | N 19 | C. 322 |

---

meat loses 23 to 34 per cent on cooking, the weight of cooked meat
e proportionately be less.

The salts, over 30 grms., would be supplied by the meat 16 grms., the bread 12 grms., and vegetables about 4 grms. The fluids should consist of about 2,500–2,800 grms., and might be given as water, with or without tea, coffee, or cocoa (which are chiefly stimulants).

## Variations in Diet Tables.

*For infancy.*—Milk affords a natural and perfect diet for infants. The amount which an infant during the first month should take is not less than 1 kilogramme (2¼ lbs.) per diem. In 1,000 grms. there would be about 6.6 grms. nitrogen and 80 to 90 of carbon. This allows for a gain of weight of 2 to 5 oz. in the time.

*For climate.*—Very slight alteration is necessary. For warm climates, slightly increase the carbohydrates.

*For hard labor.*—All the articles of diet should be increased to make up for the increased metabolism.

*Fattening diet.*—In such a diet an excess of carbohydrates should be present.

*To reduce obesity.*—The fats and carbohydrates should be diminished, but the proteids should be relatively increased.

*To increase muscle.*—It has been found that a diet consisting largely of proteids in considerable amount combined with such passive exercise as that obtained by massage, will cause the body to put on flesh.

*For training.*—The whole diet should be increased, possibly preceded by a diet in which the proteid is in excess.

*For brain work.*—The chief essential is that the diet should consist easily digestible materials.

## Income and Output of Energy.

The food must be considered from another point of view in addition to that from which we have been considering it. It not only makes up for the substances eliminated from the body, but it also supplies potential energy to balance the energy set free in the living body heat and movement. The amount of heat is measured in terms calories, as has been already pointed out. The work done may be pressed in terms of foot-pounds (English system), or metre-grammes, or metre-kilogrammes (metric system). The calories may also be pressed in terms of work, as heat is also, as has been said, *a mode of* *tion.* The heat-unit Ca, may be transformed into metric work-unit multiplying by 42 and dividing by 1000, and the converse.

*Manifestations of Force in the form either of Heat or Motion.*—In the former case (Heat), the combustion must be sufficient to maintain a temperature of about 37.8° C. (100° F.) throughout the whole substance of the body, in all varieties of external temperature, notwithstanding the arge amount continually lost in the ways previously enumerated. In the case of Motion, there is the expenditure involved in the (*a*) Ordinary muscular movements, as in Prehension, Mastication, Locomotion, and numberless other ways: as well as in (*b*) Various involuntary movements, as in Respiration, Circulation, Digestion, etc.

*Manifestation of Nerve-force;* as in the general regulation of all physiological processes, *e.g.*, Respiration, Circulation, Digestion; and n Volition and all other manifestations of cerebral activity.

*The energy expended in all physiological processes, e.g.*, Nutrition, Secretion, Growth, and the like.

The total expenditure or total manifestation of energy by an animal ody can be measured, with fair accuracy. All statements, however, must be considered for the present approximate only, and especially is his the case with respect to the comparative share of expenditure to e assigned to the various objects just enumerated.

The amount of energy daily manifested by the adult human body n (*a*) the maintenance of its temperature; (*b*) in internal mechanial work, as in the movements of the respiratory muscles, the heart, tc.; and (*c*) in external mechanical work, as in locomotion, and all ther voluntary movements, is made up, according to McKendrick, as llows:—

| | Metre-kilogrammes. | | Gramme-calories. |
|---|---|---|---|
| Work of heart per diem . . . . | 88,000 | | |
| Work of respiratory muscle . . | 14,000 | | |
| Eight hours' active work . . | 213,344 | | |
| | 315,334 | or | 743,000 |
| Amount of heat produced in 24 hours | 1,582,700 | or | 3,724,000 |
| | 1,898,034 | or | 4,467,000 |

So that 4, 467 kilogramme calories represent the total energy manifested in hours, 8 of which were employed in mechanical work, one-sixth of the tal energy being work. This estimation considerably exceeds those of others, d the most general view is that the total energy exhibited in 24 hours by e average adult is rather under than over 1,000,000 kilog. metres.

Taking the diet-scale as given above (modified from Moleschott), we may e how this supplies the energy which is given out, remembering that 1 grm. oteid = 5,000 to 5,500 calories; minus the value of ⅓ grm. urea = 700 or 800 lories, = say 4,500; 1 grm. fat = 9,000 calories; and 1 grm. carbohydrate = 00 calories.

| | | | | Gramme-calories. |
|---|---|---|---|---|
| 120 | grms. | Proteid at 4,500 per grm. | = | 544,500 |
| 90 | " | Fat at 9,000 per grm. | = | 810,000 |
| 330 | " | Carbohydrate at 4000 per grm. | = | 1,320,000 |
| | | | | 2,694,500 |

Or roughly, 2,694 kilog. calories, equivalent to 1,144,950 metre-kilogrammes of energy. This shows, although the calculation is only rough, that the diet which from other reasons was considered to be correct contains the potential energy to set free one million metre-kilogrammes of kinetic energy, and to leave a fair margin for errors of calculation.

To the foregoing amounts of expenditure must be added the quite unknown quantity expended in the various manifestations of nerve-force, and in the work of nutrition and growth (using these terms in their widest sense). By comparing the amount of energy which should be produced in the body from so much food of a given kind, with that which is actually manifested (as shown by the various products of combustion, in the excretions), attempts have been made, indeed, to estimate, by a process of exclusion, these unknown quantities; but all such calculations must be at present considered only very doubtfully approximate.

*Sources of Error.*—Among the sources of error in any such calculations as the one above given must be reckoned, as a chief one, the, at present, entirely unknown extent to which forces external to the body (mainly heat) can be utilized by the tissues. We are too apt to think that the heat and light of the sun are directly correlated, as far as living beings are concerned, with the chemico-vital transformations involved in the nutrition and growth of the members of the vegetable world only. But animals, although comparatively independent of external heat and other forces, probably utilize them, to the degree occasion offers. And although the correlative manifestation of energy in the body, due to external heat and light, may still be measured in so far as it may take the form of mechanical work; yet, in so far as it takes the form of expenditure in nutrition or nerve-force, it is evidently impossible to include it by any method of estimation yet discovered; and all accounts of it must be matters of the purest theory. These considerations may help to explain the apparent discrepancy between the amount of energy which is capable of being produced by the usual daily amount of food, with that which is actually manifested daily by the body; the former leaving but a small margin for anything beyond the maintenance of heat, and mechanical work.

It is of much interest to consider the way in which protoplasm acts in converting food into energy plus decomposition products. It is certain that the substance itself does not undergo much change in the process except a slight amount of wear and tear. We may assume that it is the

erty of protoplasm to separate from the blood the materials which
ay require to produce secretions, in the case of the protoplasm of
eting glands, or to enable it to evolve heat and energy as in the
of the protoplasm of muscle. The properties of the protoplasm are
possibly differently developed in each case, and the decomposition
ucts, too, may be different in quality or quantity. Proteid materials
ar to be specially needed, as is shown by the invariable presence of
in the urine even during starvation; and as in the latter case there
been no food from which these materials could have been derived,
urea is considered to be derived from the disintegration of the nitro-
us tissues themselves. Which, if not all, of the three varieties of
eid of the blood, viz., serum-albumin, serum-globulin, and fibrino-
is necessary for muscular metabolism is not certainly known;
ion appears to incline toward the first as the most important. The
oval of all fat from the body in a starvation period, as the first appar-
change, would lead to the supposition that fat is also a specially
ssary pabulum for the production of protoplasmic energy; and the
that, as mentioned above, with a diet of lean meat an enormous
unt appears to be required, suggests that in that case protoplasm
ins the fat it needs from the proteid food, which process must be
ently a source of much waste of nitrogen. The fat which is
sited in the tissues has for its origin, as we have before remarked,
reat part carbohydrate food, and is looked upon as a store of carbo-
ous material; it has been suggested that as it leaves the tissue to be
up, it is reconverted into a carbohydrate, viz., dextrose. Salts
ar to be absolutely essential for protoplasmic life. The idea that
eid food has two destinations in the economy, viz., to form organ or
e proteid which builds up organs and tissues, and circulating pro-
from which the organs and tissues derive the materials of their
tions or for producing their energy, is a convenient one, but cannot
id to rest upon any very certain facts. Except in the possible case
e appearance of leucin and tyrosin in pancreatic digestion, already
discussed, it must not be looked upon as more than a convenient
thesis.

ne question which has been little considered by physiologists, is
relationship, if any, there is between each tissue and the waste pro-
s of other tissues, or perhaps it should be said, the products of the
bolism of other tissues. It is not known whether, as the result of
katabolism of one tissue, products, proteid or otherwise, are not
up by the blood and carried to other tissues, supplying exactly
is necessary for their complete anabolism; whether, for example,
teid residue does not arise from the metabolism of muscle which

may be used further by glands. One step, at all events, in this direction has been taken; it has been suggested that the sarco-lactic acid continually produced by muscle is carried to the liver, either to be converted itself into glycogen, or by its influence on the hepatic cells to cause them to store up that substance.

# CHAPTER XII.

## ANIMAL HEAT.

ONE of the most important results of the metabolism of the tissues is he production of the heat of the body. It is by this means that the odily temperature is raised to such a point as to make life possible. n man and in such animals as are called warm-blooded, including only ammals and birds, it is found on the one hand, that there is an aver- ge temperature which is maintained with only slight variations in spite f changes in their environment, and on the other hand, that the pos- ible variations above and below this average are comparatively slight. t must not be thought, however, that the average temperature in all ammals and birds is the same; for example, as we shall see, the average mperature of man is just 37° C. (98.6° F.), in some birds it is as high s 44° C. (111° F.), whereas in the wolf it is said to be under 36° C 6° F.).

The average temperature of the human body in those internal parts hich are most easily accessible, as the mouth and rectum, is from 36.9° 7.4° C. (98.5° to 99.5° F.). In different parts of the external surface the human body the temperature varies only to the extent of one or o degrees (C.), when all are alike protected from cooling influences; d the difference which under these circumstances exists, depends chiefly on the different degrees of blood-supply. In the axilla—the most nvenient situation, under ordinary circumstances, for examination by thermometer—the average temperature is 36.9° C. (98.5° F.). In ferent internal parts, the variation is one or two degrees; those parts d organs being warmest which contain most blood, and in which there urs the greatest amount of chemical change, *e.g.*, the muscles and glands; and the temperature is highest, when they are in a condi- n of activity: while those tissues which, subserving only a mechanical nction, are the seat of least active circulation and chemical change, the coolest. These differences of temperature, however, are actually t slight, on account of the provisions which exist for maintaining iformity of temperature in different parts.

*Circumstances causing Variations in Temperature.*—The chief circumstances which the temperature of a healthy body is influenced are the following :—

*Age.*—The average temperature of the new-born child is only about half a ree C. (1° F.) above that of the adult; and the difference becomes still more trifling during infancy and early childhood. The temperature fal the extent of about .2° C. (.5° F.) from early infancy to puberty, an about the same amount from puberty to fifty or sixty years of age. In ol the temperature again rises, and approaches that of infancy.

*Sex.*—The average temperature of the female is slightly higher than t the male.

*Period of the Day.*—The temperature undergoes a gradual alteration, extent of about .54°–.8° C. (1° to 1.5° F.) in the course of the day and the *minimum* being at night or in the early morning, the *maximum* late afternoon.

*Exercise.*—Active exercise raises the temperature of the body from .54 C. (1° to 2° F.).

*Climate and Season.*—The temperature of the human body is practica same in temperate as in tropical climates. In summer the temperature body is a little higher than in winter; the difference amounting to a fifth of a degree C.

*Food and Drink.*—The effect of a meal upon the temperature of a body small. A very slight rise usually occurs. Cold alcoholic drinks s depress the temperature about half a degree C. Warm alcoholic drin well as warm tea and coffee, raise the temperature about a third of a deg

*Disease.*—In disease the temperature of the body deviates from the standard to a greater extent than would be anticipated from the slight of external conditions during health. Thus, in some disease, as pneu and typhus, it occasionally rises as high as 41°–41.6° C. (106° or 107° F. considerably higher temperatures have been noted. In Asiatic cholera, other hand, a thermometer placed in the mouth may sometimes rise 25°–26.2° C. (77° or 79° F.).

The temperature maintained by Mammalia in an active state of life, a ing to the tables of Tiedemann and Rudolphi, averages 38.3° C. (10 The extremes recorded by them were 34.6° C. (96° F.) and 41° C. (106° F. former in the narwhal, the latter in a bat (Vespertilio pipistrella). In the average is as high as 41.2° C. (107° F.); the highest temperature, 4 (111.25° F.) being in the small species, the linnets, etc. Among Reptiles, the medium they were in was 23.9° C. (75° F.) their average temperatu 31.2° C. (82.5° F.). As a general rule, their temperature, though it falls that of the surrounding medium, is, in temperate media, two or more d higher; and though it rises also with that of the medium, yet at very degrees it ceases to do so, and remains even lower than that of the me Fish and invertebrata present, as a general rule, the same temperature medium in which they live, whether that be high or low; only among fis tunny tribe, with strong hearts and red meat-like muscles, and more than the average of fish have, are generally 3.8° C. (7° F.) warmer th water around them.

The difference, therefore, between what are commonly called the war the cold-blooded animals, or *homoiothermal* (ὅμοιος, like, θέρμη, heat) and p *thermal* (ποικίλος, changeful, θέρμη, heat), is not one of absolutely higher or temperature; for the animals which to us in a temperate climate feel col ing like the air or water, colder than the surface of our bodies), would external temperature of 37.8° C. (100° F.) have nearly the same tempe and feel hot to us. The real difference is that warm-blooded animals certain permanent heat in all atmospheres, while the temperature of blooded animals is variable with every atmosphere.

## THE PRODUCTION OF THE BODY HEAT.

The heat which is produced in the body arises from the metabolic hanges of the tissues, the chief part of which are of the nature of oxida- ion, since it may be supposed that the oxygen of the atmosphere taken nto the system is *ultimately* combined with carbon and hydrogen, and ischarged from the body as carbonic acid and water. Any changes, ndeed, which occur in the protoplasm of the tissues, resulting in an hibition of their function, are attended by the evolution of heat and e formation of carbonic acid and water. The more active the anges the greater is the heat produced and the greater is the amount the carbonic acid and water formed. But in order that the proto- asm may perform its function, the waste of its own tissue (destructive etabolism), must be repaired by the due supply of food material to be ilt up in some way into the protoplasmic molecule. For the oduction of heat, therefore, food is necessary. In the tissues, we have several times remarked, two processes are continually ing on: the building up of the protoplasm from the food (constructive etabolism) which is not accompanied by the evolution of heat, possibly en by its storing, and the oxidation of the protoplastic materials sulting in the production of energy, by which heat is set free and rbonic acid and water are evolved.

It is not necessary to assume that the combustion processes, indeed, e as simple as the bare statement of the fact might seem to indicate; d, we have indicated, in treating of muscular metabolism, the process pears to consist first of all of building up of the oxygen into the olecule. But complicated as the various stages may be, the ultimate sult is as simple as in ordinary combustion outside the body, and the oducts are the same.

This theory that the maintenance of the temperature of the living dy depends on continual chemical change, chiefly by oxidation of mbustible materials in the tissues, has long been established by the monstration that the quantity of carbon and hydrogen as supplied as od, which, in a given time, unites in the body with oxygen, is sufficient account for the amount of heat generated in the animal within the ne period: an amount capable of maintaining the temperature of the ly at from 36.8°–38.7° C. (98°–100° F.), notwithstanding a large s by radiation and evaporation. This estimation depends upon the mical axiom that when a body undergoes a chemical change the ount of energy set free is the same, supposing the resulting products the same, whether the change takes place suddenly or gradually. If ertain number of grammes of different substances are introduced as l, and if they undergo complete oxidation, the amount of kinetic energy as shown in the amount of heat, and mechanical work, is the same if the same bodies are completely oxidized outside the body; so that if 1 gramme of fat be taken into the body and is completel oxidized, resulting in the production of a definite amount of carbo dioxide and water, it may be supposed to have produced the sam amount of heat as it would have produced outside the body. In t case of proteid food it is a little different, since it is never complete oxidized within the body, but may be supposed to give rise to a defini amount of urea, not a completely oxidized body. In this case t gramme of proteid may be considered to perform the same amount heat as the proteid would outside the body minus the amount whi would be obtained from the complete oxidation of the resulting urea.

The actual amount of heat produced per diem has been experimental ascertained in the case of small animals by the aid of an apparat called a **Calorimeter.** The animal is inclosed in a metal box co pletely contained in a second box containing water, and air is led in and out of the inner box by means of metal tubes; the one through whic the air is led out of the chamber has several coils in it. The heat give out by the animal warms the water in the outside box, and may estimated by the rise of its temperature, the amount of which is know

The amount of heat produced and of energy in the form of mechanic work set free in a given time arise from the oxidation of the substanc taken in as food in so far as they are oxidized. In order that there ma be correct data to assist in the consideration of the subject, the amou of heat evolved by the oxidation of various food-stuffs has been carefull measured. The results may be set down in terms of *gramme-calori* (Ca), a calorie being the heat unit, and meaning the amount of hea required to raise 1 gramme of water 1 degree C., or, more strictly, fro 15° C. to 16° C.* The number of gramme-calories which 1 gramm of the following substances equals will be seen in the annexed table.

| | | | | | |
|---|---|---|---|---|---|
| Hydrogen . | 3450 | Fat . . | 9000 | Urea . | 2200 |
| Carbon . . | 8100 | Carbohydrate | 4000 | | |
| | | Proteid . | 5000—5500 | | |

1 gramme of proteid giving rise to $\frac{1}{3}$ gramme of urea.

The relation between the income and expenditure of the body ha been already considered in detail in the preceding chapter. We ma now turn to the question of the chief heat-producing tissues.

**Heat-producing Tissues.**—(1.) *The Muscles.*—As the musc form so large a part of the body, and as in them metabolism is particula active, it is only reasonable to consider the muscular as the chief hea producing tissue. It will shortly be pointed out that the manifestation of muscular energy is always accompanied by the evolution of heat and the production of carbon dioxide. This production of carbon dioxide goes on while the muscles are at rest, only in a less degree to that which is noticed during muscular activity, and so it is certain that n active metabolism is going on in resting as well as in contracting muscles. This metabolism is a source of much heat, and so the total mount of heat produced in the muscular tissues per diem must be very reat. It has been calculated that, even neglecting the heat produced y the quiet metabolism of muscular tissue, the amount of heat generted by muscular activity would supply the principal part of the total eat produced within the body. (2.) The *Secreting glands*, and prinpally the liver, as being the largest and most active, come next to the uscles as heat-producing tissue. It has been found by experiment that he blood leaving the glands is considerably warmer than that entering hem. The metabolism in the glands is very active, and, as we have en, the more active the metabolism the greater the heat produced. 3.) *The Brain;* the venous blood has a higher temperature than the terial. It must be remembered, however, that although the organs bove mentioned are the chief heat-producing parts of the body, all ving tissues contribute their quota, and this in direct proportion to eir activity. The blood itself is also the seat of metabolism, and, erefore, of the production of heat; but the share which it takes in is respect, apart from the tissues in which it circulates, is very inconderable. There are two other means by which the heat produced by tabolism of the tissues is added to in slight degree, viz., by friction, , in the movements of muscles, in the circulation of blood, and elsehere. This contributes a slight but undetermined amount of heat, d by the taking in of warm foods, solid or liquid, a further small ount of heat is at the same time acquired.

---

* Sometimes the term *kilogramme-calorie* is used; one kilogramme-calo being equal to 1000 gramme-calories.

## REGULATION OF THE TEMPERATURE OF THE HUMAN BODY.

The average temperature of the body is maintained under different nditions of external circumstances by mechanisms which permit of variation in the loss of heat, and (2) variations in the production of t. In healthy warm-blooded animals the loss and gain of heat are so rly balanced one by the other that, under all ordinary circumstances, uniform temperature, within a degree or two, is preserved.

**Variation in the Loss of Heat.**—The loss of heat from the human y is principally regulated by the amount given off (1) by radiation conduction from its surface, and by means of the (2) constant evapoon of water from the same part, heat being thus rendered latent, and

to a much less degree (3) from the air-passages; in each act of resp
tion, heat is lost to a greater or less extent according to the tempera
of the atmosphere; unless indeed the temperature of the surroun
air exceed that of the blood. We must remember too that (4) all
and drink which enter the body at a lower temperature than itself
stract a small measure of heat; (5) while the urine and fæces w
leave the body at about its own temperature are also means by wh
small amount is lost.

(*a.*) *From the Surface of the Body.*—By far the most importan
of heat from the body,—probably 90 per cent and upward of the
amount, is that which takes place by radiation, conduction, and eva
tion from the skin. The actual figures are as follows:—of 100 cal
of heat produced, 2.6 are lost in heating food and drink; 2.6 in he
air inspired; 14.7 in evaporation; and 80.1 by radiation and conduc
The means by which the skin is able to act as one of the most in
tant organs for regulating the temperature of the blood, are—(1),
it offers a large surface for radiation, conduction, and evaporation;
that it contains a large amount of blood; (3), that the quantit
blood contained in it is the greater under those circumstances w
demand a loss of heat from the body, and *vice versa.* For the cir
stance which directly determines the quantity of blood in the ski
that which governs the supply of blood to all the tissues and orga
the body, namely, the power of the vaso-motor nerves to cause a gr
or less tension of the muscular element in the walls of the arteries,
in correspondence with this, a lessening or increase of the calib
the vessel, accompanied by a less or greater current of blood. A w
or hot atmosphere so acts on the nerve fibres of the skin, as to
them to cause in turn a relaxation of the muscular fibre of the bl
vessels; and, as a result, the skin becomes full-blooded, hot, and sw
ing; and much heat is lost. With a low temperature, on the o
hand, the blood-vessels shrink, and in accordance with the conseque
diminished blood-supply, the skin becomes pale, and cold, and dry;
no doubt a similar effect may be produced through the vaso-motor
tre in the medulla and spinal cord. Thus, by means of a self-regula
apparatus, the skin becomes the most important of the means by w
the temperature of the body is regulated.

In connection with loss of heat by the skin, reference has been
to that which occurs both by radiation and conduction, and by eva
tion; and the subject of animal heat has been considered almost
with regard to the ordinary case of man living in a medium colder
his body, and therefore losing heat in all the ways mentioned.
importance of the means however, adopted, so to speak, by the ski
regulating the temperature of the body, will depend on the condi

y which it is surrounded; an inverse proportion existing in most cases etween a loss by radiation and conduction on the one hand, and by aporation on the other. Indeed, the small loss of heat by evaporation cold climates may go far to compensate for the greater loss by radia- n; as, on the other hand, the great amount of fluid evaporated in t air may remove nearly as much heat as is commonly lost by both iation and evaporation together in ordinary temperatures; and thus, s possible that the quantities of heat required for the maintenance of niform proper temperature in various climates and seasons are not lifferent as they, at first sight, seem.

Iany examples may be given of *the power which the body possesses of resist- the effects of a high temperature,* in virtue of evaporation from the skin. gden and others supported a temperature varying between 92°–100° C. °–212° F.) in dry air for several minutes; and in a subsequent experiment remained eight minutes in a temperature of 126.5° C. (260° F.). "The kmen of Sir F. Chantrey were accustomed to enter a furnace, in which moulds were dried, while the floor was red-hot, and a thermometer in the stood at 177.8° C. (350° F.), and Chabert, the fire-king, was in the habit of ring an oven, the temperature of which was from 205°–315° C. (400°–600° " (Carpenter.)

But such heats are not tolerable when the air is moist as well as hot, so o prevent evaporation from the body. C. James states, that in the vapor s of Nero he was almost suffocated in a temperature of 44.5° C. (112° F.), le in the caves of Testaccio, in which the air is dry, he was but little mmoded by a temperature of 80° C. (176° F.). In the former, evaporation n the skin was impossible; in the latter it was abundant, and the layer apor which would rise from all the surface of the body would, by its very rly conducting power, defend it for a time from the full action of the ex- al heat.

We are able by suitable clothing to increase or to diminish the amount eat lost by the skin.

The ways by which the skin may be rendered more efficient as a cool- apparatus too, by exposure, by baths, and by other means which instinctively adopts for lowering his temperature when necessary, too well known to need more than passing mention.

lthough under any ordinary circumstances the external application of only temporarily depresses the temperature to a slight extent, it is other- in cases of high temperature in fever. In these cases a tepid bath may ce the temperature several degrees, and the effect so produced last in cases for many hours.

b) *From the Lungs.*—As a means for lowering the temperature, the s and air-passages are very inferior to the skin; although, by giving to the air we breathe, they stand next to the skin in importance. regulating power, the inferiority is still more marked. The air h is expelled from the lungs leaves the body at about the temperature of the blood, and is always saturated with moisture. No inver proportion, therefore, exists, as in the case of the skin, between the los of heat by radiation and conduction on the one hand, and by evaporatio on the other. The colder the air, for example, the greater will be th loss in all ways. Neither is the quantity of blood which is exposed t the cooling influence of the air diminished or increased, so far as i known, in accordance with any need in relation to temperature. It i true that by varying the number and depth of the respirations, th quantity of heat given off by the lungs may be made, to some extent to vary also. But the respiratory passages, while they must be considere important means by which heat is lost, are altogether subordinate, i the power of regulating the temperature, to the skin.

(*c*) *By Warming Cold Foods.*—This is an obvious method of expenditure of heat which may be resorted to, but the loss of heat by the excret discharged from the body at a high temperature, must be of little use a means of regulating the temperature, since the amount so lost must b capable of little variation.

**Variation in the Production of Heat.**—It may seem to have bee assumed, in the foregoing pages, that the only regulating apparatus f temperature required by the human body is one that shall, more or les produce a cooling effect; and as if the amount of heat produced wa always, therefore, in excess of that which is required. Such an assumption would be incorrect. We have the power of regulating the production of heat, as well as its loss.

The regulation of the production of heat in the body is apparentl different for each animal, as the absolute amount of heat set free b different animals in a given period varies; in one the production of hea exceeds that in another. It is even said that each individual has hi own coefficient of heat production. From all that has been said on th subject it will be seen that the amount of heat for all practical purpo depends upon the metabolism of the tissues of the body, everythin therefore which increases that metabolism will increase the heat production, so therefore the absolute amount of heat produced by a larg animal, having a larger amount of tissues in which metabolism may g on, will be, *cæteris paribus*, greater than that of a small animal. But c course the activity of the tissue change in a small animal may be great than in a large one, and naturally no strict line can be drawn betwee the two.

The ingestion of food has been proved to increase the metabolism o the tissues, and so, as one would expect, the rate of heat production i found by experiment upon the dog to be increased after a meal, an in this animal the heat production reaches its height about 6 to 9 hou after a meal.

It has also been experimentally ascertained that the rate of heat production varies somewhat with the kind of food taken, for example, f sugar be added to the meal of meat given to the dog, the height of maximum production is reached. It was always said that various nations ad found by experience what food was most suitable for the climate in hich they lived, and that such experience could be trusted to regulate he quantity consumed. Although there have been no very conclusive xperiments to prove this view, yet it is a matter of general observation at in northern climates and in colder seasons the quantity of food ken is greater than in warmer climates or in warmer seasons. More- er, the kind of food is different. For example, persons living in the lder climates require much fat in order to produce the requisite ount of heat.

In exercise, we have an important means of raising the temperature of r bodies, by it the muscular metabolism is increased, as is shown by e increased output of carbon dioxide.

**Influence of the Nervous System.**—The influence of the nervous stem in modifying the production of heat must be very important, as on nervous influence depends the amount of the metabolism of the sues. The experiments and observations which best illustrate it are ose showing, first, that when the supply of nervous influence to a part cut off, the temperature of that part after a time falls below its ordi- ry degree; and, secondly, that when death is caused by severe injury , or removal of, the nervous centres, the temperature of the body pidly falls, even though artificial respiration be performed, the circu- tion maintained, and to all appearance the ordinary chemical changes the body be completely effected. It has been repeatedly noticed, that ter division of the nerves of a limb its temperature ultimately falls; d this diminution of heat has been remarked still more plainly in bs deprived of nervous influence by paralysis.

With equal certainty, though less definitely, the influence of the rvous system on the production of heat is shown in the rapid and mentary increase of temperature, sometimes general, at other times te local, which is observed in states of nervous excitement; in the neral increase of warmth of the body, excited by passions of the mind; the sudden rush of heat to the face, which is not a mere sensation; d in the equally rapid diminution of temperature in the depressing sions. All of these examples, however, are explicable, on the suppo- on that the nervous system alters, by its power of controlling the bre of the blood-vessels, the quantity of blood supplied to a part.

Apart, however, from this vaso-motor power of increasing the blood- ply to internal organs, and to the tissues in general, by means of ch it is possible to increase their metabolism and so their production eat, there is evidence to suppose that there is another nervous apparatus closely comparable to that which regulates the secretion of saliva or of sweat, by means of which the production of heat in the warm-blooded animals is increased or diminished as occasion requires. This apparatus probably consists of a centre or centres which may be reflexly stimulated, as for example by impulses from the skin, and which act through special nerves supplied to the various tissues. The evidence upon which the existence of this regulating apparatus depends is the marked effect in the increase of the oxygen taken in by a warm-blooded animal when exposed to cold and the corresponding increase in the output of carbon dioxide, indicating that there is an increase of the metabolism and so an increased production of heat, under such circumstances and not a mere diminution of the amount of heat lost by the skin, etc. A cold-blooded animal reacts very differently to exposure to cold; instead of as in the case of the warm-blooded animal, increasing the metabolism, cold diminishes the metabolism of its tissues. It appears clear, therefore, that in warm-blooded animals there is some extra apparatus which counteracts the effects of cold which in cold-blooded animals causes diminished metabolism. In warm-blooded animals poisoned by curari, or in which section of the bulb has been done, it has been found that this regulating apparatus is no longer in action, and under such circumstances no difference appears to exist between such animals and those which are naturally cold-blooded. Warmth increases their temperature and cold lowers it, and with this there is of course evidence of diminished metabolism. The explanation of these experiments as given by modern physiologists is that in such animals the connection which naturally exists between the skin and the muscles through the nervous chain, such as a thermotaxic nervous apparatus might be supposed to afford, is broken either at the termination of the nerves in the muscles or at the section point of the bulb. The position of this hypothetical centre is a matter of some difference of opinion. It has been demonstrated that stimulation of different parts of the brain may, among other symptoms, produce increased metabolism of the tissues with increased output of carbon dioxide and a raised temperature: the parts of which this may be asserted are parts of the corpus striatum and of the optic thalamus. The exact situation of the heat centres, however, is at present not known with certainty.

Experimental observations such as have been made upon animals receive confirmation from the observations of patients who suffer from fever or pyrexia; in them the temperature of the body may be raised several degrees, as we have already pointed out (p. 464). This increase of temperature might of course be due to diminished loss of heat from the skin, but this although in all probability entering into its causation, is not the only cause. The amount of oxygen taken in and the amount n dioxide given out are both increased, and with this there must ased metabolism of the tissues, and particularly of the muscular since at the same time the amount of urea in the urine is d. Every one is familiar with the rapid wasting which is such cteristic of high fever; it must indicate not only too rapid ism of the body, but also insufficient time for the tissues to build ves up. In fever then there may be supposed to be some inter- in the ordinary channel by which the skin is able to communi- the nervous system the necessity of an increased or diminished ion of heat in the muscles and other tissues. In consequence of d in spite of the condition of heat of the surface of the body, duction of heat goes on at an abnormal rate. It is not certain way the centre acts, whether it is one which keeps the meta- in check, and when out of gear it is no longer able to do this, or , on the other hand, it is a centre by means of which the meta- of the tissues may be increased by stimuli proceeding from it. s from the skin would, according to these two possible modes n, act either in the direction of increasing its inhibitory action, he direction of increasing or of diminishing the different stimuli increased production.

**uence of Extreme Heat and Cold.**—In connection with the on of animal temperature, and its maintenance in health at the height, may be noted the result of circumstances too powerful, n raising or lowering the heat of the body, to be controlled by the regulating apparatus. Walther found that rabbits and dogs kept to a hot sun, reached a temperature of 46° C. (114.8° F.), and ed. Cases of sunstroke furnish us with several examples in e of man; for it would seem that here death ensues chiefly or om elevation of the temperature.

effect of mere loss of bodily temperature in man is less well known e effect of heat. From experiments by Walther, it appears that can be cooled down to 8.9° C. (48° F.), before they die, if arti- spiration be kept up. Cooled down to 17.8° C. (64° F.), they recover unless external warmth be applied together with the nent of artifical respiration. Rabbits not cooled below 25° C. recover by external warmth alone.

# CHAPTER XIII.

## EXCRETION.

We have now considered the methods by which the food is digested and prepared for absorption, as well as the methods by which the changed materials reach the general blood-stream, either by means of the lymphatics of the intestinal wall or by the capillaries of the portal circulation. We have also discussed the most difficult problems of physiology, viz., those concerned with the exact changes which take place in the tissues and organs of the body, when they are supplied with the food necessary for life. We have mentioned the chief forms in which the waste materials resulting from the metabolism of the tissues leave the body. We have seen how carbon dioxide and other matters are eliminated by the lungs, and, further, we have devoted some time to the consideration of the amount and composition of the fæces. The highly important function of the kidneys, in excreting the urine, and thus removing certain waste materials, and the functions of the skin remain, and it is to these that we must now direct our attention.

### The Structure and Functions of the Kidneys.

The kidneys are two in number, and are situated deeply in the lumbar region of the abdomen on either side of the spinal column behind the peritoneum. They correspond in position to the last two dorsal and two upper lumbar vertebræ; the right being slightly below the left in consequence of the position of the liver on the right side of the abdomen. They are about 4 inches long, 2½ inches broad, and 1¼ inches thick. The weight of each kidney is about 4½ oz (140 grms.).

*Structure.*—The kidney is covered by a tough fibrous capsule, which is slightly attached by its inner surface to the proper substance of the organ by means of very fine fibres of areolar tissue and minute blood-vessels. From the healthy kidney, therefore, it may be easily torn off without injury to the subjacent cortical portion of the organ. At the *hilus* or notch of the kidney, it becomes continuous with the external coat of the upper and dilated part of the ureter (fig. 291).

On dividing the kidney into two equal parts by a section carried ough its long convex border (fig. 291), the main part of its substance een to be composed of two chief portions called respectively *cortical* *medullary*, the latter being also sometimes called *pyramidal*, from fact of its being composed of about a dozen conical bundles of urine es, each bundle forming what is called a pyramid. The upper part he *ureter* or duct of the organ, is dilated into the *pelvis ;* and this, n, after separating into two or three principal divisions, is finally livided into still smaller portions, varying in number from about 8 2, or even more, and called *calyces.* Each of these little calyces or s, which are often arranged in a double row, receives the pointed



Fig. 291.



Fig. 292.

ig. 291.—Plan of a longitudinal section through the pelvis and substance of the right kidney, the cortical substance: *b*, *b*, broad part of the pyramids of Malpighi; *c*, *c*, the divisions of the named calyces, laid open; *c′*, one of those unopened; *d*, summit of the pyramids of papillæ cting into calyces; *e*, *e*, section of the narrow part of two pyramids near the calyces; *p*, pel- enlarged divisions of the ureter within the kidney; *u*, the ureter; *s*, the sinus; *h*, the hilus.
ig. 292.—A. Portion of a secreting tubule from the cortical substance of the kidney. B. The epi- l or gland-cells. × 700 times.

remity or *papilla* of a pyramid. Sometimes, however, more than one pilla is received by a calyx.

The kidney is a compound tubular gland, and both its cortical and dullary portions are composed essentially of tubes, the *tubuli urini- ri*, which, by one extremity, in the *cortical* portion, end commonly in le saccules containing blood-vessels, called *Malpighian bodies,* and, the other, opened through the papillæ into the pelvis of the kidney, thus discharge the urine which flows through them.

In the pyramids the tubes are chiefly straight—dividing and diverg- as they ascend through these into the cortical portion; while in the er region they spread out more irregularly, and become much ched and convoluted.

*Tubuli Uriniferi.*—The tubuli uriniferi (fig. 292) are composed of a nearly homogeneous membrane, and are lined internally by epitheli They vary considerably in size in different parts of their course, but a on an average, about $\frac{1}{600}$ of an inch ($\frac{1}{24}$ mm.) in diameter, and are fou



Fig. 293.—A diagram of the sections of uriniferous tubes. A, Cortex limited externally b capsule; *a*, subcapsular layer not containing Malpighian corpuscles; *a′*, inner stratum of co also without Malpighian capsules; B, boundary layer; C, papillary part next the boundary la 1, Bowman's capsule of Malpighian corpuscle; 2, neck of capsule; 3, proximal convoluted tubu spiral tubule; 5. descending limb of Henle's loop; 6, the loop proper; 7, thick part of the asce limb; 8, spiral part of ascending limb; 9, narrow ascending limb in the medullary ray; 10, t regular tubule; 11, the intercalated section, or the distal convoluted tubule; 12, the curved co ing tubule; 13, the straight collecting tubule of the medullary ray; 14, the collecting tube of boundary layer; 15, the large collecting tube of the papillary part which, joining with si tubes, forms the duct. (Klein.)

to be made up of several distinct sections which differ from one ano very markedly, both in situation and structure. According to K the following segments may be made out: (1) The *Malpighian cor*

(figs. 293, 298), composed of a hyaline membrana propria, thickened
a varying amount of fibrous tissue, and lined by flattened nucleated
helial plates. This capsule is the dilated extremity of the urinif-
us tubule, and contains within it a glomerulus of convoluted capil-
blood-vessels supported by connective tissues, and covered by flat-
d epithelial plates. The glomerulus is connected with an efferent
an afferent vessel. (2) The constricted *neck* of the capsule (fig.
2), lined in a similar manner, connects it with (3) The *Proximal*
*oluted tubule,* which forms several distinct curves and is lined with



lg. 294.—From a vertical section through the kidney of a dog—the capsule of which is supposed
on the right. *a*, the capillaries of the Malpighian corpuscle—viz., the glomerulus, are ar-
d in lobules; *n*, neck of capsule; *c*, convoluted tubes cut in various directions; *b*, irregular
; *d*, *e*, and *f*, are straight tubes running toward capsules forming a so-called *medullary ray;*
ecting tube; *e*, spiral tube; *f*, narrow section of ascending limb. × 380. (Klein and Noble
)

columnar cells, which vary somewhat in size. The tube next
s almost vertically downward, forming (4) The *Spiral Tubule,*
h is of much the same diameter, and is lined in the same way as
onvoluted portion. So far the tube has been contained in the cortex
e kidney; it now passes vertically downward through the most
nal part (boundary layer) of the Malpighian pyramid into the more
nal part (papillary layer), where it curves up sharply, forming
ether the (5 and 6) *Loop of Henle,* which is a very narrow tube
with flattened nucleated cells. Passing vertically upward just as
ube reaches the boundary layer (7), it suddenly enlarges and be-
s lined with polyhedral cells. (8) About midway in the boundary

layer the tube again narrows, forming the ***ascending spiral of Henle's loop***, but is still lined with polyhedral cells. At the point where the tube enters the cortex (9) the ascending limb narrows, but the diameter varies considerably; here and there the cells are more flattened, but both in this as in (8), the cells are in many places very angular, branched, and imbricated. It then joins (10) the "*irregular tubule*," which has a very irregular and angular outline, and is lined with angular and imbricated cells. The tube next becomes convoluted (11), forming the ***distal convoluted tube*** or ***intercalated section of Schweigger-Seidel***, which is identical in all respects with the proximal convoluted tube (12 and 13). The curved and straight collecting tubes, the former entering the latter at right angles, and the latter passing vertically downward, are lined with polyhedral, or spindle-shaped, or flattened, or angular cells. The straight collecting tube now enters the boundary layer (14) and passes on to the papillary layer, and, joining with other collecting tubes, forms larger tubes, which finally open at the apex of the papilla. These collecting tubes are lined with transparent nucleated columnar or cubical cells (14, 15).



**Fig. 295.**—Transverse section of a renal papilla; *a*, large tubes or papillary ducts; *b*, *c*, and *d*, smaller tubes of Henle; *e*, *f*, blood capillaries. distinguished by their flatter epithelium. (Cadiat.)

The cells of the tubules with the exception of Henle's loop and all parts of the collecting tubules, are, as a rule, possessed of the intranuclear as well as of the intra-cellular network of fibres, of which the vertical rods are most conspicuous.

In some places, it is stated that a distinct membrane of flattened cells can be made out lining the lumen of the tubes (*centrotubular membrane*).

## Blood-Vessels.

*ply.*—In connection with the general distribution of blood-kidney, the *Malpighian Corpuscles* must be further con-ey (fig. 297) are found only in the cortical part of the kid-ney, and are confined to the central part, which, however, makes up about seven-eighths of the whole cortex. On a section of the organ, some of them are just visible to the naked eye as minute red points; others are too small to be thus seen. Their average diameter is about $\frac{1}{120}$ of an inch ($\frac{1}{5}$ mm.). Each of them is composed, as we have seen above, of the dilated extremity of an uriniferous tube, or Malpighian *capsule*, which encloses a tuft of blood-vessels.



ular supply of kidney. *a*, h; *b*, interlobular artery; *c*, rent vessels passing to the teria recta; *e*, capillaries of ies of medulla; *g*, venous eins of medulla; *j*, vena stel- r vein. (Cadiat.)

The renal artery divides into several branches, which, passing in at the hilus of the kidney, and covered by a fine sheath of areolar tissue derived from the capsule, enter the substance of the organ chiefly in the intervals between the papillæ, and at the junction between the cortex and the boundary layer. The main branches then pass almost horizontally, forming more or less complete arches and giving off branches upward to the cortex and downward to the medulla. The former are for the most part straight; they pass almost vertically to the surface of the kidney, giving off laterally in all directions longer and shorter branches, which ultimately supply the Malpighian bodies. *afferent* artery (figs. 297 and 298) which enters the Malpig-e, breaks up in the interior as before mentioned into a dense d looped capillary plexus (rete mirabile), which is ultimately gain into several small *efferent* vessels, comparable to minute leave the capsule at one or more places near the point at which the afferent artery enters it. On leaving, they do not immediately join other small veins as might have been expected, but again breaking up into a network of capillary vessels, are distributed on the exterior of the tubule. After this second breaking up the capillary plexus terminates in a small vein, which, by union with others like it, helps to form the radicles of the renal vein. These small veins pass into others which form venous arches corresponding to the arterial arches, but which are more distinct, situated between the medulla and cortex.



Fig. 297.—Diagram showing the relation of the Malpighian body to the uriniferous ducts and blood-vessels. *a*, one of the interlobular arteries; *a′*, afferent artery passing into the glomerulus; *c*, capsule of the Malpighian body, forming the termination of and continuous with *t*, the uriniferous tube; *e′*, *e′*, efferent vessels which subdivide in the plexus, *p*, surrounding the tube, and finally terminate in the branch of the renal vein *e* (after Bowman).



Fig. 298.—Malpighian capsule and tuft of capillaries, injected through the renal artery with colored gelatin. *a*, glomerular vessels; *b*, capsule; *c*, anterior capsule; *d*, glomerular artery; efferent veins; *f*, epithelium of tubes. (Cadiat.)

Thus, in the kidney, the blood entering by the renal artery, traverses sets of capillaries before emerging by the renal vein, an arrangement ich may be compared to the *portal* system in miniature.

The tuft of vessels within the Malpighian capsule in the course of de- opment has been thrust into the dilated extremity of the urinary ule, which finally completely invests it. Thus within the Malpighian sule there are two layers of squamous epithelium, a parietal layer ng the capsule proper, and a visceral or reflected layer immediately ering the vascular tuft (fig. 299), and sometimes dipping down into interstices. This reflected layer of helium is readily seen in young ects, but cannot always be demon- ted in the adult. (See figs. 299 300.)



Fig. 299.



Fig. 300.

. 299.—Transverse section of a developing Malpighian capsule and tuft (human). × 300. foetus at about the fourth month; *a*, flattened cells growing to form the capsule; *b*, more d cells, continuous with the above, reflected round *c*, and finally enveloping it; *c*, mass of onic cells which will later become developed into blood-vessels. (W. Pye.)

. 300.—Epithelial elements of a Malpighian capsule and tuft, with the commencement of a tubule showing the afferent and efferent vessel; *a*, layer of flat epithelium forming the e; *b*, similar, but rather larger epithelial cells, placed in the walls of the tube; *c*, cells, covering sels of the capillary tuft; *d*, commencement of the tubule, somewhat narrower that the rest (W. Pye.)

he vessels which enter the medullary layer break up into smaller ioles, which pass through the boundary layer, and proceed in a ght course between the tubules of the papillary layer, giving off on way branches, which form a fine arterial meshwork around the s, and ending in a similar plexus from which the venous radicles

esides the small *afferent* arteries of the Malpighian bodies, there of course, others which are distributed in the ordinary manner, for nutrition of the different parts of the organ; and in the pyramids, een the tubes, there are numerous straight vessels, the *vasa recta*, of which are branches of *vasa efferentia* from Malpighian bodies, therefore comparable to the venous plexus around the tubules in the *cortical* portion, while others arise directly as small branches of the renal arteries.

Between the tubes, vessels, etc., which make up the substance of the kidney, there exists, in small quantity, a fine matrix of areolar tissue.

*Nerves.*—The nerves of the kidney are derived from the renal plexus of each side. This consists of both medullated and non-medullated nerve-fibres, the former of varying size, and of nerve-cells. The renal plexus is derived from the solar plexus, particularly from the semilunar ganglion. The renal plexus is thus indirectly connected with the vagi and with the splanchnic nerves. It is also directly connected with them by fibres which pass to them without first joining the solar plexus. Fibres from the anterior roots of the eleventh, twelfth, and thirteenth dorsal nerves in the dog also pass to the same plexus, either directly through the sympathetic chain or by first passing into the solar plexus.



Fig. 301.—Epithelium of the bladder; *a*, one of the cells of the first row; *b*, a cell of the second row; *c*, cells *in situ*, of first, second, and deepest layers. (Obersteiner.)

**The Ureters.**—The duct of each kidney, or *ureter*, is a tube about the size of a goose-quill, and from twelve to sixteen inches in length, which, continuous above with the pelvis of the kidney, ends below by perforating obliquely the walls of the bladder, and opening on its internal surface.

*Structure.*—It is constructed of three principal coats (*a*) an outer, tough, *fibrous and elastic* coat; (*b*) a middle *muscular coat*, of which the fibres are unstriped, and arranged in three layers—the fibres of the central layer being circular, and those of the other two longitudinal in direction; and (*c*) an internal *mucous* lining continuous with that of the pelvis of the kidney above, and of the urinary bladder below. The epithelium of all these parts (fig. 301) is alike stratified and of a somewhat peculiar form; the cells on the free surface of the mucous membrane being usually spheroidal or polyhedral with one or more spherical or oval nuclei; while beneath these are pear-shaped cells, of which the broad ends are directed toward the free surface, fitting in beneath the cells of the first row, and the apices are prolonged into processes of ous lengths, among which, again, the deepest cells of the epithelium e found spheroidal, irregularly oval, spindle-shaped or conical.

**The Urinary Bladder.**—The urinary bladder, which forms a re-eptacle for the temporary lodgment of the urine in the intervals of its xpulsion from the body, is more or less pyriform, its widest part, which situate above and behind, being termed the *fundus;* and the narrow nstricted portion in front and below, by which it becomes continuous ith the urethra, being called its *cervix* or *neck*.

*Structure.*—It is constructed of four principal coats— *serous*, *mus-lar*, *areolar* or *submucous*, and *mucous*. (*a*.) The *serous* coat, which vers only the posterior and upper part of the bladder, has the same ructure as that of the peritoneum, with which it is continuous. (*b*) he fibres of the *muscular* coat, which are unstriped, are arranged in ree principal layers, of which the external and internal have a general ngitudinal, and the middle layer a circular direction. The latter are pecially developed around the *cervix* of the organ, and are described forming a *sphincter vesicæ*. The muscular fibres of the bladder, like ose of the stomach, are arranged not in simple circles, but in figure--8 loops. (*c*) The *areolar* or *submucous* coat is constructed of connec-e tissue with a large proportion of elastic fibres. (*d*) The *mucous* embrane, which is rugose in the contracted state of the organ, does t differ in essential structure from mucous membranes in general. s epithelium is stratified and closely resembles that of the pelvis of the dney and the ureter (fig. 301).

The mucous membrane is provided with mucous glands, which are re numerous near the neck of the bladder.

The bladder is well provided with *blood- and lymph-vessels*, and with *ves*. The latter are both medullated and non-medullated fibres, th branches from the sacral plexus (spinal) and hypogastric plexus mpathetic). Ganglion-cells are found, here and there, in the course the nerve-fibres.

## The Urine.

*Physical Properties.*—Healthy urine is a perfectly transparent, am--colored liquid, with a peculiar, but not disagreeable odor, a bitterish te, and slight acid reaction. Its specific gravity varies from 1015 to 5. On standing for a short time, a little mucus appears in it as a culent cloud, *consisting chemically*, it is said, of nucleo-albumin and mucin.

*Chemical Composition.*—The urine consists of water, holding in solu-n certain organic and saline matters as its ordinary constituents, and sionally various other matters; some of the latter are indications of ased states of the system, and others are derived from unusual articles ood or drugs taken into the stomach.

### CHEMICAL COMPOSITION OF THE URINE.

| | | |
|---|---|---|
| Water | | 967 |
| Solids— | | |
| Urea | 14.230 | |
| Other nitrogenous crystalline bodies—<br>Uric acid, principally in the form of alkaline Urates, a trace only free.<br>Kreatinin, Xanthin, Hypoxathin.<br>Hippuric acid.<br>Mucus, Pigments, and Ferments. | 10.635 | |
| Salts:— | | |
| *Inorganic*—<br>Principally Sulphates, Phosphates, and Chlorides of Sodium and Potassium, with Phosphates of Magnesium and Calcium, traces of Silicates and Chlorides.<br>*Organic*—<br>Lactates, Hippurates, Oxalates, Acetates and Formates, which only appear occasionally. | 8.135 | 33 |
| Sugar | a trace sometimes. | |
| Gases (nitrogen and carbonic acid principally). | | |
| | | 1000 |

*Reaction.*—The normal reaction of the urine is slightly acid. T acidity is due to acid phosphate of sodium, and is less marked soon a meals. The urine contains no appreciable amount of free acid, as gives no precipitate of sulphur with sodium hyposulphite. After sta ing for some time the acidity increases from a kind of acid fermentati due in all probability to the presence of mucus and fungi, and a urates or free uric acid is deposited. After a time, varying in len according to the temperature, the reaction becomes strongly alkali from the change of urea into ammonium carbonate, due to the pres of one or more specific micro-organisms (*micrococcus ureæ*). The u takes up two molecules of water—a strong ammoniacal and fœtid o appears, and deposits of triple phosphates and alkaline urates take pla This does not occur unless the urine is freely exposed to the air, at least, until air has had access to it.

*Reaction of Urine in Different Classes of Animals.*—In most herbivorous a mals the urine is alkaline and turbid. The difference depends not on peculiarity in the mode of secretion, but on the difference in the food on wh the two classes subsist; for when carnivorous animals, such as dogs, are stricted to a vegetable diet, their urine becomes pale, turbid, and alkaline that of an herbivorous animal, but resumes its former acidity on the return an animal diet; while the urine voided by herbivorous animals, *e.g.*, rabb fed for some time exclusively upon animal substances, presents the acid re tion and other qualities of the urine of Carnivora, its ordinary alkali being restored only on the substitution of a vegetable for the animal Human urine is not usually rendered alkaline by vegetable diet, but it bec so after the free use of alkaline medicines, or of the alkaline salts with or vegetable acids; for these latter are changed into alkaline carbonates ous to elimination by the kidneys.

**age daily quantity of the chief urinary constituents** (modified from Parkes).

| | | | | | | Per Kilo of body weight. | |
|---|---|---|---|---|---|---|---|
| Vater . . . . | 1500 | cc. | or | 52½ | oz. | 23. | grms. |
| olids— | | | | | | | |
| Urea . . . | 33.180 | grms | " | 512.4 | grains. | .5 | " |
| Kreatinin . . . | .910 | " | " | 14.0 | " | .0140 | " |
| Uric Acid . . | .555 | " | " | 8.569 | " | .0084 | " |
| Hippuric Acid . . | .400 | " | " | 6.16 | " | .0060 | " |
| Pigment and Extractives . . . | 10. | " | " | 154. | " | .1510 | " |
| Sulphuric Acid . . | 2.012 | " | " | 30.98 | " | .0480 | " |
| Phosphoric Acid . | 3.164 | " | " | 48.80 | " | .0305 | " |
| Chlorine . . . | 7.000 | " | " | 107.8 | " | .1260 | " |
| Ammonia . . | .770 | " | " | 11.8 | " | | |
| Potassium . . . | 2.500 | " | " | 38.5 | " | | |
| Sodium . . | 11.090 | " | " | 170.78 | " | | |
| Calcium . . . | .260 | " | " | 4. | " | | |
| Magnesium . . | .207 | " | " | 3. | " | | |
| | 72. | | | | | | |

*ariations in the Quantity of the Constituents.*—From the propor- given in the above table, most of the constituents are, even in h, liable to variations. The variations of the *water* in different ns, and according to the quantity of drink and exercise, have al- y been mentioned. The water of the urine is also liable to be influ- d by the condition of the nervous system, being sometimes greatly ased, *e.g.*, in hysteria and in some other nervous affections; and at r times diminished. In some diseases it is enormously increased; its increase may be either attended with an augmented quantity of matter, as in ordinary diabetes, or may be nearly the sole change, the affection termed diabetes insipidus. In other diseases, *e.g.*, arious forms of albuminuria, the quantity may be considerably nished. A febrile condition almost always diminishes the quantity ater; and a like diminution is caused by any affection which draws large quantity of fluid from the body through any other channel that of the kidneys, *e.g.*, the bowels or the skin.

*ethod of Estimating the Solids.*—A useful rule for approximately estimating tal solids in any given specimen of healthy urine is to multiply the last figures representing the specific gravity by 2.33. Thus, in urine of sp. 25, $2.33 \times 25 = 58.25$ grains of solids, are contained in 1000 grains of the . In using this method it must be remembered that the limits of errors uch wider in diseased than in healthy urine.

*ariations in the Specific Gravity.*—The average specific gravity of uman urine is about 1020. The relative quantity of water and of constituents of which it is composed is materially influenced by ondition and occupation of the body during the time at which it is secreted; by the length of time which has elapsed since the last meal; and by several other accidental circumstances. The existence of these causes of difference in the composition of the urine has led to the secretion being described under the three heads of *Urina sanguinis*, *Urina potus*, and *Urina cibi*. The first of these names signifies the urine, or that part of it which is secreted from the blood at times in which neither food nor drink has been recently taken, and is applied especially to the urine which is evacuated in the morning before breakfast. The term *urina potus* indicates the urine secreted shortly after the introduction of any considerable quantity of fluid into the body: and the *urina cibi*, the portions secreted during the period immediately succeeding a meal of solid food. The last kind contains a larger quantity of solid matter than either of the others; the first or second, being largely diluted with water, possesses a comparatively low specific gravity. Of these three kinds, the morning urine is the best calculated for analysis in health, since it represents the simple secretion unmixed with the elements of food or drink; if it be not used, the whole of the urine passed during a period of twenty-four hours should be taken. The specific gravity of the urine may thus, consistently with health, range widely on both sides of the usual average. It may vary from 1015 in the winter to 1025 in the summer; but variations of diet and exercise, and many other circumstances, may make even greater differences than these. In disease, the variation may be greater; sometimes descending, in albuminuria, to 1004, and frequently ascending in diabetes, when the urine is loaded with sugar, to 1050, or even to 1060.

*Quantity.*—The total quantity of urine passed in twenty-four hours is affected by numerous circumstances. On taking the mean of many observations by several experiments, the average quantity voided in twenty-four hours by healthy male adults from 20 to 40 years of age has been found to amount to about 52½ fluid ounces (1½ to 2 litres).

*Abnormal Constituents.*—In disease, or after the ingestion of special foods, various abnormal substances occur in urine, of which the following may be mentioned—*Serum-albumin*, *Globulin*, *Ferments* (apparently present in health also), *Proteoses*, *Blood*, *Sugar*, *Bile acids and pigments*, *Casts*, *Fats*, *various Salts* taken as a medicine, *Micro-organisms* of various kinds, and other matters.

## The Solids of the Urine.

**Urea** ($CH_4N_2O$).—Urea is the principal solid constituent of the urine, forming nearly one-half of the total quantity. It is also the most important ingredient, since it is the chief substance by which the nitrogen which is derived from the metabolic changes in the tissues as well as that which is derived from any superfluous food is excreted the body. For its removal, the secretion of urine seems especially ided, though urea itself is not toxic.

'roperties.—Urea, like the other solid constituents of the urine, s in a state of solution. When in the solid state, it appears in the



Fig. 302.—Crystals of Urea.

ı of delicate silvery acicular crystals, which, under the microscope, ıar as four-sided prisms (fig. 302). It may be obtained in this state vaporating urine carefully to the consistence of honey, acting on inspissated mass with four parts of alcohol, then evaporating the holic solution to dryness, and purifying the residue by repeated tion in water or in alcohol, and finally allowing it to crystallize. It ily combines with some acids, like a weak base: and may thus be 'eniently procured in the form of crystals of *nitrate or oxalate of* (figs. 303 and 304).

Jrea is colorless when pure; when impure it may be yellow or



Fig. 303.—Crystals of Urea nitrate.



Fig. 304.—Crystals of Urea oxalate.

n: it is without smell, and of a cooling nitre-like taste; it has er an acid nor an alkaline reaction, and deliquesces in a moist and atmosphere. At 15° C. (59° F.) it requires for its solution less its own weight of water; it is dissolved in all proportions by boilater; but it requires five times its weight of cold alcohol for its on. It is insoluble in ether. At 120° C. (248° F.) it melts without undergoing decomposition; at a still higher temperature ebullition takes place, and carbonate of ammonium sublimes. When heated with water in a sealed tube to 100° C., urea splits up into carbonic acid and ammonia; when heated to a high temperature urea loses ammonia and first yields *biuret*, $C_2H_5N_3O_2$, which gives a rose color with caustic potash and a trace of copper sulphate, and afterward *cyanuric acid*, $C_3H_3O_3N_3$, which gives a violet color with caustic potash and a trace of copper sulphate. It is decomposed by sodium hypochlorite or hypobromite or by nitrous acid, with evolution of N. It forms compounds with acids, of which the chief are urea hydrochloride, $CH_4N_2O.HCL$; urea nitrate, $CH_4N_2OHNO_3$; and urea phosphate, $CH_4N_2O.H_3PO_4$. It forms compounds with metals such as $HgO.CH_4N_2O$; with silver $CH_2N_2OAg_2$; and with salts such as $HgCl_2$ and $HgNO_3$.

*Chemical Nature.*—Urea is isomeric with ammonium cyanate $NH_4,CNO$. It was first of all artificially prepared from that substance.

*It may also be produced artificially by treating carbonyl chloride* ($CO\,Cl_2$) with *ammonia; or by heating ethyl carbonate with ammonia* $CO\begin{matrix}OC_2H_5\\OC_2H_5\end{matrix}+2\,NH_3=CON_2H_4\ 2C_2H_6O$; *by heating ammonium carbonate* $CO\begin{matrix}NH_2\\ONH_4\end{matrix}=CON_2H_4+H_2O$; *by adding water to cyanamide* $CN.NH_2$, *or by evaporating ammonium cyanate in aqueous solution.*

It is usually considered to be a diamide of carbonic acid, in other words, carbonic acid, $CO\,(OH)'_2$, with two of hydroxyl, $(OH)'_2$, replaced by two of amidogen $(NH_2)'_2$. It may also be written as if it were a monamide of carbamic acid ($COOHNH_2$), thus $CONH_2.NH_2$; one of amidogen, $NH_2$, in the latter replacing one of hydroxyl in the former. Decomposition of the urea with development of ammonium carbonate takes place from the action of the bacteria (micrococcus ureæ), when urine is kept for some days after being voided, and explains the ammoniacal odor then evolved. The urea is sometimes decomposed before it leaves the bladder, when the mucous membrane is diseased, and the mucus secreted by it is abundant; but decomposition does not often occur unless atmospheric germs have had access to the urine.

*Variations in the Quantity excreted.*—The quantity of urea excreted is, like that of the urine itself, subject to considerable variation. For a healthy adult about 512.4 grains (about 33.18 grms.) per diem may be taken as rather a high average. Its percentage in healthy urine is from 1.5 to 2.5. Its amount is materially influenced by diet, being greater when animal food is exclusively used, less when the diet is mixed, and least of all with a vegetable diet. As a rule, men excrete a larger quantity than women, and persons in the middle periods of life a la quantity than infants or old people. The quantity of urea excreted ldren, relatively to their body-weight, is much greater than by adults; us the quantity of urea excreted per kilogram of weight was found to in a child, 0.8 grm.; in an adult only 0.4 grm. Regarded in this y, too, the excretion of carbonic acid gives similar results, the prortions in the child and adult being as 82 : 34.

The quantity of urea does not necessarily increase and decrease with t of the urine, though on the whole it would seem that whenever the ount of urine is much augmented, the quantity of urea also is usually reased; and it appears that the quantity of urea, as of urine, may be ecially increased by drinking large quantities of water. In various eases the quantity is reduced considerably below the healthy stanrd, while in other affections it is above it.

*Quantitative Estimation.*—There are two chief methods of estimating the ount of urea in the urine. (1.) By decomposing it by means of an alkaline ation of sodium hypobromite, or hypochlorite, and calculating the amount a measured quantity, by collecting and measuring the amount of nitrogen lved under such circumstances. Urea contains nearly half its weight of rogen, hence the amount of the gas collected may be taken as a measure of urea decomposed, remembering that 1 litre of nitrogen at the standard perature and pressure weighs 14 × .08936, or 1.251 grms. The percentage urea can thus be readily calculated from the volume of nitrogen evolved m a measured quantity of the urine, but this calculation is avoided by duating the tube in which the nitrogen is collected with numbers which icate the corresponding percentage of urea. The reaction is $CON_2H_4 + aBrO + 2NaHO = 3NaBr + 3H_2O + Na_2CO_3 + N_2$. (2.) By precipitating the a by adding to a given amount of urine, freed from sulphates and phostes, a standard solution of mercuric nitrate from a burette, until the whole it has been thrown down in an insoluble form; then reading off the exact ount of the mercuric nitrate solution, which it was necessary to use. As amount of urea which each cubic centimetre of the standard solution will cipitate is previously known, it is easy to calculate the amount in the samof urine taken. The precipitate which is formed was generally said to be nposed of mercuric oxide and urea. Some, however, now consider that it mixture of mercuric nitrate itself and urea.

**Uric Acid** ($C_5H_4N_4O_3$).—Uric or lithic acid is rarely absent from urine of man or animals, though in the feline tribe it seems to be netimes entirely replaced by urea.

*Properties.*—Uric acid when pure is colorless, but when deposited n the urine is yellowish-brown. It crystallizes in various forms, of ch the most common are smooth transparent, rhomboid plates, nond-shaped plates, hexagonal tables, etc. (fig. 305). It is odorless tasteless. It is very slightly soluble in cold water, and a little more n hot water, quite insoluble in alcohol and ether. It dissolves freely olution of the alkaline carbonates and other salts.

The proportionate quantity of uric acid varies considerably in different animals. In man, and Mammalia generally, especially the Herbivora, it is comparatively small. In the whole tribe of birds, and of serpents, on the other hand, the quantity is very large, greatly exceeding that of the urea. In the urine of granivorous birds, indeed, urea is rarely if ever found, its place being entirely supplied by uric acid.

*Variations in Quantity.*—The quantity of uric acid, like that of urea, in human urine, is increased by the use of animal food, and decreased by the use of food free from nitrogen, or by an exclusively vegetable diet. In most febrile diseases, and in plethora, it is formed in unnaturally large quantities; and in gout it is deposited in and around joints, in the form of urate of soda, of which the so-called chalk-stones of this disease are principally composed. The average amount secreted in twenty-four hours is about one-third of a gramme.

*Condition in the Urine.*—The condition in which uric acid exists in solution in the urine has formed the subject of some discussion. The uric acid exists as urate of soda, produced by the uric acid as soon as it is formed combining with part of the base of the alkaline sodium phosphate of the blood. Hippuric acid, which exists in human urine also, acts upon the alkaline phosphate in the same way, and increases still more the quantity of acid phosphate, on the presence of which it is probable that a part of the natural acidity of the urine depends. It is scarcely possible to say whether the union of uric acid with the bases sodium and ammonium takes place in the blood, or in the act of secretion in the kidney: the latter is more likely; but the quantity of either uric acid or urates in the blood is probably too small to allow of this question being solved.

Owing to its existence in combination in healthy urine, uric acid for examination must generally be precipitated from its bases by a stronger acid, *e.g.*, hydrochloric or nitric. When excreted in excess, however, it is deposited in a crystalline form (fig. 305), mixed with large quantities of ammonium or sodium urate. In such cases it may be procured for microscopic examination by gently warming the portion of urine containing the sediment; this dissolves urate of ammonium and sodium, while the comparatively insoluble crystals of uric acid subside to the bottom.

The most common form in which uric acid is deposited in urine, is that of a brownish or yellowish powdery substance, consisting of granules of ammonium or sodium urate. When deposited in crystals, it is most frequently in rhombic or diamond-shaped laminæ, but other forms are not uncommon (fig. 305). When deposited from urine, the crystals are generally more or less deeply colored, from being combined with the coloring principles of the urine.

*Tests.*—There are two chief tests for uric acid besides the microevidence of its crystalline structure: (1) *The Murexide test,* consists of evaporating to dryness a mixture of strong nitric acid ic acid in a water bath. This leaves a yellowish-red residue of *n* ($C_4H_2N_2O_4$) and urea, and on addition of ammonium hydrate, a ful purple color (ammonium purpurate, $C_8H_4(NH_4)N_5O_6$), deep-n addition of caustic potash, takes place. (2) *Schiff's test* con- dissolving the uric acid in sodium carbonate solution, and of ng some of it on a filter paper moistened with silver nitrate. A spot appears, which corresponds to the reduction of silver by the id.

**ppuric Acid** ($C_9H_9NO_3$) has long been known to exist in the f herbivorous animals in combination with soda. It also exists



—Various forms of uric acid crystals.



Fig. 306.—Crystals of hippuric acid.

lly in the urine of man, in a quantity equal or rather exceeding the uric acid.

quantity of hippuric acid excreted is increased by a vegetable It appears to be formed in the body from benzoic acid or from llied substance. The benzoic acid unites with glycin, probably kidneys, and hippuric acid and water are formed thus, $C_7H_6O_2$ ic acid) + $C_2H_5NO_2$ (Glycin) = $C_9H_9NO_3$ (Hippuric acid) + $H_2O$ ). It may be decomposed by acids into benzoic acid and glycin.

*perties.*—It is a colorless and odorless substance of bitter taste, lizes in semi-transparent rhombic prisms (fig. 306). It is more in cold water than uric acid, and much more soluble in hot It is soluble in alcohol.

**ments.**—The pigments of the urine are the following:—1. *Uro-* a yellow coloring matter, giving no absorption band; of which le is known. Urine owes its yellow color mainly to the pres- this body. 2. *Urobilin,* an orange pigment, of which traces may d in nearly all urines, and which is especially abundant in the passed by febrile patients. It is characterized by a well-marked scopic absorption band at the junction of green and blue, best seen in acid solutions; and by giving a green fluorescence when excess of ammonia with a little chloride of zinc is added to it. The very vexed question of the relation of the pigments of urine to bile pigments turns largely upon the spectroscopic appearances of urobilin; for orange-colored solutions having the same absorption band as urobilin may be prepared from bile pigments in two different ways—i, by reduction with sodium amalgam—*Hydrobilirubin* (Maly); ii, by oxidation with nitric acid—*Choletelin* (Jaffé), and both these bile derivatives give a fluorescence with ammonia and a drop of chloride of zinc. It is not satisfactorily settled which of these, if either, is the same as urobilin of urine. It is worth noting that choletelin may be oxidized a stage further; it then loses its absorption band, remaining however of a yellow color. It is very possible that the urochrome of normal urine may be this oxidized choletelin, and that the presence of the absorption band of urobilin in urines may mean that some of the pigment is in the stage of choletelin; *i.e.*, that its oxidation is not quite completed.

Those who believe urobilin to be identical with hydrobilirubin suppose that the bilirubin is reduced by the putrefactive processes in the intestines, and is conveyed in its reduced form by the blood stream to the kidneys.

3. *Uro-erythrin* is the pigment which is found in the pink deposits of urates which are sometimes seen in urines; it communicates a rich red-orange color to urine when in solution, and its solutions have two broad faint absorption bands in the green.

4. *Uromelanin.* When urine is boiled with strong acids it darkens to a reddish-brown color. This change, once ascribed to the formation of a new pigment uromelanin, is now believed to be due to the presence in urine of pyrocatechin and allied bodies which are capable of taking up oxygen when boiled with acids, yielding $CO_2$ and brown or black residual products.

5. *Indigo* is rarely found in urines, to which it may communicate a blue or green color. Urine frequently contains a compound which is either a glucoside, *Indican;* or more probably a salt of indoxyl-sulphuric acid. It yields indigo blue when treated with strong hydrochloric acid and left to stand for some hours exposed to the air; the indigo may be separated by treatment with boiling chloroform, which takes it up, forming a blue solution.

There is a similar compound of skatol and sulphuric acid which is sometimes recognized in the urine, by the production of a red color when nitric acid is added to it.

Many medicinal substances color the urine, for instance Rhubarb, Santonin, Senna, Fuchsine, Carbolic Acid.

Bromides and Iodides yield Bromine or Iodine, when nitric acid is added to the urine of patients taking these drugs. In the case of iodides ie liberated iodine communicates a strong mahogany color to the urine ıus treated.

**Mucus.**—*Mucus* in the urine consists principally of the epithelial bris from the mucous surface of the urinary passages. Particles of ithelium, in greater or less abundance, may be detected in most sam- s of urine, especially if it has remained at rest for some time, and the ver strata are then examined (fig. 307). As urine cools, the mucus is netimes seen suspended in it as a delicate opaque cloud, but generally falls. In inflammatory affections of the urinary passages, especially the bladder, mucus in large quantities is poured forth, and speedily lergoes decomposition. The presence of the decomposing mucus ites chemical changes in the urea, whereby carbonate of ammonium ormed, which, combining with the excess of acid in the superphos- ates in the urine, produces insoluble neutral or alkaline phosphates calcium and magnesium, and phosphate of ammonium and magne- m. These, mixing with the mucus, constitute the peculiar white, cid, mortar-like substance which collects upon the mucous surface of bladder, and is often passed with the urine, forming a thick tena- us sediment.

**Extractives.**—In addition to those already considered, urine con- ns a considerable number of nitrogenous compounds. These are ially described under the generic name of *Extractives*. Of these, the ief are: (1) *Kreatinin* ($C_4H_7N_3O$), a substance derived almost en- ely from muscle taken as food, crystallizing in colorless oblique mbic prisms; a fairly definite amount of this substance, about 15 ins (1 grm.), appears in the urine daily, so that it must be looked on as a normal constituent; it is increased by increasing the ni- genous constituents of the food; (2) *Xanthin* ($C_5N_4H_4O_2$), when lated, is an amorphous powder soluble in hot water; (3) *Sarkin*, or o-*xanthin* ($C_5N_4H_4O$); (4) *Oxaluric acid* ($C_3H_4N_2O_4$), in combi- ion with ammonium in the urine of the new-born child; (5) *Allantoin* $H_6N_4O_3$). All these extractives are chiefly interesting as being closely nected with urea, and mostly yielding that substance on oxidation. ıcin and tyrosin can scarcely be looked upon as normal constituents ırine.

**Saline Matter.**—(*a*) The *Sulphuric acid* in the urine is combined fly or entirely with sodium or potassium; forming salts which are n in very small quantity with the food, and are scarcely found in r fluids or tissues of the body; for the sulphates commonly enumer- among the constituents of the ashes of the tissues and fluids are he most part, or entirely, produced by the changes that take place ıe burning. Only about one-third of the sulphuric acid found in ırine is derived directly from the food (Parkes). Hence the greater of the sulphuric acid which the sulphates in the urine contain, must be formed during the metabolism of nitrogenous foods; the sulphur of which the acid is formed being probably derived from the decomposing nitrogenous tissues, the other elements of which are resolved into urea and uric acid. It may be in part derived also from the sulphur-holding *taurin* and *cystin,* which can be found in the liver, lungs, and other parts of the body, but not generally in the excretions; and which, therefore, must be broken up. The oxygen is supplied through the lungs, and the heat generated during combination with the sulphur is one of the subordinate means by which the animal temperature is maintained.

Besides the sulphur in these salts, some also appears to be in the urine uncombined with oxygen; for after all the sulphates have been removed from urine, sulphuric acid may be formed by drying and burning it with nitre. From three to five grains of sulphur are thus daily excreted. The combination in which it exists is uncertain: possibly it is in some compound analogous to cystin or cystic oxide. Sulphuric acid also exists normally in the urine in combination with phenol ($C_6H_6O$) as phenol-sulphuric acid or its corresponding salts, with sodium, etc.



Fig. 307.



Fig. 308.

Fig. 307.—Mucus deposited from urine.

Fig. 308.—Urinary sediment of triple phosphates (large prismatic crystals) and urate of ammonium, from urine which had undergone alkaline fermentation.

(*b*) The *phosphoric acid* in the urine is combined partly with the alkalies, partly with the alkaline earths—about four or five times as much with the former as with the latter. In blood, saliva, and other alkaline fluids of the body, phosphatês exist in the form of alkaline, neutral, or acid salts. In the urine they are acid salts, viz., the sodium, ammonium, calcium, and magnesium phosphates, the excess of acid being (Liebig) due to the appropriation of the alkali with which the phosphoric acid in the blood is combined, by the several new acids which are formed or discharged at the kidneys, namely, the uric, hippuric, and sulphuric acids, all of which are neutralized with soda.

phates are taken largely in both vegetable and animal food;
ken are excreted at once; others, after being transformed
ated with the tissues. Calcium phosphate forms the prin-
constituent of bone, and from the decomposition of the
e the urine derives a large quantity of this salt. The de-
of other tissues also, but especially of the brain and nerve-
rnishes large supplies of phosphorus to the urine, which
s supposed, like the sulphur, to be united with oxygen, and
ed with bases. The quantity is, however, liable to consid-
ion. Any undue exercise of the brain and all circumstances
ervous exhaustion increase it. The earthy phosphates are
nt after meals, whether of animal or vegetable food, and
ed after long fasting. The alkaline phosphates are in-



9.—Crystals of Cystin.



Fig. 310.—Crystals of Calcium Oxalate.

animal food, diminished after vegetable food. Exercise
alkaline, but not the earthy phosphates. Phosphorus
with oxygen appears, like sulphur, to be excreted in the
n the urine undergoes alkaline fermentation phosphates are
the form of a *urinary sediment*, consisting chiefly of
gnesium phosphates (triple phosphate) (fig. 308). The
oes not, as such, exist in healthy urine. The ammonia is
olly derived from the decomposition of urea.

*Chlorine* of the urine occurs chiefly in combination with
; to urea, sodium chloride is the most abundant solid con-
he urine), but slightly also with ammonium, and, perhaps,
As the chlorides exist largely in food, and in most of the
, their occurrence in the urine is easily understood.

**al Constituents.**—*Cystin* ($C_3H_7NSO_2$) (fig. 309) is an
nstituent of urine. It resembles taurin in containing a
y of sulphur—more than 25 per cent. It does not exist in
.

common morbid constituent of the urine is *Oxalic acid*, which is frequently deposited in combination with calcium (fig. 310) as a urinary sediment. Like cystin, but much more commonly, it is the chief constituent of certain calculi.

Of the other abnormal constituents of the urine which were mentioned on p. 486, it will be unnecessary to speak at length in this work.

**Gases.**—A small quantity of gas is naturally present in the urine in a state of solution. It consists of carbonic acid (chiefly) and nitrogen and a small quantity of oxygen.

## The Method of the Excretion of Urine.

The excretion of the urine by the kidney is believed to consist of two more or less distinct processes—viz., (1) *of Filtration*, by which the water and the ready-formed salts are eliminated; and (2) *of Tru* *Secretion*, by which certain substances forming the chief and more important part of the urinary solids are removed from the blood. Thi division of function corresponds more or less to the division in th functions of other glands of which we have already treated. It will b as well to consider them separately.

**Filtration.**—This part of the renal function is performed withi the Malpighian corpuscles by the renal glomeruli. By it not only the wat is strained off, but also certain other constituents of the urine. *e.g.* sodium chloride, are separated. The amount of the fluid filtered off depends upon the blood-pressure in the glomeruli and the speed of blood flow.

The greater the blood-pressure in the arterial system generally, an consequently in the renal arteries, the greater, *cæteris paribus*, will b the blood-pressure in the glomeruli, and the greater the quantity urine separated; but even without increase of the general blood-pr ure, if the renal arteries be locally dilated, the speed of flow in glomeruli will be increased and with it the secretion of urine. All causes, therefore, which increase the general blood-pressure will seco arily increase the secretion of urine. Of these—

(1) The heart's action is among the most important. When cardiac contractions are increased in force or frequency, incre diuresis is the result.

(2) Since the connection between the general blood-pressure and nervous system is so close it will be evident that the amount of ur secreted depends greatly upon the influence of the latter. This may demonstrated experimentally. Thus, division of the spinal cord, producing general vascular dilatation, causes a great diminution of bl pressure, and so diminishes the amount of water passed; since the l dilatation in the renal arteries is not sufficient to counteract the gen diminution of pressure. Stimulation of the cut cord produces, stran

h, the same results—*i.e.*, a diminution in the amount of the urine
l, but in a different way, viz., by constricting the arteries generally,
mong others, the renal arteries; the diminution of blood-pressure
ing from the local resistance in the renal arteries being more
to diminish blood-pressure in the glomeruli than the general
se of blood-pressure is to increase it. Section of the renal nerves
produces *local* dilatation without greatly diminishing the general
pressure will cause an increase in the quantity of fluid passed.

The fact that in summer or in hot weather the urine is dimin-
may be attributed partly to the copious elimination of water by
in in the form of sweat which occurs in summer, as contrasted
he greatly diminished functional activity of the skin in winter.



311.—Diagram of Roy's Oncometer. *a*, represents the kidney inclosed in a metal box,
ens by hinge *f*; *b*, the renal vessels and duct. Surrounding the kidney are two chambers
y membranes, the edges of which are firmly fixed by being clamped between the outside
psule, and one (not represented in the figure) inside, the two being firmly screwed together
s at *h*, and below. The membranous chamber below is filled with a varying amount of
, according to the size of the kidney experimented with, through the opening then closed
plug *i*. After the kidney has been inclosed in the capsule, the membranous chamber above
vith warm oil through the tube *e*, which is then closed by a tap (not represented in the
); the tube *d* communicates with a recording apparatus, and any alteration in the volume
dney is communicated by the oil in the tube to the chamber *d* of the Oncograph, fig. 312.

we see that in regard to the elimination of water from the system,
in and kidneys perform similar functions, and are capable to some
of acting vicariously, one for the other. Their relative activities
ersely proportional to each other.

intimate connection which exists between the volume of the kidney
variations of blood-pressure is exceedingly well shown with the
**ter**, introduced by Roy, which is a modification of the plethysmo-
fig. 311. By means of this apparatus any alteration in the volume of
ney is communicated to an apparatus [**oncograph**], capable of recording
ally, with a writing lever, such variations.

It has been found that the kidney is extremely sensitive to an alteration in the general blood-pressure, every fall in the general blood-pressure being accompanied by a decrease in the volume of the kidney, and every rise, unless produced by considerable constriction of the peripheral vessels, including those of the kidney, being accompanied by a corresponding increase of volume. Increase of volume is followed by an increase in the amount of urine secreted, and decrease of volume by a decrease in the secretion. In addition, however, to the response of the kidney to alterations in the general blood-pressure, it has been further observed that certain substances, when injected into the blood, will also produce an increase in volume of the kidney, and consequent increased flow of urine, without affecting the general blood-pressure—such bodies as sodium acetate and other diuretics. These observations appear to prove that local dilatation of the renal vessels may be produced by alterations in the blood acting upon a local nervous mechanism, as this happens when all of the renal nerves have been divided. The alterations are not only produced by the addition of drugs, but also by the introduction of comparatively small quantities of water or saline solution. To this alteration of the blood acting upon the renal vessels (either directly or) through a local vaso-motor mechanism, and not to any great alteration in the general blood-pressure, must we attribute the effects of meals, etc., observed by Roberts. The renal excretion is increased after meals and diminished during fasting and sleep. The increase begins within the first hour after breakfast, and continues during the succe ing two or three hours; then a diminution sets in, and continues un an hour or two after dinner. The effect of dinner does not appear un



Fig. 312.—Roy's Oncograph, or apparatus for recording alterations in the volume of the kidney, etc., as shown by the oncometer—*a*, upright, supporting recording lever *l*, which is raised or lowered by needle *b*, which works through *f*, and which is attached to the piston *e*, working in the chamber *d*, with which the tube from the oncometer communicates. The oil is prevented from being squeezed out as the piston descends by a membrane, which is clamped between the ring-shaped surfaces of cylinder by the screw *i* working upward; the tube *h* is for filling the instrument.

three hours after the meal; and it reaches its maximum about ourth hour. From this period the excretion steadily decreases bed-time. During sleep it sinks still lower, and reaches its mini- —being not more than one-third of the quantity excreted during hours of digestion. The increased amount of urine passed after king large quantities of fluid depends upon the temporary increase ood-pressure thus caused.

he following table* will help to explain the dependence of the tion function upon the blood-pressure and the nervous system:—

LE OF THE RELATION OF THE SECRETION OF URINE TO ARTERIAL PRESSURE.

**Secretion of urine may be increased—**

*a. By increasing the general blood-pressure;* by
  1. Increase of the force or frequency of heart-beat.
  2. Constriction of the small arteries of areas other than that of the kidney.

*b. By increasing the local blood-pressure,* by *relaxation of the renal artery, without compensating relaxation elsewhere;* by
  1. Division of the renal nerves (causing polyuria).
  2. Division of the renal nerves and stimulation of the cord, below the medulla (causing greater polyuria).
  3. Division of the splanchnic nerves; but the polyuria produced is less than in 1 or 2, as these nerves are distributed to a wider area, and the dilatation of the renal artery is accompanied by dilatation of other vessels, and therefore with a somewhat diminished general blood supply.
  4. Puncture of the floor of fourth ventricle or mechanical irritation of the superior cervical ganglion of the sympathetic, possibly from the production of dilatation of the renal arteries.

**Secretion of urine may be diminished—**

*By diminishing the general blood-pressure;* by
  1. Diminution of the force or frequency of the heart-beats.
  2. Dilatation of capillary areas other than that of the kidney.
  3. Division of spinal cord below the medulla, which causes dilatation of general abdominal area, and urine generally ceases being secreted.

*By increasing the blood-pressure,* by stimulation of the spinal cord below the medulla, the constriction of the renal artery, which follows, not being compensated for by the increase of general blood-pressure.

*By constriction of the renal artery,* by stimulating the renal or splanchnic nerves, or the spinal cord.

ough the quantity of urine secreted corresponds closely with the lood-pressure, it must be stated that it is more directly dependent quantity of blood flowing through the kidney in a given unit of Under normal conditions increased blood-pressure and increased flow go hand in hand. But the local pressure may be enormously increased by clamping the renal vein, in which circumstance the secretion of urine is suspended.

---

* Modified from Foster.

Although it is convenient to call the processes which go on in the renal glomeruli, filtration, there is reason to believe that they are not absolutely mechanical, as the term might seem to imply, since, when the **epithelium of the Malpighian capsule has been,** as it were, put out of order by ligature of the renal artery, on removal of the ligature, the urine has been found temporarily to contain albumen, indicating that a selective power resides in the healthy epithelium, which allows certain constituent parts of the blood to be filtered off, and not others.

**Secretion.**—That there is a second part in the process of the excretion of urine, which is true secretion, is suggested by the structure of the tubuli uriniferi, and the idea is supported by various experiments. It will be remembered that the convoluted portions of the tubules are lined with an epithelium, which bears a close resemblance to the secretory epithelium of other glands, whereas the Malpighian capsules and portions of the loops of Henle are lined simply by flattened epithelium. The two functions of the different parts of an uriniferous tube are, then, suggested by the differences of epithelium, and also by the fact that the blood supply to the different parts is different, since, as we have seen, the convoluted tubes are surrounded by capillary vessels derived from the breaking up of the efferent vessels of the Malpighian tufts. As to the functions of the different parts of the uriniferous tubes in the secretion of urine, two chief theories have been brought forward. The first, suggested by Bowman (1842), and still generally accepted, is that the cells of the convoluted tubes, by a process of true secretion, separate from the blood substances such as urea, whereas from the glomeruli are separated the water and the inorganic salts. The second, suggested by Ludwig (1844), is that in the glomeruli are filtered off from the blood all the constituents of the urine in a very diluted condition. When this passes along the tortuous uriniferous tube, part of the w
is re-absorbed into the vessels surrounding them, leaving the urin
a more concentrated condition—retaining all its proper constitu
This osmosis is promoted by the high specific gravity of the bloo



Fig. 313.—Curve taken by renal oncometer compressed—with that of ordinary blood-pressure. a, Kidney curve; b, blood-pressure curve. (Roy.)

e capillaries surrounding the convoluted tubes, but the return of the ea and similar substances is prevented by the secretory epithelium of e tubules. The first theory is, however, more strongly supported by rect experiment.

By using the kidney of the newt, which has two distinct vascular plies, one from the renal artery to the glomeruli, and the other from renal-portal vein to the convoluted tubes, Nussbaum has shown that tain substances, *e.g.*, peptones and sugar, when injected into the od, are eliminated by the glomeruli, and so are not got rid of when renal arteries are tied; whereas certain other substances, *e.g.*, urea, en injected into the blood, are eliminated by the convoluted tubes, n when the renal arteries have been tied. This evidence is very ect that urea is excreted by the convoluted tubes, that is to say, if it ertain that ligature of the renal artery assists the circulation through glomeruli, which, however, is denied by Adami.

Heidenhain also has shown by experiment that if a substance (sodium ph-indigotate), which ordinarily produces blue urine, be injected o the blood after section of the medulla which causes lowering of the od-pressure in the renal glomeruli, that when the kidney is examined, e cells of the convoluted tubules (and of these alone) are stained with e substance, which is also found in the lumen of the tubules. This pears to show that under ordinary circumstances the pigment at any e is eliminated by the cells of the convoluted tubules, and that when diminishing the blood-pressure, the filtration of urine ceases, the ment remains in the convoluted tubes, and is not, as it is under linary circumstances, swept away from them by the flushing of them ich ordinarily takes place with the watery part of urine derived from glomeruli. It therefore is probable that the cells, if they excrete pigment, excrete urea and other substances also. But urea acts newhat differently to the pigment, as when it is injected into the od of an animal in which the medulla has been divided, and the retion of urine stopped, a copious secretion of urine results, which ot the case when the pigment is used instead under similar condi- ns. The flow of urine, independent of the general blood-pressure, ght be supposed to be due to the action of the altered blood upon ne local vaso-motor mechanism; and, indeed, the local blood-pressure directly affected in this way, but there is reason for believing that t of the increase of the secretion is due to the direct stimulation of cells by the urea contained in the blood.

To sum up, then, the relation of the two functions: (1.) The process filtration, by which the chief part, if not the whole, of the fluid is ninated, together with certain inorganic salts and possibly other ids, is indirectly dependent upon blood-pressure and speed of flow, is omplished by the renal glomeruli, and is accompanied by a free dis- rge of solids from the tubules. (2.) The process of secretion proper, by which urea and the principal urinary solids are eliminated, is accomplished by the cells of the convoluted tubes, and is sometimes (as in the case of the elimination of urea and similar substances) accompanied by the elimination of copious fluid, produced by the chemical stimulation of the epithelium of the same tubules.

## The Passage of Urine into the Bladder.

As each portion of urine is secreted it propels that which is already in the uriniferous tubes onward into the pelvis of the kidney. Thence through the ureter the urine passes into the bladder, into which its rate and mode of entrance has been watched in cases of *ectopia vesicæ*, *i.e.*, of such fissures in the anterior or lower part of the walls of the abdomen, and of the front wall of the bladder, as expose to view its hinder wall together with the orifices of the ureters. The urine does not enter the bladder at any regular rate, nor is there a synchronism in its movement through the two ureters. During fasting, two or three drops enter the bladder every minute, each drop as it enters first raising up the little papilla on which, in these cases, the ureter opens, and then passing slowly through its orifice, which at once again closes like a sphincter. In the recumbent posture, the urine collects for a little time in the ureters, then flows gently, and, if the body be raised, runs from them in a stream till they are empty. Its flow is aided by the peristaltic contractions of the ureters, and is increased in deep inspiration, or by straining, and in active exercise, and in fifteen or twenty minutes after a meal. The urine collecting is prevented from regurgitation into the ureters by the mode in which these pass through the walls of the bladder, namely, by their lying for between half and three-quarters of an inch between the muscular and mucous coats before they turn rather abruptly forward, and open through the latter into the interior of the bladder.

**Micturition.**—The contraction of the muscular walls of the bladder may by itself expel the urine with little or no help from other muscles. In so far, however, as it is a *voluntary* act, it is performed by means of the abdominal and other expiratory muscles, which in their contraction, as before explained, press on the abdominal viscera, the diaphragm being fixed, and cause the expulsion of the contents of those whose sphincter muscles are at the same time relaxed. The muscular coat of the bladder co-operates, in micturition, by reflex *involuntary* action, with the abdominal muscles; and the act is completed by the *accelerator urinæ*, which, as its name implies, quickens the stream, and expels the last drop of urine from the urethra. The act, so far as it is not directed by volition, is under the control of a nervous *centre* in the lumbar spinal cord, through which, as in the case of the similar centre for defæcation, the various muscles concerned are harmonized in their action. It is well known that the act may be reflexly induced, *e.g.*, in children who ffer from intestinal worms, or other such irritation. Generally the erent impulse which calls into action the desire to micturate is excited over-distention of the bladder, or even by a few drops of urine ssing into the urethra. This passes up to the lumbar centre (or cen-s) and produces on the one hand inhibition of the sphincter and on other hand contraction of the necessary muscles for the expulsion of contents of the bladder.

## The Structure and Functions of the Skin.

The skin serves—(1), as an external integument for the protection the deeper tissues, and (2), as a sensitive organ in the exercise of ich, a subject to be considered in the Chapter on the Special Senses; is also (3), an important secretory and excretory, and (4), an absorb- organ, already noticed, p. 439; while it plays an important part in the regulation of the temperature of the body. (See the Chapter on imal Heat.)

*Structure.*—The skin consists principally of a vascular tissue named *corium, derma,* or *cutis vera,* and of an external covering of epithe-m termed the *epidermis* or *cuticle.* Within and beneath the corium imbedded several organs with special functions, namely, *sudoriferous* nds, *sebaceous* glands, and *hair follicles;* and on its surface are sensi-e *papillæ.* The so-called appendages of the skin—the *hair* and *nails* re modifications of the epidermis.

**Epidermis.**—The epidermis is composed of several strata of cells of rious shapes and sizes; it closely resembles in its structure the epithe-m of the mucous membrane that lines the mouth. The following r layers may be distinguished in a more or less developed form: 1. *atum corneum* (fig. 314, *a*), consisting of superposed layers of horny les. The different thickness of the epidermis in different regions of body is chiefly due to variations in the thickness of this layer; *e.g.,* the horny parts of the palms of the hands and soles of the feet it is great thickness. The stratum corneum of the buccal epithelium iefly differs from that of the epidermis in the fact that nuclei are to distinguished in some of the cells even of its most superficial layers.

2. *Stratum lucidum,* a bright homogeneous membrane consisting of amous cells closely arranged, in some of which a nucleus can be seen.

3. *Stratum granulosum,* consisting of one layer of flattened cells ich appear fusiform in vertical section: they are distinctly nucleated, a number of granules extend from the nucleus to the margins of cell.

4. *Stratum Malpighii* or *Rete mucosum* consists of many strata. deepest cells, placed immediately above the cutis vera, are columnar h oval nuclei: this layer of columnar cells is succeeded by a number ayers of more or less polyhedral cells with spherical nuclei; the cells

of the more superficial layers are considerably flattened. The deeper surface of the rete mucosum is accurately adapted to the papillæ of the true skin, being, as it were, moulded on them. It is very constant in thickness in all parts of the skin. The cells of the middle layers of the stratum Malpighii are almost all connected by processes, and thus form prickle cells (fig. 35). The pigment of the skin, the varying quantity of which causes the various tints observed in different individuals and different races, is contained in the deeper cells of rete mucosum; the pigmented cells as they approach the free surface gradually losing their color. Epidermis maintains its thickness in spite of the constant wear and tear to which it is subjected. The columnar cells of the deepest layer of the rete mucosum elongate, and their nuclei divide into two (fig. 314, *e*). Lastly the upper part of the cell divides from the lower; thus from a long columnar cell are produced a polyhedral cell and a short columnar cell: the latter elongates and the process is repeated. The polyhedral cells thus formed are pushed up toward the free surface by the production of fresh ones beneath them, and become flattened from pressure: they also become gradually horny by evaporation and transformation of their protoplasm into keratin, till at last by rubbi in ordinary wear and tear they are detached as dry horny scales at t free surface. There is thus a constant production of fresh cells in t



Fig. 314.—Vertical section of the epidermis of the prepuce. *a*, stratum corneum, of very few layers, the stratum lucidum and stratum granulosum not being distinctly represented; *b*, *c*, *d*, and *e*, the layers of the stratum Malpighii, a certain number of the cells in layers *d* and *e* showing signs of segmentation; layer *c* consists chiefly of prickle or ridge and furrow cells; *f*, basement membrane; *g*, cells in cutis vera. (Cadiat.)

eeper layers, and a constant throwing off of old ones from the free sur-
ace. When these two processes are accurately balanced, the epidermis
aintains its thickness. When, by intermittent pressure a more active
ell-growth is stimulated, the production of cells exceeds their waste and
e epidermis increases in thickness, as we see in the horny hands of the
borer.

The thickness of the epidermis on the different portions of the skin
directly proportioned to the friction, pressure, and other sources of
jury to which it is exposed; for it serves as well to protect the sensi-
ve and vascular cutis from injury from without, as to limit the evap-
ation of fluid from the blood-vessels. The adaptation of the epider-
is to the latter purposes may be well shown by exposing to the air two
ad hands or feet, of which one has its epidermis perfect, and the
her is deprived of it; in a day, the skin of the latter will become
own, dry and horn-like, while that of the former will almost retain its
tural moisture.

**Cutis vera.**—The corium or cutis vera, which rests upon a layer of
ipose and cellular tissue of varying thickness, is a dense and tough,
t yielding and highly elastic structure, composed of fasciculi of areolar
sue, interwoven in all directions, and forming, by their interlace-
nts, numerous spaces or areolæ. These areolæ are large in the deeper
ers of the cutis, and are there usually filled with little masses of fat
. 298): but, in the superficial parts, they are small or entirely oblit-
ted. Unstriped muscular fibres are also abundantly present.

**Papillæ.**—The cutis vera presents numerous conical papillæ, with a
gle or divided free extremity, which are more prominent and more
sely set at some parts than at others. This is especially the case on
palmar surface on the hands and fingers, and on the soles of the feet
arts, therefore, in which the sense of touch is most acute. On these
ts they are disposed in double rows, in parallel curved lines, separated
m each other by depressions. Thus they may be easily seen on the
m, whereon each raised line is composed of a double row of papillæ,
is intersected by short transverse lines or furrows corresponding
h the interspaces between the successive pairs of papillæ. Over
er parts of the skin they are more or less thinly scattered, and are
cely elevated above the surface. Their average length is about $\frac{1}{100}$
an inch ($\frac{1}{4}$ mm.), and at their base they measure about $\frac{1}{250}$ of an
in diameter. Each papilla is abundantly supplied with blood, re-
ing from the vascular plexus in the cutis one or more minute arte-
twigs, which divide into capillary loops in its substance, and then
ite into a minute vein, which passes out at its base. This abun-
pply of blood explains the turgescence or kind of erection which
ndergo when the circulation through the skin is active. The
ty, but not all, of the papillæ contain also one or more terminal

nerve-fibres, from the ultimate ramifications of the cutaneous ple on which their exquisite sensibility depends.

The *nerve-terminations* in the skin have been described under Sensory Nerve Terminations (p. 102 *et seq.*).

**Glands of the Skin.**—The skin possesses glands of two kinds: Sudoriferous, or Sweat Glands; (*b*) Sebaceous glands.

(*a*) *Sudoriferous, or Sweat Glands.*—Each of these glands consi of a small lobular mass, formed of a coil of tubular gland-duct,



Fig. 315.—Vertical section of skin. A. Sebaceous gland opening into hair follicle. B. M fibres. C. Sudoriferous or sweat-gland. D. Subcutaneous fat. E. Fundus of hair-follic hair-papillæ. (Klein.)

rounded by blood-vessels and embedded in the subcutaneous ad tissue (fig. 315, C). From this mass, the duct ascends, for a short tance in a spiral manner through the deeper part of the cutis, passing straight, and then sometimes again becoming spiral, it through the epidermis and opens by an oblique valve-like ape In the parts where the epidermis is thin, the ducts themselves thinner and more nearly straight in their course (fig. 315). The which maintains nearly the same diameter throughout, is lined w layer of columnar epithelium (fig. 315) continuous with the epidermis; while the part which passes through the epidermis is a mere passage through the epidermal cells not being bounded by any special lining; but the cells which immediately form the boundary of the canal in this part are somewhat differently arranged from those of the adjacent cuticle. The coils or terminal portions of the gland are lined with at least two layers of short columnar cells with very distinct nuclei (fig. 316), and possess a large lumen distinctly bounded by a special lining of cuticle.

The sudoriferous glands are abundantly distributed over the whole surface of the body; but are especially numerous, as well as very large, in the skin of the palm of the hand and of the sole of the foot. The glands by which the peculiar odorous matter of the axillæ is secreted



Fig. 316.—Terminal tubules of sudoriferous glands, cut in various directions from the skin of the pig's ear. (V. D. Harris.)

form a nearly complete layer under the cutis, and are like the ordinary sudoriferous glands, except in being larger and having very short ducts.

The peculiar bitter yellow substance secreted by the skin of the external auditory passage is named *cerumen*, and the glands themselves *ceruminous* glands; but they do not much differ in structure from the ordinary sudoriferous glands.

(*b*) *Sebaceous Glands.*—The sebaceous glands (figs. 315, 320), like sudoriferous glands, are abundant in most parts of the surface of the body, particularly in parts largely supplied with hair, as the scalp and face. They are thickly distributed about the entrances of the various passages into the body, as the anus, nose, lips, and external ear. They are entirely absent from the palmar surface of the hand and the plantar surfaces of the feet. They are racemose glands composed of an aggregate of small tubes or sacculi lined with columnar epithelium and with an opaque white substance, like soft ointment, which consists ken-up epithelial cells which have undergone fatty degeneration. e capillary vessels overspread them; and their ducts open on either the surface of the skin, close to a hair, or, which is more usual, directly into the follicle of the hair. In the latter case, there are generally two or more glands to each hair (fig. 316).

**Hair.**—A hair is produced by a peculiar growth and modification of the epidermis. Externally it is covered by a layer of fine scales closely imbricated, or overlapping like the tiles of a house, but with the free edges turned upward (fig. 318, A). It is called the *cuticle* of the hair. Beneath this is a much thicker layer of elongated horny cells, closely packed together so as to resemble a fibrous structure. This, very commonly, in the human subject, occupies the whole inside of the hair; but in some cases there is left a small central space filled by a substance called the *medulla* or *pith*, composed of small collections of irregularly shaped cells, containing sometimes pigment granules or fat, but mostly air.



Fig. 317.—Transverse section of a hair and hair-follicle made below the opening of the sebaceous gland. *a*, medulla or pith of the hair; *b*, fibrous layer or cortex; *c*, cuticle; *d*, Huxley's layer; *e*, Henle's layer of internal root-sheath; *f* and *g*, layers of external root-sheath, outside of *g* is a light layer, or "glassy membrane," which is equivalent to the basement membrane; *h*, fibrous coat of hair sac; *i*, vessels. (Cadiat.)

The follicle, in which the root of each hair is contained (fig. 319), forms a tubular depression from the surface of the skin,—descending into the subcutaneous fat, generally to a greater depth than the sudoriferous glands, and at its deepest part enlarging in a bulbous form, and often curving from its previous rectilinear course. It is lined throughout by cells of epithelium, continuous with those of the epidermi its walls are formed of pellucid membrane, which commonly i follicles of the largest hairs has the structure of vascular fibrous t ttom of the follicle is a small papilla, or projection of true it is by the production and outgrowth of epidermal cells from :e of this papilla that the hair is formed. The inner wall of .e is lined by epidermal cells continuous with those covering



face of a white hair, magnified 160 diameters. The wave lines mark the upper or free f the cortical scales. *B*, separated scales, magnified 350 diameters. (Kölliker.)

al surface of the skin; as if indeed the follicle had been formed le thrusting in of the surface of the integument (fig. 319). ermal lining of the hair-follicle, or *root-sheath* of the hair, is of two layers, the inner one of which is so moulded on the d scaly cuticle of the hair, that its inner surface becomes imlso, but of course in the opposite direction. The color of the e to the presence of a diffuse pigment in the cortical portion of When a hair is pulled out, the inner layer of the root-sheath of the outer layer also are commonly pulled out with it.

.—A nail, like a hair, is a peculiar arrangement of epidermal undermost of which, like those of the general surface of the at, are rounded or elongated, while the superficial are flat-



-Longitudinal section of a hair follicle. *a*, Stratum of Malpighi, deep layer forming root-sheath, and continued to the surface of the papilla to form the medullary sheath , second external sheath; *c*, internal root-sheath; *d*, fibroid sheath of the hair; *e*, eath or medulla; *f*, hair papilla; *g*, blood-vessels of the hair-papilla; *h*, fibro-vascular liat.)

tened, and of more horny consistence. That specially modified portion of the corium, or true skin, from which the nail is formed is called the *matrix*.

The back edge of the nail, or the *root* as it is termed, is received into a shallow crescentic groove in the *matrix*, while the front part is free and projects beyond the extremity of the digit. The intermediate portion of the nail rests by its broad under surface on the front part of the matrix, which is here called the *bed* of the nail. This part of the matrix is not uniformly smooth on the surface, but is raised in the form of longitudinal and nearly parallel ridges or laminæ, on which are moulded the epidermal cells of which the nail is made up.

The growth of the nail, like that of the hair, or of the epidermis generally, is effected by a constant production of cells from beneath and behind, to take the place of those which are worn or cut away. Inasmuch, however, as the posterior edge of the nail, from its being lodged in a groove of the skin, cannot grow backward, on additions being made to it, so easily as it can pass in the opposite direction, any growth at its hinder part pushes the whole forward. At the same time fresh cells are added to its under surface, and thus each portion of the nail becomes gradually thicker as it moves to the front, until, projecting beyond the surface of the matrix, it can receive no fresh addition from beneath, and is simply moved forward by the growth at its root, to be at last worn away or cut off.

## FUNCTIONS OF THE SKIN.

The function of the skin to be considered in this chapter is that of the excretion of the sweat. The fluid secreted by the sweat-glands is usually formed so gradually that the watery portion of it escapes by evaporation as fast as it reaches the surface. But during strong exercise, exposure to great external warmth, in some diseases, and when evaporation is prevented, the secretion becomes more sensible, and collects on the skin in the form of drops of fluid.

The *perspiration*, as the term is sometimes employed in physiology, includes all that portion of the secretions and exudations from the skin which passes off by evaporation; the *sweat* includes that which may be collected only in drops of fluid on the surface of the skin. The two terms are, however, most often used synonymously; and for distinction, the former is called *insensible* perspiration; the latter, *sensible* perspiration. The fluids are the same, except that the sweat is commonly mingled with various substances lying on the surface of the skin. The contents of the sweat are, in part, matters capable of assuming the form of vapor, such as carbonic acid and water, and in part, other matters which are deposited on the skin, and mixed with the sebaceous secretions.

The secretion of the sebaceous glands and hair-follicles consists of helium cells, with nuclei and granules, together with an oily ractive matter, and stearin; in certain parts, also, it is mixed liar odorous principle, which contains caproic, butyric, and It is, perhaps, nearly similar in composition to the unctu-, or *vernix caseosa*, which is formed on the body of the e in the uterus, and which contains large quantities of t. Its purpose seems to be that of keeping the skin moist and, by its oily nature, of both hindering the evaporation rface, and guarding the skin from the effects of the long-



lg. 320.—Sebaceous gland from human skin. (Klein and Noble Smith.)

ction of moisture. But while it thus serves local purposes, from the body entitles it to be reckoned among the excre- skin.

Chemical Composition of Sweat.

| | | |
|---|---|---|
| er . . . . . . . . . | | 995 |
| ls :— | | |
| Organic Acids (formic, acetic, butyric, propionic, caproic, caprylic) . . | .9 | |
| Salts, chiefly sodium chloride . . . . . | 1.8 | |
| Neutral fats and cholesterin . . . . | .7 | |
| Extractives (including urea), with epithelium | 1.6 | 5 |
| | | 1000 |

at is a colorless, slightly turbid fluid, alkaline, neutral or tion, of a saltish taste, and peculiar characteristic odor. everal substances it contains, however, only the *carbonic acid* eed particular consideration.

*Vapor.*—The quantity of watery vapor excreted from the skin is on an average between $1\frac{1}{2}$ and 2 lb. daily (about 1 kilo). This subject has been very carefully investigated by Lavoisier and Sequin. The latter chemist enclosed his body in an air-tight bag, with a mouthpiece. The bag being closed by a strong band above, and the mouthpiece adjusted and gummed to the skin around the mouth, he was weighed, and then remained quiet for several hours, after which time he was again weighed. The difference in the two weights indicated the amount of loss by pulmonary exhalation. Having taken off the air-tight dress, he was immediately weighed again, and a fourth time after a certain interval. The difference between the two weights last ascertained gave the amount of the cutaneous and pulmonary exhalation together; by subtracting from this the loss by pulmonary exhalation alone, while he was in the air-tight dress, he ascertained the amount of cutaneous transpiration. During a state of rest, the average loss by cutaneous and pulmonary exhalation in a minute, is eighteen grains,—the minimum eleven grains, the maximum thirty-two grains; and of the eighteen grains, eleven pass off by the skin, and seven by the lungs.

The quantity of watery vapor lost by transpiration is of course influenced by all external circumstances which affect the exhalation from other evaporating surfaces, such as the temperature, the hygrometri state, and the stillness of the atmosphere. But, of the variations to which it is subject under the influence of these conditions, no calculation has been exactly made.

*Carbonic Acid.*—The quantity of *carbonic acid* exhaled by the ski on an average is about $\frac{1}{150}$ to $\frac{1}{200}$ of that furnished by the pulmonar respiration.

The cutaneous exhalation is most abundant in the lower classes of animal more particularly the naked Amphibia, as frogs and toads, whose skin is thin a moist, and readily permits an interchange of gases between the blood circulati in it, and the surrounding atmosphere. Bischoff found that, after the lungs frogs had been tied and cut out, about a quarter of a cubic inch of carbon acid gas was exhaled by the skin in eight hours. And this quantity is ve large, when it is remembered that a full-sized frog will generate only abo half a cubic inch of carbonic acid by his lungs and skin together in six hou

The importance of the respiratory function of the skin, which was on thought to be proved by the speedy death of animals whose skins, after remov of the hair, were covered with an impermeable varnish, has been shown further observations to have no foundation in fact; the immediate cause death in such cases being the loss of temperature. A varnished animal is sa to have suffered no harm when surrounded by cotton wadding, and to have di when the wadding was removed.

### *Influence of the Nervous System.*

**The secretion of sweat is closely connected with the quantity of blo flowing through the cutaneous vessels. The quantity of sweat i creases with vaso-dilatation and diminishes with vaso-constriction.**

s practically certain that the sweat-glands are also under the control f efferent impulses passing to them from the special sweat centres n the brain and spinal cord through special sweat nerves. Thus, if he sciatic nerve be divided in a cat and the peripheral end be stimlated, beads of sweat are seen to appear upon the pad of the correspondng foot, although at the same time the blood-vessels are constricted or hile the aorta is pressed upon, whereas if atropin have been injected reviously to the stimulation, no sweat appears, although dilatation of he vessels be present. Secretion of sweat, too, may be reflexly brought bout.

The circulation of venous blood in the spinal bulb causes the sweating f phthisis and of dyspnœa generally, by stimulating the sweat centre. f the cat whose sciatic nerve is divided be rendered dyspnœic, abundant weat occurs upon the foot of the uninjured, and none on the injured ide. The effect of heat in producing sweating may be both local and general, and again, the various drugs which produce an increased secretion of sweat do not all act in the same way; thus, there is reason for thinking that *pilocarpin* acts upon the local apparatus, that *strychnia* and *picrotoxin* act upon the sweat centres, and that *nicotin* acts both upon the central and upon the local apparatus.

The special sweat-nerves appear to issue from the spinal cord, in the case of the hind limb of the cat by the last two or three dorsal and first two or four lumbar nerves, pass to the abdominal sympathetic and from thence to the sciatic nerve. In the case of the fore limb, the nerves leave the cord by the 5th and 6th cervical nerves into the thoracic sympathetic, and then join the brachial plexus, reaching the arm through the median and ulnar nerves.

It will be as well to repeat here the other functions which the skin ubserves. In addition to its *excretory* office, we have seen that it acts s a channel for *absorption*. It is also concerned with a special sense, iz., that of *touch*, to the consideration of which as well as to its funcion of *regulating the temperature* of the body we shall presently return. t should be recollected, however, that apart from these special funcions, by means of its toughness, flexibility and elasticity, the skin is minently qualified to serve as the general integument of the body, for efending the internal parts from external violence, while readily yieldng and adapting itself to their various movements and changes of osition.

# CHAPTER XIV.

## MUSCLE-NERVE PHYSIOLOGY.

### Chemical Composition of Muscle.

THE muscles make up about one-half of the total body weight. principal substance which can be extracted from muscle, when exam after death, is the proteid body, *Myosin*, some of the reactions of w have been already discussed, p. 116. This body appears to bear s what the same relation to the living muscle as fibrin does to the li blood, since the coagulation of muscle after death is due to the form of myosin. Thus, if coagulation be delayed in muscles removed i diately from recently killed animals, by subjecting them to a temper below 0° C., it is possible to obtain from them by expression a v fluid of slightly alkaline reaction, called *muscle-plasma* (Kühne, H burton). And muscle plasma, if exposed to the ordinary temperat the air (and more quickly at 37°–40° C.), undergoes coagulation in the same way as, under similar circumstances, does blood pl separated from the blood corpuscles by the action of a low temper The appearances presented by the fluid during the process are also similar to the phenomena of blood-clotting, viz., that first of all creased viscidity appears on the surface of the fluid, and at the si the containing vessel, which gradually extends throughout the mass, until a fine transparent clot is obtained. In the course of hours the clot begins to contract, and to squeeze out of its meshes corresponding to blood-serum. In the course of coagulation, ther muscle plasma separates into *muscle-clot* and *muscle-serum*. The m clot is the substance myosin. It differs from fibrin in being easily s in a 2 per cent solution of hydrochloric acid, and in a 10 per cent tion of sodium chloride. It is insoluble in distilled water, and its tions coagulate on application of heat. It is in short a *globulin*. D the process the reaction of the fluid becomes distinctly acid.

The coagulation of muscle plasma cannot only be prevented by but also, as Halliburton has shown, by the presence of neutral sa certain proportions; for example, of sodium chloride, of magn sulphate, or of sodium sulphate. It will be remembered that th also the case with blood plasma. Dilution of the salted muscle pl will produce its slow coagulation, which is prevented by the prese the neutral salts in strong solution.

It is highly probable that the formation of muscle-clot is due t sence of a ferment (*myosin-ferment*). The antecedent myosin in liv- muscle has received the name of *myosinogen*, in the same way as the in-forming element in the blood is called fibrinogen. Myosinogen however, made up of two globulins, which coagulate at the tempera- es 47° C. and 56° C. respectively. Myosin may also, as we have before ntioned, p. 116, be obtained from dead muscle by subjecting it, after the blood, fat, and fibrous tissue, and substances soluble in water have n removed, to a 10 per cent solution of sodium chloride, or 5 per t solution of magnesium sulphate, or 10 to 15 per cent solution of monium chloride, filtering and allowing the filtrate to drop into a ge quantity of water; the myosin separates out as a white flocculent ecipitate.

A very remarkable fact with regard to the properties of myosin has en demonstrated by Halliburton, namely, that a solution of dead uscle in strong neutral saline solution, possesses very much the same operties as muscle plasma, and that if diluted with twice or three nes its bulk of water, myosin will separate out *as a clot*, which clot can gain dissolved in a strong neutral saline solution, and the solution n be again made to clot on dilution. This process can often be re- ated; but in the fluid which exudes from the clot there is no proteid esent. Myosin when dissolved in neutral saline fluids is converted in- myosinogen, but reappears on dilution of the fluid. Muscle clot is most pure myosin; but it appears to be combined with a certain ount of salts, for if it be freed of salts, especially of those of calcium, prolonged dialysis, it loses its solubility. If a small amount of cal- m salts be added, however, it regains that property.

Muscle serum is acid in reaction, and almost colorless. It contains ee proteid bodies, viz.—(*a*) A *globulin* (*myoglobulin*), which can be pre- itated by saturation with sodium chloride, or magnesium sulphate, and ich can be coagulated at 63° C. (145° F.). (*b*) *Serum-albumin* (*myo- umin*), which coagulates at 73° C. (163° F.), but is not precipitated saturation with either of those salts. And (*c*) *Myo-albumose*, which neither precipitated by heat, nor by saturation with sodium chloride magnesium sulphate, but may be precipitated by saturation with am- nium sulphate. It is closely connected with, even if it is not itself, osin ferment. Neither casein nor peptone has been found by Halli- rton in muscle extracts. In extracts of muscles, especially of red scles, there is a certain amount of *Hæmoglobin*, and also of a pigment cial to muscle, called by McMunn *Myo-hæmatin*, which has a spectrum ite distinct from hæmoglobin, viz., a narrow band just before D, two arrow between D and E, and two other faint bands, nearly violet, , and between E and F close to F.

In addition to muscle *ferments*, already mentioned, muscle extracts contain certain small amounts of ***pepsin and fibrin ferment***, an *amylolytic ferment.*

Certain *acids* are also present, particularly sarco-lactic, acetic and formic.

Of carbohydrates, *glycogen* and *glucose* (or maltose), also in

**Nitrogenous crystalline bodies**, such as ***kreatin***, ***kreatini*** *hypo-xanthin*, or carnin, *taurin*, *urea*, in very small amount, and *inosinic acid.*

*Salts*, the chief of which is ***potassium phosphate.***

## Muscle at Rest.

*Physical Condition.*—During rest or inactivity a muscle h but very perfect *Elasticity;* it admits of being considerably but returns readily and completely to its normal condition. ing body the muscles are always stretched somewhat beyond the length, they are always in a condition of slight tension; an ar which enables the whole force of the contraction to be utiliz proximating the points of attachment. It is obvious that if t were lax, the first part of the contraction until the muscle bec would be wasted.

There is no doubt that even in a condition of rest ***Oxygen*** is *from the blood*, and *carbonic acid is given out* by a muscle; for becomes venous in the transit, and since the muscles form b largest element in the composition of the body, chemical cha be constantly going on in them as in other tissues and organs, not necessarily accompanied by contraction. When cut out o such muscles retain their contractility longer in an atmosphere than in an atmosphere of hydrogen or carbonic acid, and durin amount of oxygen is no doubt necessary to the manifestation as well as for the metabolism going on in the resting condition

The reaction of living muscle in a resting or inactive co *neutral or faintly alkaline.*

**Demarcation Currents or Currents of Injury**:—I which have been removed from the body, it has been found some little time *electrical currents can be demonstrated pas point to point on their surface;* but as soon as the muscles di into rigor mortis, these currents disappear.

**The demonstration of muscle currents** is usually done as follows:– muscles are the most convenient for experiment; and a muscle shape, in which the fibres are parallel, is selected. The ends are clean vertical cuts, and the resulting piece of muscle is called a *reg prism.* The muscle prism is insulated, and a pair of non-polarizable

ted with a very delicate galvanometer (fig. 321) is applied to various
of the prism, and by a deflection of the needle to a greater or less extent
direction or another, the strength and direction of the currents in the
of muscle can be estimated. It is necessary to use non-polarizable and
tallic electrodes in this experiment, as otherwise there is no certainty
e whole of the current observed is communicated from the muscle itself,
not derived from the metallic electrodes arising in consequence of the
of the saline juices of the tissues upon them. The form of the non-
able electrodes is a modification of Du Bois Reymond's apparatus (fig.
hich consists of a somewhat flattened glass cylinder, *a*, drawn abruptly



321.—Reflecting galvanometer. (Thomson.) A. The galvanometer, which consists of
ms of small astatic needles suspended by a fine hair from a support, so that each set of
s within a coil of fine insulated copper wire, that forming the lower coil is wound in an
direction to the upper. Attached to the upper set of needles is a small mirror about
diameter; the light from the lamp at B is thrown upon this little mirror, and is re-
on the scale on the other side of B, not shown in figure. The coils *l l* are arranged
s uprights, and their ends are carried to the binding screws. The whole apparatus is
on a vulcanite plate capable of being levelled by the screw supports, and is covered
s-bound glass shade, L, the cover of which is also of brass, and supports a brass rod,
ch moves a weak curved magnet, *m*. C is the shunt by means of which the amount of
nt sent into the galvanometer may be regulated. When in use the scale is placed
e feet from the galvanometer, which is arranged east and west, the lamp is lighted,
r is made to swing, and the light from the lamp is adjusted to fall upon it, and it is
lated until the reflected spot of light from it falls upon the zero of the scale. The
n the non-polarizable electrodes touching the muscle are attached to the outer binding
the galvanometer, a key intervening for short-circuiting, or if a portion only of the
to pass into the galvanometer, the shunt should intervene as well with the appropriate
When a current passes into the galvanometer the needles and, with them, the mirror,
to the right or left according to the direction of the current. The amount of the de-
the needle is marked on the scale by the spot of light travelling along it.

t, and fitted to a socket capable of movement, and attached to a stand,
at it can be raised or lowered as required. The lower portion of the

cylinder is filled with china clay moistened with saline solution, part of whi
projects through its drawn-out point; the rest of the cylinder is fitted with
saturated solution of zinc sulphate into which dips a well amalgamated pi
of zinc connected by means of a wire with the galvanometer. In this w
the zinc sulphate forms a homogeneous and non-polarizable conductor betw
the zinc and the china clay. A second electrode of the same kind is, of cou
necessary.



Fig. 322.—Diagram of Du Bois Reymond's non-polarizable electrodes. *a*, Glass tube
with a saturated solution of zinc sulphate, in the end, *c*, of which is china clay drawn out
point; in the solution a well amalgamated zinc rod is immersed and connected, by means
wire which passes through A, with the galvanometer. The remainder of the apparatus is s
for convenience of application. The muscle and the end of the second electrode are t
right of the figure.

In a regular muscle prism the currents are found to be as follows
If from a point in the surface a line—the equator—be drawn across
muscle prism equally dividing it, currents pass from this point to po
away from it, which are weak if the points are near, and increased



Fig. 323.—Diagram of the currents in a muscle prism. (Du Bois Reymond.)

strength as the points are farther and farther away from the equ e strongest passing from the equator to a point representing the middle the cut ends (fig. 323, 2); currents also pass from points nearer the uator to those more remote (fig. 323, 1, 3, 4), but not from points ually distant or iso-electric points (fig. 323, 6, 7, 8). The cut ends always negative to the equator. These currents are constant for ne time after removal of the muscle from the body, and in fact remain long as the muscle retains its life. They are in all probability due to emical changes going on in the muscles. The currents are diminished fatigue and are increased by an increase of temperature within natural its.

It is now held by some that the strength of current in the mus- prism does not vary with approach toward or retreat from the ator.

The above-mentioned currents were formerly called the natural scle currents or currents of rest. It has since been shown, however, t the intact resting muscle shows no differences of potential, and t these are not developed unless some part of the muscle or tendon is red. These currents have, therefore, been more properly named *arcation currents*, or *currents of injury*.

## Muscle in Activity.

The property of muscular tissue, by which its peculiar functions are rcised, is its *Contractility*, which is excited by all kinds of stimuli plied either directly to the muscles, or indirectly to them through the dium of their motor nerves. This property, although commonly ught into action through the nervous system, is inherent in the scular tissue. For—(1.) it may be manifested in a muscle which is lated from the influence of the nervous system by division of the rves supplying it, so long as the natural tissue of the muscle is duly urished; and (2.) it is manifest in a portion of muscular fibre, in ich, under the microscope, no nerve-fibre can be traced. (3.) Sub- nces such as *curari*, which paralyze the nerve-endings in muscles, do at all diminish the irritability of the muscle itself.

(4.) When a muscle is fatigued, a local stimulation is followed by a traction of a small part of the fibre in the immediate vicinity without regard to the distribution of nerve-fibres.

**The Conditions which Affect the Irritability of Muscle**—that its readiness of response to stimuli—are numerous. The chief causes ariation in irritability are the following:

*Blood-Supply.*—The irritability of muscles is also soon lost, unless a supply of *arterial blood* to them is kept up. Thus, after ligature of the main arterial trunk of a limb, the power of moving the muscles is partially or wholly lost, until the collateral circulation is established; and when, in animals, the abdominal aorta is tied, the hind legs are rendered almost powerless.

The same fact may be readily shown by compressing the abdominal aorta in a rabbit for about 10 minutes; if the pressure be released and the animal be placed on the ground, it will work itself along with its front legs, while the hind legs sprawl helplessly behind. Gradually the muscles recover their power and become quite as efficient as before.

So, also, it is to the imperfect supply of arterial blood to the muscular tissue of the heart that the cessation of the action of this organ in asphyxia is in some measure due.

*Fatigue.*—The irritability of muscle is decreased by undue functional activity. The cause of the diminished irritability is twofold—when a muscle contracts, part of its substance is expended, part of its store of nutriment is exhausted, and it cannot readily contract again until the loss is made up. To this extent fatigue is much the same in its effect as cutting off or diminishing the blood-supply. The other cause for the diminution of irritability is the accumulation of poisonous products in the lymphatics of the muscle—substances generated during contraction.

*Separation from Central Nervous System.*—Generally a muscle begins to lose its irritability to all forms of stimuli about two weeks after its nerve is severed. Within a short time, however, its readiness of response to mechanical stimuli and to direct battery currents is heightened, while to induction shocks it is lessened. The increase of irritability reaches its maximum in about seven weeks, after which the irritability to all forms of stimuli diminishes, until it is completely lost toward the end of the seventh or eighth month.

The loss of irritability in muscle is due to degenerative changes in its protoplasm. But the cause of the degeneration is a matter of controversy, being considered due to loss of trophic influences from the central nervous system on the one hand, and to circulatory disturbances on the other.

*Use.*—Not only irritability but strength and power of endurance in muscle are increased by use. The effect of properly regulated exercises on muscles is too well known to need more than bare mention. And, on the contrary,

*Disuse* leads to diminution or loss of irritability. This fact is familiarly shown when a limb is disabled for a time, as through breaking a bone, in the stiffness of the muscles and the slowness with which they respond to the will.

*perature.*—The irritability of muscle is increased by raising its ture slightly above that of the animal from which it has been while it is decreased by cooling. If, however, the temperature l too high (45° C. for frog, 50° C. for mammal), the muscle en- a condition of heat rigor and its irritability is forever lost. oling, unless the cold be too severe and prolonged, the irritabil- ns as the temperature is raised. The effect of cold on irritabil- own in the superficial muscles of the face in winter.

*icals and Drugs.*—Most chemical substances cause a marked n of irritability in muscle. In general terms, it may be said se which produce any effect at all at first increase and then irritability.

*anical stimuli* at first increase and then diminish the irritability e. If they are powerful enough, the muscle is destroyed.

## The Phenomena of Muscular Contraction.

power which muscles possess of contraction may then be called stimuli of various kinds, and these stimuli may also be applied to the muscle or indirectly to the nerve supplying it. There are advantages, however, in applying the stimulus to the nerve, as e convenient, as well as more potent. The stimuli are of four iz.:—

*Mechanical stimuli*, as by a blow, pinch, prick of the muscle or , will produce a contraction, repeated on the repetition of the ; but if applied to the same point for a limited number of times such stimuli will soon destroy the irritability of the preparation.

*Thermal Stimuli.*—If a needle be heated and applied to a muscle rve, the muscle will contract. A temperature of over 45° C. ) will cause the muscles of a frog to pass into a condition known *igor.*

*Chemical Stimuli.*—A great variety of chemical substances will e contraction of muscles, some substances being more potent in g the muscle itself, and other substances having more effect upon e. Of the former may be mentioned, dilute acids, salts of cer- tals, *e.g.*, zinc, copper and iron; to the latter belong strong strong acids, ammonia and bile salts in strong solution.

*Electrical Stimuli.*—For the purpose of experiment electrical re most frequently used, as the strength of the stimulus may be nveniently regulated. Any form of electrical current may be l for this purpose, but galvanism or the induced current is usu- en.

**Galvanic currents** are usually obtained by the employment of a continuous current battery such as that of Daniell, by which an electrical current which varies but little in intensity is obtained. The battery (fig. 320) consists of a positive plate of well-amalgamated zinc immersed in a porous cell, containing dilute sulphuric acid; and this cell is again contained within a large copper vessel (forming the negative plate), containing besides a saturated solution of copper sulphate. The electrical current is made continuous by the use of the two fluids in the following manner. The action of the dilute sulphuric acid upon the zinc plate partly dissolves it, and liberates hydrogen, and this gas passes through the porous vessel, and decomposes the copper sulphate into copper and sulphuric acid. The former is deposited upon the copper plate, and the latter passes through the porous vessel to renew the sulphuric acid which is being used up. The copper sulphate solution is renewed by spare crystals of the salt, which are kept on a little shelf attached to the copper plate, and slightly below the level of the solution in the vessel. The current of electricity supplied by this battery will continue without variation for a considerable time. Other continuous current batteries, such as Grove's, may be used in place of Daniell's. The way in which the apparatus is arranged is to attach wires to the copper and zinc plates, and to bring them to a *key*, which is a little apparatus for connecting the wires of a battery. One often employed is Du Bois Reymond's (fig. 325); it consists of two pieces of brass about an inch long, in each of which are two holes for wires and binding screw, to hold them tightly; these pieces of brass are fixed upon a vulcanite plate, to the under surface of which is a screw clamp by which it can be secured to the table. The interval between the pieces of brass can be bridged over by means of a third thinner piece of similar metal fixed by a screw to one of the brass pieces, and capable of movement by a handle at right angles, so as to touch the other piece of brass. If the wires from the battery are brought to the inner binding screws, and the bridge connects them, the current passes across it and back to the battery. Wires are connected with the outer binding screws, and the other ends are joined together for about two inches, but, being covered except at their points, are insulated; the uncovered points are about an eighth of an inch apart. These wires are the *electrodes*, and the electrical stimulus is applied to the muscle through them, if they are placed behind its nerve. When the connection between the two brass plates of the key is broken by depressing the handle of the bridge, the key is then said to be opened.



Fig. 324.—Diagram of a Daniell's battery.

**An induced current** is developed by means of an apparatus, called an induc *n coil*, and the one employed for physiological purposes is mostly Du Bois ymond's, the one seen in fig. 327.

Wires from a battery are brought to the two binding screws *d'* and *d*, a key ervening. These binding screws are the ends of a coil of coarse covered wire



325.—Du Bois Reymond's Key.



Fig. 326.—Mercury Key.

alled the primary coil. The ends of a coil of finer covered wire *g*, are attached two binding screws to the left of the figure, one only of which is visible. s is the secondary coil, and is capable of being moved nearer to *c* along a ove and graduated scale. To the binding screws to the left of *g*, the wires lectrodes used to stimulate the muscle are attached. If the key in the cir-



Fig. 327.—Du Bois Reymond's induction coil.

of wires from the battery to the primary coil (primary circuit) be closed, current from the battery passes through the primary coil, and across the to the battery, and continues to pass as long as the key continues closed. he moment of closure of the key, at the exact instant of the completion of the primary circuit, an instantaneous current of electricity is induced in the secondary coil, $g$, if it be sufficiently near and in line with the primary coil; and the nearer it is to $c$, the stronger is the current induced. The current is *only momentary in duration* and does not continue during the whole of the period while the primary circuit is complete. When, however, the primary current is broken by opening the key, a second, also momentary, current is induced in $g$. The former induced current is called the *making* and the latter the *breaking* shock; the former is in the opposite direction to, and the latter in the same as, the primary current.

The induction coil may be used to produce a rapid series of shocks by means of another and accessory part of the apparatus at the right of the fig., called the *magnetic interrupter*. If the wires from a battery are connected with the two pillars by the binding screws, one below $c$, and the other, $a$, the course of the current is indicated in fig. 328, the direction being indicated by the arrows. The current passes up the pillar from $e$, and along the springs if the end of $d'$ is close to the spring, the current passes to the primary coil $c$, and to wires covering two upright pillars of soft iron, from them to the pillar $a$, and out by the wires to the battery; in passing along the wire, $b$, the soft iron is converted into a magnet, and so attracts the hammer, $f$, of the spring, breaks the connection of the spring with $d'$, and so cuts off the current from the primary coil, and also from the electro-magnet. As the pillars, $b$, are no longer magnetized the spring is released, and the current passes in the first direction, and is in like manner interrupted. At each make and break of the primary current, currents corresponding are induced in the secondary coil. These currents are opposite in direction, but are not equal in intensity, the break shock being greater. In order that the shocks should be nearly equal at the make and break, a wire (fig. 328, $e'$) connects $e$ and $d'$, and the screw $d'$ is raised out of reach of the spring, and $d$ is raised (as in fig. 328), so that part of the current always passes through the primary coil and electro-magnet. When the spring touches $d$, the current in $b$ is diminished, but never entirely withdrawn, and the primary current is altered in intensity at each contact of the spring with $d$, but never entirely broken.



Fig. 328.—Diagram of the course of the current in the magnetic interrupter of Du Bois Reymond's induction coil. (Helmholz's modification.)

**Record of Muscular Contraction under Stimuli.**—The muscles of the frog are most convenient for the purpose of recording contractions. The frog is pithed, that is to say, its central nervous system is entirely destroyed by the insertion of a stout needle into the spinal cord, and the parts above it. One of its lower extremities is used in the following manner. The large trunk of the sciatic nerve is dissected out at the back of the thigh, and a pair of electrodes is



9.—Arrangement of the apparatus necessary for recording muscle contractions
lving cylinder carrying smoked paper. A, Revolving cylinder; B, the frog arranged
k-covered board which is capable of being raised or lowered on the upright, which
moved along a solid triangular bar of metal attached to the base of the recording
-the tendon of the gastrocnemius is attached to the writing lever, properly weighted,
ure. The electrodes from the secondary coil pass to the apparatus—being, for the
nvenience, first of all brought to a key, D (Du Bois Reymond's); C, the induction
battery (in this fig. a bichromate one); E, the key (Morse's) in the primary circuit.

behind it. The tendo-achillis is divided from its attachment to the
and a ligature is tightly tied round it. This tendon is part of the
scle of the thigh (gastrocnemius), which arises from above the con-



Fig. —Moist Chamber.

dyles of the femur. The femur is now fixed to a board covered with cork and the ligature attached to the tendon is tied to the upright of a piece of metal bent at right angles (fig. 329, B), which is capable of movement about a pivot at its knee, the horizontal portion carrying a writing lever (myograph When the muscle contracts, the lever is raised. It is necessary to attach a small weight to the lever. In this arrangement the muscle is *in situ*, and the nerve disturbed from its relations as little as possible.

The muscle may, however, be detached from the body with the lower end of the femur from which it arises, and the nerve going to it may be taken away with it. The femur is divided at about the lower third. The bone is held in a firm clamp, the nerve is placed upon two electrodes connected with an induction apparatus, and the lower end of the muscle is connected by means of a ligature attached to its tendon with a lever which can write on a recording apparatus.

To prevent evaporation this so-called *nerve-muscle preparation* is placed under a glass shade (*moist chamber*, fig. 330), the air in which is kept moist by means of blotting paper saturated with saline solution.



Fig. 331.—Simple form of pendulum myograph and accessory parts. *A*, Pivot upon which pendulum swings: *B*, catch on lower end of myograph opening the key, *C*, in its swing; *D*, a spring-catch which retains myograph, as indicated by dotted lines, and on pressing down the handle of which the pendulum swings along the arc to *D* on the left of figure, and is caught by its spring.

**Effects of a Single Induction Shock.**—With a nerve-muscle preparation arranged in either of the above ways, on closing or opening the key in the primary circuit, we obtain and can record a contraction, and if we use the clockwork apparatus revolving rapidly, a curve is traced such as is shown in fig. 332.

Another way of recording the contraction is by the use of the pendulum myograph (fig. 331). Here the movement of the pendulum along a certain arc is substituted for the clockwork movement of the other apparatus. The penarries a smoked glass plate upon which the writing lever of a myograph is mark. The opening or breaking shock is sent into the nerve-muscle prep- by the pendulum in its swing opening a key (fig. 331, *C.*) in the primary A muscle or its nerve is more irritable to an opening shock than it is to a shock of the same strength, because the duration of the former is shorter at of the latter.

**igle Muscle Contractions.**—The tracing (*muscle curve*) ob- of a single muscle contraction or *twitch* is seen in fig. 332; and thus explained.

e upper line (*m*) represents the curve traced by the end of the lever nection with a muscle after stimulation of the muscle by a single ion-shock: the middle-line (*l*) is that described by the marking- and indicates by a sudden drop the exact instant at which the ion-shock was given. The lower wavy line (*t*) is traced by a ng tuning-fork, and serves to measure precisely the time occupied part of the contraction.



332.—Muscle-curve obtained by means of the pendulum myograph. *s*, indicates the tant of the induction shock; *c*, commencement; and *m x*, the maximum elevation of the line of a vibrating tuning-fork. (M. Foster.)

vill be observed that after the stimulus has been applied, as indi- y the vertical line *s*, there is an interval before the contraction nces, as indicated by the line *c*. This interval, termed (*a*) the **period,** when measured by the number of vibrations of the tun- k between the lines *s* and *c*, is found to be about $\frac{1}{100}$ sec. The period is longer in some muscles than in others, and differs also ng to the condition of the muscle, being longer in fatigued mus- d the kind of stimulus employed. During the latent period there *parent* change in the muscle.

second part is the (*b*) **stage of contraction** proper. The lever d by the sudden contraction of the muscle. The contraction is at ry rapid, but then progresses more slowly to its maximum, indicated by the line $m\ x$, drawn through its highest point. It occupies in the figure $\frac{4}{100}$ sec. ($c$) The next stage, **stage of elongation.** After **reaching its highest point,** the lever begins to descend, **in** consequence of the elongation of the muscle. At first the fall is rapid, but then becomes more gradual until the lever reaches the *abscissa* or base line, and the muscle attains its pre-contraction length, indicated in the figure by the line $c'$. The stage occupies $\frac{5}{100}$ second. Very often after the main contraction the lever rises once or twice to a slight degree, producing curves, one of which is seen in fig. 335. These contractions, due to the elasticity of the muscle, are called most properly ($d$) **stage of elastic after-vibration,** or contraction remainder.

The latent period has been found by exact methods of determination to be only $\frac{1}{400}$ second in length. The remainder of the time indicated above is occupied in the propagation of the impulse along the nerve and in overcoming the resistance of the apparatus used for recording the curve.

## Accompaniments of Muscular Contraction.

(1.) *Heat* is developed in the contraction of muscles. Becquerel and Breschet found, with the thermo-multiplier, about .5° C. of heat produced by each forcible contraction of a man's biceps; and when the actions were long continued, the temperature of the muscle increased 1°. This estimate is probably high, as in the frog's muscle a considerable contraction has been found to produce an elevation of temperature equal on an average to less than $\frac{1}{5}$° C. The cause of the rise of temperature is the increased chemical activity at the time of contraction. As we have already seen (Animal Heat), muscles produce heat even when uncontracted.

(2.) *Sound* is produced, as mentioned above, when voluntary muscles contract. Wollaston showed that this sound might be easily heard by placing the tip of the little finger in the ear, and then making some muscles contract, as those of the ball of the thumb, whose sound may be conducted to the ear through the substance of the hand and finger. A low shaking or rumbling sound is heard. The sound is due to the vibration of the individual muscle fibres. Experimentally it has been found that the number of vibrations corresponds to the number of excitations, and that muscle exhibits no normal rate of vibration, except in so far as a rate is expressed in the discharge of nerve impulses from the cells controlling the muscle. Nerve cells do not send out a single, but a series of impulses. Moreover, the muscle sound corresponds to the rate at which the muscle is stimulated.

Helmholtz found that, in the voluntary contraction of muscle, only

ds having a vibration of 18–20 per second were thrown into motion;
l since this rate is too slow to produce a tone, he concluded that the
nd heard was the first overtone. But this rate has been called into
stion by later experiments, in which a tambour, connected with a
ording apparatus, is placed on a contracting muscle. The rate of
ration thus obtained is stated to be from 8–12 per second, according
he muscle investigated and its condition. Tremors are shown by a
scle in fatigue and in many conditions of disease. Since the reso-
ce tone of the membrana tympani corresponds to 36–40 vibrations a
nd, the muscle sound does not indicate the number of vibrations in
ntracting muscle. This sound has been called the *natural muscle*
, in contradistinction to the sound produced by a muscle contract-
in response to rapidly repeated stimuli from an induction-coil, which
nown as the *artificial muscle tone*. For example, the tone of a tuning
used as interrupter in the primary circuit may be reproduced in
muscle whose nerve is thus stimulated. Such a muscle, placed in
it with a telephone, will, by means of its action currents, reproduce
ound in the telephone. Two tones of different pitch may be pro-
d in the same muscle at the same time when its nerve is stimulated
wo series of stimuli of different frequency.

3.) *Changes in Shape.*—There is a considerable difference of opinion
the mode in which the transversely striated muscular fibres con-
. The most probable account is, that the contraction is effected
approximation of the constituent parts of the fibrils, which, at
nstant of contraction, without any alteration in their general direc-
become closer, flatter, and wider; a condition which is rendered
nt by the approximation of the transverse striæ seen on the surface
e fasciculus, and by its increased breadth and thickness. The
rance of the zigzag lines into which it was supposed the fibres are
wn in contraction, is due to the relaxation of a fibre which has been
tly contracted, and is not at once stretched again by some antago-
fibre, or whose extremities are kept close together by the contractions
her fibres. The contraction is therefore a simple and, according to
Weber, a uniform, simultaneous, and steady shortening of each fibre
its contents. What each fibril or fibre loses in length, it gains in
kness: the contraction is a change of form not of size; it is, there-
not attended with any diminution in bulk, from condensation of
tissue. This has been proved for entire muscles, by making a mass
uscles, or many fibres together, contract in a vessel full of water,
which a fine, perpendicular, graduated tube communicates. Any
nution of the bulk of the contracting muscle would be attended by
l of fluid in the tube; but when the experiment is carefully per-

formed, the level of the water in the tube remains the same, whether the muscle be contracted or not.

In thus shortening, muscles *appear to swell up, becoming rounder, more prominent, harder, and apparently tougher.* But this hardness of muscle in the state of contraction is not due to increased firmness or condensation of the muscular tissue, but to the increased tension to which the fibres, as well as their tendons and other tissues, are subjected from the resistance ordinarily opposed to their contraction. When no resistance is offered, as when a muscle is cut off from its tendon, not only is no hardness perceived during contraction, but the muscular tissue is even softer, more extensile, and less elastic than in its ordinary uncontracted state. During contraction in each fibre it is said that the anisotropous



Fig. 333.—The microscopic appearances during a muscular contraction in the individual fibrillæ, after Engelmann. 1. A passive muscle-fibre; c to d = doubly refractive discs, with median disc a b in it; h and g are lateral discs; f and e are secondary discs, only slightly doubly refractive; fig. on right same fibre in polarized light; bright part is doubly refracted, black ends not so. 2. Transition stage; and 3. Stage of entire contraction; in each case the right-hand figure represents the effect of polarized light. (Landois after Engelmann.)

or doubly refractive elements become less refractive and the singly refractive more so (fig. 333).

(4.) *Chemical Changes.*—(*a*) The reaction of the muscle which is normally alkaline or neutral becomes decidedly *acid*, from the development of sarcolactic acid. (*b*) The muscle gives out carbonic acid gas and takes up oxygen, the amount of the $CO_2$ given out not appearing to be entirely dependent upon the O taken in, and so doubtless in part arising from some other source. (*c*) Certain imperfectly understood chemical changes occur, in all probability connected with (*a*) and (*b*). Glycogen is diminished, and glucose, or muscle sugar (inosite) appears; the extractives are increased.

(5.) *Electrical Changes.*—When a muscle, which has been removed from the body and consequently shows a demarcation current, is made to contract, this current undergoes a diminution as indicated by the galvanometer needle, which swings back in the opposite direction. This is known as the *negative variation*, or, more properly, the *action current*, since it also occurs where no previous demarcation current existed.

For the study of the action current, either the galvanometer or capillary electrometer (for description see page 255) may be used. hearts of cold-blooded animals, because of their slow contraction, ll for demonstration. The muscle contraction passes over the ventricle the form of a wave, the electric potential of the muscle changing as becomes active or passive. For any two points on the heart muscle, erefore, there will be two changes of potential, the active part first coming negative to the inactive, and then, as the wave passes down d the inactive part becomes active, the current is reversed. This is own as a *diphasic current.*

### Conditions which Affect the Characters of the Contraction.

n addition to the factors already considered which influence the irri-ility of muscle as such, these and others may affect the characters of contraction and hence the curve produced.

*Effect of Load.*—Within certain limits a muscle contracts more pow-ally when acting against resistance—that is, when it is *loaded.* Be-d this point of maximum contraction, however, increase of load di-ishes the height and duration of contraction and increases the length he latent period.

*Effect of Fatigue.*—As already stated, exercise increases the strength nuscles, so that the first effect of contraction is to increase the height he curve; but if the stimulation be kept up and the muscle be made ontract frequently, both the height and form of the curve are altered. latent period is lengthened, the height of the curve is lessened, and



g. 334.—Influence of temperature on single twitch of frog's gastrocnemius. *a*, Room tempera-17° C.; *b*, heated to 35° C.; *c*, cooled to 4° C.

duration of the contraction is much prolonged. Later a condition eached in which the muscle remains more or less contracted for a siderable time. This condition is called *contracture.*

*Effect of Temperature.*—Heat up to a certain point increases the irri- of muscle and favors rapidity in chemical activity, with the re-lt when it contracts the latent period is shortened, the height of re is increased, and the duration of the contraction is lessened. roduces contrary effects.

*Effect of Drugs.*—Veratrine does not alter the rapidity with which contraction occurs, but enormously prolongs the stage of relaxation. The salts of barium act similarly, and to a less extent those of calcium and strontium. In this connection it is interesting to recall that suprarenal extract acts likewise on voluntary muscles.

*Effect of Strength of Stimulus.*—A strength of current that is just sufficient to give a contraction is called a *minimal* stimulus. As the strength of the current is increased, the height of the contraction curve increases until the *maximal* stimulus is reached, beyond which no increase occurs. The latent period shortens with increased strength of stimulus.

*Effect of Rate of Stimulation.*—If we stimulate the nerve-muscle preparation with two induction shocks, one immediately after the other, when the point of stimulation of the second one corresponds to the maximum of the first, a second curve (fig. 335) will occur, which will commence at the highest point of the first and will rise nearly as high, so that the sum of the height of the two curves almost exactly equals twice the height of the first. If a third and fourth shock be passed, a similar effect will ensue, and curves one above the other will be traced, the third being slightly lower than the second, and the fourth than the third. If a more numerous series of shocks occur, however, the lever after a time ceases to rise any further, and the contraction, which has reached its maximum, is maintained. The condition which ensues is called *Tetanus*. A tetanus is really a summation of contractions, but unless the stimuli become very rapid indeed, the muscle will still be in a condition of vibratory contraction and not of unvarying contraction.



Fig. 335.—Tracing of a double muscle-curve. To be read from left to right. While the muscle was engaged in the first contraction (whose complete course, had nothing intervened, is indicated by the dotted line), a second induction-shock was thrown in, at such a time that the second contraction began just as the first was beginning to decline. The second curve is seen to start from the first, as does the first from the base line. (M. Foster.)

If the shocks, however, be repeated at very short intervals, varying in the frog, from 12 to 18 per second, the muscle contracts to its utmost suddenly and continues at its maximum contraction for some time, and r rises almost perpendicularly and then describes a straight line , *c*). If the stimuli are not so rapid the line of maximum con- becomes wavy, indicating a tendency of the muscle to relax the intervals between the stimuli (fig. 336, *b*). As the muscle



.—*a*, Frog's gastrocnemius muscle stimulated with four induction shocks per second, show- te relaxation between stimuli ; *b*, same muscle stimulated eight times per second, showing xation between stimuli (incomplete tetanus) ; *c*, same muscle stimulated twelve times per wing development of complete tetanus.

fatigued, a less rapid rate of stimulation is required to produce ete tetanus, owing to the prolongation of the relaxation period a muscle. The height of the contraction, however, is lessened. ndition of prolonged relaxation is known as *contracture*.

**scular Work.**—We have seen that *work* is estimated by multi- he weight raised by the height through which it has been lifted. een found that in order to obtain the maximum of work a mus- be moderately *loaded:* if the weight is increased beyond a cer- nt, however, the muscle becomes strained and raises it through a distance that less work is accomplished. If the load is still increased, the muscle is completely overtaxed and cannot raise the weight. No work is then done at all. Practical illustrations of these facts must be familiar to every one.

The **power of a muscle** is usually measured by the maximum weight which it will support without stretching. In man this is readily determined by weighting the body to such an extent that it can no longer be raised on tiptoe: thus the power of the calf-muscles is determined. The power of a muscle thus estimated depends of course upon its cross-section. The power of a human muscle is from two to three times as great as a frog's muscle of the same sectional area.

**Fatigue of Muscle.**—A muscle becomes rapidly exhausted from repeated stimulation, and the more rapidly, the more quickly the induction-shocks succeed each other. This is indicated by the diminished height of the muscular contractions. Where a number of successive single twitches of a muscle undergoing fatigue are recorded, graphically, the form of the curve is seen to change as follows: the height of the contraction is diminished; the contraction is slower; and the relaxation period is still more markedly prolonged.



Fig. 337.—Fatigue curve of frog's gastrocnemius muscle stimulated once per second, contractions recorded at the same place each time. Every fourth contraction is recorded. Shows decrease in height of contraction, increase in time of contraction, and increase of relaxation period.

A fatigued muscle has a much longer latent period than a fresh one. The slowness with which muscles respond to the will when fatigued must be familiar to every one.

In a muscle which is exhausted, stimulation only causes a contraction producing a local bulging near the point irritated. A similar effect may be produced in a fresh muscle by a sharp blow, as in striking the biceps smartly with the edge of the hand, when a hard muscular swelling is instantly formed.

As we have seen in discussing the irritability of muscle, the cause of fatigue is twofold, being in part due to its nutritive condition, and in part to the accumulation of poisonous products formed during contraction—probably sarcolactic acid, chiefly. In a living animal these poisonous products exert their influence not only upon the muscle or muscles immediately concerned in contraction, but upon the musculatu the body generally, and the effect remains until they are elimin from the body. Massage of the muscles increases the passage of into the general blood-stream and the rapidity of their elimination.

Under normal circumstances muscles do not become completely fa-
ued, for the reason that the nerve cells which send out the impulses
contraction become fatigued sooner than the muscles themselves do.
rve cells, however, recover from fatigue more quickly than muscles.
ese facts are sometimes shown when one feels utterly exhausted and
rcely able to drag one foot after another, yet under a strong effort of
ll, as from fright, is able to make unwonted effort.

**Response to Stimuli in Voluntary and Involuntary Muscles.**
The two kinds of fibres, the striped and the unstriped, have charac-
istic differences in the mode in which they act on the application of
same stimulus; differences which may be ascribed in great part to
ir respective *differences of structure*, but in some degree, possibly, to
ir respective *modes of connection with the nervous system.* When ir-
tion is applied directly to a muscle with striated fibres, or to the
tor nerve supplying it, contraction of the part irritated, and of that
y, ensues; and this contraction is instantaneous, and ceases on the in-
t of withdrawing the irritation. But when any part with unstriped
scular fibres, *e.g.*, the intestines or bladder, is irritated, the subse-
nt contraction ensues more slowly, extends beyond the part irritated,
, with alternating relaxation, continues for some time after the
hdrawal of the irritation. The difference in the modes of contrac-
of the two kinds of muscular fibres may be particularly illustrated
the effects of the repeated stimuli with the magnetic interrupter.
e rapidly succeeding shocks given by this means to the nerves of mus-
excite in all the transversely striated muscles, except in the case of
heart, a fixed state of tetanic contraction as previously described,
ich lasts as long as the stimulus is continued, and on its withdrawal
tantly ceases; but in the muscles with unstriped fibres they excite a
v vermicular movement, which is comparatively slight and alternates
h rest. It continues for a time after the stimulus is withdrawn.

n their mode of responding to these stimuli, all the skeletal muscles, or
e with transverse striæ, are alike; but among those with unstriped fibres
e are many differences—a fact which tends to confirm the opinion that
r peculiarity depends as well on their connection with nerves and ganglia
n their own properties. The ureters and gall-bladder are the parts least
ted by stimuli; they do not act at all till the stimulus has been long applied,
then contract feebly, and to a small extent. The contractions of the cæcum
stomach are quicker and wider spread: still quicker those of the iris, and of
urinary bladder if it be not too full. The actions of the small and large
stines, of the vas deferens, and pregnant uterus, are yet more vivid, more
lar, and more sustained; and they require no more stimulus than that of the
o excite them. The heart, on account, doubtless, of its striated muscle, is
uickest and most vigorous of all the muscles of organic life in contracting
irritation, and appears in this, as in nearly all other respects, to be the con-
ing member of the two classes of muscles.

ll the muscles retain their property of contracting under the influence of stimuli applied to them or to their nerves for some time after death, the period being longer in cold-blooded than in warm-blooded Vertebrata, and shorter in Birds than in Mammalia. It would seem as if the more active the respiratory process in the living animal, the shorter is the time of duration of the irritability in the muscles after death; and this is confirmed by the comparison of different species in the same order of Vertebrata. But the period during which this irritability lasts is not the same in all persons, nor in all the muscles of the same person. In a man it ceases, according to Nysten, in the following order:—first in the left ventricle, then in the intestines and stomach, the urinary bladder, right ventricle, œsophagus, iris; then in the voluntary muscles of the trunk, lower and upper extremities; lastly, in the right and left auricle of the heart.

## Muscle in Rigor Mortis.

After the muscles of the dead body have lost their irritability or capability of being excited to contraction by the application of a stimulus, they spontaneously pass into a state of contraction, apparently identical with that which ensues during life. It affects all the muscles of the body; and, when external circumstances do not prevent it, commonly fixes the limbs in that which is their natural posture of equilibrium or rest. Hence, and from the simultaneous contraction of all the muscles of the trunk, is produced a general stiffening of the body, constituting the *rigor mortis* or *post-mortem rigidity*.

When this condition has set in, the muscle (*a*) *becomes acid in reaction* (due to development of sarcolactic acid), (*b*) *gives off carbonic acid* in great excess, (*c*) *diminishes in volume slightly*, (*d*) *becomes shortened and opaque*, its substance setting firm. Rigor comes on much more rapidly after muscular activity, and is hastened by warmth. It may be brought on, in muscles exposed for experiment, by the action of distilled water and many acids, also by freezing and thawing.

*Cause.*—The immediate cause of rigor seems to be a chemical one, namely, the coagulation of the muscle plasma. We may distinguish three main stages—(1.) Gradual coagulation. (2.) Contraction of coagulated muscle-clot (myosin), and squeezing out of muscle-serum. (3.) Putrefaction. After the first stage, restoration is possible through the circulation of arterial blood through the muscles, and even when the second stage has set in, vitality may be restored by dissolving the coagulum of the muscle in salt solution, and passing arterial blood through the vessels. In the third stage recovery is impossible.

It has been noticed that the relaxation in muscles after rigor sometimes occurs too quickly to be caused by putrefaction, and the suggestion that in such cases at any rate such relaxation is due to a ferment-a is very plausible. It is known that pepsin is present in muscles,—that this ferment will act in an acid medium. The conditions for the olution of the coagulated myosin are therefore present as the reaction f rigored muscle is acid. Subjecting fresh muscle to the action of heat 50° to 60° C.) or immersing it in distilled water causes a similar coagu-ation to that of rigor mortis. The former is known as *heat rigor* and he latter as water rigor.

*Order of Occurrence.*—The muscles are not affected simultaneously by igor mortis. It affects the neck and lower jaw first; next, the upper xtremities, extending from above downward; and lastly, reaches the ower limbs; in some rare instances only, it affects the lower extremities efore, or simultaneously with, the upper extremities. It usually ceases n the order in which it begins: first at the head, then in the upper xtremities, and lastly in the lower extremities. It never commences arlier than ten minutes, and never later than seven hours after death; nd its duration is greater in proportion to the lateness of its accession. Heat is developed during the passage of a muscular fibre into the condi-ion of rigor mortis.

Since rigidity does not ensue until muscles have lost the capacity of eing excited by external stimuli, it follows that all circumstances which ause a speedy exhaustion of muscular irritability, induce an early oc-urrence of the rigidity, while conditions by which the disappearance of he irritability is delayed, are succeeded by a tardy onset of this rigidity. Hence its speedy occurrence, and equally speedy departure in the bodies f persons exhausted by chronic diseases; and its tardy onset and long ontinuance after sudden death from acute diseases. In some cases of udden death from lightning, violent injuries, or paroxysms of passion, gor mortis has been said not to occur at all; but this is not always the ase. It may, indeed, be doubted whether there is really a complete bsence of the post-mortem rigidity in any such cases; for the experi-ents of Brown-Séquard make it probable that the rigidity may supervene mmediately after death, and then pass away with such rapidity as to be arcely observable.

The occurrence of rigor mortis is not prevented by the previous exist-ce of paralysis in a part, provided the paralysis has not been attended th very imperfect nutrition of the muscular tissue.

The rigidity affects the involuntary as well as the voluntary muscles, hether they be constructed of striped or unstriped fibres. The rigidity involuntary muscles with striped fibres is shown in the contraction of e heart after death. The contraction of the muscles with unstriped res is shown by an experiment of Valentin, who found that if a grad-ted tube connected with a portion of intestine taken from a recently-lled animal, be filled with water, and tied at the opposite end, the ter will in a few hours rise to a considerable height in the tube, ing to the contraction of the intestinal walls. It is still better shown in the arteries, of which all that have muscular coats contract after death, and thus present the roundness and cord-like feel of the arteries of a limb lately removed, or those of a body recently dead. Subsequently they relax, as do all the other muscles, and feel lax and flabby, and lie as if flattened, and with their walls nearly in contact.

## Action of the Voluntary Muscles.

The greater part of the voluntary muscles of the body act as sources of power for moving levers,—the latter consisting of the various bones to which the muscles are attached.

**Examples of the three orders of levers in the Human Body.**—All levers have been divided into three kinds, according to the relative position of the *power*, the *weight* to be moved, and the *axis of motion* or *fulcrum*. In a lever of the *first* kind the *power* is at one extremity of the lever, the *weight* at the other, and the *fulcrum* between the two. If the initial letters only of the *power*, *weight*, and *fulcrum* be used, the arrangement will stand thus:—P. F. W. A poker as ordinarily used, or the bar in fig. 338, may be cited as an example this variety of lever; while, as an instance in which the bones of the h



Fig. 338.

skeleton are used as a lever of the same kind, may be mentioned the act raising the body from the stooping posture by means of the hamstring mus attached to the tuberosity of the ischium (fig. 338).

In a lever of the second kind, the arrangement is thus:—P. W. F.; and th leverage is employed in the act of raising the handles of a wheelbarrow, or stretching an elastic band, as in fig. 339. In the human body the act of op ing the mouth by depressing the lower jaw is an example of the same kin the tension of the muscles which close the jaw representing the weig (fig. 339).

In a lever of the third kind the arrangement is—F. P. W., and the act raising a pole, as in fig. 340, is an example. In the human body there numerous examples of the employment of this kind of leverage. The act ng the fore-arm may be mentioned as an instance (fig. 340). The act of ; is another example.

; the ankle we have examples of all three kinds of lever. 1st kind—Exng the foot. 3d kind—Flexing the foot. In both these cases the foot sents the weight: the ankle joint the fulcrum, the power being the calf les in the first case and the tibialis anticus in the second case. 2d kind—



Fig. 339.

ı the body is raised on tiptoe. Here the ground is the fulcrum, the ıt of the body acting at the ankle joint the weight, and the calf muscles ower.

the human body, levers are most frequently used at a disadvantage as ds power, the latter being sacrificed for the sake of a greater range of n. Thus in the diagrams of the first and third kinds it is evident that ower is so close to the fulcrum, that great force must be exercised in order duce motion. It is also evident. however, from the same diagrams, that



Fig. 340.

closeness of the power to the fulcrum a great range of movement can tained by means of a comparatively slight shortening of the muscular

he greater number of the more important muscular actions of the n body—those, namely, which are arranged harmoniously so as to rve some definite purpose or other in the animal economy—are ded in various parts of this work, in the sections which treat of the ology of the processes by which these muscular actions are resisted rried out. There are, however, one or two very important and hat complicated muscular acts which may be best described in lace.

**Walking.**—In the act of walking, almost every voluntary muscle in the body is brought into play, either directly for purposes of progression, or indirectly for the proper balancing of the head and trunk. The muscles of the arms are least concerned; but even these are for the most part instinctively in action to some extent.

Among the chief muscles engaged directly in the act of walking are those of the calf, which, by pulling up the heel, pull up also the astragalus, and with it, of course, the whole body, the weight of which is transmitted through the tibia to this bone (fig. 341). When starting to walk, say with the left leg, this raising of the body is not left entirely to the muscles of the left calf, but the trunk is thrown forward in such a way, that it would fall prostrate were it not that the right foot is brought forward and planted on the ground to support it. Thus the muscles of the left calf are assisted in their action by those muscles on the front of the trunk and legs which, by their contraction, pull the body forward; and, of course, if the trunk form a slanting line, with the inclination forward, it is plain that when the heel is raised by the calf-muscles, the whole body will be raised, and pushed obliquely forward and upward. The successive acts in taking the first step in walking are represented in fig. 337, 1, 2, 3.



Fig. 341.

Now it is evident that by the time the body has assumed the position No. 3, it is time that the right leg should be brought forward to support it and prevent it from falling prostrate. This advance of the other leg (in this case the *right*) is effected partly by its mechanically swinging forward, pendulum-wise, and partly by muscular action; the muscles used being—*1st*, those on the front of the *thigh*, which bend the thigh forward on the pelvis, especially the rectus femoris, with the psoas and the iliacus; *2dly*, the hamstring muscles, which slightly bend the *leg* on the thigh; and, *3dly*, the muscles on the front of the *leg*, which raise the front of the foot and toes, and so prevent the latter in swinging forward from hitching in the ground.

The second part of the act of walking, which has been just described, is shown in the diagram (4, fig. 341).

When the *right* foot has reached the ground the action of the *left* leg has not ceased. The calf-muscles of the latter continue to act, and by pulling up the heel, throw the body still more forward over the *right* leg, now bearing nearly the whole weight, until it is time that in *its* turn the *left* leg should swing forward, and the left foot be planted on the ground to prevent the body from falling prostrate. As at first, while the calf-muscles of one leg and foot are preparing, so to speak, to *push* the body forward and upward from behind by raising the heel, the muscles on the *front* of the trunk and the same leg (and of the other leg, except when it is swinging forward) are helping the *pulling* the legs and trunk, so as to make them incline forward, the ı in the inclining forward being effected mainly at the ankle joint. ain kinds of leverage are, therefore, employed in the act of walking, this idea be firmly grasped, the details will be understood with com- e ease. One kind of leverage employed in walking is essentially the ith that employed in pulling forward the pole, as in fig. 340. And the ess exactly, is that employed in raising the handles of a wheelbarrow. upposing the lower end of the pole to be placed in the barrow, we have a very rough and inelegant, but not altogether bad representation two main levers employed in the act of walking. The body is *pulled* l by the muscles in front, much in the same way that the pole might be force applied at P., while the raising of the heel and *pushing* forward runk by the calf-muscles is roughly represented on raising the handles barrow. The manner in which these actions are performed alternately h leg, so that one after the other is swung forward to support the which is at the same time *pushed* and *pulled* forward by the muscles ther, may be gathered from the the previous description.



Fig. 342.

re is one more thing to be especially noticed in the act of walking. In- as the body is being constantly supported and balanced on each leg ely, and therefore on only one at the same moment, it is evident that ust be some provision made for throwing the centre of gravity over the support formed by the bones of each leg, as, in its turn, it supports the of the body. This may be done in various ways, and the manner in it is effected is one element in the differences which exist in the walk- ifferent people. Thus it may be done by an instinctive slight rotation of is on the head of each femur in turn, in such a manner that the centre ity of the body shall fall over the foot of this side. Thus when the body ed onward and upward by the raising, say, of the *right* heel, as in fig. the pelvis is instinctively by various muscles made to rotate on the f the left femur at the acetabulum, to the left side, so that the weight may fall over the line of support formed by the left leg at the time that the *right* leg is swinging forward, and leaving all the work of support to fall on its fellow. Such a "rocking" movement of the trunk and pelvis, however, is accompanied by a movement of the whole trunk and leg over the foot which is being planted on the ground (fig. 342): the action being accompanied with a compensatory outward movement at the hip, more easily appreciated by looking at the figure (in which this movement is shown exaggerated) than described.

Thus the body in walking is continually rising and swaying alternately from one side to the other, as its centre of gravity has to be brought alternately over one or other leg; and the curvatures of the spine are altered in correspondence with the varying position of the weight which it has to support. The extent to which the body is raised or swayed differs much in different people.

In walking, one foot or the other is always on the ground. The act of leaping or jumping, consists in so sudden a raising of the heels by the sharp and strong contraction of the calf-muscles, that the body is jerked off the ground. At the same time the effect is much increased by first bending the thighs on the pelvis, and the legs on the thighs, and then suddenly straightening out the angles thus formed. The share which this action has in producing the effect may be easily known by attempting to leap in the upright posture, with the legs quite straight.

**Running** is performed by a series of rapid low jumps with each leg alternately; so that, during each complete muscular act concerned, there is a moment when both feet are off the ground.

In all these cases, however, the description of the manner in which any given effect is produced, can give but a very imperfect idea of the infinite number of combined and harmoniously arranged muscular contractions which are necessary for even the simplest acts of locomotion.

**Action of the Involuntary Muscles.**—The involuntary muscles are for the most part not attached to bones arranged to act as levers, but enter into the formation of such hollow parts as require a diminution of their calibre by muscular action, under particular circumstances. Examples of this action are to be found in the intestines, urinary bladder, heart and blood-vessels, gall-bladder, gland-ducts, etc.

The difference in the manner of contraction of the striated and non-striated fibres has been already referred to (p. 535); and the peculiar vermicular or peristaltic action of the latter fibres has also been described.

## ELECTRICAL CURRENTS IN NERVES.

The electrical condition of nerves is so closely connected with the phenomena of muscular contraction, that it will be convenient to consider it in the present chapter.

If a piece of nerve be removed from the body and subjected to examination in a way similar to that adopted in the case of muscle, which has been described, electrical currents are found to exist which correspond exactly to the demarcation currents of muscle, and which are called demarcation currents of nerve or currents of injury, as in the case with

uscle. One point (equator) on the surface being positive to all other
ints nearer to the cut ends, and the greatest deflection of the needle
the galvanometer taking place when one electrode is applied to the
uator and the other to the centre of either cut end. As in the case of
uscle, these nerve currents undergo a negative variation when the
rve is stimulated, the variation being momentary and in the opposite
rection to the natural currents; and are similarly known as the cur-
nts of action. The currents of action are propagated in both direc-
ons from the point of the application of the stimulus, and are of
omentary duration.

**Rheoscopic Frog.**—This negative variation may be demonstrated by means of
e following experiment. The new current produced by stimulating the nerve
one nerve-muscle preparation may be used to stimulate the nerve of a second
rve-muscle preparation. The foreleg of a frog with the nerve going to the
strocnemius cut long is placed upon a glass plate, and arranged in such way
at its nerve touches in two places the sciatic nerve, exposed but preserved
*situ* in the opposite thigh of the frog. The electrodes from an induction
il are placed behind the sciatic nerve of the second preparation, high up.
stimulating it with a single induction shock, the muscles not only of the
me leg are found to undergo a twitch, but also those of the first preparation,
hough this is not near the electrodes, and so the stimulation cannot be due
an escape of the current into the first nerve. This experiment is known
der the name of the *rheoscopic frog*.

**Nerve-stimuli.**—Nerve-fibres require to be stimulated before they can
anifest any of their properties, since they have no power of themselves
generating force or of originating impulses. The stimuli which are
pable of exciting nerves to action are, as in the case of muscle, very
verse. They are very similar in each case. The mechanical, chem-
al, thermal, and electric stimuli which may be used in the one case
also, with certain differences in the methods employed, efficacious in
other. The chemical stimuli are chiefly these: withdrawal of water,
by drying, strong solutions of neutral salts of potassium, sodium, etc.,
e inorganic acids, except phosphoric; some organic acids; ether,
oroform, and bile salts. The electrical stimuli employed are the
uction and continuous currents concerning which the observations in
erence to muscular contraction should be consulted. Weaker elec-
cal stimuli will excite nerve than will excite muscle; the nerve stimuli
pears to gain strength as it descends, and a weaker stimulus applied
from the muscle will have the same effect as a stronger one applied
the nerve near the muscle.

It will be only necessary here to add some account of the *effect of a*
*stant current*, such as that obtained from a Daniell's battery, upon a
ve. This effect may be studied with the apparatus described before.
air of electrodes is placed behind the nerve of the nerve-muscle prep-

aration, with a Du Bois Reymond's key arranged for short circuiting the battery current, in such a way that when the key is opened the current is sent into the nerve, and when closed the current is cut off. It will be found that with a current of moderate strength there will be a contraction of the muscle both at the opening and at the closing of the key (called respectively *making* and *breaking* contractions), but that during the interval between these two events the muscle remains flaccid, provided the battery current continues of constant intensity. If the current be a very weak or a very strong one the effect is not quite the same; one or other of the contractions may be absent. Which of these contractions is absent depends upon another circumstance, viz., the *direction of the current*. The direction of the current may be *ascending* or *descending:* if ascending, the anode or positive pole is nearer the muscle than the cathode or negative pole, and the current to return to the battery has to pass up the nerve; if descending, the position of the electrodes is reversed. It will be necessary before considering this question further to return to the apparent want of effect of the constant current during the interval between the make and break contraction: to all appearances no change is produced, but in reality a very important alteration of the irritability and conductivity is brought about in the nerve by the passage of this constant (polarizing) current. This may be shown in two ways, first of all by the galvanometer. If a piece of nerve be taken, and if at either end an arrangement be made to test the electrical condition of the nerve by means of a pair of non-polarizable electrodes connected with a galvanometer, while to the central portion a pair of electrodes connected with a Daniell's battery be applied, it will be found that the demarcation nerve-currents are profoundly altered on the passage of the constant current in the neighborhood. If the polarizing current be in the same direction as the latter the demarcation current is increased, but if in the direction opposite to it, the demarcation current is diminished. This change, produced by the continual passage of the battery-current through a portion of the nerve, is to be distinguished from the negative variation of the demarcation current to which allusion has been already made, and which is a momentary change occurring on the sudden application of the stimulus. The condition produced by the passage of a constant current is known by the name of **Electrotonus.**

A second way of showing the effect of the polarizing current is by taking a nerve-muscle preparation and applying to the nerve a pair of electrodes from an induction coil, while at a point further removed from the muscle, electrodes from a Daniell's battery are arranged with a key for short circuiting and an apparatus (reverser) by which the battery current may be reversed in direction. If the exact point be ascertained to which the secondary coil should be moved from the primary coil in der that a minimum contraction be obtained by the induction shock, d the secondary coil be removed slightly further from the primary, e induction current cannot now produce a contraction; but if the larizing current be sent in a descending direction, that is to say, with e cathode nearest the other electrodes, the induction current, which s before insufficient, will prove sufficient to cause a contraction; ereby indicating that with a descending current the irritability of e nerve is increased. By means of a somewhat similar experiment it y be shown that an ascending current will diminish the irritability a nerve. Similarly, if instead of applying the induction electrodes ow the other electrodes they are applied between them, like effects demonstrated, indicating that in the neighborhood of the cathode irritability of the nerve is increased by the passage of a constant rent, and in the neighborhood of the anode diminished. This in-se in irritability is called **katelectrotonus**, and similarly the rease is called **anelectrotonus**. As there is between the electrodes h an increase and a decrease of irritability on the passage of a po-zing current, it must be evident that the increase must shade off into decrease, and that there must be a *neutral point* where there is ther increase nor decrease of irritability. The position of this tral point is found to vary with the intensity of the polarizing cur-t—when the current is weak the point is nearer the anode, when



g. 343.—Diagram illustrating the effects of various intensities of the polarizing currents. nerve; *a*, anode: *k*, kathode; the curves above indicate increase, and those below decrease itability, and when the current is small the increase and decrease are both small, with the al point near *a*, and so on as the current is increased in strength.

ng nearer the kathode (fig. 343); when a constant current passes a nerve, therefore, if a contraction result, it may be assumed that due to the increased irritability produced in the neighborhood of kathode, but the breaking contraction must be produced by a rise rritability from a lowered state to the normal in the neighborhood he anode. The contractions produced in the muscle of a nerve-le preparation by a constant current have been arranged in a table h is known as Pflüger's **Law of Contractions**. It is really only a ment as to when a contraction may be expected:—

| STRENGTH OF CURRENT USED. | DESCENDING CURRENT. | | ASCENDING CURRENT. | |
|---|---|---|---|---|
| | Make. | Break. | Make. | Break. |
| Very Weak | Yes. | No. | No. | No. |
| Weak | Yes. | No. | Yes. | No. |
| Moderate | Yes. | Yes. | Yes. | Yes. |
| Strong | Yes. | No. | No. | Yes. |

During the passage of a constant current through a nerve and immediately after its cessation, there is a change in the conductivity as well as of the irritability of the nerve at the anode and kathode respectively. During the passage of the current, the conductivity is increased at the kathode and decreased at the anode. After the passage of the current, the effect is reversed. With strong currents the area of decreased conductivity may be sufficient to act as a block, preventing the passage of impulses over it.

The foregoing statements concerning the changes produced in a nerve by the passage of a constant current may be briefly summarized as follows:

I. A nerve is more irritable to the closing of a constant current than it is to the opening of a constant current.

II. During the passage of the current through the nerve, both its irritability and conductivity are increased at the kathode and decreased at the anode.

III. After the passage of the current, the irritability and conductivity are both decreased at the kathode and increased at the anode.

Sometimes (when the preparation is specially irritable?) instead of a simple contraction a tetanus occurs at the make or break of the constant current. This is especially liable to occur at the break of a strong ascending current which has been passing for some time into the preparation; this is called **Ritter's tetanus,** and may be increased by passing a current in an opposite direction or stopped by passing a current in the same direction.

### THE EFFECT OF BATTERY CURRENTS ON NORMAL HUMAN NERVES.

The following account is condensed from Lombard in "An American Text-book of Physiology."

As an electric current cannot be applied to living human nerves directly, it is applied to the skin along the course of the nerve. The current passes from the anode or positive pole through the skin, and out in the tissues much as the bristles of a brush; it then gr concentrates and leaves the skin at the kathode or negative pole.

In addition to the physical anode and kathode of the battery, there e what are called physiological anodes and kathodes. There is a ysiological anode *at every point* where the current *enters* a nerve, and physiological kathode *at every point* where it *leaves* it.

Generally when the current is applied to nerves through the skin, ly part of it flows longitudinally along the nerves; most of it passes agonally through them to the tissues below. Thus it happens that in at part of the nerve beneath either the physical anode or kathode, oups of physiological anodes and kathodes are found.

The contraction which occurs when the current is closed (*closing con-ction*) represents irritation at the physiological *kathode*, while the *ning contraction* represents irritation at the physiological *anode.*



Fig. 344.—Diagram of skin and subjacent nerve. A, the positive electrode or physical anode; e negative electrode or physical kathode. Signs +, physiological anodes; signs —, physio- al kathodes. (After Waller.)

ce there are physiological anodes and kathodes beneath each elec-de, one or more of four conditions may arise:

1. *Anodic closing contraction*, *i.e.*, the effect of the change developed the physiological kathode, beneath the physical anode (positive e).
2. *Anodic opening contraction*, *i.e.*, the effect of the change devel-d at the physiological anode, beneath the physical anode (positive e).
3. *Kathodic closing contraction*, *i.e.*, the effect of the change devel-d at the physiological kathode, beneath the physical kathode (nega- pole).
4. *Kathodic opening contraction*, *i.e.*, the effect of the change devel-d at the physiological anode, beneath the physical kathode (negative ).

The following abbreviations of these contractions are used: ACC, , KCC, KOC.

The closing contractions, KCC and ACC, are stronger than the ing contractions, KOC and AOC. Of the closing contractions, is stronger than ACC. Of the opening contractions, AOC is ger than KOC. These facts are also shown in a table of the effects adually increasing the strength of the current.

| Weak currents. | Medium currents. | Strong currents. |
|---|---|---|
| KCC | KCC | KCC |
| —— | ACC | ACC |
| —— | AOC | AOC |
| —— | —— | KOC |

Sometimes AOC is stronger than ACC.

In diseases which cause degeneration of the nerves going to a muscle, stimulation causes results different from the above, and we get what is known as the *reaction of degeneration.*

### MUSCULAR AND NERVOUS METABOLISM.

The question of the metabolism of muscle both in a resting and in an active condition has for many years occupied the attention of physiologists. It cannot be said even now to be thoroughly understood. Most of the facts with reference to the subject have been already mentioned. We may shortly recapitulate them here:—First, muscle during rest absorbs oxygen and gives out carbon dioxide. This has been shown by an analysis of the gases of the blood going to and leaving muscles. During activity, *e. g.*, during tetanus, the same interchange of gases takes place, but the quantities of the oxygen absorbed and of the carbon dioxide given up are increased, and the proportion between them is altered thus:—

| Venous Blood. | O, less than Arterial Blood. | $CO_2$, more than Arterial Blood. |
|---|---|---|
| Of resting muscle.... ............. | 9 per cent. | 6.71 per cent. |
| Of active muscle .................. | 12.26 per cent. | 10.79 per cent. |

There is then a greater proportion of carbon dioxide produced in muscle during activity than during rest.

During rigor mortis there is also an increased production of carbon dioxide.

Second, muscle during rest produces nitrogenous crystallizable substances, such as kreatin, from the metabolism which is constantly going on in it during life; in addition there is in all probability sarcolactic acid formed and other non-nitrogenous matters.

During activity the nitrogenous substances, such as kreatin, undergo very slight, if any, increase—about the amount produced during rest—but the sarcolactic acid is distinctly increased; sugar (glucose) is also increased, whereas the glycogen is diminished.

During rigor mortis the sarcolactic acid is also increased, and in ad-tion myosin is formed.

From these data it is assumed that the processes which take place in sting and active muscle are somewhat different, at any rate in degree. om actively contracting muscle, also, there are obtained an increased ount of heat and mechanical work, more potential is converted into netic energy.

Many theories have been proposed to explain the facts of muscular ergy. **It has been suggested by Herman that muscular activity de-nds** upon the splitting up and subsequent re-formation of a complex trogenous body, called by him *Inogen*. When this body so splits up ere result from its decomposition, carbon dioxide, sarcolactic acid, d a gelatino-albuminous body. Of these the carbon dioxide is carried ay by the blood stream; the albuminous substance and possibly the d, at any rate in part, go to re-form the inogen. The other materials which the inogen is formed are supplied by the blood; of these mate-ls we know that some carbohydrate substance and oxygen form a part. e decomposition, although taking place in resting muscle, reaches a max in active muscle, but in that condition the destruction of inogen gely exceeds restoration, and so there must be a limit to muscular ivity. But this is not the only change going on in muscle, there are ers which affect the nitrogenous elements of the tissue, and from m result the nitrogenous bodies of which kreatin is the chief; these nges may be unusually large during severe exercise.

It has been further suggested that, as myosin is undoubtedly formed rigor mortis, when the muscle becomes acid and gives off carbon xide, that myosin is also formed when muscle contracts, and that, in er words, contraction is a condition akin to partial death. The trical reaction appears to justify this; both contracted and dead scle are negative to living muscle, when at rest. What happens to myosin which is formed when muscle contracts, if this view be the rect one, is unknown. Halliburton suggests that the myosin which be made to clot and unclot easily enough outside the body, is able lo the same thing in the body. It is possible that the clotting of sinogen which is supposed to occur during contraction, is not of the e intensity or extent as that which occurs post mortem. The rela- of the hypothetical inogen to the rest of the muscle-fibre is unde-nined. It may be that the inogen is formed by the activity of the scle-protoplasm, and stored up within itself, and that during rest of scle it is gradually used up, whereas in activity it is suddenly and losively decomposed. In the rest of the fibre the nitrogenous meta-sm continues much the same during rest as during activity.

Again, histologically, the question as to which is the contractile and which is the non-contractile part of muscle, has been, as we have seen (p. 86 *et seq.*), a matter of much controversy.

As regards *nervous metabolism*, we have little knowledge of anything except the electrical phenomena which have been already considered. For the maintenance of nervous irritability, oxygen is required; to form this, it has been suggested that the nervous impulse is the result of processes of an oxidative character, etc. The chief seat of the metabolism is no doubt the axis-cylinder. The question whether a nervous impulse is possibly an electrical change, as has been asserted by some, cannot be at present settled, but if it be so, at any rate it differs essentially from an ordinary current, if in no other respect, at any rate in the rate of transmission.

# CHAPTER XV.

## THE PRODUCTION OF THE VOICE.

BEFORE commencing the consideration of the Nervous system and e Special Senses it will be convenient to consider first speech, the roduction of the human voice, and the physiology of the Larynx enerally.

**The Larynx.**—In nearly all air-breathing vertebrate animals there re arrangements for the production of sound, or *voice*, in some parts of



Fig. 345.—The cartilages and ligaments of the larynx, viewed from the front. *a*, Epiglottis; *b*, id bone; *c*, cartilago tritica; *d*, thro-hyoid membrane; *e*, superior cornu of thyroid cartilage; *f*, roid notch; *g*, pomum Adami; *h*, cricothyroid membrane; *i*, inferior cornu of thyroid cartilage; *j*, oid cartilage. (Cunningham.)

e respiratory apparatus. In many animals, the sound admits of being riously modified and altered during and after its production; and, in n, one such modification occurring in obedience to dictates of the ebrum, is *speech*.

It has been proved by observations on living subjects, by means of laryngoscope (p. 558), as well as by experiments on the larynx taken n the dead body, that the sound of the human voice is the result the vibration of the inferior laryngeal ligaments, or the true vocal cords which bound the *glottis*, caused by currents of expired air impell over their edges. If a free opening exists in the trachea, the sound the voice ceases, but it returns if the opening is closed. An openin into the air-passages above the glottis, on the contrary, does not prev the voice being produced. By forcing a current of air through th larynx in the dead subject, clear vocal sounds are elicited, though th epiglottis, the upper ligaments of the larynx or false vocal cords, th ventricles between them and the inferior ligaments or true vocal cor and the upper part of the arytenoid cartilages, be all removed; provid the true vocal cords remain entire, with their points of attachm and be kept tense and so approximated that the fissure of the glottis be narrow.

The vocal ligaments or cords, therefore, are regarded as the pr organs for the production of vocal sounds: the modifications of t sounds being effected, as will be presently explained, by other p viz., by the tongue, teeth, lips, etc. The structure of the vocal is adapted to enable them to vibrate like tense membranes, for they essentially composed of elastic tissue; and they are so attached to cartilaginous parts of the larynx that their position and tension ca variously altered by the contraction of the muscles which act on th parts.

Thus it will be seen that the larynx is the organ of voice. It m be said to consist essentially of the two vocal cords and the various ca tilaginous, muscular, and other apparatus by means of which not on can the aperture of the larynx (rima glottidis), of which they are th lateral boundaries, be closed against the entrance and exit of air to from the lungs, but also by means of which the cords themselves can stretched or *relaxed*, brought together and separated in accordance wi the conditions that may be necessary for the air in passing over them, set them vibrating to produce the various sounds. Their action respiration has been already referred to.

**Anatomy of the Larynx.**—The principal parts entering into the formatio the larynx (figs. 346 and 347) are—the thyroid cartilage; the cricoid cartil the two arytenoid cartilages; and the two true vocal cords. The epiglo (fig. 343), has but little to do with the voice, and is chiefly useful in prot ing the upper part of the larynx from the entrance of food and drink deglutition. It also probably guides mucus or other fluids in small amo from the mouth around the sides of the upper opening of the glottis into pharynx and œsophagus: thus preventing them from entering the lary The false vocal cords and the ventricle of the larynx, which is a space betw the false and the true cord of either side, need be here only referred to.

*Cartilages.*—(*a*) The *thyroid* cartilage (fig. 346, 1 to 4) does not form a plete ring around the larynx, but only covers the front portion. (*b*) *cricoid* cartilage (fig. 346, 5, 6), on the other hand, is a complete ring;

art of the ring being much broader than the front. On the top of this portion of the cricoid are (*c*) the *arytenoid* cartilages (fig. 346, 7), the tion between the cricoid below and arytenoid cartilages above being a joint ynovial membrane and ligaments, the latter permitting tolerably free



346.—Cartilages of the larynx seen from the front. 1 to 4, thyroid cartilage; 1, verti- e or pomum Adami; 2, right ala; 3, superior, and 4, inferior cornu of the right side; 5, 6, cartilage; 5, inside of the posterior part; 6, anterior narrow part of the ring; 7, arytenoid s. × ¾.

between them. But although the arytenoid cartilages can move on the , they of course accompany the latter in all its movements, just as the ay nod or turn on the top of the spinal column, but must accompany l its movements as a whole.

*ts and Ligaments.*—The thyroid cartilage is also connected with the , not only by ligaments, but also by joints with synovial membranes; ver *cornua* of the thyroid clasping, or nipping, as it were, the cricoid n them, but not so tightly but that the thyroid can revolve, within a



—The larynx as seen from behind after removal of the muscles. The cartilages and lig- aments only remain. (Stoerk.)

range, around an axis passing transversely through the two joints at the cricoid is clasped. The vocal cords are attached (behind) to the ortion of the base of the arytenoid cartilages, and (in front) to the ring angle at the back part of the thyroid; it is evident, therefore, that all movements of either of these cartilages must produce an effect on th some kind or other. Inasmuch, too, as the arytenoid cartilages rest c top of the back portion of the cricoid cartilage, and are connected with capsular and other ligaments, all movements of the cricoid cartilage move the arytenoid cartilages, and also produce an effect on the vocal co

*Intrinsic Muscles.*—The intrinsic muscles of the larynx are so con with the laryngeal cartilages that by their contraction alterations in the dition of the vocal cords and glottis are produced. They are usually di into four classes according to their action, viz., into *abductors, addu sphincters,* and *tensors.* The Abductors, the *crico-arytenoidei,* widen the g by separating the cords; the Adductors, consisting of the *thyro-ary-epigl* the *arytenoideus posticus seu transversus,* the *thyro-arytenoidei externi,* the *arytenoidei laterales,* and the *thyro-arytenoidei interni,* approximate the cords, diminish the rima glottidis, and act generally as Sphincters an porters of the glottis. Finally, the Tensors of the cords put the cords stretch, with or without elongating them; the tensors are the *crico-th* and the *thyro-arytenoidei interni.*

The attachments and the action of the muscles will be readily unde from the following table. All the muscles are in pairs except the aryten posticus.

TABLE OF THE SEVERAL GROUPS OF THE INTRINSIC MUSCLES OF THE L AND THEIR ATTACHMENTS.

| GROUP. | MUSCLE. | ATTACHMENTS. | ACTION. |
|---|---|---|---|
| I. **Abductors.** | Crico-arytenoidei postici. | This pair of muscles arises, on either side, from the posterior surface of the corresponding half of the cricoid cartilage. From this depression their fibres converge on either side upward and outward to be inserted into the outer angle of the base of the arytenoid cartilages behind the crico-arytenoid laterales. | Draw inwar backward outer ang arytenoid lages, and tate outw the process calis and the glottis. |
| II. and III. **Adductors and Sphincters.** | In three layers:<br>(a) *Outer layer,* Thyro-ary-epiglottici. | A pair of muscles. Flat and narrow, which arise on either side from the processus muscularis of the arytenoid cartilage, then passing upward and inward cross one another in the middle line to be inserted into the upper half of the lateral border of the opposite arytenoid cartilage and the posterior border of the cartilage of Santorini. The lower fibres run forward and downward to be inserted into the thyroid cartilage near the commissure. The fibres attached to the cartilage of Santorini are continued forward and upward into the ary-epiglottic fold. | Help to narr close the glottidis. |

| GROUP. | MUSCLE. | ATTACHMENTS. | ACTION. |
|---|---|---|---|
| I. and III. dductors and phincters. *continued.* | (b) *Middle layer.*<br>i. Arytenoideus posticus. | A single muscle. Half-quadrilateral, attached to the borders of the arytenoid cartilages, its fibres running horizontally between the two. | Draws together the arytenoid cartilages and also depresses them. When the muscle is paralyzed the inter-cart laginous part the cords cannt come together |
| | ii. Thyro-arytenoidei externi. | A pair of muscles. Each of which consists of three chief portions —lower, middle, and upper. The lower and principal fibres may be further divided into two layers, internal and external. These fibres arise side by side from the lower half of the internal surface of the thyroid cartilage, close to the angle, and from the fibrous expansion of the crico-thyroid ligament, and are inserted into the lateral border of the arytenoid cartilage. The inner fibres run horizontally, to be attached to the lower half of this border, and the outer fibres pass obliquely outward to be inserted into the upper half, while some pass to the cartilage of Wrisburg and the ary-epiglottic fold. | |
| | iii. Crico-arytenoidei laterales. | A pair of muscles. They arise on either side from the middle third of the upper border of the cricoid cartilage and are inserted into the whole anterior margin of the base of the arytenoid cartilage. Some of their fibres join the thyroid-ary-epiglottici. | Approximate the vocal cords by drawing the processus muscularis of the arytenoid cartilages forward and downward and so rotate the processus vocalis inward. |
| | (c) *Innermost layer*, Thyro-arytenoidei interni. | A pair of muscles. They arise on either side, internally from the angle of the thyroid cartilage, internal to the last described muscle ( (b), iii.), and running parallel to and in the substance of the vocal cords are attached posteriorly to the processus vocalis along their whole length and to the adjacent part of the outer surface of the arytenoid cartilages. | Render the vocal cords tense and rotate the arytenoid cartilages and approximate the processus vocalis. |

| GROUP. | MUSCLE. | ATTACHMENTS. | ACTION. |
|---|---|---|---|
| **IV. Tensors.** | Crico-thyroidei. | A pair of fan-shaped muscles attached on either side to the cricoid cartilage below; from the mesial line in front for nearly one-half of its lateral circumference backward the fibres pass upward and outward to be attached to the lower border of the thyroid cartilage and to the front border of its lower cornea. | The thyroid cartilage being fixed by its extrinsic muscles, the front of the cricoid cartilage is drawn upward, and its back, with the arytenoids attached, is drawn down. Hence the vocal cords are elongated antero-posteriorly and put upon the stretch. Paralysis of these muscles causes an inability to produce high notes. |
| | Thyro-arytenoidei interni. | The most posterior part is almost a distinct muscle and its fibres are all but horizontal: sometimes this muscle is described as consisting of two layers, superficial with cortical fibres, deep with oblique fibres, described under Group III. | Described above. |

*Nerve Supply.*—In the performance of the functions of the larynx the sensory filaments of the *superior laryngeal branch* of the vagus supply that acute sensibility by which the glottis is guarded against the ingress of foreign bodies, or of irrespirable gases. The contact of these stimulates the nerve filaments; and the impression conveyed to the medulla oblongata, whether it produce sensation or not, is reflected to the filaments of the *recurrent or inferior laryngeal* branch, and excites contraction of the muscles that close the glottis. Both these branches of the vagi co-operate also in the production and regulation of the voice; the inferior laryngeal determining the contraction of the muscles that vary the tension of the vocal cords, and the superior laryngeal conveying to the mind the sensation of the state of these muscles necessary for their continuous guidance. And both the branches co-operate in the actions of the larynx in the ordinary slight dilatation and contraction of the glottis in the acts of expiration and inspiration, and more evidently in those of coughing and other forcible respiratory movements.

**The laryngoscope** is an instrument employed in investigating during life the condition of the pharynx, larynx, and trachea. It consists of a large concave mirror with perforated centre and of a smaller mirror fixed in a long hand It is thus used: the patient is placed in a chair, a good light (argand burner, lamp) is arranged on one side of, and a little above his head. The operat fixes the large mirror round his head in such a manner, that he looks throu the central aperture with one eye. He then seats himself opposite the patient, and so alters the position of the mirror, which is for this purpose provided with a ball and socket joint, that a beam of light is reflected on the lips of the patient.

The patient is now directed to throw his head slightly backward, and to open his mouth; the reflection from the mirror lights up the cavity of the mouth, and by a little alteration of the distance between the operator and the patient the point at which the greatest amount of light is reflected by the mirror—in other words its focal length—is readily discovered. The small mirror fixed in the handle is then warmed, either by holding it over the lamp, or by putting it into a vessel of warm water; this is necessary to prevent the condensation of breath upon its surface. The degree of heat is regulated by applying the back of the mirror to the hand or cheek, when it should feel warm without being painful.



Fig. 348.—The larynx as seen from behind. To show the intrinsic muscles posteriorly. (Stoerk.)

After these preliminaries the patient is directed to put out his tongue, which is held by the left hand gently but firmly against the lower teeth by means of a handkerchief. The warm mirror is passed to the back of the mouth, until it rests upon and slightly raises the base of the uvula, and at the same time the light is directed upon it: an inverted image of the larynx and trachea will be seen in the mirror. If the dorsum of the tongue be alone seen, the handle of the mirror must be slightly lowered until the larynx comes into view; care should be taken, however, not to move the mirror upon the uvula, as it excites retching. The observation should not be prolonged, but should rather be repeated at short intervals.

The structures seen will vary somewhat according to the condition of the parts as to inspiration, expiration, phonation, etc.; they are (fig. 351) first, and apparently at the posterior part, the *base of the tongue*, immediately below ich is the accurate outline of the *epiglottis*, with its cushion or tubercle. n are seen in the central line the *true vocal cords*, white and shining in their mal condition. The cords approximate (in the inverted image) posteriorly;

between them is left a chink, narrow while a high note is being sung, wide during a deep inspiration. On each side of the true vocal cords, and on a higher level, are the pink *false vocal cords.* Still more externally than the



Fig. 349.—The parts of the Laryngoscope.

false vocal cords is the *aryteno-epiglottidean* fold, in which are situated up each side three small elevations; of these the most external is the *cartilage Wrisberg*, the intermediate is the *cartilage of Santorini*, while the summit the *arytenoid cartilage* is in front, and somewhat below the preceding, bei



Fig. 350.—To show the position of the operator and patient when using the Laryngoscope.

only seen during deep inspiration. The *rings of the trachea*, and even th bifurcation of the trachea itself, if the patient be directed to draw a deep breath may be seen in the interval between the true vocal cords.

## Movements of the Vocal Cords.

ı *Respiration.*—The position of the vocal cords in ordinary tran- breathing is so adapted by the muscles, that the opening of the is is wide and triangular (fig. 351, B) becoming a little wider at



. 351.—Three laryngoscopic views of the superior aperture of the larynx and surrounding *A*, the glottis during the emission of a high note in singing; B, in easy and quiet inha- of air; C, in the state of the widest possible dilatation, as in inhaling a very deep breath. agrams A′, B′, and C′, show in horizontal sections of the glottis the position of the vocal nts and arytenoid cartilages in the three several states represented in the other figures. he figures, so far as marked, the letters indicate the parts as follows, viz.: *l*, the base of gue; *e*, the upper free part of the epiglottis; *e′*, the tubercle or cushion of the epiglottis; t of the anterior wall of the pharynx behind the larynx; in the margin of the aryteno- tidean fold *w*, the swelling of the membrane caused by the cartilages of Wrisberg; *s*, that cartilages of Santorini; *a*, the tip or summit of the arytenoid cartilages; *c v*, the true ords or lips of the rima glottidis; *c v s*, the superior or false vocal cords; between them ntricle of the larynx; in C, *tr* is placed on the anterior wall of the receding trachea, ndicates the commencement of the two bronchi beyond the bifurcation which may be t into view in this state of extreme dilatation. (Quain after Czermak.)

inspiration, and a little narrower at each expiration. On making id and deep inspiration the opening of the glottis is widely dilated 351, C), and somewhat lozenge-shaped.

ı *Vocalization.*—At the moment of the emission of a note, it is nar- l, the margins of the arytenoid cartilages being brought into contact he edges of the vocal cords approximated and made parallel, at me time that their tension is much increased. The higher the note ced, the tenser do the cords become (fig. 351, A); and the range of a voice depends, of course, in the main, on the extent to which the degree of tension of the vocal cords can be thus altered. In the production of a high note the vocal cords are brought well within sight, so as to be plainly visible with the help of the laryngoscope. In the utterance of grave tones, on the other hand, the epiglottis is depressed and brought over them, and the arytenoid cartilages look as if they were trying to hide themselves under it (fig. 352). The epiglottis, by being somewhat pressed down so as to cover the superior cavity of the larynx, serves to render the notes deeper in tone and at the same time somewhat duller, just as covering the end of a short tube placed in front of caoutchouc tongues lowers the tone. In no other respect does the epiglottis appear to have any effect in modifying the vocal sounds.



Fig. 352.—View of the upper part of the larynx as seen by means of the laryngoscope during the utterance of a grave note. *c*, Epiglottis; *s*, tubercles of the cartilages of Santorini; *a*, arytenoid cartilages; *z*, base of the tongue; *ph*, the posterior wall of the pharynx. (Czermak.)

The degree of approximation of the vocal cords also usually corresponds with the height of the note produced; but probably not always, for the width of the aperture has no essential influence on the height of the note, as long as the vocal cords have the same tension: only with a wide aperture the tone is more difficult to produce and is less perfect, the rushing of the air through the aperture being heard at the same time.

No true vocal sound is produced at the posterior part of the aperture of the glottis, that, viz., which is formed by the space between the arytenoid cartilages. For if the arytenoid cartilages be approximated in such a manner that their anterior processes touch each other, but yet leave an opening behind them as well as in front, no second vocal tone is produced by the passage of the air through the posterior opening, but merely a rustling or bubbling sound; and the height or pitch of the note produced is the same whether the posterior part of the glottis be open or not.

## THE VOICE IN SINGING AND SPEAKING.

*Varieties of Vocal Sounds.*—The laryngeal notes may observe three different kinds of sequence. The first is the monotonous, in which notes have nearly all the same pitch as in ordinary speaking; variety of the sounds of speech being due to articulation in the mo n speaking, however, occasional syllables generally receive a higher ntonation for the sake of accent. The second mode of sequence is the ccessive transition from high to low notes, and *vice versâ*, without ntervals; such as is heard in the sounds, which, as expressions of pas- on, accompany crying in men, and in the howling and whining of ogs. The third mode of sequence of the vocal sounds is the musical, which each sound has a determinate number of vibrations, and the umbers of the vibrations in the successive sounds have the same relative oportions that characterize the notes of the musical scale.

In different individuals this comprehends one, two, or three octaves. singers—that is, in persons apt for singing—it extends to two or ree octaves. But the male and female voices commence and end at fferent points of the musical scale. The lowest note of the female ice is about an octave higher than the lowest of the male voice; the ghest note of the female voice about an octave higher than the highest the male. The compass of the male and female voices taken together, the entire scale of the human voice, includes about four octaves. e principal difference between the male and female voice is, therefore, their *pitch;* but they are also distinguished by their *tone*,—the male ce is not so soft. The voice presents other varieties besides that of le and female; there are two kinds of male voice, technically called *bass* and *tenor*, and two kinds of female voice, the *contralto* and *rano*, all differing from each other in tone. The bass voice usually ches lower than the tenor, and its strength lies in the low notes; ile the tenor voice extends higher than the bass. The contralto ce has generally lower notes than the soprano, and is strongest in the er notes of the female voice; while the soprano voice reaches higher the scale. But the difference of compass, and of power in different ts of the scale, is not the essential distinction between the different es; for bass singers can sometimes go very high, and the contralto uently sings the high notes like soprano singers. The essential erence between the base and tenor voices, and between the contralto soprano, consists in their *tone* or *timbre*, which distinguishes them when they are singing the same note. The qualities of the bary- e and mezzo-soprano voices are less marked; the *barytone* being in- ediate between the bass and tenor, the *mezzo-soprano* between the ralto and soprano. They have also a middle position as to pitch in scale of the male and female voices.

The differences in the pitch of the male and the female voices nds on the different length of the vocal cords in the two sexes; relative length in men and women being as three to two. The nce of the two voices in tone or timbre, is owing to the different and form of the resounding walls, which in the male larynx are much more extensive, and form a more acute angle anteriorly. different qualities of the tenor and bass, and of the alto and so voices, probably depend on some peculiarities of the ligaments, an membranous and cartilaginous parietes of the laryngeal cavity, are not at present understood, but of which we may form some by recollecting that musical instruments made of different mate *e.g.*, metallic and gut-strings, may be tuned to the same note, but each will give it with a peculiar tone or *timbre*.

The boy's larynx resembles the female larynx; their vocal before puberty are not two-thirds the length of the adult cords; the angle of their thyroid cartilage is as little prominent as i female larynx. Boys' voices are *alto* and *soprano*, resembling in those of women, but louder, and differing somewhat from them in But, after the larynx has undergone the change produced durin period of development at puberty, the boy's voice becomes bass or t While the change of form is taking place, the voice is said to *crac* becomes imperfect, frequently hoarse and crowing, and is unfitt singing until the new tones are brought under command by pra In eunuchs, who have been deprived of the testes before puberty, the does not undergo this change. The voice of most old people is det in tone, unsteady, and more restricted in extent: the first def owing to the ossification of the cartilages of the larynx and the condition of the vocal cords; the want of steadiness arises from the nervous power and command over the muscles; the result of w here, as in other parts, a tremulous movement. These two causes bined render the voices of old people void of tone, unsteady, bl and weak.

In any class of persons arranged, as in an orchestra, according character of voices, each would possess, with the general characte of a bass, or tenor, or any other kind of voice, some peculiar ch by which his voice would be recognized from all the rest. The tions that determine these distinctions are, however, quite unk They are probably inherent in the tissues of the larynx, and indiscernible as the minute differences that characterize men's fe one often observes, in like manner, hereditary and family peculi of voice, as well marked as those of the limbs or face.

Most persons, particularly men, have the power, if at all cap singing, of modulating their voices through a double series of n different character: namely, the notes of the natural voice, or *notes*, and the *falsetto notes*. The natural voice, which alone ha hitherto considered, is fuller, and excites a distinct sensation of stronger vibration and resonance than the falsetto voice, whic more a flute-like character. The deeper notes of the male voic be produced only with the natural voice, the highest with the falsetto only; the notes of middle pitch can be produced either with the natural or falsetto voice; the two registers of the voice are therefore not limited in such a manner as that one ends when the other begins, but they run in part side by side.

The natural or chest-notes are, as we have seen, produced by the ordinary vibrations of the vocal cords. The mode of production of the falsetto notes is still obscure.

By Müller they were thought to be due to vibrations of only the inner borders of the vocal cords. In the opinion of Petrequin and Diday, they do not result from vibrations of the vocal cords at all, but from vibrations of the air passing through the aperture of the glottis, which they believe assumes, at such times, the contour of the *embouchure* of a flute. Others, considering some degree of similarity which exists between the falsetto notes and the peculiar tones called harmonic, which are produced when, by touching or stopping a harp-string at a particular point, only a portion of its length is allowed to vibrate, have supposed that, in the falsetto notes, portions of the cords are thus isolated, and made to vibrate while the rest are held still. The question cannot yet be settled; but any one in the habit of singing may assure himself, both by the difficulty of passing smoothly from one set of notes to the other, and by the necessity of exercising himself in both registers, lest he should become very deficient in one, that there must be some great difference in the modes in which their respective notes are produced.

The *pitch of the note*, which depends upon the rapidity of the vibrations, is altered by alterations of the vocal cords, and so the strength of the voice is in proportion (*a*) to the degree to which the vocal cords can be made to vibrate; and partly (*b*) to the fitness for resonance of the membranes and cartilages of the larynx, of the parietes of the thorax, lungs, and cavities of the mouth, nostrils, and communicating sinuses. It is diminished by anything which interferes with such capability of vibration.

The *intensity or loudness* of a given note with maintenance of the same pitch, cannot be rendered greater by merely increasing the force of the current of air through the glottis; for increase of the force of the current of air, *cæteris paribus*, raises the pitch both of the natural and the falsetto notes. Yet, since a singer possesses the power of increasing the loudness of a note from the faintest *piano* to *fortissimo* without its pitch being altered, there must be some means of compensating the tendency of the vocal cords to emit a higher note when the force of the
nt of air is increased. This means evidently consists in modify-
the tension of the vocal cords. When a note is rendered louder
more intense, the vocal cords must be relaxed by remission of the

muscular action, in proportion as the force of the current of the breath through the glottis is increased. When a note is rendered fainter, the reverse of this must occur.

The arches of the palate and the uvula become contracted during the formation of the higher notes; but their contraction is the same for a note of given height, whether it be falsetto or not; and in either case the arches of the palate may be touched with the finger, without the note being altered. Their action, therefore, in the production of the higher notes seems to be merely the result of involuntary associate nervous action, excited by the voluntarily increased exertion of the muscles of the larynx. If the palatine arches contribute at all to the production of the higher notes of the natural voice and the falsetto, it can only be by their increased tension strengthening the resonance.

The office of the ventricles of the larynx is evidently to afford a free space for the vibrations of the lips of the glottis; they may be compared with the cavity at the commencement of the mouthpiece of trumpets, which allows the free vibration of the lips.

**Speech.**—Besides the musical tones formed in the larynx, a great number of other sounds can be produced in the vocal tubes, between the glottis and the external apertures of the air-passages, the combination of which sounds by the agency of the cerebrum into different groups to designate objects, properties, actions, etc., constitutes language. The languages do not employ all the sounds which can be produced in this manner, the combination of some with others being often difficult. Those sounds which are easy of combination enter, for the most part, into the formation of the greater number of languages. Each language contains a certain number of such sounds, but in no one are all brought together. On the contrary, different languages are characterized by the prevalence in them of certain classes of these sounds, while others are less frequent or altogether absent.

**Articulate Sounds.**—The sounds produced in speech, or the articulate sounds, are commonly divided into *vowels* and *consonants:* the distinction between which is, that the sounds for the former are generated by the larynx, while those for the latter are produced by interruption of the current of air in some part of the air-passages above the larynx. The term consonant has been given to these because several of them are not properly sounded, except *consonantly with* a vowel. Thus, if it be attempted to pronounce aloud the consonants **b**, **d**, and **g**, or their modifications, **p**, **t**, **k**, the intonation only follows them in their combination with a vowel. To recognize the essential properties of the articulate sounds, it is necessary first to examine them as they are produced in whispering, and then investigate which of them can also be uttered in a modified character conjoined with vocal tone. By this procedure we l two series of sounds: in one the sounds are mute, and cannot be ered with a vocal tone; the sounds of the other series can be formed ependently of voice, but are also capable of being uttered in con- ction with it.

All the vowels can be expressed in a whisper without *vocal tone*, that *mutely*. These mute vowel-sounds differ, however, in some meas- , as to their mode of production, from the consonants. All the te consonants are formed in the vocal tube above the glottis, or in cavity of the mouth or nose, by the mere rushing of the air between surfaces differently modified in disposition. But the sound of the vels, even when mute, has its source in the glottis, though its vocal ds are not thrown into the vibrations necessary for the production of ce; and the sound seems to be produced by the passage of the current ir between the relaxed vocal cords. The same vowel-sound can be pro- ed in the larynx when the mouth is closed, the nostrils being open, l the utterance of all vocal tone avoided. The sound, when the mouth pen, is so modified by varied forms of the oral cavity, as to assume characters of the vowels **a**, **e**, **i**, **o**, **u**, in all their modifications.

The cavity of the mouth assumes the same form for the articulation each of the mute vowels as for the corresponding vowel when vocal- l; the only difference in the two cases lies in the kind of sound itted by the larynx. It has been pointed out that the conditions essary for changing one and the same sound into the different vowels, differences in the size of two parts—the oral canal and the oral open- g; and the same is the case with regard to the mute vowels. By oral nal, is meant here the space between the tongue and palate: for the onunciation of certain vowels both the opening of the mouth and the ace just mentioned are widened; for the pronunciation of other vowels th are contracted; and for others one is wide, the other contracted. lmitting five degrees of size, both of the opening of the mouth and of e space between the tongue and palate, Kempelen thus states the mensions of these parts for the following vowel-sounds:—

| Vowel. | | Sound. | Size of oral opening. | Size of oral canal. |
|---|---|---|---|---|
| **a** | as in | "far" | 5 | 3 |
| **a** | " | "name" | 4 | 2 |
| **e** | " | "theme" | 3 | 1 |
| **o** | " | "go" | 2 | 4 |
| **oo** | " | "cool" | 1 | 5 |

Another important distinction in articulate sounds is, that the utter- e of some is only of momentary duration, taking place during a sud- change in the conformation of the mouth, and being incapable of longation by a continued expiration. To this class belong **b**, **p**, **d**, the hard **g**. In the utterance of other consonants the sounds may continuous; they may be prolonged, ad libitum, as long as a particu- disposition of the mouth and a constant expiration are maintained.

Among these consonants are **h, m, n, f, s, r, l.** Corresponding differences in respect to the time that may be occupied in their utterance exist in the vowel sounds, and principally constitute the differences of long and short syllables. Thus the **a** as in **far** and **fate,** the **o** as in **go** and **fort,** may be indefinitely prolonged; but the same vowels (or more properly different vowels expressed by the same letters), as in **can** and **fact,** in **dog** and **rotten,** cannot be prolonged.

All sounds of the first or explosive kind are insusceptible of combination with vocal tone (*intonation*), and are absolutely mute; nearly all the consonants of the second or continuous kind may be attended with intonation.

*Ventriloquism.*—The peculiarity of speaking, to which the term ventriloquism is applied, appears to consist merely in the varied modification of the sounds produced in the larynx, in imitation of the modifications which voice ordinarily suffers from distance, etc. From the observations of Müller and Colombat, it seems that the essential mechanical parts of the process of ventriloquism consist in taking a full inspiration, then keeping the muscles of the chest and neck fixed, and speaking with the mouth almost closed, and the lips and lower jaw a motionless as possible, while air is very slowly expired through a very narrow glottis; care being taken also, that none of the expired air passes through the nose. But, as observed by Müller, much of the ventriloquist's skill in imitating the voices coming from particular directions, consists in deceiving other senses than hearing. We never distinguish very readily the direction in which sounds reach our ear; and, when our attention is directed to a particular point, our imagination is very apt to refer to that point whatever sounds we may hear.

*Action of the Tongue in Speech.*—The tongue, which is usually credited with the power of speech—language and speech being often employed as synonymous terms—plays only a subordinate, although very important part. This is well shown by cases in which nearly the whole organ has been removed on account of disease. Patients who recover from this operation talk imperfectly, and their voice is considerably modified; but the loss of speech is confined to those letters in the pronunciation of which the tongue is concerned.

*Stammering* depends on a want of harmony between the action the muscles (chiefly abdominal) which expel air through the larynx, an that of the muscles which guard the orifice (rima glottidis) by which escapes, and of those (of tongue, palate, etc.) which modulate the soun to the form of speech.

Over either of the groups of muscles, by itself, a stammerer m have as much power as other people. But he cannot harmonious arrange their conjoint actions.

# CHAPTER XVI.

## THE NERVOUS SYSTEM.

THE nervous system consists of the following parts: firstly, of large ses of nervous matter situated within the bony cranium and spinal mn, and constituting the brain and spinal cord; secondly, of ller masses of nervous matter, situated for the most part in the minal and thoracic cavities, but also in the neck and head, and stituting what are known as sympathetic ganglia; thirdly, of cords erve-fibres which connect the central nervous system with the phery and with the so-called sympathetic ganglia, which are not in ity a system independent of the brain and cord as was formerly ght, but are really part and parcel of the same system; and fourthly, eripheral organs in connection with the beginnings or endings of the ves at the periphery of the body.

It will be necessary to consider these several parts of the nervous system atim; it will be most useful for the understanding of the subject, ever, to proceed first of all with the consideration of the properties erve-fibres, as this forms the most elementary portion of the subject.

*Nerve-fibres.*—The structure of the different kinds of nerve-fibres been already dealt with (p. **91**, *et seq.*); their function remains to be idered here.

### FUNCTION OF NERVE-FIBRES.

The office of nerve-fibres is to conduct impressions. From the ount of nervous action previously given (p. 543 *et seq.*) it will be dily understood, that nerve-fibres may be stimulated to act by anyng which, with sufficient suddenness, increases their irritability; y are incapable of originating of themselves the condition necessary the manifestation of their own energy. The stimulus produces its ct upon the termination of the nerve stimulated, being conducted to y the nerve-fibre. The effect of the stimulus upon a nerve therefore nds upon the nature of its end-organ. Normally, within the body, e impulses pass in two directions: (1) away from the cell body of neuron over its axon, and (2) toward the cell body over its dendron endrite. Those neurons which bring the cerebro-spinal axis into tion with the periphery may be divided into two classes: (*a*) those ch carry impulses from the central nervous mass toward the periphery, efferent or centrifugal, and (*b*) those which carry impulses to the central nervous mass from the periphery, afferent or centripetal. Ordinarily, centrifugal impulses originate in the cell body of the neuron. Centripetal impulses originate at the peripheral nerve-ending of the afferent nerve. The same nerve-fibre will carry effective impulses in one direction only, although, when a nerve is irritated anywhere along its trunk, impulses, as shown by electric changes, are propagated in both directions over the axis cylinder and its branches. The direction of effective conduction is probably determined by the nature of the end-organ.

Those neurons which lie entirely within the cerebro-spinal axis and which have no direct connection with the periphery are known as intra-central neurons. They serve to bring into relation various cell groups, in the cerebro-spinal axis, with one another.

Impressions made upon the terminations or upon the trunk of a *centripetal* nerve may cause (*a*) pain, or some other kind of sensation; (*b*) special sensation; or (*c*) reflex action of some kind; or (*d*) inhibition, restraint of action. Similarly impressions made upon a *centrifugal* nerve may cause (*a*) contraction of muscle (motor nerve); (*b*) it may influence nutrition (trophic nerve); or (*c*) may influence secretion (secretory nerve); or (*d*) inhibit, augment, or stop any other efferent action.

It is a law of action in all nerve-fibres, and corresponds with the continuity and simplicity of their course, that an impression made on any fibre is simply and uninterruptedly transmitted along it, without itself being imparted or diffused to any of the fibres lying near it. Although it has been supposed by some that the myelin sheath of the nerve-fibre acts as an insulator of the axis cylinder, this can be looked upon, perhaps, only as an additional protection, since a large class of nerve-fibres is devoid of medullation. It must therefore be an inherent property of the nerve-fibre, itself, to carry impulses, without transmission to adjacent fibres.

*Velocity of a Nervous Impulse.*—The change which a stimulus sets up in a nerve, of the exact nature of which we are unacquainted, appears to travel along a nerve-fibre in both directions with considerable velocity in the form of a wave. Helmholtz and Baxt have estimated the average rate of conduction in human motor nerves at 111 feet (nearly 29 metres) per second; this result agreeing very closely with that previously obtained. It is probably rather under than over the average velocity. Rutherford's observations agree with those of Von Wittich, that the rate of transmission in sensory nerves is about 140 feet (42 metres) per second.
velocity of the nerve impulse in motor nerves has been calculated by no
ing the duration of the interval between two contractions of the s

uscle when stimulated by means of two pairs of electrodes, one placed hind the nerve close to the muscle, and the second placed at a known stance further away from the muscle. The contraction ensues when e stimulus is applied farther from the muscle later than the other se, and the interval between the two contractions is occupied by the ssage of the impulse down the nerve. With these data it is concluded at the velocity of the passage of the nerve impulse in a frog's motor erve is 28 to 30 metres per second. In the human motor nerve, calulated by applying the stimulus through the skin instead of directly the nerve, the velocity is greater, viz., about 33 to 50 metres per econd. In sensory nerves the velocity is said to be about 30 to 33 etres per second. Various conditions modify the rate of transmission, which *temperature* is one of the most important, a very low or a very igh temperature diminishing it; *fatigue* of the nerve acting in the me direction, but *increase of the stimulus* up to a certain point increasg it, as does also the *katelectrotonic* condition of the nerve.

*The Cerebro-Spinal Nervous System.*—The parts of which this sys- m is composed are the following: (*a*) the spinal cord and its nerves; ) the brain made up of cerebrum, crura cerebri and the ganglia in con- ction with them, pons varolii, cerebellum, and the medulla oblongata bulb which connects the upper parts of the system with the spinal rd, or medulla spinalis.

All of these parts of the nervous system are nerve-centres, in contra- stinction to nerve-trunks, and differ from the nerves in being made up nerve-cells and their branchings as well as of nerve-fibres. As now nceived, the nerve-centres are composed of neurons, while the nerve- nks are made up of the neuraxons with their various terminals. (See 91 *et seq.*) There are other ganglia besides these, distributed elsewhere d not within the cranium and spinal column, but these are, for the e of convenience, considered apart, under the head of the sympathetic tem, as they present some differences to the more central ganglia.

The cerebro-spinal centres then are distinguished from mere nerve- nks by the possession of nerve-cells; these are, as we have seen in a mer chapter (p. 99 *et seq.*), of different kinds; they very possibly er in function. It is, however, to the possession of ganglion-cells t the increase of the functions of nerve-centres over that of nerve- nks is credited. Before turning to the discussion of the functions the spinal cord it will be as well to devote a little time therefore to question of the functions of the nerve-centres in general. The glia of the sympathetic system also contain nerve-cells, but to these supposed a different use is to be assigned, and what is said as to the ctions of nerve-ganglia in this place is only to be applied to those he cerebro-spinal centres.

### Functions of Nerve-centres.

**Reflex Action.**—From a physiological point of view, it may b considered necessary that before a nerve-cell can send out a nerve i pulse it must first receive a stimulus of some kind. This stimul usually consists of an afferent impulse from the periphery. Its effe upon the receiving-cell may be insufficient to cause any response, or t response may be delayed for a long period and may involve many complicated nervous activities, and even psychological processes. Where the response is approximately immediate, the reaction is known as a reflex.



Fig. 353.—Schematic sketch of a reflex arc; *A*, with two neurons, an afferent and an efferent; with three neurons, an afferent, efferent, and a connecting or intracentral neuron.

A reflex, reduced to its simplest terms, consists of the following elements: (*a*) a sensory surface; (*b*) an afferent neuron; (*c*) an efferent neuron; (*d*) a muscle or gland. These associated elements form what is known as the **reflex arc.** The simplest form of reflex arc is schematically shown in figs. 353, 354.



Fig. 354.—Showing the arra ment of a simple reflex mech ism composed of a motor and s sory neuron. *sq.* Posterior sp ganglion; *s*, and *sth*, sensory r *m*, motor nerve cell; *mw*, m root.

The gap between the termination of the afferent neuron and the dendron of the efferent neuron shown in fig. 353 is called a *synapsis.* The reflex arc is probably seldom as simple as that shown in fig. 354, where only two neurons are involved. More often, three or more neurons take part, as shown in figs. 353, 355.

The neuron connecting the afferent neuron with the efferent neuron belongs to the class of intracent or connecting neurons. Since all parts of the cerebro-spinal a ectly connected with one another by intracentral neurons, the y of increasing the number of efferent limbs of the reflex be readily understood. The transmission of impulses with-brain and cord, however, occurs over the pathways of least e. Increasing the number of synapses, or the number of links in the chain of conduction, increases the resistance, reflexes will occur most readily, other conditions being equal, he least number of neurons is involved. In addition to the of synapses in the reflex arc, other factors are of importance nining reflex reaction; *e.g.*, the intensity of the exciting stimu-quality of the stimulus, the rapidity of the recurrence of the , and the duration of its application. Thus, a strong stimulus ng about a reflex reaction sooner than a weak stimulus of the nd. A single weak stimulus which will cause no reflex may do n enough and rapidly enough repeated. This is known as the *n of stimuli.*

lex act once started may continue for some time after the ex-ause has been removed. The same phenomenon is observed



iowing the arrangement of the reflex mechanism, with a neuron intercalated between the sensory and motor neurons.

oups of nerve-cells are stimulated directly. It has been found ving electrical changes in nerve-fibres, by means of the capillary eter, that when their cells of origin are stimulated they dis-mpulses in a rhythmical manner at the rate of 6 to 10 per

lly, impulses are transmitted to a nerve-cell only over its den-ut it must be also assumed that such a conveyance of impulses place over the collaterals of its axone, near the cell body. In this case the axone, with its collateral, acts as a *double pathway*, conducting impulses both centrifugally and centripetally. The peripheral axone of the spinal ganglion nerve-cell, although it has the structure of a neuraxone, may be looked upon both phylogenetically and physiologically as a dendron, since homologues in lower vertebrates and in man himself (olfactory nerve-cells) have this structure, the nerve-cell body being situated near the sensory surface from which impressions are received.

*Diffusion of impulses within the cord.*—Taking a frog whose brain has been destroyed as an example, a simple reflex may be demonstrated by irritating the skin of one foot with a weak stimulus. In response to such a stimulus the foot is flexed upon the leg, due to a contraction of the muscles corresponding to the sensory surface irritated. If the strength or duration of the stimulus be increased, other groups of muscles are involved in the following order: (1) Those of the leg and thigh of the same side; (2) homologous muscles of the opposite side; (3) arm of the opposite side; (4) arm of the same side. This is due to an overcoming of resistance in other reflex pathways, and the afferent impulses are said to be *diffused* within the cord.

Involvement of multiple pathways may also be accomplished through decreasing the resistance within the cord, as through the use of some drug such as strychnine. Under these circumstances a slight stimulus may bring about multiple and violent reflex spasms. The decrease in resistance may be due to a decrease in the resistance at the synapses, and possibly also to an increase in the irritability of the discharging nerve-cells. We must also suppose that the centres are particularly sensitive to certain kinds of stimuli, sometimes producing very extensive and violent muscular actions in response to a slight stimulus of a special kind. Such a condition is illustrated in the violent and general muscular spasms occurring when a small particle of food passes into the larynx, violent expiratory spasms accompanied by contractions of other muscles taking place.

The time taken in a reflex action has been found to be .066 to .058 second, but this is only a rough and arbitrary estimation.

**Automatism.**—A second function which appears to be possessed by certain nerve-centres and not by others is that of automatic action or automatism. By this is meant that it is not dependent for its discharge upon any afferent stimuli, but that it is capable of sending out of itself efferent impulses of various kinds. The centre may be supposed to do this by the nature of its own metabolism, anabolism or building up of the explosive substance being followed by katabolism or its discharge. So that the centre sends out its impulses to muscles rhythmically. Such a power of automatism we have seen is attributed to the respiratory centres in the bulb. In this connection it must be remembered that the term automatism is simply a relative one, and that some kind of a stimulus is necessary to cause a nerve-cell to discharge impulses.

**Inhibition and Augmentation.**—Not only may movements of muscles, discharge of secretion from gland-cells and the like be produced by afferent impulses reaching nerve-centres, but also inhibition of action which is already taking place. This is well seen in the matter of the inhibitory action of the vagus upon the cardiac contractions. The vagi convey to the heart impulses from the cardio-inhibitory centres which have a restraining action upon the contractions of the heart, as is seen by the increase in the frequency of the heart-beats when the vagi are divided; but we have seen that appropriate afferent stimuli, as, for example, when applied to the abdominal sympathetic, may increase the action of the centre to such an extent that the heart may be altogether stopped in diastole. In such a case the result of the afferent stimuli upon the centre has been to produce complete inhibition and not muscular contraction. This is not the only example of inhibition which might be instanced; the action of almost any centre may be inhibited by impulses reaching it; indeed the effect of afferent impulses upon a centre may be not only not to set it into activity, but to prevent or stop an action already going on. On the other hand, the action of afferent impulses upon a nerve-centre may be to **augment,** render more powerful or extensive, and increase in a certain direction an action already in course. Such may be well illustrated by the action of the vagi upon the respiratory centres to which attention has been drawn in the chapter upon respiration.

**Membranes of the Brain and Spinal Cord.**—The Brain and Spinal Cord are enveloped in three membranes—(1) the Dura Mater, (2) the Arachnoid, (3) the Pia Mater.

(1) The *Dura Mater*, or external covering, is a tough membrane composed of bundles of connective-tissue which cross at various angles, and in whose interstices branched connective-tissue corpuscles lie: it is lined by a thin elastic membrane, and on the inner surface and where it is not adherent to the bone, on the outer surface also is a layer of endothelial cells very similar to those found in serous membranes. (2.) The *Arachnoid* is a much more delicate membrane, very similar in structure to the dura mater, and lined on its outer or free surface by an endothelial membrane.

(3.) The *Pia Mater* consists of two chief layers, between which numerous blood-vessels ramify. Between the arachnoid and pia mater is a network of fibrous-tissue trabeculæ sheathed with endothelial cells: these sub-arachnoid trabeculæ divide up the sub-arachnoid space into a number of irregular sinuses. There are some similar trabeculæ, but much fewer in number, traversing the sub-dural space, i.e., the space between the dura mater and arachnoid.

*Cerebro-spinal fluid* occupies the sub-arachnoid space. Its quantity varie cording to age, and its principal use seems to be that of a cushion to protect the bro-spinal axis from jar. It is transparent, colorless, non-viscid, having a saline



Fig. 356.—View of the cerebro-spinal axis of the nervous system. The right half cranium and trunk of the body has been removed by a vertical section; the membranes brain and spinal cord have also been removed, and the roots and first part of the fifth and cranial, and of all spinal nerves of the right side, have been dissected out and laid separate the wall of the skull and on the several vertebræ opposite to the place of their natural exi the cranio-spinal cavity. (After Bourgery.)

and alkaline reaction, and is not affected by heat or acids. It contains 981 parts of water, NaCl; traces of KCl, sulfates, carbonates, alkaline and hosphates, minute traces of urea, sodium lactate, fatty matter, cholesterin, and bumen. (Flint.)

*Pacchionian* bodies are growths from the sub-arachnoid network of connec- ve-tissue trabeculæ which project through small holes in the inner layers of e dura mater into the venous sinuses of that membrane. The venous sinuses the dura mater have been injected from the sub-arachnoidal space through e intermediation of these villous outgrowths.

## The Spinal Cord and its Nerves.

The Spinal cord is a cylindriform column of nerve-substance con- cted above with the brain through the medium of the bulb, and ter- inating below, about the lower border of the first lumbar vertebra, in a nder filament of gray substance, the *filum terminale*, which lies in the idst of the roots of many nerves forming the *cauda equina*.

*Structure.*—The cord is composed of white and gray nervous sub- ance, of which the former is situated externally, and constitutes its chief rtion, while the latter occupies its central or axial portion, and is so ranged, that on the surface of a transverse section of the cord it pears like two somewhat crescentic masses connected together by a rrower portion or isthmus (fig. 357). Passing through the centre of is isthmus in a longitudinal direction is a minute canal (central nal), which is continued through the whole length of the cord, and ens above into the space at the back of medulla oblongata and pons rolii, called the fourth ventricle. It is lined by a layer of columnar iated epithelium.

The spinal cord consists of two exactly symmetrical halves, separated teriorly and posteriorly by vertical *fissures* (the posterior fissure being eper, but less wide and distinct than the anterior), and united in the ddle by nervous matter which is usually described as forming two mmissures—an *anterior* commissure, in front of the central canal, nsisting of medullated nerve-fibres, and a *posterior* commissure behind e central canal consisting also of medullated nerve-fibres, but with re neuroglia, which gives the gray aspect to this commissure. The res of the commissures are mainly composed of collaterals. Each lf of the spinal cord is marked on the sides (obscurely at the lower rt, but distinctly above) by two longitudinal furrows, which divide it o three portions, columns, or tracts, an *anterior*, *lateral*, and *posterior*. om the groove between the anterior and lateral columns spring the *terior roots* of the spinal nerves (4); and just in front of the groove tween the lateral and posterior columns arise the *posterior roots* of the ne; a pair of roots on each side corresponding to each vertebra.

**White Matter.**—The white matter of the cord is seen to be de up of medullated nerve-fibres, of different sizes, arranged longitudinally, and of a supporting material of two kinds, viz.:—(*a*) ordinary fibrous connective tissue with elastic fibres, which is connected with septa from the pia mater which pass into the cord to carry the blood vessels. (*b*) Neuroglia; this material is made up of the branching cells (fig. 359), the bodies of which, in consequence of the high development of the branchings, are small. The processes of the neuroglia-cells are arranged so as to support the nerve-fibres which are without the usual external nerve sheaths. Neuroglia was formerly considered to be a kind of connective tissue, but is now considered to be a distinct material.



Fig. 357.—Horizontal section of the cord and its envelopes, at the middle of a vertebral body (Schematic). 1, Spinal cord with 2, its anterior median fissure; 3, its posterior median fissure; 4, anterior roots; 5, posterior roots; 6, pia mater (in red); 7, ligamentum dentatum; 8, connecting fibres passing from the pia to dura mater; 9, visceral layer and 9′, parietal layer of the arachnoid (in blue); 10, subarachnoid space; 11, arachnoid cavity; 12, dura mater (in yellow); 13, periosteum; 13′, external periosteum; 14, cellular tissue situated between the dura mater and the wall of the vertebral canal; 15, common posterior vertebral ligament; 16, intra-spinal veins; 17, vertebra in section. (Testut.)

It is derived from the neural epiblast, and yields neuro-keratin. (See p. 107.)

The general rule respecting the size of different parts of the cord appears to be, that each part is in direct proportion in this respect to the size and number of nerve-roots given off from it, and has but little relation to the size or number of those given off below it. Thus the cord is very large in the middle and lower part of its cervical portion, whence arise the large nerve-roots for the formation of the brachial plexuses and the supply of the upper extremities, and again enlarges at the lowest f its dorsal portion and the upper part of its lumbar, at the origins large nerves which, after forming the lumbar and sacral plexuses, stributed to the lower extremities. The chief cause of the greater t these parts of the spinal cord is increase in the quantity of gray r; for there seems reason to believe that the white part of the becomes gradually and progressively larger from below upward, less from the addition of a certain number of upward passing from each pair of nerves.



358.—From the lower lumbar cord of man, after a preparation by Klönne and Müller, of No. 11,153), stained by Weigert and Pal's method. A portion of the gray substance of the cornu with the adjoining portions of the lateral column is represented, showing anterior ls and the fine medullated fibres which enter the gray substance from the lateral column round the nerve-cells, which here are provided with fine pigmented granules. High power. er.)

rom careful estimates of the number of nerve-fibres in a transverse n of the cord toward its upper end, and the number entering or g from it by the anterior and posterior roots of each pair of nerves, s been shown that in the human spinal cord not more than half total number of nerve-fibres of all the spinal nerves are contained ransverse section near its upper end. It is obvious, therefore, that st half of the nerve-fibres entering it must terminate somewhere in rd itself.

tudinally, and of a supporting material of two kinds, viz.:—(*a*) ordinary fibrous connective tissue with elastic fibres, which is connected with septa from the pia mater which pass into the cord to carry the blood vessels. (*b*) Neuroglia; this material is made up of the branching cells (fig. 359), the bodies of which, in consequence of the high development of the branchings, are small. The processes of the neuroglia-cells are arranged so as to support the nerve-fibres which are without the usual external nerve sheaths. Neuroglia was formerly considered to be a kind of connective tissue, but is now considered to be a distinct material.



Fig. 357.—Horizontal section of the cord and its envelopes, at the middle of a verte (Schematic). 1, Spinal cord with 2, its anterior median fissure; 3, its posterior me 4, anterior roots; 5, posterior roots; 6, pia mater (in red); 7, ligamentum dentatum; ing fibres passing from the pia to dura mater; 9, visceral layer and 9', parietal arachnoid (in blue); 10, subarachnoid space; 11, arachnoid cavity; 12, dura mater periosteum; 13', external periosteum; 14, cellular tissue situated between the dura wall of the vertebral canal; 15, common posterior vertebral ligament; 16, intra-vertebra in section. (Testut.)

It is derived from the neural epiblast, and yields neuro-kerati 107.)

The general rule respecting the size of different par appears to be, that each part is in direct proporti size and number of nerve-roots given off from tion to the size or number of those given off very large in the middle and lower arise the large nerve-roots for the f the supply of the upper extremiti part of its dorsal portion and [illegible] f the large nerves which, [illegible] re distributed to the lower [illegible] ze at these parts of the spinal [illegible] atter; for there seems [illegible] rd becomes gradually and [illegible] ubtless from the addition [illegible] es from each pair of nerves.



—From the lower [illegible] 1,1871, stained [illegible] with the [illegible] d the fine [illegible] the nerve-[illegible] ts of the white gray matter. 7. [illegible] eneration. Semi-

careful [illegible] the [illegible] om it [illegible] viz., the posterior [illegible] rough it, (i.) in con- [illegible] ection it is consider- [illegible] matter with it, and called [illegible] formation. of the posterior [illegible] ated at the base and me- [illegible] ed of fairly large cells, fusi- [illegible] vesicular column, or Clarke's [illegible] ar to the lower cervical region. [illegible] er, midway between the anterior [illegible] lls, known as the *cells of the lateral* spindle-shaped, and are more or less

**The gray matter** of the spinal-cord consists of numerous groups of nerve-cells, of a close meshwork of medullated fibres, most of which ar very fine and delicate, and of an extremely delicate network of axis-cylinders. This latter fine plexus has been called "Gerlach's network." Mingled with it and supporting it, is the meshwork of the neuroglia, which is finer even, in its structure, than that of the nerve-tissue, s that except under proper staining and illumination, it may app granular. This is especially developed around the central canal, whi is lined with columnar ciliated epithelium, the cells of which at th outer end terminate in fine processes, which join the neurogliar network surrounding the canal, and form the *substantia gelatinosa centralis.*



Fig. 259.—Different types of neuroglia cells. (After v. Gehuchten.) *b*, Neuroglia cells of th white substance, and *c*, of the gray substance of the cord of an embryo calf.

Neuroglia was formerly thought to be mainly present in the tip of th posterior cornu of gray matter, forming what is known as the *substan gelatinosa lateralis* of Rolando, through which the posterior nerve-ro pass. This is now known to be composed of very small nerve-cells a their processes.

*Groups of cells in gray matter.*—The multipolar cells are either sc tered singly or arranged in groups, of which the following are to be di tinguished on either side—certain of the groups being more or l marked in all of the regions of the cord, viz., those (*a*) in the anteri cornu, (*b*) those in the posterior cornu, and (*c*) intrinsic cells distribut throughout the gray matter.

(*a*) The cells in the anterior cornu are large and branching, a gives rise to an axis-cylinder process which passes out in the ior nerve-root. These cells are everywhere conspicuous, but are ularly numerous in the cervical and lumbar enlargements. In these cts they may be divided into several groups—(i.) a group of large lose to the tip of the inner part of the anterior cornu—all the cells anterior cornu in the dorsal or thoracic region are said to belong is group; (ii.) several lateral groups (2, *a*, *b*, and *c*, fig. 361) on ter side of the gray matter, and (iii.) a certain number of cells at se of the inner part of the anterior cornu particularly well marked thoracic region. (*b*) Cells of the posterior cornu—these are not rous; they are small and branched, and each has an axis-cylinder



360.—Section of spinal cord, one half of which (left) shows the tracts of the white and the other half (right) shows the position of the nerve cells in the gray matter. 7, d 3 are tracts of descending degeneration, 1, 4, 6 and 8, of ascending degeneration. Semi-matic. (After Sherrington.)

s passing off; but these processes do not pass into the posterior roots. The groups are two at least in number, viz., (i.) in con-n with the edge of the gray matter externally, where it is consider-roken up by the passage of bundles of fibres through it, and called *teral reticular formation;* and (ii.) in connection with a similar lar formation, more at the tip of the gray matter of the posterior ; this is known as the *posterior reticular formation.*

group of cells (No 3, fig. 360) is situated at the base and me-ide of the posterior cornu. It is formed of fairly large cells, fusi-in shape, and constitutes the posterior vesicular column, or Clarke's n. It extends from the upper lumbar to the lower cervical region. e outer portion of the gray matter, midway between the anterior osterior cornua, is a group of cells, known as the *cells of the lateral olumn.* These are small and spindle-shaped, and are more or less marked in the lumbar region, as well as in the thoracic region (No. 5, fig. 360).

(*c*) Besides these groups, which have their names largely on account of their location, there are distributed throughout the gray matter a very large number of other cells, which are known as *intrinsic cells*. These send out neuraxons which pass into the white matter of the same or the opposite side, pass up and down the cord, enter the gray matter again, and connect there by their end-brushes with cells at a different level of the cord. The intrinsic cells are, therefore, in the main, commissural in their function, that is to say, they unite the two sides or different levels of the cord. They are also, themselves, in relation with the fibres and cells of the anterior and posterior cornua.

*Columns and tracts in the white matter of the spinal cord.*—In addition to the columns of the white matter which are marked out by the points from which the nerve-roots issue, and which are the *anterior*, the *lateral* and *posterior*, the posterior is further divided by a septum of the pia mater into two almost equal parts, constituting the *postero-external* column, or *column of Burdach* (fig. 361, 2), and the *postero-median*, or *column of Goll* (fig. 361, 1). In addition to these columns, however, it has been shown that the white matter can be still further subdivided. This subdivision has been accomplished by evidence of several kinds, that the parts or, as they are called, tracts in the white matter, perform different functions in the conduction of impulses.

The methods of observation are the following:—

(*a*) The *embryological* method. It has been found that if the development of the spinal cord be carefully observed at different stages that certain groups of the nerve-fibres put on their myelin sheath at earlier periods than others, and that the different groups of fibres can therefore be traced in various directions. This is known as the method of Flechsig.

(*b*) *Wallerian or degeneration method.*—This method depends upon the fact that if a nerve-fibre is separated from its nerve-cell, it wastes or degenerates. It consists in tracing the course of tracts of degenerated fibres, which result from an injury to any part of the central nervous system. When fibres degenerate below a lesion the tract is said to be of *descending degeneration*, and when the fibres degenerate in the opposite direction the tract is one of *ascending degeneration*. By modern methods of staining of the central nervous system it has proved comparatively easy to distinguish degenerated parts in sections of the cord and of other portions of the central nervous system. Degenerated fibres have a different staining reaction when the sections are stained by what are called Weigert's and Marchi's methods. Accidents to the central nervous system in man have given us much information this subject, but this has of late years been supplemented and la extended by the experiments on animals, particularly upon mon d considerable light has been by these means shed upon the conduction impulses to and from the nervous system by the study of the results of tion of different parts of the central nervous system, and of the spinal rve-roots. Thus we have not only embryological evidence mapping t different tracts, but also confirmatory pathological and experimental servations.

The tracts which have been made out are the following:—

**(a) Of descending degeneration.**

(i.) *The crossed pyramidal tract* (fig. 360,7).—This tract is situated the outer part of the posterior cornu of gray matter. It is found oughout the whole length of the spinal cord; at the lower part it ex- ds to the margin of the cord, but higher up it becomes displaced m this position by the interpolation of another tract of fibres, to be sently described, viz., the direct cerebellar tract. The crossed amidal tract is large, and may touch the tip of gray matter of the terior cornu, but is separated from it elsewhere. In shape on cross- tion it is somewhat like a lens, but varies in different regions of the d, and diminishes in size from the cervical region downward. e tract is particularly well marked out, both by the degeneration and embryological methods. The fibres are supposed to pass off as they cend, and to join the various local nervous mechanisms of nerve cells their branchings which are represented in the cord. The tract of eneration may be traced upward beyond the cord, in a way to be sently described. The fibres of which this tract is composed are derately large, but are mixed with some that are smaller.

(ii.) *The direct or uncrossed pyramidal tract* (fig. 360, 10).—This ct is situated in the anterior column by the sides of the anterior ure. It is smaller than (i.), and is not present in all animals, ugh conspicuous in the human cord and in that of the monkey. It n be traced upward to the cerebral cortex, and downward as far as e mid or lower thoracic region, where it ends.

(iii.) *Antero-lateral descending tract* (fig. 360,9).—An extensive act, elongated but narrow, and reaching from the crossed to the direct ramidal tract. It is a mixed tract, since not all of its fibres degenerate low the lesions.

(iv.) *Comma tract* (fig. 360, 3) is a small tract of fibres which degen- ate below section or injury of the cord. Its presence has been demon- ated in the cervical and thoracic regions. It is supposed to consist of descending collaterals of the posterior nerve-roots as they pass into postero-external columns.

**(b) Of ascending degeneration.**

(i.) *Postero-median column and postero-lateral column* (fig. 360, 1).—ese tracts degenerate upward on injury or on section of the cord, as as on section of the posterior nerve roots. They exist throughout whole of the cord from below up, and can be traced into the bulb. ey consist of fine fibres.

connect with groups of intrinsic cells in the median or posterior portion of the gray matter of the cord.

(*b*) The **posterior roots** enter the spinal cord to the inner or median side of the posterior cornu. The fibres, as soon as they reach the cord, divide in a fork-like fashion, one branch passing down a short distance (only about three centimetres), the other branch passing up for a longer or shorter distance. This upper branch sometimes reaches nearly the whole extent of the cord, but generally it extends over only one or two segments of the cord. These divisions of the posterior root fibres give off in their course numerous collaterals. The nerve-fibres of the posterior roots are divided into two sets, an internal or median, an external or lateral. The lateral set consists mostly of small fibres, and it enters the cord opposite the tip of the posterior horn. The fibres pass in part to the marginal column of Lissauer, where they ascend and descend; in part they penetrate the posterior horn, and come in relation with its cells. The median set sends some fibres which pass to Clarke's column of cells, others pass by way of the posterior commissure to the median cells of the other side. Some others pass through the median gray matter to the anterior horn cells of the same side. Thus the posterior root-fibres are connected with all the cell groups of the posterior horn, of the anterior horn of the same side, and the cells of the me gray of the opposite side. Besides this, they are connected through



Fig. 362.—Section of the spinal cord showing the grouping of nerve-cells and the course of nerve fibres entering in posterior and anterior roots.

aterals with the intrinsic cells of the gray matter at different levels of the cord. One can realize that each nerve-root has, in this way, an effective grip upon a large extent of the cord. This is seen well by studying figs. 361 and 362.

**The Peculiarities of different regions of the Spinal Cord.**—The outline of the gray matter and the relative proportion of the white matter varies in different egions of the spinal cord, and it is, therefore, possible to tell approximately rom what region any given transverse section of the spinal cord has been aken. The white matter increases in amount from below upward. The amount of gray matter varies; it is greatest in the cervical and lumbar enlarge-ments, viz., at and about the 5th lumbar and 6th cervical nerve, and least in the horacic region. The greatest development of gray matter corresponds with reatest number of nerve-fibres passing from the cord.

*In the cervical enlargement* the gray matter occupies a large proportion of the ection, the gray commissure is short and thick, the anterior horn is blunt, while he posterior is somewhat tapering. The anterior and posterior roots run some istance through the white matter before they reach the periphery.

*In the dorsal region* the gray matter bears only a small relation to the white, nd the posterior roots in particular run a long course through the white matter efore they leave the cord; the gray commissure is thinner and narrower than n the cervical region. The tractus intermedio-lateralis is here most marked.

*In the lumbar enlargement* the gray matter again bears a very large propor-on to the whole size of the transverse section, but its posterior cornua are orter and blunter than they are in the cervical region. The gray commis-re is short and extremely narrow.

*At the upper part of the conus medullaris,* which is the portion of the cord mmediately below the lumbar enlargement, the gray substance occupies early the whole of the transverse section, as it is only invested by a thin yer of white substance. This thin layer is wanting in the neighborhood of e posterior nerve-roots. The great commissure is extremely thick.

*At the level of the fifth sacral vertebra* the gray matter is again in excess, and e central canal is enlarged, appearing T-shaped in section; while in the *per portion of the filum terminale* the gray matter is uniform in shape without y central canal.

The shape of the cord changes from the sacral and lumbar region here it is circular to the thoracic where it is oval, and to the cervical here the lateral diameter considerably exceeds the antero-posterior; e change in shape is due to a gradual increase of the lateral columns.

THE SPINAL CORD AND NERVE-ROOTS A MASS OF NERVE-UNITS.—e have, in the foregoing, described the spinal cord as being composed white and gray matter, and these substances, in turn, being composed nerve-fibres and nerve-cells, and a supporting substance called *neurog-*. From the physiologist's point of view, the spinal cord is considered be composed of a mass of nerve-units or *neurons.* These are divided o three great classes: the motor neurons, the sensory neurons, and e intermediate neurons. The *motor neurons* make up the larger part the nerve-tissue in the anterior horns; their neuraxons pass out

connect with groups of intrinsic cells in the median or posterior porti
of the gray matter of the cord.

(*b*) The **posterior roots** enter the spinal cord to the inner or m
dian side of the posterior cornu. The fibres, as soon as they reach t
cord, divide in a fork-like fashion, one branch passing down a short di
tance (only about three centimetres), the other branch passing up for
longer or shorter distance. This upper branch sometimes reaches near
the whole extent of the cord, but generally it extends over only one
two segments of the cord. These divisions of the posterior root fibr
give off in their course numerous collaterals. The nerve-fibres of th
posterior roots are divided into two sets, an internal or median, an e



Fig. 362.—Section of the spinal cord showing the grouping of nerve-cells and the course of n
fibres entering in posterior and anterior roots.

ternal or lateral. The lateral set consists mostly of small fibres, and
enters the cord opposite the tip of the posterior horn. The fibres p
in part to the marginal column of Lissauer, where they ascend and d
scend; in part they penetrate the posterior horn, and come in relati
with its cells. The median set sends some fibres wh [illegible] to Clark
column of cells, others pass by way of the poste [illegible] sure to th
median cells of the other side. Some others p [illegible]
gray matter to the anterior horn c [illegible] of the [illegible]
terior root-fibres are connected wi [illegible]
horn, of the anterior horn of the [illegible]
gray of the opposite side. Bes [illegible]

into the anterior roots. The *sensory neurons* have their cells or starting-points in the posterior spinal ganglia, these being large ganglionic masses which lie upon the posterior roots. These cells have a process which runs spineward through the posterior roots into the spinal cord, and another which runs peripherally, forming the sensory nerve. The *intermediate neurons* have their cells of origin in the posterior horns and median part of the gray matter, and, to a slight extent, in the anterior horns. Their cells form the intrinsic cells of the spinal cord, and also assist in the conduction of sensory and other afferent impulses. For example, the neurons, starting with the cells lying in Clarke's column, send their processes up into the cerebellum, and thus continue afferent impulses brought to the neurons through the posterior roots. On the other hand, other groups of cells lie in the lateral part of the gray matter and give rise to processes which pass out into the lateral columns and then enter the gray matter again, to connect with cells at different levels. These are the intermediate neurons which are commissural in their functions.

## FUNCTIONS OF THE SPINAL NERVE-ROOTS.

The anterior spinal nerve-roots are efferent in function: the posterior are afferent. The fact is proved in various ways. Division of the anterior roots of one or more nerves is followed by complete loss of motion in the parts supplied by the fibres of such roots; but the sensation of the same parts remains perfect. Division of the posterior roots destroys the sensibility of the parts supplied by their fibres, while the power of motion continues unimpaired. Moreover, irritation of the ends of the distal portions of the divided anterior roots of a nerve excites muscular movements; irritation of the ends of the proximal portions, which are still in connection with the cord, is followed by no appreciable effect. It must be remembered, however, that in the anterior or efferent nerves other besides motory are contained, *e.g.*, vaso-motor, secretory, heat fibres, and it may be supposed that when the distal end of a divided nerve is stimulated, the effects would be exercised not only upon muscles, but upon glands, blood-vessels, etc. Irritation of the distal portions of the divided posterior roots, on the other hand, produces no muscular movements and no manifestations of pain; for, as already stated, sensory nerves convey impressions only toward the nervous centres: but irritation of the proximal portions of these roots elicits signs of intense suffering. Occasionally, under this last irritation, muscular movements also ensue; but these are either voluntary, or the result of the irritation being reflected from the sensory to the motor fibres. Occasionally, too, irritation of the distal ends of divided anterior roots elicits signs of pain, well as producing muscular movements: the pain thus excited is prob- y the result either of *cramp* or of so-called recurrent sensibility.

*Recurrent Sensibility.*—If the anterior root of a spinal nerve be ided, and the peripheral end be irritated, not only movements of the scles supplied by the nerve take place, but also of other muscles, indic- ve of pain. If the main trunk of the nerve (after the coalescence of roots beyond the ganglion) be divided, and the anterior root be itated as before, the general signs of pain still remain, although the ntraction of the muscles does not occur. The signs of pain disappear en the posterior root is divided. From these experiments it is be- ved that the stimulus passes down the anterior root to the mixed rve, and returns to the central nervous system through the posterior ot by means of certain sensory fibres from the posterior root, which p back into the anterior root before continuing their course into the xed nerve-trunk. These fibres degenerate when the posterior nerve- ot is divided beyond the ganglion.

*Functions of the Ganglia on Posterior Roots.*—The cells of the pos- ior ganglia act as centres for the nutrition of the nerve-fibres given off m them. When these are cut, the parts of the nerves so severed de- nerate, while the parts which remain in connection with the cells do t. Thus on section of the posterior nerve-root beyond the ganglion peripheral part wastes and the central does not, and on section of root between the ganglion and the cord the central part to a great ent wastes and the peripheral remains unaffected.

### Functions of the Spinal Cord.

The power of the spinal cord, as a nerve-centre, may be arranged ler the heads of (1) Conduction; (2) Reflex action.

(1) *Conduction.*—The functions of the spinal cord in relation to duction may be best remembered by considering its anatomical con- tions with other parts of the body. From these it is evident that re is no way by which nerve-impulses can be conveyed from the trunk extremities to the brain, or *vice versa*, other than that formed by spinal cord. Through it, the impressions made upon the peripheral emities or other parts of the spinal sensory nerves are conducted to brain, where alone they can be *perceived.* Through it, also, the ulus of the will, conducted from the brain, is capable of exciting the on of the muscles supplied from it with motor nerves. And for all e conductions of impressions to and fro between the brain and the al nerves, the perfect state of the cord is necessary; for when any of it is destroyed, and its communication with the brain is inter- ted, impressions on the sensory nerves given off from it below the

seat of injury, cease to be propagated to the brain, and the brain loses the power of voluntarily exciting the motor nerves proceeding from the portion of cord isolated from it. Illustrations of this are furnished by various examples of paralysis, but by none better than by the common paraplegia, or loss of sensation and voluntary motion in the lower part of the body, in consequence of destructive disease or injury of a portion, including the whole thickness, of the spinal cord. Such lesions destroy the communication between the brain and all parts of the spinal cord below the seat of injury, and consequently cut off from their connection with the brain the various organs supplied with nerves issuing from those parts of the cord.

It is not probable that the conduction of motor or sensory impulses is effected under ordinary circumstances (to any great extent), as was formerly supposed, through the gray substance, *i.e.*, through the nerve-corpuscles and filaments connecting them. All parts of the cord are not alike able to conduct all impressions; and as there are separate nerve-fibres for motor and for sensory impressions, so in the cord, separate and determinate tracts serve to conduct always the same kind of impression. The sensations of touch, temperature, and pain, however, do not appear to have such sharply limited tracts as the motor impulses.

Experimental and other observations point to the following conclusions regarding the conduction of sensory and motor impressions through the spinal cord. Many of these conclusions must, however, be received with considerable reserve.

*a.* **Sensory Impressions.**—By sensory impressions are here meant the sensations of touch and pain, of heat and cold, and of muscular sense. These impressions are conveyed to the spinal cord by the posterior nerve-roots. Part of them are then carried directly into the postero-median column on the same side, and thence up to the nucleus of this column in the medulla. It is mainly the impulses of muscle sense that are thus carried. Other sensations are carried by the posterior root-fibres to the cells of the column of Clarke. . From there the impulses are conveyed to the direct cerebellar tract on the same side, and thence up to the cerebellum. These are mainly sensations that subserve the sense of equilibrium, and are closely connected in function with those which pass up the column of Goll to its nucleus. The impressions of touch and pain, and of heat and cold, are conveyed to the nerve-cells in the posterior cornua of the same side in part, and in part to the nerve-cells in the posterior cornua and median gray of the opposite side. From this point, the impulse is taken up again by intermediary neurons and conveyed through the anterior and lateral columns of the cord, in the ascending tract of Gowers and Tooth, to the brain. By reason of the great number of collaterals and the interpolation in the course of the sensory imp of many intermediary neurons, no very sharply defined tract has been satisfactorily made out in the spinal cord for the conduction of sensations of temperature, pain, and touch. If one set of fibres is oyed by disease, others seem able, through the collaterals, to take ts function. We can only say that most of these sensory impressions up in the lateral and anterior columns. It is probable, also, that and temperature sensations cross over at once, to a considerable ex- , and pass up in the opposite side of the cord to which they enter. ch and pressure sensations, as well as muscle-sense impressions, and ations of equilibrium, pass up largely upon the same side until they h the medulla or cerebellum.

The direct cerebellar tract is believed to commence in the cells of the erior vesicular column of Clarke of the same side; it goes chiefly to cerebellum, through the restiform body, but is said also to contain s which pass up as far as the corpora quadrigemina and then turn ward and lying near the brachium pass to the cerebellum. The s of the antero-lateral ascending tract are believed to arise from gray matter of the posterior cornu. In the case of the ascending ts, with the exception of the posterior columns, the connection with posterior nerve-roots is not direct.

. **Motor Impressions.**—Motor impressions are conveyed down- from the brain along *the pyramidal tracts, viz., the direct or an- r, and the crossed or lateral,* chiefly in the latter. Generally king, the impressions pass down on the side opposite to which they nate, having undergone decussation in the medulla; but some im- ions do not cross in the medulla, but lower down, in the cord, being eyed by the anterior or uncrossed pyramidal fibres, and decussate in anterior commissure. The motor-fibres for the legs *partially* pass ward in the lateral columns of the *same side*. This is also probably ase with the bilateral muscles, *i.e.*, muscles of the two sides acting her, such as the intercostal muscles and other muscles of the trunk, ll as the costo-humeral muscles.

t is quite certain, as was just now pointed out, that the fibres of the ior nerve-roots are more numerous than the fibres proceeding down- from the brain in the pyramidal tracts, or the so-called pyramidal . This is because each pyramidal fibre is really a very long nerve ss or neuraxon, and is supplied in its course with a large number llaterals, which go off at different points, and thus put it in relation different groups of nerve-cells in the anterior cornua at various . Each nerve-fibre of the pyramidal tract, by means of its col- ls, can control a number of nerve-cells, and can thus co-ordinate ction of impulses sent out through the anterior roots to a number oups of muscles. In other words, the gray matter of the anterior a contains an apparatus with various complicated co-ordinating rs, which apparatus is under the control of the neurons whose of origin are in the cortex of the brain. This apparatus is also re- influenced by sensory impressions passing to the cord.

Division of the anterior pyramids of the medulla at the point decussation is followed by paralysis of motion, never quite absolute, all parts below. Disease or division of any part of the cerebro-spi axis above the seat of decussation is followed by impaired or lost pow of motion on the opposite side of the body; while a like injury inflict below this part induces similar, never quite absolute no doubt, on th corresponding side.

When one half of the spinal cord is cut through in monkeys, following results follow (Mott):—Motor paralysis of the muscles of same side (never complete of muscles used in bilateral associated actio followed by gradual recovery of muscular movement, except of the fi movements of the hand and foot; wasting and flabbiness of the mu sensory paralysis of the same side (temperature, touch, pain and p sure); temporary vaso-motor paralysis on same side. The temperatur the affected side was depressed 1 to 3° (F.).

*Reflex Action.*—In man the spinal cord is so much under the co of the higher nerve-centres, that its own individual functions in re tion to reflex action are apt to be overlooked; so that the result injury, by which the cord is cut off completely from the influence of encephalon, is apt to lessen rather than increase our estimate of importance and individual endowments. Thus, when the hu spinal cord is divided, the lower extremities fall into any position th their weight and the resistance of surrounding objects combine to gi them; and if the body is irritated, they do not move toward the irrit tion; and if they are touched, the consequent reflex movements a disorderly and purposeless; all power of voluntary movement is absolut abolished. In other mammals, however, *e.g.*, in the rabbit or dog, aft recovery from the shock of the operation, which takes some time, re action will occur in the parts below after the spinal cord has been divide a very feeble irritation being followed by extensive and co-ordin movements. In the case of the frog, and many other cold-blood animals, in which experimental and other injuries of the nerve-ti are better borne, and in which the lower nerve-centres are less sub dinate in their action to the higher, the reflex functions of the cord still more clearly shown. When, for example, a frog's head is cut its limbs remain in, or assume a natural position; they resume it wh disturbed; and when the abdomen or back is irritated, the feet moved with the manifest purpose of pushing away the irritation. T main difference in the cold-blooded animals being that the reflex mo ments are more definite, complicated, and effective, although less en getic than in the case of mammals. It might indeed be thought, superficial examination, that the mind of the animal was engaged the acts; and yet all analogy would lead us to the belief that the spi cord of the frog has no different endowment, in kind, from those whi

long to the cord of the higher vertebrata: the difference is only in
gree. And if this be granted, it may be assumed that, in man and
e higher animals, many actions are performed as reflex movements
curring through and by means of the spinal cord, although the latter
nnot by itself initiate or even direct them independently.

*Cutaneous and Muscle Reflexes.*—In the human subject two kinds of
flex actions dependent upon the spinal cord are usually distinguished,
e alterations of which, either in the direction of increase or of diminu-
on, are indications of some abnormality, and are used as a means of
agnosis in nervous and other disorders. They are termed respectively
-) *cutaneous reflexes*, and (*b*.) *muscle reflexes*. (*a*.) Cutaneous reflexes
e set up by a gentle stimulus applied to the skin. The subjacent
uscle or muscles contract in response. Although these cutaneous
flex actions may be demonstrated almost anywhere, yet certain of such
tions as being most characteristic are distinguished, *e.g.*, plantar
flex; glutear reflex, *i.e.*, a contraction of the gluteus maximus when
e skin over it is stimulated; cremaster reflex, retraction of the
ticle when the skin of the inside of the thigh is stimulated, and the
e. The ocular reflexes, too, are important. They are contraction
the iris on exposure to light, and its dilatation on stimulating the skin
the cervical region. All of these cutaneous reflexes are true reflex
ions. They differ in different individuals, and are more easily elicited
the young. Muscle reflexes, or as they are often termed, tendon
lexes, consist of a contraction of a muscle under conditions of more or
s tension, when its tendon is sharply tapped. The so-called patellar-
don-reflex is the most well-known of this variety of reflexes. If one
ee be slightly flexed, as by crossing it over the other, so that the
adriceps femoris is extended to a moderate degree, and the patella
don be tapped with the fingers or the earpiece of a stethoscope, the
scle contracts and the foot is jerked forward.

Another variety of the same phenomenon is seen if the foot is flexed so
to stretch the calf muscles and the tendo Achillis is tapped; the
t is extended by the contraction of the stretched muscles. It appears,
vever, that the tendon reflexes are not exactly what their name im-
s. The interval between the tap and the contraction is said to be
short for the production of a true reflex action. It is suggested
t the contraction is caused by local stimulation of the muscle, but
t this would not occur unless the muscle had been reflexly stimulated
viously by the tension applied, and placed in a condition of excessive
tability. It is further probable that the condition on which it
ends is a reflex spinal irritability of the muscle or (exaggerated)
scular tone, which is admitted to be a reflex phenomenon—or an ex-
le of automatism—in the spinal cord.

*Inhibition of Reflex Actions.*—Movements such as are produced by irritating the skin of the lower extremities in the human subject, after division or disorganization of a part of the spinal cord, do not follow the same irritation when the cerebrum is active and the connection between the cord and the brain is intact. This is, probably, due to the fact that the mind ordinarily perceives the irritation and instantly inhibits or controls the action; for, even when the cord is perfect, such involuntary movements may follow an irritation, applied when the cerebrum is inactive. When, for example, one is anxiously thinking, even slight stimuli may produce involuntary and reflex movements. So, also, during sleep, such reflex movements may be observed, when the skin is touched or tickled; for example, when one touches with the finger the palm of the hand of a sleeping child, the finger is grasped—the impression on the skin of the palm producing a reflex movement of the muscles which close the hand. But when the child is awake, no such effect is produced.

Further, many reflex actions are capable of being more or less controlled or even altogether prevented by the will: thus an inhibitory action may be exercised by the cerebrum over reflex functions of the cord and the other nerve-centres. The following may be quoted as familiar examples of this action:—

To prevent the reflex action of crying out when in pain, it is often sufficient firmly to clench the teeth or to grasp some object and hold it tight. When the feet are tickled we can, by an effort of will, prevent the reflex action of jerking them up. So, too, the involuntary closing of the eyes and starting, when a blow is aimed at the head, can be similarly restrained.

Darwin has mentioned an interesting example of the way in which, on the other hand, such an instinctive reflex act may override the strongest effort of the will. He placed his face close against the glass of the cobra's cage in the Reptile House at the Zoological Gardens, and though, of course, thoroughly convinced of his perfect security, could not by any effort of the will prevent himself from starting back when the snake struck with fury at the glass.

It has been found by experiment that in a frog the *optic lobes and optic thalami* have a distinct action in inhibiting or delaying reflex action, and also that more generally any afferent stimulus, if sufficiently strong, may inhibit or modify any reflex action even in the absence of these centres.

On the whole, therefore, it may, from these and like facts, be concluded that reflex acts, performed under the influence of the reflecting power of the spinal cord, are essentially independent of the brain and may be performed perfectly when the brain is separated from the cord: th

hese include a much larger number of the natural and purposive move-
ents of the lower animals than of the warm-blooded animals including
an: and that over nearly all of them the mind may exercise, through
e higher nerve-centres, some control; *determining*, *directing*, *hinder-*
*g*, or *modifying* them, either by direct action, or by its power over
sociated muscles.

To these instances of spinal reflex action, some add yet many more,
cluding nearly all the acts which seem to be performed unconsciously,
ch as those of walking, running, writing, and the like: for these are
ally involuntary acts. It is true that at their first performances they
e voluntary, that they require education for their perfection, and are
all times so constantly performed in obedience to a mandate of the
ill, that it is difficult to believe in their essentially involuntary nature.
ut the will really has only a *controlling* power over their performance;
can hasten or stay them, but it has little or nothing to do with the
tual carrying out of the effect. And this is proved by the circum-
ance that these acts can be performed during complete mental abstrac-
on: and, more than this, that the endeavor to carry them out entirely
the exercise of the will is not only not beneficial, but positively in-
rferes with their harmonious and perfect performance. Any one may
nvince himself of this fact by trying to take each step as a voluntary
t in walking downstairs, or to form each letter or word in writing by
distinct exercise of the will.

These actions, however, will be again referred to.

*Morbid reflex actions.*—The relation of the reflex action to the strength
the stimulus is the same as was shown generally to occur in nerve-
ntres, a slight stimulus producing a slight movement, and a greater,
greater movement, and so on; but in instances in which we must
ume that the cord is *morbidly more irritable*, *i.e.*, apt to issue more
rvous force than is proportionate to the stimulus applied to it, a slight
pression on a sensory nerve produces extensive reflex movements.
is appears to be the condition in the disease called tetanus, in
ich a slight touch on the skin may throw the whole body into
nvulsions.

*Special Centres.*—It may seem to have been implied that the spinal
d as a single nerve-centre, reflects alike from all parts all the impres-
ns conducted to it. This, however, is not the case, and it should be
arded as we have indicated, as a collection of nervous centres united
a continuous column. This is well illustrated by the fact that seg-
nts of the cord may act as distinct nerve-centres, in which special
ordinated muscular actions are represented, and excite muscular action
the parts supplied with nerves given off from them; as well as by the
logy of certain cases in which the muscular movements of single

organs are under the control of certain circumscribed portions of the cord. The special centres are the following (on each side):—

(*a.*) *The Defæcation, or Ano-Spinal centre.*—The mode of action of the ano-spinal centre appears to be this. The mucous membrane of the rectum is stimulated by the presence of fæces or of gas in the bowel. The stimulus passes up by the afferent nerves of the hæmorrhoidal and inferior mesenteric plexuses to the centre in the cord, situated in the lumbar enlargement, and is reflected through the pudendal plexus to the anal sphincter on the one hand, and on the other to the muscular tissue in the wall of the lower bowel. In this way is produced a relaxation of the first and a contraction of the second, and expulsion of the contents of the bowel follows. The centre in the spinal cord is partially under the control of the will, so that its action may be either inhibited or augmented. The action may be helped by the abdominal muscles which are under the control of the will, although under a strong stimulus they may also be compelled to contract by reflex action.

(*b.*) *The Micturition, or the Vesico-Spinal centre.*—The vesico-spinal centre acts in a very similar way to that of the ano-spinal. The centre is also in the lumbar enlargement of the cord. It may be stimulated to action by impulses descending from the brain, or reflexly by the presence of urine in the bladder. The action of the brain may be voluntary, or it may be excited to action by the sensation of distention of the bladder by the urine. The sensory fibres concerned are the posterior roots of the lower sacral nerves. The action of the centre thus stimulated is double, or it may be supposed that the centre consists of two parts, one which is usually in action and maintains the tone of the sphincter, and the other which causes contraction of the bladder and other muscles. When evacuation of the bladder is to occur, impulses are sent to one part of the centre on the one hand, and from it to the bladder and to certain other muscles which cause their contraction, and on the other to the other part of the centre, inhibiting its action on the sphincter urethræ which procures its relaxation. The way having been opened by the relaxation of the sphincter, the urine is expelled by the combined action of the bladder and accessory muscles. The cerebrum may act not only in the way of stimulating the centre to action, but also in the way of inhibiting its action. The abdominal muscles may be called into action as in defæcation.

(*c.*) *The Emission of Semen, or Genito-Spinal centre.*—The centre situated in the lumbar enlargement of the spinal cord is stimulated to action by sensory impressions from the glans penis. Efferent impulses from the centre excite the successive and co-ordinate contractions of the muscular fibres of the vasa deferentia and vesiculæ seminales, and of the accelerator urinæ and other muscles of the urethra; and a forcible expul of semen takes place, over which the mind has little or no control, which, in cases of paraplegia, may be unfelt.

(d.) *The Erection of the Penis Centre.*—This centre is also situated he lumbar region. It is excited to action by the sensory nerves of penis, and also by impulses passing down from the cerebrum. rent impulses produce dilatation of the vessels of the penis, which appears to be in part the result of a reflex contraction of the muscles which the veins returning the blood from the penis are compressed.

(e.) *Parturition centre.*—The centre for the expulsion of the con- ts of the uterus in parturition is situated in the lumbar spinal cord her higher up than the other centres already enumerated. The nulation of the interior of the uterus by its contents may, under tain conditions, excite the centre to send out impulses which produce ontraction of the uterine walls and expulsion of the contents of the ity. The centre is independent of the will since delivery can take ce in paraplegic women, and also while a patient is under the influ- e of chloroform. Again, as in the cases of defæcation and micturi- n, the abdominal muscles assist; their action being for the most t reflex and involuntary.

(f.) *The Centre for the Movements of the Lymphatic Hearts of Frogs.*— lkmann has shown that the rhythmical movements of the anterior pair lymphatic hearts in the frog depend upon nervous influence derived n the portion of spinal cord corresponding to the third vertebra, and se of the posterior pair on influence supplied by the portion of cord osite the eighth vertebra. The movements of the heart continue, ugh the whole of the cord, except the above portions, be destroyed; but he instant of destroying either of these portions, though all the rest of cord be untouched, the movements of the corresponding hearts cease.

(g.) *The Centre for the Tone of Muscles.*—The influence of the spinal l on the sphincter ani and sphincter urethræ has been already men- ed (see above). It maintains these muscles in permanent contrac- . The condition of these sphincters, however, is not altogether ptional. It is the same in kind, though it exceeds in degree that ition of muscles which has been called *tone*, or passive contraction; te in which they always, when not active, appear to be during health, in which, though called inactive, they are in slight contraction, and ainly are not relaxed, as they are soon after death, or when the spinal is destroyed. This tone of all the muscles of the trunk and limbs nds on the spinal cord, just as the contraction of the sphincters . If an animal be killed by injury or removal of the brain, the les retain their tone; but if the spinal cord be destroyed, the ncter ani relaxes, and all the muscles feel loose, flabby, and atonic, aining so till *rigor mortis* commences.

This kind of tone must be distinguished from that mere firmness and tension which it is customary to ascribe, under the name of tone, to all tissues that feel robust and not flabby, as well as to muscles. The tone peculiar to muscles has in it a degree of vital contraction: that of other tissues is only due to their being well nourished, and therefore compact and tense.

All the foregoing examples illustrate the fact that the spinal cord is a collection of reflex centres, upon which the higher centres act by sending down impulses to set in motion, modify or control them. The movements or other phenomena of reflex action are, as it were, the function of the ganglion cells to which an afferent impression is conveyed by the posterior nerve-trunks in connection with them. The extent of the movement depends upon the strength of the stimulus, the position in which it is applied as well as the condition of the nerve-cells; the connection between the cells being so intimate that a series of co-ordinated movements may result from a single stimulation. Whether the cells possess as well the power of originating impulses (automatism) is doubtful, but this is possible in the case of (*h*) *vaso-motor centres* which are situated in the cord (p. 246), and of (*i*) *sweating centres* which must be closely related to them, and possibly in the case of (*j*) the centres for maintaining *the tone of muscles.*

The *Nutrition* (*a*) of the muscles appears to be under the control of the spinal cord. When the nerve-cells of the anterior cornu are diseased the muscles atrophy. In the same way (*b*) the bones and (*c*) joints are seriously affected when the cord is diseased. The former when the anterior nerve-cells are implicated, do not grow, and the latter are disorganized in some cases when the posterior columns are affected. (*d*) The skin, too, is evidently only maintained in a healthy condition as long as the cord and its nerves are intact. No doubt part of this influence which the cord exercises over nutrition is due to the relationship which it bears to the vaso-motor nerves.

Within the cord are contained, for some distance, fibres (*a*) which regulate the dilatation of the pupil, (*b*) which have to do with the glycogenic function of the liver, (*c*) which control the nerve-supply of the vessels of the face and head, (*d*) which produce acceleration of the heart's action, and, (*e*) have a thermotaxic action on the muscles, etc.

## THE RELATIONS OF THE DIFFERENT PARTS OF THE BRAIN.

Before considering the parts of the brain separately, it will be best for the comprehension of the plan of its construction to take a general survey of the whole. The brain on superficial examination presents four distinct parts, viz. (*a.*) The large and prominent masses of nervous divided by fissures into convolutions (fig. 363), and covering to a extent the other parts, separated from one another by a deep running from front to back. These constitute the cerebral pheres or *cerebrum*. (*b*) On the under or central surface of the can be seen a broad mass rounded on the surface more or less lateral in shape; this is the *pons Varolii* (fig. 363, VI.). An-



63.—Base of the brain. 1, superior longitudinal fissure; 2, 2', 2", anterior cerebral issure of Sylvius, between anterior and 4, 4', 4'', middle cerebral lobe; 5, 5', posterior edulla oblongata. The figure is in the right anterior pyramid; 7, 8, 9, 10, the cerebellum; erior verimform process. The figures from I. to IX. are placed against the corresponding erves; III. is placed on the right crus cerebri. VI. and VII. on the pons Varolii; X. ervical or suboccipital nerve. (Allen Thomson.) ½.

it is seen to branch off into two strands, which are the *crura* and posteriorly it joins with a narrower portion, which is the *oblongata or bulb*. This latter is continuous with the spinal cord. ection with the bulb and pons are seen many nerve-trunks pass- ; these are the chief part of the *cranial nerves*. Two of the nerves, however, are more interior, and one, the optic (fig. 363, een to send off a broad band of fibres which apparently passes e substance of the cerebrum. The most anterior nerve-root on side, viz., the olfactory (fig. 363, 1), extends for some distance e under surface of each cerebral hemisphere. (*c*.) The pons is be connected laterally with a large mass of nervous matter, upon n the position of the brain turned upward, the bulb also rests;

this is the *cerebellum*, and (*d.*) When the brain is viewed in the normal position at the bottom of the fissure, between the hemispheres is seen a broad band of white matter connecting one hemisphere with its fellow, the main commissure or *corpus callosum* (fig. 366). Such parts of the brain are evident even on superficial examination. On dissection, it is found that the central nervous system is not a solid mass of nerve material; it incloses certain cavities, the *cerebral ventricles.* Forming the walls and boundaries of these ventricles are very important masses of nervous matter. The cerebrum proper incloses a large central cavity, but separated by a median partition into two *lateral ventricles.* Into the cavity of each lateral ventricle (fig. 364) projects a rounded mass of gray matter anteriorly, which is the caudate nucleus of an important structure known as the *corpus striatum*, the more external part of which, the lenticular nucleus, is embedded in the mass of the cerebral hemisphere. Below, or more posterior to the *caudate nucleus*, and also projecting into the lateral ventricle, is a second mass of gray matter, called the *optic thalamus;* the upper part of this only, however, is seen in the lateral ventricle, the lower and more internal part approaching its fellow in the middle line leaves a space which on vertical section is more or less triangular, called the *third ventricle.* The lateral ventricles are separated from one another by means of a partition made of two layers of white matter, the *septum lucidum.* On section the septum is seen to be more or less triangular, and between the two layers there is the space of the *fifth ventricle* filled with fluid.

At the posterior part of the septum lucidum, and joining with it, is the *fornix.* This is a longitudinal commissure; it is arched and its edge is seen in the lateral ventricle on either side. Between its edge and the upper part of the optic thalamus projects a fringe of blood-vessels, which is the upper part of the septum of the vascular pia mater, which passes into the interior of the brain, and which is called the *choroid plexus;* the whole of the projection forming a roof for the third ventricle is called the *velum interpositum.*

The fornix (fig. 364, *e*) is made up of two strands anteriorly, called the anterior pillars, and of two similar pillars posteriorly; the middle portion called the body consists of the parts of the two pillars which are joined together in the middle line. The body of the fornix is triangular in shape, broad and flat behind, where it is connected with the corpus callosum, and narrow in front where it is connected to the septum lucidum. The anterior pillars pass downward, separated from one another on either side of the third ventricle in front of the foramen, by which the lateral communicates with the third ventricle, called the *foramen of Monro;* each pillar then passes forward and down, and twisting upon itself forms the *corpus albicans*, and then passes in part to join the optic us. The posterior pillars pass down and out and form part of erior of that part of the lateral ventricle which descends into the or lobe of the cerebrum. Thus, when the fornix is reflected from nt, first of all the velum interpositum is seen, and when that is d the third ventricle comes into sight.

e third ventricle terminates at its posterior extremity in the pineal From this ventricle a short narrow passage, the *iter a tertio ad*



64.—Dissection of brain, from above, exposing the lateral fourth and fifth ventricles surrounding parts. ⅙. *a*, Anterior part, or *genu* of corpus callosum; *b*, corpus striathe corpus striatum of left side, dissected so as to expose its gray substance; *c*, points to the tænia semicircularis; *d*, optic thalamus; *e*, anterior pillars of fornix divided; y are seen descending in front of the third ventricle, and between them is seen part of ior commissure; in front of the letter *e* is seen the slit-like fifth ventricle, between the æ of the septum lucidum; *f*, soft or middle commissure; *g* is placed in the posterior he third ventricle; immediately behind the latter are the posterior commissure (just nd the pineal gland, the two crura of which extend forward along the inner and upins of the optic thalami; *h* and *i*, the corpora quadrigemina; *k*, superior crus of cerelose to *k* is the valve of Vieussens, which has been divided so as to expose the fourth ; *l*, hippocampus major and corpus fimbriatum, or tænia hippocampi; *m*, hippocampus , eminentia collateralis; *o*, fourth ventricle; *p*, posterior surface of medulla oblongata; of cerebellum; *s*, upper part of left hemisphere of cerebellum exposed by the removal the posterior cerebral lobe. (Hirschfield and Leveillé.)

*m ventriculum*, or aqueduct of Sylvius, passes through the next of the brain called the mid-brain. This part is covered in by rs of nerve-ganglia, the anterior and the posterior corpora quaina, and the floor is formed by the crura cerebri. The aqueduct ius opens at the upper angle of a lozenge-shaped cavity, the ventricle, which is situated on the dorsal aspect of the pons and The fourth ventricle has no roof of its own beyond a layer of epithelium, but it is covered in by the cerebellum, the superior peduncles of which, converging forward, form its anterior limits, and the inferior peduncles form its posterior boundaries on either side.

The lateral, third and fourth ventricles communicate, and through the last with the central canal of the spinal cord. They are all lined with columnar ciliated epithelium, beneath which is a development of neuroglia. This lining so formed is called the *ependyma* of the ventricles. Where the superior peduncles of the cerebellum are approaching each other at the upper part of the fourth ventricle, the interval between them is bridged over by a thin layer of gray matter called the valve of Vieussens.

The portions of the central nervous system are thus classified:—

(i.) Cerebral hemispheres with the corpora striata, developed from the cerebral vesicles—and enclosing the lateral ventricles.

(ii.) *Fore-brain*, formed of the parts, including the optic thalami, which inclose the third ventricle.

(iii.) *Mid-brain*, consisting of the parts inclosing the aqueduct of Sylvius, viz., the corpora quadrigemina, which form the roof, and the crura cerebri which form the floor.



Fig. 365.—Plan in outline of the encephalon, as seen from the right side. ½. The parts are represented as separated from one another somewhat more than natural, so as to show their connections. A, Cerebrum; *f*, *g*, *h*, its anterior, middle, and posterior lobes; *e*, fissure of Sylvius; B, cerebellum; C, pons Varolii; D, medulla oblongata; *a*, peduncles of the cerebrum; *b*, *c*, *d*, superior, middle, and inferior peduncles of the cerebellum. (From Quain.)

(iv.) *Hind-brain*, the pons Varolii and the cerebellum form respectively the floor and roof of the fore-part of the hind-brain, and the bulb the floor of the back part of the hind-brain, the roof being practically absent.

division of the brain into the four parts is justified by a consid- of its development. As will be seen later on, the brain consists ly of three cerebral vesicles, the dilated extremity of the neural



.—View of the Corpus Callosum from above. ⅙.—The upper surface of the corpus as been fully exposed by separating the cerebral hemispheres and throwing them to ie gyrus fornicatus has been detached, and the transverse fibres of the corpus callo- for some distance into the cerebral medullary substance. 1, the upper surface of the osum; 2, median furrow or raphe; 3, longitudinal striæ bounding the furrow; 4, rmed by the transverse bands as they pass into the cerebrum; 5, anterior extremity the corpus callosum; 6, posterior extremity; 7, anterior, and 8, posterior part of the res proceeding from the corpus callosum; 9, margin of the swelling; 10, anterior part olution of the corpus callosum; 11, hem or band of union of this convolution; 12, in- olutions of the parietal lobe; 13, upper surface of the cerebellum. (Sappey after

ıd these consist of fore-, mid-, and hind-brain. From the fore- ıere is first of all budded off on either side a new vesicle, the sicle from which is developed the optic nerve and retina, and d a large vesicle, the cerebral vesicle, which grows rapidly, divided by a central partition into two, each of which incloses al ventricle. The cerebral vesicles grow so quickly as to cover fore- and the mid-brain. The parts of which the fore-, mid-, l-brains are made up are developed from the corresponding cere- cles.

ll be as well here to indicate briefly the structure of the brain. sts of white and gray matter differently arranged in different

## Distribution of the Gray Matter.

(i.) *In the bulb*, at the lower part the distribution of gray matter follows that which prevails in the cord. Higher up the chief part is found toward the posterior or dorsal aspect, surrounding the central canal. When the central canal opens out into the fourth ventricle the gray matter comes to that surface chiefly, and is found to consist more particularly, on either side, of the nuclei of origin of the cranial nerves, viz., the 12th, 11th, 10th, 9th, and 8th, and more externally of the nucleus gracilis and nucleus cuneatus (*n.g.*, *n.c.*, figs. 370, 371). In addition to these masses of gray matter, there are the *olivary bodies* (*o*, figs. 370, 371) toward the ventral surface with the *accessory olives* (*o'*), and the *external arcuate* (*n.ar.* in figs.) nuclei, placed at the tip of the anterior fissure on either side on the ventral surface of the anterior pyramids.

(ii.) *In the pons Varolii.*—In addition to the origins of nerves in the floor of the fourth ventricle on the dorsal aspect of the pons, viz., of the 7th, 6th, and 5th nerves, there are several masses of gray matter, viz., in the back part, the *superior olive* (fig. 371), and in the front part the *locus cæruleus*, as well as small amounts of the same material mixed with fibres in the more ventral surface.

(iii.) In the mid-brain, the gray matter preponderates in the *optic thalami*, *corpora quadrigemina*, and *corpora geniculata*. It is also found surrounding the aqueduct of Sylvius, and in other parts of the crura, notably such masses as the *red nucleus* (fig. 372), *locus niger* (fig. 374).

(iv.) *In the cerebral hemispheres*, the cerebral cortex is made up of gray matter which incloses white matter, and the corpus striatum is made up more or less of the same material.

(v.) *In the cerebellum*, the gray matter forms the incasing material. In the interior too there are masses of gray matter forming the *corpora dentata*.

This then roughly indicates the localities in which gray matter is found; the arrangement of the fibres and their relationship to the gray matter will be dealt with later on.

### THE BULB OR MEDULLA OBLONGATA.

The medulla oblongata (figs. 367, 368), is a column of gray and white matter formed by the prolongation upward of the spinal cord and connecting it with the brain.

*Structure.*—The gray substance which it contains is situated in the interior and variously divided into masses and laminæ by the white or fibrous substance which is arranged partly in external columns, and rtly in fasciculi traversing the central gray matter. The medulla longata is larger than any part of the spinal cord. Its columns are yriform, enlarging as they proceed toward the brain, and are continuous ith those of the spinal cord. Each half of the medulla, therefore, may e divided into three columns or tracts of fibres, continuous with the three racts of which each half of the spinal cord is made up,—the columns re more prominent than those of the spinal cord, and are separated rom each other by deeper grooves. The *anterior*, continuous with the nterior columns of the cord, are called the *anterior pyramids*, and the



Fig. 367.



Fig. 368.

**Fig. 367.—Ventral or anterior surface of the pons Varolii, and medulla oblongata.** *a*, *a*, an-ior pyramids; *b*, their decussation; *c*, *c*, olivary bodies; *d*, *d*, restiform bodies; *e*, arciform res; *f*, fibres passing from the anterior column of the cord to the cerebellum; *g*, anterior col-n of the spinal cord; *h*, lateral column; *p*, pons Varolii; *i*, its upper fibres; 5, 5, roots of the h pair of nerves.

Fig. 368.—Dorsal or posterior surface of the pons Varolii, corpora quadrigemina, and me-lla oblongata. The peduncles of the cerebellum are cut short at the side. *a*, *a*, the upper r of corpora quadrigemina; *b*, *b*, the lower; *f*, *f*, superior peduncles of the cerebellum; *c*, inence connected with the nucleus of the hypoglossal nerve; *e*, that of the glosso-pharyngeal rve; *i*, that of the vagus nerve; *d*, *d*, restiform bodies; *p*, *p*, posterior pyramids; *v*, *v*, groove the middle of the fourth ventricle, ending below in the calamus scriptorius; 7, 7, roots of the litory nerves.

stero-median and postero-external columns are also represented at the sterior or dorsal aspect of the cord as the *fasciculus gracilis* and the *sciculus cuneatus*. The posterior pyramids of the medulla which in-ade these two columns of white matter soon become much increased width by the addition of a new column of white matter outside the her two which is known as the *fasciculus of Rolando*. The lateral col-ns of the cord undergo considerable change and are scarcely repre-ted as such in the bulb.

It may be said then that the bulb at its commencement differs only ghtly in size from the cord with which it is continuous. It soon becomes larger both laterally and antero-posteriorly, and after a time opens out on the dorsal surface into a space which is known as the fourth ventricle, and from being a cylinder with a central canal, it is flattened out on one surface by the gradual approach of the central canal to that surface. The central canal of the cord, therefore, is directly continuous with the fourth ventricle.



Fig. 369.—Dorsal or posterior view of the medulla, fourth ventricle, and mesencephalon (natural size). *p.n.*, line of the posterior roots of the spinal nerves; *p.m.f.*, posterior median fissure; *f.g.*, funiculus gracilis; *cl.*, its clava; *f.c.*, funiculus cuneatus; *f.R.*, funiculus of Rolando; *r.b.*, restiform body; *c.s.*, calamus scriptorius: *l*, section of ligula or tænia; part of choroid plexus is seen beneath it; *l.r.*, lateral recess of the ventricle; *str.*, striæ acusticæ; *i.f.*, inferior fossa; *s.f.*, posterior fossa; between it and the median sulcus is the fasciculus teres; *cbl.*, cut surface of the cerebellar hemisphere; *nd.*, central or gray matter; *s.m.v.*, superior medullary velum; *lng.*, ligula; *s.c.p.*, superior cerebellar peduncle cut longitudinally; *σ.*, combined section of the three cerebellar peduncles; *c.q.s.*, *c.q.i.*, corpora quadrigemina (superior and inferior); *fr.*, frænulum; *f.*, fibres of the fillet seen on the surface of the tegmentum; *c.*, crusti; *l.g.*, lateral groove; *c.g.i.*, corpus geniculum internus; *th.*, posterior part of thalamus; *p.*, pineal body. The Roman numbers indicate the corresponding cranial nerves. (E. A. Schäfer.)

If the bulb be examined on its anterior or ventral surface it is found that the anterior fissure, which is a continuation of the same fissure in the cord, is occupied at the most posterior part by fibres which are crossing from one side to the other; the central canal being pushed now toward the posterior surface. This is what is known as the *anterior decussation* of the medulla oblongata. It is formed of the fibres which in the cord occupy the postero-lateral region and are called the crossed pyramidal fibres. The lateral pyramidal fibres of either side after crossing in the middle line in this way become part of the anterior pyramid pposite side; the rest of the pyramid being made up of the fibres anterior column of the cord known as the direct or uncrossed al fibres. These two pyramidal strands of fibres are those which te on lesions of certain parts of the cerebrum which are known otor areas of the cortex. They can therefore be traced downward lesions as tracts of degeneration. They are the fibres of commu- between the cerebral cortex and the different segments of the rd. The anterior pyramids of the bulb are marked out by the n that part of the nervous axis to the outside of them, of a e 12th or hypoglossal. More laterally than this nerve, there omes very prominent on either side a rounded elevation or col- ich is known as the *olivary body.* It is not seen at the begin- the bulb at its junction with the cord, but begins at a lower n the opening of the fourth ventricle. On the further side of ry body is seen the line of origin of fibres of the 11th, 10th, and es, and from this to the posterior fissure is the posterior pyramid. whole of that part of the medulla which is situated laterally the olivary body and the posterior fissure is known as the *resti- ly;* it is continued forward on either side as the inferior peduncle rebellum.

changes which are noticed by the study of series of sections of from below upward may be summarized thus: In the dorsal or region, the posterior cornua are pushed more to each side, and tance of Rolando is increased and becomes rounded, reaching the surface of the bulb on each side, a small tract of longitu- res of the ascending root of the 5th nerve only intervening. a great increase of the reticular formation around the central d the lateral approaches the anterior cornu. Then at the ven- nterior aspect the decussation of the lateral fibres begins. By sing over of the fibres, the tip of the gray anterior cornu is cut the rest of the gray matter. The central canal is pushed further he posterior surface, first of all by the decussation of the anterior s just mentioned, and later on, *i.e.*, above, by another decussa- fibres more dorsal. These fibres of the second decussation as s form a median raphe and also help to break up the remaining ter into what is called a *reticular formation.* There has been le doubt as to the origin of these descussating fibres, but the orities now consider them to be, at any rate in part, the fibres nuclei of the fasciculus gracilis and fasciculus cuneatus of le, and look upon them as a sensory decussation. At the pos- rt soon there appear in the columns of white matter of the s gracilis and fasciculus cuneatus new masses of gray matter. horn approaches the anterior; but soon the latter is pushed further and further toward the centre, while the lateral horn remains near the lateral surface. The anterior gray matter becomes broken up and merged into the reticular formation. There is also a similar reticular formation both toward the centre and also laterally in the dorsal region. At the level where the central canal opens into the 4th ventricle, the posterior pyramids diverging to form the lower and outside boundaries, and inclosing a space, the calamus scriptorius, between them, there are to be made out various masses of gray matter in addition to the reticular formation, viz., the nuclei of the fasciculus gracilis



Fig. 370.—Anterior or dorsal section of the medulla oblongata in the region of the superior pyramidal decussation. *a.m.f.*, anterior median fissure; *f.a.*, superficial arciform fibres emerging from the fissure; *py.*, pyramid; *n.ar.*, nuclei of arciform fibres; *f.a.*, deep arciform becoming superficial; *o*, lower end of olivary nucleus; *n.l.*, nucleus lateralis; *f.r.*, formatio reticularis; *f.a.*$^2$, arciform fibres proceeding from the formatio reticularis; *g.*, substantia gelatinosa of Rolando; *a.V.*, ascending root of fifth nerve; *n.c.*, nucleus cuneatus; *n.c'.*, external cuneate nucleus; *n.g.*, nucleus gracilis; *f.g.*, funiculus gracilis; *p.m.f.*, posterior median fissure; *c.c.*, central canal surrounded by gray matter, in which are *n.XI.*, nucleus of the spinal accessory, and *n.XII.*, nucleus of the hypoglossal; *s.d.*, superior pyramidal decussation. (Modified from Schwalbe.)

and fasciculus cuneatus (370, *n.g.* and *n.c.*), which are at this level, however, already diminishing and are lost at a level of the pons Varolii.

The olivary bodies extend forward almost to the level of the pons. They consist of gray and white matter. The gray matter consists of a plicated thinnish strand containing small nerve-cells, folded upon itself in the form of a loop, with the ends turned inward and slightly dorsal (Fig. 371, *o*). The gray loop is filled with and covered by white matter, part of the fibres passing through the gray.

Internal to the olivary body on either side are two small masses gray matter, one more ventral to the other, called accessory olives, ternal and internal, and on the surface of the anterior pyramid on eit

a small mass of gray matter, external arcuate nucleus; laterally
her mass of the same material, the representative of the lateral nu-
s of the cord, is seen, viz., the antero-lateral nucleus, which gives
in to the spinal accessory nerve.

t will be necessary to follow as shortly as possible the fibres of the
al cord upward into the bulb and beyond:—

The crossed and direct pyramidal tracts have already been described.
ing definite is known of the antero-lateral descending tracts. The
ellar tracts pass laterally into the restiform bodies and go to the
ellum. The antero-lateral ascending tracts appear to have the
destination and pass directly or indirectly into the cerebellum.
ibres of the postero-median and postero-external columns end in
uclei of the fasciculus gracilis and cuneatus respectively, either in
out the cells contained in those nuclei; at any rate, ascending de-
ation of these columns cannot be traced above these nuclei.

he rest of the fibres of the cord appear to end in the reticular for-
n of the bulb. The bundle of fibres constituting the ascending
f the 5th nerve appears to correspond with the tract of Lissauer.

*onnections of the bulb with the cerebrum and cerebellum.*—In addition



g. 371.—Section of the medulla oblongata at about the middle of the olivary body. *f.l.a.*,
or median fissure; *n.ar.*, nucleus arciformis; *p.*, pyramid; *XII.*, bundle of hypoglossal
emerging from the surface; at *b*, it is seen coursing between the pyramid and the olivary
s, *o.*; *f.a.e.*, external arciform fibres; *n.l.*, nucleus lateralis; *a.*, arciform fibres passing
restiform body, partly through the substantia gelatinosa, *g.*, partly superficial to the
ing root of the fifth nerve, *a, V.*; *X*, bundle of vagus root emerging; *f.r.*, formatio retic-
; *c.r.*, corpus restiform, beginning to be formed, chiefly by arciform fibres, superficial
ep; *n.c.*, nucleus cuneatus; *n.g.*, nucleus gracilis; *t*, attachment of the ligula; *f.s.*, funi-
solitarius; *n.X.*, *n.X.'*, two parts of the vagus nucleus; *n.XII.*, hypoglossal nucleus; *n.t.*,
s of the funiculus teres; *n.am.*, nucleus ambiguus; *r.*, raphe; *A.*, continuation of the
r column of cord; *o'*, *o"*, accessory olivary nucleus; *p.o.*, pedunculus olivæ. (Modified
chwalbe.)

to the pyramidal tracts connecting the bulb with the cerebrum and the direct cerebellar and the antero-lateral ascending tract connecting it with the cerebellum, there are other connections of the bulb with the cerebrum, and with the cerebellum, not actually direct.

(1.) Fibres from the nucleus gracilis and nucleus cuneatus, which, as we have said, are the bulbar endings of the fibres of the postero-median and postero-external columns of the cord, pass in sets as it were in the following manner:—

(*a.*) *Internal arcuate fibres.*—Some pass down and inward to the other side in the reticular formation, forming in part the superior or sensory decussation, and in the inter-olivary region become longitudinal in a band of fibres called the *fillet*, which passes upward. These fibres are probably augmented by the addition of fibres from the anterior columns of the cord.

(*b.*) *External arcuate* fibres also decussate in the same way, pass down along the anterior fissure, and then running outward superficially over the anterior pyramid and olivary body, reach the restiform body and pass to the side of the cerebellum opposite to their nuclei of origin. These fibres appear to have some relation with the external arcuate nuclei. They connect one side of the spinal cord with the opposite side of the cerebellum through the gracile and cuneate nuclei.

(*c.*) *Direct lateral fibres* pass to the restiform body and so to the same side of the cerebellum.

(2.) *Fibres from the olivary body* pass to the opposite side of the cerebellum probably through the reticular formation.

(3.) *Arciform fibres.*—Fibres from the nucleus of the 8th or auditory nerve in the floor of the 4th ventricle, pass to the same side of the cerebellum.

### FUNCTIONS OF THE BULB OR MEDULLA OBLONGATA.

The functions of the bulb are those of, (*a.*) conduction; (*b.*) reflex action; and (*c.*) automatism.

(*a.*) *Conduction.*—As a conductor of impressions, the medulla oblongata has a wider extent of function than any other part of the nervous system, since it is obvious that all impressions passing to and fro between the brain and the spinal cord must be transmitted through it.

(*b.*) *Reflex Action.*—As a nerve centre by which impressions are *reflected*, the medulla oblongata also resembles the spinal cord; the only difference between them consisting of the fact that many of the reflex actions performed by the former are much more complicated than any performed by the spinal cord.

It has been proved by repeated experiments on the lower an
that the entire brain may be gradually cut away in successive port

l yet life may continue for a considerable time, and the respiratory vements be uninterrupted. Life may also continue when the spinal d is cut away in successive portions from below upward as high as point of origin of the phrenic nerve. In amphibia, the brain has n all removed from above, and the cord, as far as the medulla oblon- ta, from below; and so long as the medulla oblongata was intact, piration and life were maintained. But if, in any animal, the me- lla oblongata is wounded, particularly if it is wounded in its central rt, opposite the origin of the vagi, the respiratory movements cease, d the animal dies asphyxiated. And this effect ensues even when all rts of the nervous system, except the medulla oblongata, are left intact.

Injury and disease in men prove the same as these experiments on imals. Numerous instances are recorded in which injury to the me- lla oblongata has produced instantaneous death; and, indeed, it is rough injury of it, or of the part of the cord connecting it with the igin of the phrenic nerve, that death is commonly produced in frac- res attended by sudden displacement of the upper cervical vertebræ.

## Special Centres.

In the medulla are contained a considerable number of centres which side over many important and complicated co-ordinated movements muscles. The majority of these centres are (*a.*) *reflex centres* simply, ich are stimulated by afferent or by voluntary impressions. Some of m are (*b.*) *automatic centres*, being capable of sending out efferent pulses, generally rhythmical, without previous stimulation by afferent by voluntary impressions. The automatic centres are, however, gen- lly influenced by reflex or by voluntary impulses. Some again of the tres, whether reflex or automatic, are (*c.*) *control centres*, by which sidiary spinal centres are governed. Finally the action of some of the tres is (*d.*) *tonic*, *i.e.*, they exercise their influence either directly or ough another apparatus, continuously and uninterruptedly in main- ning a regular action.

### Simple Reflex centres.

(1.) Bilateral centres for the co-ordinated movements of ***Mastication***, afferent and efferent nerves of which have been already enumerated 346).

(2.) Bilateral centres for the movements of *Deglutition*. The medulla ongata appears to contain the centre whence are derived the motor ulses enabling the muscles of the palate, pharynx, and œsophagus to duce the successive co-ordinate and adapted movements necessary to act of deglutition (p. 365). This is proved by the persistence of llowing in some of the lower animals after destruction of the cerebral hemispheres and cerebellum; its existence in anencephalous monsters; the power of swallowing possessed by the marsupial embryo before the brain is developed; and by the complete arrest of the power of swallowing when the medulla oblongata is injured in experiments.

(3.) Bilateral centres for the combined muscular movements of *Sucking*, the motor nerves concerned being the facial for the lips and mouth, the hypoglossal for the tongue, and the inferior maxillary division of the 5th for the muscles of the jaw.

(4.) Bilateral centres for the *Secretion of Saliva*, which have been already mentioned (p. 354).

(5.) Bilateral centres for *Vomiting* (p. 383).

(6.) Bilateral centres for *Coughing*, which are said to be independent of the respiratory centre, being situated above the inspiratory part of that centre.

(7.) Bilateral centres for *Sneezing*, connected no doubt with the respiratory centre.

(8.) Bilateral centres for the *Dilatation of the pupil*, the fibres from which pass out partly in the third nerve and partly through the spinal cord (through the last two cervical and two upper dorsal nerves?) into the cervical sympathetic.

(*b.*) **Automatic centres.**

(1.) *Respiratory centres.*—The action of the respiratory centre has been already discussed. It is only necessary to repeat here that although it can be influenced by afferent impulses, it is also automatic in its action, being capable of direct stimulation, as by the condition of the blood circulating within it. It is also bilateral. It probably consists of an inspiratory part and of an expiratory part. The centre is capable of being influenced both reflexly and to a certain extent also by voluntary impulses. The vagus influence is probably constant in the direction of stimulating the inspiratory portion of the centre, whereas the influence of the superior laryngeal is not always in action, and is inhibitory.

(2.) *Cardio-Inhibitory* centres. The action of these centres in maintaining the proper rhythm of the heart through the vagus fibres, which terminate in a local intrinsic mechanism, has been already discussed. The centre can be directly stimulated, as by the condition of the blood circulating within it, and also indirectly by afferent stimuli, especially by stimulating the abdominal sympathetic nerves, but also by stimulating any sensory nerve, including the vagus itself.

(3.) *Accelerator* centres for the heart. The centres from which arise the accelerator fibres of the heart, in the medulla. They are automatic but not tonic in action.

(4.) *Vaso-motor* centres, which control the unstriped muscle of the arteries, are also situated in the medulla. Like the respiratory centre, are bilateral. As has already been pointed out, these centres may irectly or reflexly stimulated, as well as by impressions conveyed ward from the cerebrum to the medulla. The condition of the circulating in them is the direct stimulus. Its influence is no t a tonic or else a rhythmic one. It is also supposed that there is e medulla a special *vaso-dilator* centre not acting tonically, stimu- of which produces vascular dilatation. The *diabetic* centre is ly a part of the vaso-motor centre, at any rate stimulation of it s dilatation of the vessels of the liver.

.) Bilateral chief centres for the secretion of *Sweat* exist in the lla. The centres on either side control the subsidiary spinal sweat es. They may be excited unequally so as to produce unilateral ing. They are probably automatic and reflex.

.) Bilateral *Spasm* centres are said to be present in the medulla, e stimulation of which, as by suddenly produced excessive venosity blood, general spasms of the muscles of the body are produced.

.) **Control centres.** These are centres whose influence may be ted to controlling the action of subsidiary centres. They are—

.) The *Respiratory* centres, which probably control the action of subordinate centres in the spinal cord.

.) The *Cardio-Inhibitory* centres, which act upon a local ganglionic anism in the heart.

.) The *Accelerator* centres, if they exist, probably act through a mechanism in the heart.

.) The *Vaso-motor* centres control spinal as well as local tonic es.

.) The medullary *Sweat* centres control the spinal sweat centres.

.) **Tonic centres.** Of the centres whose action is tonic or con- us up to a certain degree, may be cited the *vaso-motor* and the *car- hibitory.*

t should not be forgotten that in the medulla are intermediate cen- for the special senses, *Hearing* and *Taste*, and that other special es are supposed to be localized there, of which may be mentioned the hypothetical *Inhibitory heat centre*, which controls the pro- ion of heat by the tissues, independently of the vaso-motor centre.

## The Cranial Nerves.

he cranial nerves consist of twelve pairs; they appear to arise (su- ial origin) from the base of the brain in a double series, which ds from the under surface of the anterior part of the cerebrum to ower end of the medulla oblongata. Traced into the substance of rain and medulla, the roots of the nerves are found to take origin various masses of gray matter.

The roots of the first or olfactory and of the second or optic nerves will be mentioned elsewhere. The third and fourth nerves arise from gray matter beneath the corpora quadrigemina; and the roots of origin of the remainder of the cranial nerves can be traced to gray matter in the floor of the fourth ventricle, and in the more central part of the medulla, around its central canal, as low down as the decussation of the pyramids.

According to their several functions the cranial nerves may be thus arranged:—

| | |
|---|---|
| a. Nerves of special sense . | Olfactory, Optic, Auditory, part of the Glosso-pharyngeal, and part of the Fifth. |
| b. Nerves of common sensation . | The greater portion of the Fifth. |
| c. Nerves of motion . . . . | Third, Fourth, lesser division of the Fifth, Sixth, Facial, and Hypoglossal. |
| d. Mixed nerves . . . . . | Glosso-pharyngeal, Vagus, and Spinal accessory. |

The physiology of the First, Second, and Eighth will be considered with the organs of **Special sense.**

### The IIIrd Nerve (*Motor Oculi*).

*Origin.*—The third nerve arises in three distinct bands of fibres from the gray matter surrounding the aqueduct of Sylvius near the middle line ventral to the canal. The nucleus of origin consists of large multi-polar ganglion-cells, and extends to the back part of the third vent



Fig. 372.—Section through anterior corpus quadrigeminum and part of optic thalamus. *a.*, Aqueduct of Sylvius; *gr.*, gray matter of the aqueduct; *c.q.s.*, quadrigeminal eminence; *l.*, stratum lemnisci; *o.*, stratum opticum; *c.*, stratum cinereum; *Th.*, pulvinate of optic thalamus; *c.g.e.*, *c.g.i.*, lateral and median corpora geniculata; *br.s.*, *br.i.*, superior and inferior brachia; *f.*, fillet; *p.l.*, posterior longitudinal bundle; *r.*, raphé; *III.*, third nerve, and *n. III.*, its nucleus; *l.p.p.*, posterior perforated space; *s.n.*, substantia nigra, above this is the tegmentum with the circular area of the red nucleus; *cr.*, crusta; *II.*, optic tract; *M.*, medullary centre of hemisphere; *n.c.*, nucleus caudatus; *st.*, stria terminalis. (After Quain, from Meynert.)

as far as the level of the anterior corpus quadrigeminum. The pass from their origin partly through the red nucleus to their supe in in front of the pons, at the median side of each crus. They de- ate with their fellows in the middle raphe. The nerve is connected ı the optic nerve.

*Function.*—It supplies the levator palpebræ superioris muscle, and of the muscles of the eyeball, except the superior oblique to which



ig. 373.—Diagram of a longitudinal section through the pons, showing the relation of the i for the ocular muscles. CQ, corpora quadrigemina; 3, third nerve; III, its nucleus; 4, h nerve; IV, its nucleus, the posterior part of the third; 6, sixth nerve. The probable ion of the centre and nerve fibres for accommodation is shown at *a* and *a'*, for the reflex n of iris, at *b*, and *b'*; for the external rectus muscles, at *c*, *c'*. The lines beneath the of the fourth ventricle indicate fibres, which connect the nuclei. (Gowers.)

fourth nerve is appropriated, and the rectus externus which receives sixth nerve. Through the medium of the ophthalmic or lenticular glion, of which it forms what is called the short root, it also supplies or filaments to the iris and ciliary muscle. The fibres which sub- e the three functions, accommodation, contraction of the pupil, and 'e-supply to the external ocular muscles, arise from three distinct ıps of cells.

When the third nerve is irritated within the skull, all those muscles hich it is distributed are convulsed. When it is *paralyzed* or *divided* following effects ensue:—(1) the upper eyelid can be no longer ed by the levator palpebræ, but droops (*ptosis*) and remains gently ed over the eye, under the unbalanced influence of the orbicularis ebrarum, which is supplied by the facial nerve: (2) the eye is turned ward and downward (*external strabismus*) by the unbalanced action the rectus externus and superior oblique to which the sixth nerve is ropriated; and hence, from the irregularity of the axes of the eyes, ble sight, *diplopia*, is often experienced when a single object is within r of both the eyes: (3) the eye *cannot be moved either upward, down- d*, or *inward:* (4) *the pupil becomes dilated* (mydriasis): (5) the eye not *accommodate* for short distances.

## The IVth Nerve (*Trochlearis*).

*Origin.*—The IVth nerve arises from a nucleus consisting of large tipolar ganglion cells situated below, *i.e.*, ventral to the aqueductus Sylvius, which extends from the back part of the nucleus of the d nerve to the hind level of the posterior corpus quadrigeminum. fibres from either side sweep round the central gray matter, and reach the valve of Vieussens, where they decussate in the middle line and appear at the front of the pons at the lateral edge of the crus. The



Fig. 374.—Fourth ventricle with the medulla oblongata and the corpora quadrigemina. T roman numbers indicate superficial origins of the cranial nerves, while the other number dicate their deep origins, or the position of their central nuclei. 8, 8', 8'', 8''', auditory nerves; t, funiculus teres; A, B, corpora quadrigemina; c. g, corpus geniculatum; p, c, pe culus cerebri; m, c, p, middle cerebellar peduncle; s, c, p, superior cerebellar peduncle; i, c, p, inferior cerebellar peduncle; l, c, locus cæruleus; e, t, eminentia teres; a, c, ala cinerea; a, n, accessory nucleus; o, obex; c, clava; f, c, funiculus cuneatus; f, g, funiculus gracilis.

nucleus of the fourth nerve on either side is connected with those of the third and sixth nerves.

*Functions.*—The IVth nerve is exclusively motor, and supplies only the trochlearis or obliquus superior muscle of the eyeball.

## The Vth Nerve (*Trigeminus*).

*Origin.*—The Vth or Trigeminal nerve resembles, as already stated, the spinal nerves, in that its branches are derived through two roots; namely, the larger or *sensory*, in connection with which is the Gasserian ganglion, and the smaller or *motor* root which has no ganglion, and which passes under the ganglion of the sensory root to join the third branch or division which ensues from it. The fibres of origin of the fifth nerve come from the floor of the fourth ventricle. The motor ro to the inside of the sensory, about the middle of each lateral half. T sensory fibres, however, can be traced down in the medulla oblongata far as the upper part of the cord. From the motor nucleus the stretches forward as far as the anterior corpus quadrigeminum a bun of long fibres termed the descending root, which has attached to it sp spheroidal nerve-cells. It is also connected with the locus cærule The sensory nucleus outside the motor has connected with it a tract ibres from the cord as low as the second cervical nerve, and this forms tract at the tip of the posterior cornu, between it and the restiform ody. No nerve cells are connected with it. The roots can be traced bliquely through the pons Varolii, beneath the floor of the front part f the fourth ventricle. The motor root is in a position median to ensory. The nerve appears at the ventral surface of the pons near its ront edge, at some distance from the middle line.

*Function.*—The first and second divisions of the nerve, which arise holly from the larger root, are purely sensory. The third division eing joined, as before said, by the motor root of the nerve, is of course oth motor and sensory.

(a.) *Motor.*—Through branches of the lesser or non-ganglionic porion of the fifth, *the muscles of mastication*, namely, the temporal, master, two pterygoid, anterior part of the digastric, and mylohyoid, erive their motor nerves. Filaments are also supplied to the *tensor mpani and tensor palati.* The motor function of these branches is roved by the violent contraction of all the muscles of mastication in perimental irritation of the third or inferior maxillary division of the erve; by paralysis of the same muscles, when it is divided or disorgan-



ig. 375.—Section across the pons, about the middle of the fourth ventricle. *py.*, pyramidal dles; *po.*, transverse fibres passing $po_1$, behind, and $po_2$, in front of *py.*; *r.*, raphé; *o.s.*, suor olive; *a. V.*, bundles of ascending root of *V.* nerve inclosed in a prolongation of the subce of Rolando; *VI.*, the sixth nerve, *n VI.*, its nucleus; *VII.*, facial nerve; *VII.a.*, inediate portion, *n. VII.*, its nucleus; *VIII.*, auditory nerve, *n VIII.*, lateral nucleus of the tory. (After Quain.)

or from any reason deprived of power; and by the retention of the of these muscles, when all those supplied by the facial nerve lose power through paralysis of that nerve. The last instance proves that though the buccinator muscle gives passage to, and receives some filaments from, a buccal branch of the inferior division of the fifth nerve, yet it derives its motor power from the facial, for it is paralyzed together with the other muscles that are supplied by the facial, but retains its power when the other muscles of mastication are paralyzed. Whether, however, the branch of the fifth nerve which is supplied to the buccinator muscle is entirely sensory, or in part motor also, must remain for the present doubtful. From the fact that this muscle, besides its other functions, acts in concert or harmony with the muscles of



Fig. 376.—General plan of the branches of the fifth pair. ⅙.—1, lesser root of the pair; 2, greater root passing forward into the Gasserian ganglion; 3, placed on the bone the ophthalmic nerve, which is seen dividing into the supra-orbital, lachrymal, and branches, the latter connected with the ophthalmic ganglion; 4, placed on the bone close foramen rotundum, marks the superior maxillary division, which is connected below with spheno-palatine ganglion, and passes forward to the infra-orbital foramen; 5, placed on the over the foramen ovale, marks the inferior maxillary nerve, giving off the anterior and muscular branches, and continued by the inferior dental to the lower jaw, and by the tatory to the tongue; *a*, the submaxillary gland, the submaxillary ganglion placed above connection with the gustatory nerve; 6, the chorda tympani; 7, the facial nerve issuing the stylomastoid foramen. (Charles Bell.)

mastication, in keeping the food between the teeth, it might be sup posed from analogy, that it would have a motor branch from the sam nerve that supplies them. There can be no doubt, however, that th so-called buccal branch of the fifth is, in the main, sensory; althoug it is not quite certain that it does not give a few motor filaments to th buccinator muscle.

(b.) *Sensory.*—Through the branches of the greater or ganglion portion of the fifth nerve, all the anterior and antero-lateral parts of th

and head, with the exception of the skin of the parotid region
ich derives branches from the cervical spinal nerves), acquire com-
sensibility; and among these parts may be included the organs of
ial sense, from which common sensations are conveyed through the
nerve, and their special sensations through their several nerves of
ial sense. The muscles, also, of the face and lower jaw acquire
cular sensibility, through the filaments of the ganglionic portion of
fifth nerve distributed to them with their proper motor nerves. The
ory function of the branches of the greater division of the fifth nerve
roved, by all the usual evidences, such as their distribution in parts
are sensitive and not capable of muscular contraction, the exceeding
ibility of some of these parts, their loss of sensation when the nerve
ralyzed or divided, the pain without convulsions produced by mor-
or experimental irritation of the trunk or branches of the nerve,
the analogy of this portion of the fifth to the posterior root of the
al nerve.

*ther Functions.*—In relation to *muscular movements*, the branches
he greater or ganglionic portion of the fifth nerve exercise a mani-
influence on the movements of the muscles of the head and face
other parts in which they are distributed. They do so, in the first
e (*a*), by providing the muscles themselves with that sensibility
out which the mind, being unconscious of their position and state,
ot voluntarily exercise them. It is, probably, for conferring this
ibility on the muscles, that the branches of the fifth nerve commu-
te so frequently with those of the facial and hypoglossal, and the
es of the muscles of the eye; and it is because of the loss of this
bility that when the fifth nerve is divided, animals are always slow
awkward in the movement of the muscles of the face and head, or
them still, or guide their movements by the sight of the objects
rd which they wish to move.

*b*.) Again, the fifth nerve has an indirect influence on the muscular
ements, by conveying sensations of the state and position of the skin
other parts: which the mind perceiving, is enabled to determine
opriate acts. Thus, when the fifth nerve or its infra-orbital branch
vided, the movement of the lips in feeding may cease, or be imper-

*c*.) An intimate connection with muscular movements through the
y reflex acts of muscles of which it is the necessary excitant. Hence,
n it is divided and can no longer convey impressions to the nervous
res to be thence reflected, the irritation of the conjunctiva produces
losure of the eye, the mechanical irritation of the nose excites no
zing.

(*d*.) Through its ciliary branches and the branch which forms the long root of the ciliary or ophthalmic ganglion, it exercises also some influence on the movements of the iris. When the trunk of the ophthalmic portion is divided, the pupil becomes, according to Valentin, contracted in men and rabbits, and dilated in cats and dogs; but in all cases, becomes immovable even under all the varieties of the stimulus of light. How the fifth nerve thus affects the iris is unexplained; it has been ingeniously suggested the influence of the fifth nerve on the movements of the iris may be ascribed to the affection of vision in consequence of the disturbed circulation or nutrition in the retina, when the normal influence of the fifth nerve is disturbed. In such disturbance, increased circulation making the retina more irritable might induce extreme contraction of the iris.

*Trophic influence.*—The morbid effects which division of the fifth nerve produces in the organs of special sense, make it probable that, in the normal state, the fifth nerve exercises some special or *trophic* influence on the nutrition of all these organs; although, in part, the effect of the section of the nerve is only indirectly destructive by abolishing sensation, and therefore the natural safeguard which leads to the protection of parts from external injury. Thus, after such division, within a period varying from twenty-four hours to a week, the cornea begins to be opaque; then it grows completely white; a low destructive inflammatory process ensues in the conjunctiva, sclerotica, and interior parts of the eye; and within one or a few weeks, the whole eye may be quite disorganized, and the cornea may slough or be penetrated by a large ulcer. The sense of smell (and not merely that of mechanical irritation of the nose), may be at the same time lost or gravely impaired; so may the hearing, and commonly, whenever the fifth nerve is paralyzed, the tongue loses the sense of taste in its anterior and lateral parts, and according to Gowers in the posterior part as well.

*In relation to Taste.*—The loss of tactile sensibility as well as the sense of taste, is no doubt due (*a*) to the lingual branch of the fifth nerve being a nerve of tactile sense, and also because with it runs the chorda tympani, which is one of the nerves of taste; partly, also, it is due (*b*), to the fact that this branch supplies, in the anterior and lateral parts of the tongue, a necessary condition for the proper nutrition of that part; while (*c*), it forms also one chief link in the nervous circle for reflex action, in the secretion of saliva. But, deferring this question until the glosso-pharyngeal nerve is to be considered, it may be observed that in some brief time after complete paralysis or division of the fifth nerve, the power of all the organs of the special senses may be lost; they may lose not merely their sensibility to common impressions, for which they all depend directly on the fifth nerve, but also their sensibility to their several peculiar impressions for the reception and conduction of which are purposely constructed and supplied with special nerves besides fifth. The facts observed in these cases can, perhaps, be only ex- ned by the influence which the fifth nerve exercises on the nutritive esses in the organs of the special senses. It is not unreasonable to ve, that, in paralysis of the fifth nerve, their tissues may be the of such changes as are seen in the laxity, the vascular congestion, na, and other affections of the skin of the face and other tegumen- parts which also accompany the paralysis; and that these changes, h may appear unimportant when they affect external parts, are ient to destroy that refinement of structure by which the organs of pecial senses are adapted to their functions.

## The VIth Nerve (*Abducens*).

*rigin.*—The VIth nerve arises from a compact oval nucleus, situ- somewhat deeply at the back part of the pons near the middle of loor of the fourth ventricle. The eminentia teres marks its posi- . It contains moderately large nerve-cells with distinct axis cylin- processes. It is connected (fig. 373) with the nuclei of the third, th, and seventh nerves. It is nearer the middle line than the nuclei he fifth and seventh. The root is thin, and passes ventrally and ally through the reticular formation, to the surface, which it reaches e hind end of the pons opposite the front end of anterior pyramid.

*unctions.*—The sixth nerve is exclusively motor, and supplies only ectus externus muscle of the eye.

he rectus externus is convulsed, and the eye is turned outward, the sixth nerve is irritated; and the muscle is paralyzed when the e is divided. In all such cases of paralysis, the eye squints inward, cannot be moved outward.

n its course through the cavernous sinus, the sixth nerve forms er communications with the sympathetic nerve than any other nerve in the cavity of the skull does. But the import of these communi- ons with the sympathetic, and the subsequent distribution of its ments after joining the sixth nerve, are quite unknown.

## The VIIth Nerve (*Facial*).

*Origin.*—The facial, or *portio dura* of the seventh pair of nerves, es from the floor of the central part of the fourth ventricle behind in line with the motor nucleus of the fifth, to the outside of and er down than the nucleus of the sixth. The nucleus is narrower in t than behind, and consists of large cells with well marked axis nder-processes, which are gathered up at the dorsal surface of the eus to form a root. The root describes a loop round the nucleus of the sixth nerve, running forward for some little distance dorsal to the nucleus, then descending vertically, passing to outside of its own nucleus between it and the ascending root of the fifth nerve. It emerges at the hinder margin of the pons lateral to the sixth nerve, opposite the front edge of the groove between the olivary and restiform bodies. It may be connected with the hypoglossal nucleus. There are two roots; the lower and smaller is called the portio intermedia.

*Functions.*—The seventh nerve is the motor nerve of all the muscles of the face, including the platysma, but not including any of the muscles of mastication already enumerated; it supplies, also, the parotid gland, and through the connection of its trunk with the Vidian nerve, by the petrosal nerves, some of the muscles of the soft palate, probably the levator palati and azygos uvulæ. By its tympanic branches it supplies the stapedius and laxator tympani; and through the optic ganglion, the tensor tympani; through the *chorda tympani* it sends branches to the submaxillary gland and to the lingualis and some other muscular fibres of the tongue, and to the mucous membrane of its anterior two-thirds; and by branches given off before it comes upon the face, it supplies the muscles of the external ear, the posterior part of the digastricus, and the stylo-hyoideus.

Beside its motor influence, the facial is also, by means of the fibres which are supplied to the submaxillary and parotid glands, a *secretory* nerve. For, through the last-named branches, impressions may be conveyed which excite increased secretion of saliva.

*Paralysis of Facial Nerve.*—When the facial nerve is divided, or in any other way paralyzed, the loss of power in the muscles which it supplies, while proving the nature and extent of its functions, displays also the necessity of its perfection for the perfect exercise of all the organs of the special senses. Thus, in paralysis of the facial nerve, the orbicularis palpebrarum being powerless, the eye remains open through the unbalanced action of the levator palpebræ; and the conjunctiva, thus continually exposed to the air and the contact of dust, is liable to repeated inflammation, which may end in thickening and opacity of the cornea. These changes, however, ensue much more slowly than those which follow paralysis of the fifth nerve, and never bear the same destructive character.

The sense of hearing, also, is impaired in many cases of paralysis of the facial nerve; not only in such as are instances of simultaneous disease in the auditory nerves, but in such as may be explained by the loss of power in the muscles of the internal ear. The sense of smell is commonly at the same time impaired through the inability to draw air briskly toward the upper part of the nasal cavities in which part alone the olfactory nerve is distributed; because, to draw the air perfectly direction, the action of the dilators and compressors of the nos-s should be perfect.

Lastly, the sense of taste is impaired, or may be wholly lost in paral- of the facial nerve, provided the source of the paralysis be in some t of the nerve between its origin and the giving off of the chorda tym- i. This result, which has been observed in many instances of disease he facial nerve in man, appears explicable on the supposition that the rda tympani is the nerve of taste to the anterior two-thirds of the gue, its fibres being distributed with the so-called gustatory or lingual ich of the fifth. Some look upon the chorda as partly or entirely e up of fibres from the fifth nerve, and not strictly speaking as a ich of the facial; others consider that it receives its taste fibres from munications with the glosso-pharyngeal.

Together with these effects of paralysis of the facial nerve, the mus- of the face being all powerless, the countenance acquires on the lyzed side a characteristic, vacant look, from the absence of all ex- sion: the angle of the mouth is lower, and the paralyzed half of the th looks longer than that on the other side; the eye has an unmean- stare. All these peculiarities increase, the longer the paralysis ; and their appearance is exaggerated when at any time the muscles he opposite side of the face are made active in any expression, or in of their ordinary functions. In an attempt to blow or whistle, one of the mouth and cheeks acts properly, but the other side is mo- less, or flaps loosely at the impulse of the expired air; so in trying ick, one side only of the mouth acts; in feeding, the lips and cheeks owerless, and on account of paralysis of the buccinator muscle food es between the cheek and gums.

## The VIIIth Nerve (*Auditory*).

*Origin.*—The VIIIth nerve arises from two nuclei, *median* and *lat-* in the floor of the fourth ventricle, in the anterior part of the in front and to the side of the twelfth nerve; it extends from the lle line to the outside margin of the ventricle. There is also an *sory* nucleus situated on the ventral surface of the restiform body. nerve leaves the surface of the brain from the ventral surface of the part of the restiform body at the hind margin of the pons in two s. One winds round the restiform body dorsal to it and the other es median to it. The former is called the *dorsal root.* The latter lled the *ventral root.* Most of the fibres of the dorsal root (*cochlear*) in cells of the *accessory* nucleus, but fibres emerging from this nu- s pass inward to the bulb, superficially, forming the *striæ acusticæ* e floor of the fourth ventricle and end in the median nucleus. Most of the fibres of the ventral root (*vestibular*) end in cells of the lateral nucleus. The cells of the median nucleus are small, those of the lateral nucleus large.

*Functions.*—The cochlear branch is the auditory nerve proper, and the vestibular is distributed to the semicircular canals, the utricule and saccule, parts of the internal ear not directly concerned with hearing.

## The IXth Nerve (*Glosso-Pharyngeal*).

*Origin.*—The glosso-pharyngeal nerves (ix., fig. 364), in the enumeration of the cerebral nerves by numbers according to the position in which they leave the cranium, are considered as divisions of the *eighth pair of nerves*, the vagus and spinal accessory nerves being included with them. The union of the nuclei is indeed so intimate that it will be as well to take the origins of the ninth, tenth, and eleventh nerves together.

These three nerves emerge from the bulb and spinal cord in their numerical order from above downward, the *bulbar portion* from the lateral aspect of the bulb in a line between the olivary and restiform bodies; and the *spinal portion* from a line intermediate between the anterior and posterior nerve roots as far down as the sixth or seventh cervical.

The combined glosso-pharyngeal-accessory-vagus nucleus appears to consist of two parts, viz., one *median* or common origin, having conspicuous nerve-cells of moderate size, and three *lateral origins*, having but few cells of small size. These are—i. the *nucleus ambiguus*, which lies on the lateral side of the reticular formation and is the origin of the vagus; ii. the *fasciculus solitarius*, situated in the bulb, ventral and a little lateral to the combined nucleus, is also called the ascending root of the glosso-pharyngeal nerve or the respiratory bundle; and iii. the *spinal portion* which takes origin from a group of cells lying in the extreme lateral margin of the anterior cornu. This is the origin of the spinal accessory; it corresponds to the antero-lateral nucleus of the bulb, and the lateral part of the gray matter of the spinal cord.

The fibres of the spinal origin of the nerve pass from these cells through the lateral column to the surface of the cord.

The fibres from the *combined nucleus*, chiefly from the *median part*, pass in a ventral and lateral direction through the reticular formation, then ventral to or through the gelatinous substance and strand of fibres connected with the fifth nerve, to the surface of bulb.

The fibres from the *nucleus ambiguus* join the combined nerve, but especially the vagus.

The bundles of fibres of the *fasciculus solitarius* start in the lateral gray matter of the cervical cord and higher in the reticular formation of the bulb, run longitudinally forward to pass into the roots of the ninth nerve.

*Nerve.—Distribution.*—The glosso-pharyngeal nerve gives fila- hrough its tympanic branch (Jacobson's nerve), to the fenestra d fenestra rotunda, and the Eustachian tube, parts of the mid- also, to the carotid plexus, and through the petrosal nerve, to eno-palatine ganglion. After communicating, either within or the cranium, with the vagus, and soon after it leaves the cra- ith the sympathetic, digastric branch of the facial, and the y nerve, the glosso-pharyngeal nerve parts into the two principal s indicated by its name, and supplies the mucous membrane of erior and lateral walls of the upper part of the pharynx, the ian tube, the arches of the palate, the tonsils and their mucous ne, and the tongue as far forward as the foramen cæcum in the ine, and to near the tip at the sides and inferior part.

*tions.*—The glosso-pharyngeal nerve contains some motor fibres, with those of common sensation and the sense of taste.

**otor** fibres are distributed to the palato-pharyngeus, the stylo- eus, palato-glossus, and constrictors of the pharynx.

**ensory** fibres in the parts which it supplies, and a centripetal rough which impressions are conveyed to be reflected to the ad- uscles.

ibres for the SPECIAL NERVE of taste (from its fibres derived from , Gowers), in all the parts of the tongue and palate to which it is ted. After many discussions, the question, Which is the nerve —the chorda tympani, the gustatory, or the glosso-pharyngeal? e most probably answered by stating that they are not them- rictly speaking, nerves of this special function, but through nnection with the fifth nerve. For very numerous experiments s have shown that when the trunk of the fifth nerve is paralyzed ed, the sense of taste is completely lost in the superior surface terior and lateral parts of the tongue, at the back of the tongue, the soft palate and palatine arches. The loss is instantaneous ision of the nerve, and, therefore, cannot be ascribed wholly to ctive nutrition of the part, though to this, perhaps, may be the more complete and general loss of the sense of taste when e of the fifth nerve has been paralyzed.

### The Xth Nerve (*Vagus or Pneumogastric*).

origin of the Vagus nerve is, as we have just seen, situated in r half of the calamus scriptorius in the ala cinerea (fig. 374). us is said to represent the cells of Clarke's (posterior vesicular) of the spinal cord. In origin it is closely connected with the leventh, and the twelfth. The combined glosso-pharyngeal-vago-accessory nuclei lie outside of, close to, and parallel with the nucleus of the twelfth.

*Distribution.*—It supplies sensory branches, which accompany the sympathetic on the middle meningeal artery, and others which supply the back part of the meatus and the adjoining part of the external ear. It is connected with the petrous ganglion of the glosso-pharyngeal, by means of fibres to its jugular ganglion; with the spinal accessory which supplies it with its motor fibres for the larger and upper portion of the œsophagus, and with its inhibitory fibres for the heart; also with the twelfth; with the superior cervical ganglion of the sympathetic; and with the cervical plexus. It has, of all the nerves, the most varied distribution and functions, either through its own filaments, or through those which, derived from other nerves, are mingled in its branches. The parts supplied by the branches of the vagus are as follows:—

(1.) By its *pharyngeal* branches, which enter the pharyngeal plexus, a large portion of the mucous membrane, and, probably, all the muscles of the pharynx.

(2.) By the *superior laryngeal* nerve, the mucous membrane of the under surface of the epiglottis, the glottis, and the greater part of the larynx, and the crico-thyroid muscle.

(3.) By the *inferior laryngeal nerve*, the mucous membrane and muscular fibres of the trachea, the lower part of the pharynx and larynx, and all the muscles of the larynx except the crico-thyroid. It also supplies the first segment of the œsophagus.

(4.) By its *œsophageal* branches, the mucous membrane and muscular coats of the œsophagus.

(5.) Through the *cardiac nerves*, moreover, the branches of the vagus form a large portion of the supply of nerves to the heart and the great arteries.

(6.) Through the anterior and the posterior *pulmonary* plexuses to the lungs.

(7.) Through its *gastric* branches to the stomach; and to the intestines, and kidneys, by its terminal branches.

(8.) Through its *hepatic* and *splenic* branches, the liver and the spleen are partly supplied with nerves.

*Functions.*—Throughout its whole course, the vagus contains both sensory and motor fibres. To summarize the many functions of this nerve, which have been for the most part considered in the preceding chapters, it may be said that it supplies (1) **motor** influence to pharynx and œsophagus, stomach and intestines, to the larynx, trac bronchi, and lung; (2) **sensory** and, in part, (3) **vaso-motor** influe to the same regions; (4) **inhibitory** influence to the **heart;** (5) inh



Fig. 377.



Fig. 378.

. 377.—The distribution of the tenth or vagus nerve. *Va.R.*, *Va.L.*, Right and left vagi; *r*, n of the root and connections with *Sy.*, sympathetic, superior cervical ganglion; *g.Ph.*, glosso-geal; *Acc.*, spinal accessory nerve; *m*, meningeal branch; *Aur.*, auricular branch; *t*, ganglion runk and connections with *Hy.*, hypoglossal nerve; *C* 1, *C* 2, loop between the first two cervical *Sy.*, sympathetic; *Acc.*, spinal accessory nerve; *Ph.*, pharyngeal branch; *Ph. Pl.*, pharyngeal *S.L.*, superior laryngeal nerve; *I.L.*, internal laryngeal branch; *E.L.*, external laryngeal ; *I.C.*, internal, and *E.C.*, external carotid arteries; *Ca.* 1, superior cervical cardiac branch; nferior cervical cardiac branch; *R.L.*, recurrent laryngeal nerve; *Ca.* 3, cardiac branches of nt laryngeal nerve; *Ca.* 4, thoracic cardiac branch (right vagus); *A.P.Pl.*, anterior, and , posterior pulmonary plexuses; *Oes.Pl.*, œsophageal plexus; *Gast.R.* and *Gast.L.*, gastric es of vagus (right and left); *Coe.Pl.*, cœliac plexus; *Hep.Pl.*, hepatic plexus; *Spl.Pl.*, splenic *Ren. Pl.*, renal plexus. (Cunningham.)

. 378.—The constitution of the cardiac plexus. *Sy*, Cervical sympathetic cord; *C.* 1, superior, iddle, and *C.* 3, inferior cervical ganglia; *Car.* 1, superior, *Car.* 2, middle, and *Car.* 3, inferior cardiac sympathetic branches; *Va*, vagus nerve; *R.L.*, recurrent laryngeal nerve; *s*, superior, nferior cervical cardiac branches of vagus; *D.C.P.*, deep cardiac plexus; *S.C.P.*, superficial plexus; *A.P.P.*, anterior pulmonary plexus; *P.P.P.*, posterior pulmonary plexus; *R. Car. P.*, nd *L. Car. P.*, left coronary plexuses; *Art.Pul.*, pulmonary artery. (Cunningham.)

**tory** afferent impulses to the **vaso-motor centre** ; (6) **excito-secretory** to the salivary glands; (7) **excito-motor** in coughing, vomiting, etc.

*Effects of Section.*—Division of both vagi, or of both their recurrent branches, is often very quickly fatal in young animals; but in old animals the division of the recurrent nerve is not generally, and that of both the vagi is not always, fatal, and, when it is so, death ensues slowly. This difference is, that the yielding of the cartilages of the larynx in young animals permits the glottis to be closed by the atmospheric pressure in inspiration, and so they are quickly suffocated unless tracheotomy be performed. In old animals, the rigidity and prominence of the arytenoid cartilages prevent the glottis from being completely closed by the atmospheric pressure; even when all the muscles are paralyzed, a portion at its posterior part remains open, and through this the animal continues to breathe.

In the case of slower death, after division of both the vagi, the lungs are commonly found gorged with blood, œdematous, or nearly solid, from a kind of low pneumonia, and the bronchial tubes full of frothy bloody fluid and mucus, to which, in general, the death may be ascribed. These changes are due, in part, to the passage of food and of the various secretions of the mouth and fauces through the glottis, which, being deprived of its sensibility, is no longer stimulated or closed in consequence of their contact.

### The XIth Nerve (*Spinal Accessory*).

*Origin and Connections.*—The nerve arises by two distinct origins—one from a centre in the floor of the fourth ventricle, partly but chiefly in the medulla, and connected with the glosso-pharyngeal-vagus-nucleus; the other, from the outer side of the anterior cornu of the spinal cord as low down as the fifth or sixth cervical nerve. The fibres from the two origins come together at the jugular foramen, but separate again into two branches, the inner of which, arising from the medulla, joins the vagus, to which it supplies its motor fibres, consisting of small medullated or visceral nerve-fibres, while the outer consisting of large medullated fibres, supplies the trapezius and sterno-mastoid muscles. The small-fibred branch is said to arise from a nucleus corresponding to the posterior vesicular column of Clarke.

The principal branch of the accessory nerve, its external branch, then supplies the sterno-mastoid and trapezius muscles; and, though pain is produced by irritating it, is composed almost exclusively of motor fibres. The internal branch of the accessory nerve supplies chiefly viscero-motor filaments to the vagus. The muscles of the larynx, all of which, as already stated, are supplied, apparently, by branches of the vagus, are said to derive their motor nerves from the accessory; and

h is a very significant fact) Vrolik states that in the chimpanzee
iternal branch of the accessory does not join the vagus at all, but
lirect to the larynx.

mong the roots of the accessory nerve, the lower or external, aris-
rom the spinal cord, appears to be composed exclusively of motor
, and to be destined entirely to the trapezius and extending from
ack of the fourth ventricle to the level of the olivary bodies close
middle line, inside the combined nucleus of the ninth, tenth, and
nth nerves.

## The XIIth Nerve (*Hypoglossal*).

*rigin and Connections.*—The nerve arises from a large-celled and
long nucleus in the bulb, extending from the back of the fourth
icle to the level of the olivary bodies close to the middle line, inside
ombined nucleus of the ninth, tenth, and eleventh nerves. Fibres
this nucleus run from the ventral surface through the reticular
tion in a series of bundles passing between the olivary nucleus lat-
and the anterior pyramid and accessory olive medially, to gain
urface. The nerve emerges from a groove between the anterior
nid and olivary body. The fibres of origin are continuous with
nterior roots of the spinal nerves. It is connected with the vagus,
uperior cervical ganglion of the sympathetic and with the upper
al nerves.

*istribution.*—This nerve is the motor nerve to the muscles con-
l with the hyoid bone, including those of the tongue. It supplies
gh its descending branch (*descendens noni*), the sterno-hyoid,
-thyroid, and omo-hyoid; through a special branch, the thyro-
, and through its lingual branches, the genio-hyoid, stylo-glossus,
lossus, and genio-hyo-glossus and linguales.

*nctions.*—The function of the hypoglossal is exclusively motor.
notor nerve, its influence on all the muscles enumerated above is
by their convulsions when it is irritated, and by their loss of
when it is paralyzed. The effects of the paralysis of one hypo-
nerve are, however, not very striking. Often, in cases of hemi-
involving the functions of the hypoglossal nerve, it is not possible
rve any deviation in the direction of the protruded tongue; prob-
cause the tongue is so compact and firm that the muscles on either
heir insertion being nearly parallel to the median line, can push
ght forward or turn it for some distance toward either side.

## The Pons Varolii.

e pons Varolii is generally spoken of as a great commissure of
of fibres which connect the two halves of the cerebellum and of

fibres which connect the bulb and spinal cord with the upper part of the brain. Although this is true it must not be forgotten that the p contains several masses of gray matter, and also in addition smaller col lections of nerve-cells. It is found that on section the following p may be made out in its structure, beginning from the anterior or v tral surface.

(*a.*) Transverse or commissural fibres connecting the one side of t cerebellum with the other, forming the middle peduncle. These f emerge from the lateral parts of the white substance of the hemisph having come from the superficial gray matter of the whole surface, f the median vermis, and from the lateral hemispheres. Some of t fibres are truly commissural and probably connect the same points the surfaces of the two halves; some end in the gray matter of the s side of the pons on the ventral surface, and others cross to the opp side of the pons and then become longitudinal, passing on to the t *mentum*, a system of fibres and gray matter to be immediately describ

(*b.*) Fibres longitudinal in direction which are arranged in large smaller bundles separated by gray matter; some of these fibres are v are called the pyramidal fibres, which pass down to the anterior py mids of the bulb.

(*c.*) The dorsal portion of the pons is made up to a considerable tent of the reticular formation of the tegmental region together w one or two distinct bundles of longitudinal fibres: (i.), the chief, situat toward the junction of the ventral two thirds with the dorsal third, the *fillet*, which consists of two portions, outer and median; and (ii.), t second, a bundle of similar fibres, *posterior longitudinal bundles*, is sit ated between the two divisions of the fillet below the lateral and to t outer side of the median.

(*d.*) In the fore part of the pons, a mass of gray matter containi pigment, the *locus cœruleus*, possibly forming the origin of the fifth ner and in the back part a second mass of gray matter, the *superior oliv*.

## The Crura Cerebri.

The crura cerebri (III, fig. 363) diverge from the anterior edg the pons Varolii and pass upward on either side toward the cere hemispheres. At their anterior termination each of them appears have upon its dorsal surface, to the inner and outer sides respectiv two large masses of gray matter which have been already spoken of, v the optic thalamus and the corpus striatum. These bodies are not as it were placed upon the surface of each crus, but are also deeply bedded in its substance.

The crus is found to be made up of two principal parts:—

(*a.*) The one, the *tegmentum*, situated for the most part on the dorsal
ect, is composed chiefly of gray matter and some longitudinal fibres.
And (*b.*) the other, the *crusta*, situated toward the other surface, is
mposed almost entirely of longitudinal fibres. It is known also as the
t. Separating these two parts, is a mass of gray matter of the shape
a lens, called the *locus* or *nucleus niger* or *substantia nigra*.

The tegmentum situated dorsally ends for the most part in the
ghborhood of the optic thalamus and the parts beneath. In conse-
ence of this the fibres of the pes are allowed to come dorsally and to
ceed between the optic thalamus and the more posterior part (the
ticular nucleus) of the corpus striatum, on their course to the cere-
l cortex. When in this situation they form a compact mass of fibres.
they pass more dorsally the fibres spread out in the form of a fan,
l this arrangement is called the *corona radiata*. The fibres of the pes



Fig. 379.—Diagram of the motor tract as shown in a diagrammatic horizontal section
ugh the cerebral hemispheres, Crura, Pons, and Medulla. Fr., Frontal lobe; Oc., occipital
; AF., ascending frontal, AP., ascending parietal convolutions; PCF., pre-central fissure,
ront of the ascending frontal convolution; FR., fissure of Rolando; IPF., inter-parietal fis-
, a section of crus is lettered on the left side. SN., Substantia nigra; Py., pyramidal motor
, which on the right is shown as continuous lines converging to pass through the posterior
of IC. internal capsule (the knee or elbow of which is shown thus *) upward into the
isphere and downward through the pons to cross the medulla in the anterior pyramids.
wers.)

found to stretch not only between the optic thalamus and the len-
ular nucleus, but also more anteriorly between the former and the
date nucleus of the corpus striatum which, as we have seen, is to be
in the floor of the lateral ventricle. The fibres of the pes thus
ead out, have the form of a fan bent upon itself as they rise to pass
the cerebral hemisphere. This constitutes the *internal capsule*, and
portion of it which forms the angle at which the fibres are bent is
ed the *genu* of the capsule, that in front of it being the front limb, and

that behind, the hind limb. The fibres constituting the internal capsule are distributed to different districts of the cerebral cortex. They are made up of fibres not only constituting the pyramidal system, but also of others which end in the masses of gray matter in the pons or crus itself; but the function of all of the fibres is believed to be to carry impulses downward from the cerebrum either to the spinal cord and so to the cranial nerves, or to the cerebellum.

The tegmentum of either side, on the other hand, is supposed to be concerned, for the most part at any rate, with afferent impulses. It is made up to a very considerable extent of collections of gray matter, the most important of which are (*a*) the *locus* or *nucleus niger*, separating the pes and tegmentum; (*b*) the *nucleus ruber*, which is a rounded mass situated more toward the aqueduct of Sylvius; this extends from the third ventricle to the anterior corpus quadrigeminum. The locus niger extends back as far as the posterior corpus quadrigeminum. (*c*) A third mass of gray matter is situated beneath the optic thalamus, and is the *corpus subthalamicum*. Posteriorly the tegmentum is made up chiefly of the reticular material so often spoken of, and in the pons consists almost entirely of that kind of structure, but with the two additional masess of gray matter already indicated, viz., the locus cœruleus and superior olive.

It will be as well here to indicate briefly the other collections of gray matter in the neighborhood of the crura, viz., the corpus striata, optic thalami, corpora quadrigemina, corpora geniculata, and the corpora dentata of the cerebellum.

**Corpora Striata.**—The corpora striata are situated in front and to the outside of the optic thalami, partly within and partly without the lateral ventricle.

Each corpus striatum consists of two parts:—

(*a*.) An intraventricular portion (*caudate nucleus*) which is conical in shape, with the base of the cone forward; it consists of gray matter, with white substance in its centre. (*b*.) An extraventricular portion (*lenticular nucleus*), which is separated from the other portion by a layer of white material, which forms a portion of the internal capsule,—the *anterior limb*. The lenticular nucleus is seen, on a horizontal section of the hemisphere, to consist of three parts (the two internal called *globus pallidus*, *major and minor*, and the outer called the *putamen*), separated from one another by white matter, of which the smallest of the three is inside. Each part somewhat resembles a wedge in shape. The upper and internal surface is in relation with the caudate nucleus, being separated from it by the anterior limb of the internal capsule. The remainder of the internal surface is in relation to the optic thalamus, being separated from it by the *posterior limb* of the internal capsule. The horizontal section is wider in the centre than at the ends. On the out-e is the gray lamina (claustrum) separated by a thin white layer—*ernal capsule*—from the lenticular nucleus.

The cells of the corpora striata are evenly distributed, and not uped in nuclei. Their neuraxons pass, for the most part, into the ernal capsule. The corpora striata are connected with the cerebellum ough these fibres. It is doubtful if these ganglia have any anatomical ations with the cortex of the brain.

**Optic Thalami.**—The optic thalami are oval in shape, and rest on the inner and dorsal surfaces of the crura cerebri. The upper sur-e of each thalamus is free, and of white substance; it projects into lateral ventricle. The posterior surface is also white. The inner es of the two optic thalami form the outer borders of the third tricle, are in partial contact, and are composed of gray material un-ered by white and are, as a rule, connected together by a transverse tion.

The optic thalamus is composed of several collections of gray matter, ming somewhat indistinctly defined masses separated by white fibres. ese masses of gray matter are known as the *nuclei of the thalamus*, l they are six in number. They are called the anterior tubercle, the dian nucleus, the lateral nucleus, the ventral nucleus, the pulvinar, l the posterior nucleus. The anterior tubercle is composed of large ve-cells whose neuraxons pass down to the corpora mammillaria at the e of the brain. There they meet the fibres of the fornix which con-t this tubercle of the thalamus with the hippocampal convolution. e median nucleus is connected by its neuraxons with the cortex of the nd of Reil and the second and third convolutions. The lateral nu-s is quite large and lies against the internal capsule, into which it ds fibres. It is connected with the central convolutions. The ven-nucleus lies beneath the preceding; it is small in size. It is con-ted with the cortex of the frontal lobe and with the operculum, the tral convolutions, and the supramarginal gyrus. The fifth nucleus, wn as the *pulvinar*, forms the posterior tip of the thalamus, and is nected with the optic tract. The posterior nucleus, lying just below pulvinar, is a small mass and is connected with the cortex of the in-or parietal convolution. The cells of the optic thalamus are thus to be connected with a large area of the cerebral cortex. They are connected with the sensory, and probably, to some extent, with the or tracts coming from below.

**Corpora Quadrigemina.**—There are two on each side, anterior posterior; they form prominences on the dorsal surface of the pons crura above the aqueduct of Sylvius. They are composed of alter-layers of white and gray matter. The posterior bodies receive s from the eighth nerve and the sensory tract, known as the *f*. They send fibres out to the temporal region of the brain. They losely associated with the lateral corpora geniculata. The anterior corpora quadrigemina are connected by fibres with the optic nerve and also the fillet, and send fibres to the occipital cortex of the brain. They are closely associated with the median corpora geniculata.

**Corpora Geniculata.**—These are two on either side, lateral or outer and median or inner; the former is developed from the fore-brain, the latter from the mid-brain. The lateral corpus geniculatum is at the side of the crus and appears to be a swelling on the lateral division of the optic tract. Similarly the median appears to be the termination of the median division of the optic tract. They both contain gray matter (fig. 372).

**Corpora Dentata** are plicated areas of gray matter in the interior of the cerebellum, not unlike the olivary body of the bulb. The fibres from each pass chiefly to the superior peduncle of its own side.

**The Cerebrum.**—For convenience of description, the surface of the brain has been divided into *five lobes* (Gratiolet).



Fig. 380.—Left hemisphere, from without. (After Eberstaller.)

1. *Frontal* (fig. 380), limited behind by the fissure of Rolando (central fissure), and beneath by the fissure of Sylvius. Its surface consists of three main convolutions, which are approximately horizontal in direction, and are broken up into numerous secondary gyri. They are termed the superior, middle, and inferior frontal convolutions. In addition, the frontal lobe contains, at its posterior part, a convolution which runs upward almost vertically (*ascending frontal*), and is bounded in front by a fissure termed the præcentral, behind by that of Rolando.

2 *Parietal.* This lobe is bounded in front by the fissure of Rolando, behind by the external perpendicular fissure (parieto-occipital), and below by the fissure of Sylvius. Behind the fissure of Rolando is the *ascending parietal* convolution, which swells out at its upper end into what is termed the superior parietal lobule. The superior parietal lobule is separated from the inferior parietal lobule by the intra-parietal

. The inferior parietal lobule (pli courbe) is situated at the pos- and upper end of the fissure of Sylvius; it consists of (*a*) an or part (*supra-marginal convolution*) which hooks round the end fissure of Sylvius, and joins the superior temporal convolution, posterior part (*b*) (angular gyrus) which hooks round into the e temporal convolution.

*Temporal* contains three well-marked convolutions, parallel to other, termed the superior, middle, and inferior temporal. The or and middle are separated by the parallel fissure.

*Occipital.* This lobe lies behind the external perpendicular



Fig. 381.—The cerebrum, from above. (After Eberstaller.)

ieto-occipital fissure, and contains three convolutions, termed the or, middle, and inferior occipital. They are often not well marked. n, the external parieto-occipital fissure is only to be distinguished otch in the inner edge of the hemisphere; below this it is quite ated by the four annectant gyri (plis de passage) which run nearly ntally. The upper two connect the parietal, and the lower two mporal with the occipital lobe.

*Central lobe*, or island of Reil, which contains a number of radiat- nvolutions (gyri operti).

e fig. 382 shows the following *gyri* and *sulci*:—

*rus fornicatus*, a long curved convolution, parallel to and curving round the corpus callosum, and swelling out at its hinder and upper end into the quadrate lobule (præcuneus), which is continuous with the superior parietal lobule on the external surface. *Marginal convolution* runs parallel to the preceding, and occupies the space between it and the edge of the longitudinal fissure. The two convolutions are separated by the calloso-marginal fissure. The *internal perpendicular* fissure is well marked, and runs downward to its junction with the *calcarine* fissure: the wedge-shaped mass intervening between these two is termed the *cuneus*. The calcarine fissure corresponds to the projection into the posterior cornu of the lateral ventricle, termed the *Hippocampus minor*. The *temporal lobe* on its internal aspect is seen to end in a hook (uncinate gyrus). The notch round which it curves is continued up and back as the dentate or hippocampal sulcus: this fissure underlies the projection of the hippocampus major within the brain. There are three internal temporo-occipital convolutions, of which the superior and inferior ones are usually well marked, the middle one generally less so.



Fig. 382.—Right hemisphere, from within. (After Eberstaller.)

The collateral fissure (corresponding to the eminentia collateralis) forms the lower boundary of the superior temporo-occipital convolution.

All the above details will be found indicated in the diagrams (figs. 381, 382).

*Structure.*—The cerebrum is constructed like the other chief divisions of the cerebro-spinal system, of *gray* and *white* matter; and, as in the case of the Cerebellum (and unlike the spinal cord and medulla oblongata) the gray matter (*cortex*) is external, and forms a capsule or covering for the white substance. For the evident purpose of increasing its amount without undue occupation of space, the gray matter is variously infolded so as to form the cerebral *convolutions*.

The cortical **gray matter** of the cerebral cortex has an average ickness of about $\frac{1}{8}$ inch (3 mm.), being thin in the occipital lobe, $\frac{1}{12}$ ch (2 mm.), and thick in the pre-central, $\frac{1}{6}$ inch (4 mm.). The cells which the substance is composed are of different kinds: (*a*) The ical process is very long and reaches up often nearly to the surface. gives off lateral branches, and is studded along its course with little ojections called gemmules. This process is a protoplasmic process or ndrite; the cell has other dendrites given off from the angles of the dy of the cell. It always has an axis-cylinder process or neuraxon hich passes off usually from about the middle of the base. There are, sides these large pyramidal cells, others practically of the same shape d structure but smaller. They are the small pyramidal cells.

(*b*) In the superficial layer of the cortex there is a peculiar type of ll, first described by Cajal. Most of these bodies are fusiform in shape, th the long axis parallel to the surface of the convolution. They give f usually two neuraxons which run along parallel to the surface and nd down numerous fine collaterals at right angles. Another form of jal cell, triangular or quadrangular in shape, is also seen. Both rms have, as a rule, more than one neuraxon. Their collaterals pass a horizontal direction, forming a fine band of fibres, known as *tan-ntial fibres.*

(*c*) A third type of cell is the *fusiform* or *polymorphous*. Some of ese are strictly fusiform in shape and lie with their axis parallel to the rface of the convolution. They give off protoplasmic processes which ss down toward the white matter, some of them turning to run in a rizontal direction. The fusiform and polymorphous cells are grouped the same layer, and are, therefore, described together.

(*d*) Besides these cells we find scattered through the cortex a consid-able number of the neuroglia-cells. The character and position of ese are shown in fig. 383.

The general arrangement of the layers of the cortex is described very ferently by different authors, and it differs in different parts of the ain. The simplest and most representative type, however of the ar-ngement is that in which the cortex is divided into four layers. The termost, or superficial, known as the *molecular* layer, contains rela-ely few cells. It is composed of neuroglia tissue, embedded in which a number of cells of the Cajal type, which have just been described. ere are also in this layer many neuroglia-cells. In the superficial part the layer of some areas of the cortex are many tangential fibres. The ond layer is composed of small pyramidal cells. In parts of the brain re are here interposed what are known as the *vertical fusiform* cells. e third layer is composed of large pyramidal cells, in which, however, e sees many small pyramids also. The fourth layer is composed of the iform and polymorphous cells, and beneath this is the white substance. This arrangement is shown in the accompanying figure and 384). The gray matter of the brain contains, however, n these layers and cells, but an infinitely rich mass of fibres, which shown by various stains to have a certain definite arrangement. of the fibres are vertical in direction, passing directly up to th superficial layers of cells; others have a horizontal direction, di



Fig. 383.—The principal constituent elements of the gray cortical layer of the anterior cerebrum. (After Ramon y Cajal.)

the gray matter into different layers. These layers of fibres hav ceived different names. They vary somewhat in accordance with area of the cortex examined. A typical arrangement is shown i 385. The most conspicuous are certain large triangular or pyra




I
II
III
IV
Sb
Tangential fibres.
Striæ of Bechterew and de Kaes.
Superradiary network (of the second and third layers).
Striæ of Baillarger.
Interradiary network (of the third and fourth layers).
Meynert's intracortical association fibres.
Subcortical association fibres.

384.

Fig. 385.

—Schematic diagram of the different layers of the cerebral cortex. (After Ramon y
The tangential fibres, Vicq d'Azyr's ribbon, Baillarger's internal and external striæ,
substance are stained red; *M*, molecular layer; *pPy*, layer of small pyramidal cells;
large pyramidal cells; *Pm*, layer of polymorphous cells.

-Schematic diagram showing the arrangement of the nerve fibres in the cerebral
dotted lines separate the four cellular layers of Cajal. *Sb*, white substance.

cells, granular or fibrillated, with large and distinct nuclei, arranged with their apices toward the surface.

*Chemical Composition.*—The chemistry of nerves and nerve-cells has been chiefly studied in the brain and spinal cord. Nerve matter contains several albuminous and fatty bodies (cerebrin, lecithin, and some others), also fat matter which can be extracted by ether (including cholesterin) and various salts, especially Potassium and Magnesium phosphates, which exist in larger quantity than those of Sodium and Calcium.

*Arrangement of the parts of the cerebrum.*—The great relative and absolute size of the Cerebral hemispheres in the adult man, masks to a great extent the real arrangement of the several parts of the brain, which is illustrated in the two accompanying diagrams (**figs.** 386, 387).



Fig. 386.—Diagrammatic horizontal section of a vertebrate brain. The figures serve both for this and the next diagram. *Mb*, mid-brain: what lies in front of this is the fore-, and what lies behind, the hind-brain; *Lt*, lamina terminalis; *Olf*, olfactory lobes; *Hmp*, hemispheres; *Th. E*, thalamencephalon; *Pn*, pineal gland; *Py*, pituitary body; *F.M*, foramen of Munro; cs corpus striatum; *Th*, optic thalamus; *CC*, crura cerebri: the mass lying above the canal represents the corpora quadrigemina; *Cb*, cerebellum; *I—IX*, the nine pairs of cranial nerves; 1, olfactory ventricle; 2, lateral ventricle; 3, third ventricle; 4, fourth ventricle; +, iter a tertio ad quartum ventriculum. (Huxley.)

From these it is apparent that the parts of the brain are disposed a linear series, as follows (from before backward): olfactory lobes, cer l hemispheres, optic thalami, and third ventricle, corpora quadrimina, or optic lobes, cerebellum, medulla oblongata.

This linear arrangement of parts actually occurs in the human fœtus; d it is permanent in some of the lower Vertebrata, *e.g.*, Fishes, in ich the cerebral hemispheres are represented by a pair of ganglia ervening between the olfactory and the optic lobes, and considerably aller than the latter. In Amphibia the cerebral lobes are furthei veloped, and are larger than any of the other ganglia.

In reptiles and birds the cerebral ganglia attain a still further develment, and in mammalia the cerebral hemispheres exceed in weight the rest of the brain. As we ascend the scale, the relative size of the ebrum increases, till in the higher apes and man the hemispheres, ich commenced as two little lateral buds from the anterior cerebral icle, have grown upward and backward, completely covering in and ing from view all the rest of the brain. At the same time the smooth face of the brain, in many lower mammalia, such as the rabbit, is laced by the labyrinth of convolutions of the human brain.



Fig. 387.—Longitudinal and vertical diagrammatic section of a vertebrate brain. Letters efore. Lamina terminalis is represented by the strong black line joining *Pn* and *Py*. xley.)

**Weight of the Brain.**—The brain of an adult man weighs from 48 to 50 oz.—bout 3 lbs. (about 1550 grms.). It exceeds in absolute weight that of all the er animals except the elephant and whale. Its weight, *relatively to that of body*, is only exceeded by that of a few small birds, and some of the ller monkeys. In the adult man it ranges from $\frac{1}{30}$—$\frac{1}{60}$ of the body weight.

**Variations.** *Age.*—In a new-born child the brain (weighing 10 to 14 oz.) is f the body weight. At the age of 7 years the weight of the brain already rages 40 oz., and about 14 years the brain not infrequently reaches the ght of 48 oz. Beyond the age of forty years the weight slowly but steadily lines at the rate of about 1 oz. in 10 years.

*Sex.*—The average weight of the female brain is less than the male: and this erence persists from birth throughout life. In the adult it amounts to at 5 oz. Thus the average weight of an adult woman's brain is about 44 oz.

*ntelligence.*—The brains of idiots are generally much below the average, e weighing less than 16 oz. Still the facts at present collected do not war- more than a very general statement, to which there are numerous exceps, that the brain weight corresponds to some extent with the degree of lligence. There can be little doubt that the *complexity* and *depth* of the convolutions, which indicate the area of the gray matter of the cortex, correspond with the degree of intelligence.

*Weight of the Spinal Cord.*—The spinal cord of man weighs from 1–1½ oz.; its weight relatively to the brain is about 1 : 36. As we descend the scale, this ratio constantly increases till in the mouse it is 1 : 4. In cold-blooded animals the relation is reversed, the spinal cord is the heavier and the more important organ. In the newt, 2 : 1; and in the lamprey, .75 : 1.

**Distinctive Characters of the Human Brain.**—The following characters distinguish *the brain of man and apes from those of all other animals.* (*a.*) The rudimentary condition of the olfactory lobes. (*b.*) A perfectly defined fissure of Sylvius. (*c.*) A posterior lobe completely covering the cerebellum. (*d.*) The presence of posterior cornua in the lateral ventricles.

The most *distinctive points in the human brain*, as contrasted with that of apes, are:—(1.) The much greater size and weight of the whole brain. The brain of a full-grown gorilla weighs only about 15 oz. (450 grms.), which is less than ⅓ the weight of the human adult male brain, and barely exceeds that of the human infant at birth. (2.) The much greater complexity of the convolutions, especially the existence in the human brain of tertiary convolutions in the sides of the fissures. (3.) The greater relative size and complexity, and the blunted quadrangular contour of the frontal lobes in man, which are relatively both broader, longer, and higher, than in apes. In apes the frontal lobes project keel-like (rostrum) between the olfactory bulbs. (4.) The much greater prominence of the temporo-sphenoidal lobes in apes. (5.) The fissure of Sylvius is nearly horizontal in man, while in apes it slants considerably upward. (6.) The distinctness of the external perpendicular fissure, which in apes is a well-defined almost vertical "slash," while in man it is almost obscured by the adjacent gyri.



Fig. 388.—Brain of the Orang, ⅔ natural size, showing the arrangement of the convolutions. *Sy*, fissure of Sylvius; *R*, fissure of Rolando; *E P*, external perpendicular fissure; *Olf*, olfactory lobe; *Cb*, cerebellum; *PV*, pons Varolii; *M O*, medulla oblongata. As contrasted with the human brain, the frontal lobe is short and small relatively, the fissure of Sylvius is oblique, the temporo-sphenoidal lobe very prominent, and the external perpendicular fissure very well marked. (Gratiolet.)

Most of the above points are shown in the accompanying figure of the brain of the Orang.

## The Motor areas of the Cerebral Cortex.

The experiments upon the brains of various animals by means of ectrical stimulation have demonstrated that there are definite re-



Fig. 389.



Fig. 390.

Figs. 389 and 390.—Brain of dog, viewed from above and in profile. *F*, frontal fissure some- es termed crucial sulcus, corresponding to the fissure of Rolando in man. *S*, fissure of vius, around which the four longitudinal convolutions are concentrically arranged; 1, flexion head on the neck, in the median line; 2, flexion of head on the neck, with rotation toward side of the stimulus; 3, 4, flexion and extension of anterior limb; 5, 6, flexion and extension Posterior limb; 7, 8, 9, contraction of orbicularis oculi, and the facial muscles in general. unshaded part is that exposed by opening the skull. (Dalton.)

ns of the cerebral cortex the stimulation of which produces definite vements of co-ordinated groups of muscles of the opposite side of e body. Fritsch and Hitzig were the first to show that the cerebral cortex responded to electric irritation. They employed a weak constant current in their experiments, applying a pair of fine electrodes not more than $\frac{1}{12}$ in. apart to different parts of the cerebral cortex. The results thus obtained have been confirmed and extended by Ferrier and many others, chiefly with induction currents.

The fundamental phenomena observed in all these cases may be thus epitomized:—

(1). Excitation of the same spot is always followed by the same movement in the same animal. (2). The area of excitability for any given movement is extremely small, and admits of very accurate definition. (3). In different animals excitations of anatomically corresponding spots produce similar or corresponding results.

The various definite movements resulting from the electric stimulation of circumscribed areas of the cerebral cortex, are enumerated in the description of the accompanying figures of the dog and monkey's brain.

In the case of the dog, the results obtained are summed up as follows, by Hitzig:—

(*a*.) One portion (anterior) of the convexity of the cerebrum is motor; another portion (posterior) is non-motor. (*b*.) Electric stimulation of the motor portion produces co-ordinated muscular contraction on the opposite side of the body. (*c*.) With very weak currents, the contractions produced are distinctly limited to particular groups of muscles; with stronger currents the stimulus is communicated to other muscles of the same or neighboring parts. (*d*.) The portions of the brain intervening between these motor centres are inexcitable by similar means.

Following strong stimulation of cortical motor centres, after-contractions of the muscles involved occur. Other groups of muscles than those innervated by the centres stimulated may also take part in the contractions. Other irritations of the cortex, such as the mechanical irritation produced by a spicule of bone will cause spasmodic contractions of the muscles which may be limited to the group corresponding to the cortical area irritated, or first starting with these muscles may involve, possibly, all the muscles of the trunk and limbs. Such after-contractions of muscles, following irritation of cortical areas, are known as epilepsy, and that form involving groups of muscles in a certain area as Jacksonian epilepsy (after Hughlings Jackson, who first described this type).

*Motorial area of the Monkey's Brain.*—According to the observations of Ferrier, confirmed and extended by later experimenters, stimulation of various parts of the monkey's brain, as indicated by the numbers in figs. 391, 392, produces movements of definite muscles, thus:—

Stimulation of the district marked 1, causes movement of hind foot; of 2, chiefly adduction of the foot; of 3, movements of hind foot and tail; of 4, of latissimus dorsi; of 5, extension forward of arm; *a*, *b*, *c*, *d*, movements of hand and wrist; of 6, supination and flexion of forearm; of 7, elevation of the upper lip; of 8, conjoint action of elevation of upper lip and depression of lower; of 9, opening of mouth and protrusion of tongue; of 10, retraction of tongue; of 11, action of platysma; of 12, elevation of eyebrows and eyelids, dilatation of pupils, and turning head to opposite side; of 13, eyes directed to opposite side and upward, with usually contraction of the pupils; of 13′, similar ction, but eyes usually directed downward; of 14, retraction of oppoite ear, head turns to the opposite side, the eyes widely opened, and pupils dilated; of 15, stimulation of this region, which corresponds to



Fig. 391.

Fig. 392.

gs. 391 and 392.—Diagrams of monkey's brain to show the effects of electric stimulation of certain spots. (According to Ferrier.)

e tip of the uncinate convolution, causes torsion of the lip and nostril the same side.

It is thus seen that the motor areas chiefly correspond with the ending frontal and ascending parietal convolutions, and that the vements of the leg are represented at the upper part of these conlutions, then follow from above downward the centres for the arms, face, the lips, and the tongue.

According to the further researches of Schäfer and Horsley, electrical mulation of the marginal convolution internally at the parts corrending with the ascending frontal and parietal convolutions, from before backward, produces movements of the **arm**, of the **trunk**, and of the **leg**.

A good deal of doubt was thrown upon the experiments of Ferrier by Goltz and other observers, from the results of excising the so-called motor areas of the dog's brain. It was found that the part might be sliced away or washed away with a stream of water, but that no permanent paralysis ensued.

More extensive observations however, have confirmed Ferrier's original statement, at any rate with regard to the monkey's brain. Destruction of the motor areas for the arm produces at any rate some permanent paralysis of the arm of the opposite side, and similarly of that for the leg, paralysis of the opposite leg. If both areas are destroyed permanent hemiplegia ensues. Paralysis of so extensive and permanent character does not, however, appear the rule when the brain of a dog is used instead of that of the monkey. It is suggested that in the animal lower in the scale, the functions which in the monkey are discharged by the cortical centres may be subserved by the basal ganglia.



Fig. 393.—The Cortical Centres. (Dana.)

*Motorial Areas of the Human Brain.*—It is naturally of great importance to discover how far the results of experiments upon the dog and monkey hold good with regard to the human brain. Evidence furnished by diseased conditions is not wanting to support the general idea of the existence of cortical motorial centres in the human brain (fig. 393).

So far, however, it has been possible to localize motor functions in the frontal and ascending parietal convolutions only, to the convolutions which bound the fissure of Rolando, and to those on the inner side of the hemispheres which correspond thereto, and possibly to the frontal lobe in front of the ascending convolution.

The position of the centres is probably much the same as in the monkey's brain—those for the leg above, those for the arm, face, lips, and tongue from above downward. Destruction of these parts causes paralysis, corresponding to the district affected, and irritation causes convulsions of the muscles of the same part. Again, a number of cases are on record in which *aphasia*, or the loss of power of expressing ideas in words, has been associated with disease of the posterior part of the ower or third frontal convolution n the left side. This condition s usually associated with paraly-is of the right side (right hemi-legia).

This district of the brain is ow generally known as the *motor* *rea;* and there seems no doubt hatever that from this area pass ne nerve-fibres which proceed to ne spinal cord, and are there rep-esented as the pyramidal tracts.

This is the reason, no doubt, nat movements are produced on imulation of the white matter ter the superficial gray matter the animal's brain has been iced off.

*Motor tracts in the brain.*—hese motor fibres are connected ith the pyramidal cells of the rtex, and are indeed their con-nuations.

It will be necessary, therefore, trace them from the cortex wnward. From the motor area the cortex they converge to the *ernal capsules*, and pass down to the crusta of the crus in the way eady indicated.



Fig. 394.—Diagram to show the connecting of the Frontal Occipital Lobes with the Cerebellum, etc. The dotted lines passing in the crusta (TOC), outside the motor fibres, indicate the connection between the temporo-occipital lobe and the cerebellum. F.F., the fronto-cerebellar fibres, which pass internally to the motor tract in the crusta; I. F., fibres from the caudate nucleus to the pons. Fr., frontal lobe; Oc., occipital lobe; AF., ascending frontal; AP., ascending parietal convolutions; PCF., precentral fissure in front of the ascending frontal convolution; FR., fissure of Rolando; IPF., interparietal fissure, a section of crus is lettered on the left side. SN., substantia nigra; PY., pyramidal motor fibre, which on the right is shown as continuous lines converging to pass through the posterior limb of IC. internal capsule (the knee or elbow of which is shown thus *) upward into the hemisphere and downward through the pons to cross at the medulla in the anterior pyramids. (Gowers.)

In the internal capsule the fibres which pass onward and downward the pyramidal tracts of the spinal cord do not occupy more than a all section, namely, that part known as the knee, and the anterior o-thirds of the posterior segment (fig. 395). In this district the res for the face, arm, and leg are in this relation: those for the face and tongue are just at the knee, and below or behind them cor the fibres for the arm and then those for the leg.

The more accurate arrangement of these fibres in the monkey' from above down are those for the eye, head, tongue, mouth, sh elbow, digits, abdomen, lip, knee, digits. These fibres come f most part from the part of the cortex on either side of the fis Rolando, hence called the *Rolandic area* on either side. But th



Fig. 395.—Diagram to show the relative positions of the several motor tracts in th from the cortex to the crus. The section through the convolution is vertical; that th internal capsule, I, C, horizontal; that through the crus again vertical. C, N, caudat O, TH, optic thalamus; L2 and L3, middle and outer part of lenticular nucleus; *f*, arm, and leg fibres. The words in italic indicate corresponding cortical centres. (Go

for the head and eyes lie more anterior in the frontal lobe, to th of the precentral sulcus, that for the head above that for the ey an area for the trunk (not indicated in the fig. 394), is situate toward the middle line of the hemisphere, internal to that for th

But there are other fibres which are arranged in front pyramidal fibres in the front limb of the capsule, as well as others them in the hind limb of the capsule. Those in front are fr *anterior part of the frontal* lobe, and these in passing into the found on the median side of the pyramidal fibres (fig. 394). appear to end in the gray matter of the pons, and there to be co with fibres from the middle peduncle of the opposite side of th bellum. Those behind the pyramidal fibres in the hind limb of t sule are from the *temporal-occipital lobe.* These fibres pass into t to the outer side of the pyramidal fibres (fig. 394), they proba end in the gray matter in the same way. There are other fibres fr corpus striatum, from both nuclei, but particularly from the nucleus, which pass to the crus, and are situated between the pyr tract and the locus niger (fig. 394), some of which terminate i nucleus, while others terminate in the pons. Besides the above ll of which are believed to be efferent fibres, and are at any rate fibres f descending degeneration, there are fibres which pass from the cortex o the optic thalamus and tegmentum, fibres of ascending degeneration ound in the internal capsule, viz., those from the frontal lobes are ituated at the extreme tip of the front limb, in front of the motor fibres rom the same district, and others from the temporal-occipital district onverge to the posterior part of the hind limb. Those passing between he occipital lobe and the optic thalamus are believed to be concerned ith vision, and are called fibres of the *optic radiation.*

It may be as well to mention here that some other fibres from the mporo-occipital lobe pass into the optic thalamus, without forming a art of the internal capsule.

The optic thalamus then receives fibres from nearly all parts of the rebral cortex, some of which are not found in the internal capsule. he tegmentum, the afferent or sensory tract of the crus to a great exnt ends in the optic thalamus, and is, therefore, connected through it ith nearly all parts of the cortex, indirectly. It is also more directly nnected with cortex (*a*) by fibres of the optic radiation which do not to the optic thalamus, (*b*) by fibres from the frontal and parietal bes, which pass through the lenticular nucleus, and (*c*) by fibres from th the lenticular and caudate nuclei of the corpus striatum.

In the tegmentum the longitudinal fibres may be thus enumerated:—

(*a.*) The *fillet*, which consists of fibres from the sensory decussation of



Fig. 396.—Vertical section through the cerebrum and basic ganglia to show the relations of latter. *co*, cerebral convolutions; *c,c*, corpus callosum; *v.l.*, lateral ventricle; *f*, fornix; , third ventricle; *n.c.*, caudate nucleus; *th*, optic thalamus; *n.l.*, lenticular nucleus; *c.i.*, rnal capsule; *c.l.*, claustrum; *c.e.*, external capsule; *m*, corpus mammillare; *t.o.*, optic t; *s.t.t.*, stria terminalis; *n.a.*, nucleus amygdalæ; *cm*, soft commissure. (Schwalbe.)

bulb, which becomes longitudinal in the inter-olivary region, and in course upward, from masses of gray matter, such as the superior e; it divides into two bundles. (i.) *Lateral*, ends in gray matter of posterior corpus quadrigeminum and in white matter beneath the anterior, and (ii.) *median*, ends in anterior corpus quadrigeminum and in the corpus subthalamicum, thence to the optic thalamus and the cerebral cortex.

(*b.*) *Posterior longitudinal bundles.*—A bundle of fibres which appear to begin in the bulb as certain fibres of the anterior column of the cord, which are the short longitudinal commissures between segments of the cord. It is traceable upward as far as the nucleus of the third nerve. It is supposed to connect the nuclei of the fourth and sixth nerves with the third, and with the anterior corpus quadrigeminum.

(*c.*) *Superior peduncle of the cerebellum.*—This arises on either side from the superficial gray matter, but chiefly from the corpus dentatum, and passes forward and outward beneath the posterior corpus quadrigeminum, and beneath it and the anterior corpus quadrigeminum decussates with its fellow; the fibres then pass forward in the anterior district of the tegmentum and end in the red nucleus.

(*d.*) *Fibres from the corpora quadrigemina.*—From each corpus quadrigeminum passes forward and downward a tract called the brachium. The anterior brachium goes to the lateral corpus geniculatum, and then to the optic tract, other fibres pass into the tegmentum, and thence directly to the occipital cortex. The posterior brachium goes to the median corpus geniculatum, thence to the tegmentum, and through it possibly to the temporal region of the cerebral cortex.

*Commissural fibres.*—In addition to the fibres of the corpus callosum, which connect all parts of the hemispheres, and fornix, there are three other commissures, the anterior white commissure, and the posterior white commissure in the third ventricle connecting by white fibres the two sides of the brain. The fibres in the anterior commissure come chiefly from the temporo-sphenoidal convolution, but a few are part of the olfactory tract. The posterior connects the optic thalami and tegmenta. The middle is chiefly composed of gray matter, but also contains some transverse fibres.

## Functions of the Cerebrum.

Speaking in the most general way, and for the present omitting the accumulating evidence in favor of the direct representation of the various co-ordinated movements of the muscles of the body in cell groups situated in different parts of the cerebral cortex, it may be said that:—(1.) The cerebral hemispheres are the organs by which are perceived those clear and more impressive sensations which can be retained, and regarding which we can judge. (2.) The cerebrum is the organ of the will, in so far, at least, as each act of the will requires a deliberate determination. (3.) It is the means of retaining impressions sensible things, and reproducing them in subjective sensations and eas. (4.) It is the medium of all the higher emotions and feelings, and the faculties of judgment, understanding, memory, reflection, induc-n, imagination and the like.

Evidence regarding the physiology of the cerebral hemispheres, has en obtained, as in the case of other parts of the nervous system, from e study of Comparative Anatomy, from Pathology, and from Experi-nts on the lower animals. The chief evidences regarding the func-ns of the cerebral hemispheres derived from these various sources, are efly these:—1. Any severe injury of them, such as a general concus-n, or sudden pressure as by apoplexy, may instantly deprive a man of power of manifesting externally any mental faculty. 2. In the same ieral proportion as the higher mental faculties are developed in the rtebrate animals, and in man at different ages and in different indi-uals, the more is the size of the cerebral hemispheres developed in nparison with the rest of the cerebro-spinal system. 3. No other part the nervous system bears a corresponding proportion to the develop-nt of the mental faculties. 4. Congenital and other morbid defects the cerebral hemisphere are, in general, accompanied by correspond-deficiency in the range or power of the intellectual faculties and the her instincts. 5. Removal of the cerebral hemispheres in one of the er animals produces effects corresponding with what might be antici-ed from the foregoing facts.

*Effects of the Removal of the Cerebrum.*—The removal of the cere-m in the lower animals appears to reduce them to the condition of a hanism without spontaneity.

In the case of the *frog*, when the cerebral lobes have been removed, animal appears similarly deprived of all power of spontaneous move-it. But it sits up in a natural attitude, breathing quietly; when ked it jumps away; when thrown into the water it swims; when ed upon the palm of the hand it remains motionless, although, if hand be gradually tilted over till the frog is on the point of losing balance, he will crawl up till he regains his equilibrium, and comes e perched quite on the edge of the hand. This condition contrasts that resulting from the removal of the entire brain, leaving only spinal cord; in this case only the simpler reflex actions can take e. The frog does not breathe, he lies flat on the table instead of ng up; when thrown into a vessel of water he sinks to the bottom; n his legs are pinched he kicks out, but does not leap away.

A *pigeon* from which the cerebrum has been removed will remain ionless and apparently unconscious unless disturbed. When dis-ed in any way it soon recovers its former position; when thrown the air it flies.

In mammals it is difficult to remove the cerebral hemispheres, but in those animals in which the operation has been carried out, as for example in the rabbit and rat, a result very similar to those observed in the case of the frog and pigeon has been obtained. The animal is able to maintain its equilibrium, to run or jump, and in fact carry out all the most complicated co-ordinated movements, but it is unable to originate them without stimulation. In the case of the dog, however, it has been found impossible to remove the whole brain, but when it has been removed piecemeal the animal may be kept alive for some time, and can carry out co-ordinated movements well, and even manifest intelligence.

It is quite evident, therefore, that the apparatus for carrying out co-ordinated movements is in these animals not localized either in the cerebrum or in the spinal cord, and must therefore be connected in some way with the parts of the brain below the cerebrum and above the cord. There is no reason why such an arrangement may not be supposed to exist in the human brain.

We must look upon the cerebrum, however, as the originator of voluntary movements.

As regards the theory of the localization of different movements in different parts of the cerebral cortex which as we have seen has received so much support from observation on animals such as the dog and the monkey, at any rate, we may say that certain parts of the cerebral cortex appear to be highly sensitive to electrical stimuli, particularly the Rolandic area and the frontal lobe in front of it. Stimulation of certain other regions, viz., of the occipital region, of the parietal and temporal region, and of the gyrus fornicatus and the frontal region in front of the motor area, does not give rise to such movements. Such observations as it has been possible to make on man show that the localization of movement on the human cerebral cortex is, if anything, superior to that observed in monkeys. We have, of course, but few data upon which to base our conclusion, except such as have been obtained from the observation of the symptoms of disease, but with the help of these we may assume that in the cerebral cortex the co-ordinated movements of the body in some way are represented. The cases which have given us most of our knowledge upon the subject are those in which hæmorrhages have occurred in different parts of the brain, followed by paralysis of the opposite side of the body. These hæmorrhages chiefly occur in the neighborhood of the corpus striatum. The paralysis of the extremities is practically permanent, although, as a rule, the muscles connected with the trunk are not paralyzed. This means that some interruption has taken place between the cerebral cortex and the paralyzed muscles, and if the lesion is a destroying one, the connection is never re-established. In the case of the animals, such as the dog, this is not the case, as the paralysis is temporary. It is supposed that in man not only the more highly skilled movements but all voluntary movements of the muscles are

ually represented in the cortical areas, and that the pyramidal tracts
actually essential for voluntary movements. If the pyramidal
cts be partially or wholly destroyed, anywhere in their course, a
alysis corresponding with the amount destroyed invariably follows.
the dog experiments have shown that this is not the case, and the
duction of voluntary impulse to muscles may take place, for example,
other parts of the cord besides the pyramidal tract, after hemisection.
The pyramidal tracts in man, however, must be considered also as
only path connecting the cortical centres with the co-ordinated
tres lower down in the brain, as, for example, in the bulb. The
pulses which pass down from the cortex, whatever they may be, are
however of necessity connected with consciousness, and many volun-
y movements of a complicated nature may take place really better with-
consciousness than with it. This is shown in such co-ordinated
vements as writing, walking, marching, and the like, all of which are
uired with time and much labor, but when once perfect in the
ividual, can best be performed without voluntary effort. Such
vements must be represented by impulses passing in the pyramidal
ts, for if they are interrupted, the movements are no longer per-
med.

What actually originates a voluntary action, or one performed by
effort of the will, we are unable to say. No doubt impulses from the
iphery conducted to the cerebral cortex along all kinds of afferent
nnels must have something to do with it; directly or indirectly,
ner or later. In the human cortex it would seem that the apparatus
performing all manner of possible co-ordinated movements which may
lt in speech or action, are stored. This apparatus is capable of
ng set in action either in the absence of consciousness by afferent
nuli of some kind directly, or by what may be, indirectly or remotely,
ome way the result of afferent stimuli, viz., the will. It is also prob-
that the will of another may take the place of the man's own will,
may call for the movements, actions, and speech, all of which are,
t were, ready to be called forth by a stimulus of some kind. It may
upposed that the condition of development of the brain inherited by
individual has something to do both with the potentialities of the
aratus for co-ordinated acts, which he receives at birth, and with the
in which the apparatus is set in motion.

*Unilateral Action.*—Respecting the mode in which the brain dis-
ges its functions, there is no evidence whatever. But it appears
, for all but its highest intellectual acts, one of the cerebral hemi-
res is sufficient. For numerous cases are recorded in which no
tal defect was observed, although one cerebral hemisphere was so
rganized or atrophied that it could not be supposed capable of dis-

charging its functions. The remaining hemisphere was, in these cases, adequate to the functions generally discharged by both; but the mind does not seem in any of these cases to have been tested in very high intellectual exercises; so that it is not certain that one hemisphere will suffice for these. In general, the brain combines, as one sensation, the impressions which it derives from one object through both hemispheres, and the ideas to which the two such impressions give rise are single. In relation to common sensation and the efforts of the will, it must always be remembered that the impressions to and from the hemispheres of the brain are carried across the middle line; so that in destruction or compression of either hemisphere, whatever effects are produced in loss of sensation or voluntary motion, are observed on the side of the body opposite to that on which the brain is injured.

**Sleep.**—All parts of the body which are the seat of active change require periods of rest. The alternation of work and rest is a necessary condition of their maintenance, and of the healthy performance of their functions. These alternating periods, however, differ much in duration in different cases; but, for any individual instance, they preserve a general and rather close uniformity. Thus, as before mentioned, the periods of rest and work, in the case of the heart, occupy, each of them, about half a second; in the case of the ordinary respiratory muscles the periods are about four or five times as long. In many cases, again (as of the voluntary muscles during violent exercise), while the periods during active exertion alternate very frequently, yet the expenditure goes far ahead of the repair, and, to compensate for this, an after repose of some hours becomes necessary; the rhythm being less perfect as to *time*, than in the case of the muscles concerned in circulation and respiration.

Obviously, it would be impossible that, in the case of the brain, there should be short periods of activity and repose, or in other words, of consciousness and unconsciousness. The repose must occur at long intervals; and it must therefore be proportionately long. Hence the necessity for that condition which we call *Sleep;* a condition which seeming at first sight exceptional, is only an unusually perfect example of what occurs, at varying intervals, in every actively working portion of our bodies.

A temporary abrogation of the functions of the cerebrum imitating sleep may occur, in the case of injury or disease, as the consequence of two apparently widely different conditions. Insensibility is equally produced by a *deficient* and an *excessive* quantity of blood within the cranium (coma); but it was once supposed that the latter offered the truest analogy to the normal condition of the brain in sleep, and in the absence of any proof to the contrary, the brain was said to be during sleep *congested*. Direct experimental inquiry has led, however, to the opposite conclusion.

By exposing, at a circumscribed spot, the surface of the brain of living animals, and protecting the exposed part by a watch-glass, Durham was able to prove that the brain becomes visibly paler (anæmic) during sleep; and the anæmia of the optic disc during sleep, observed by Hughlings Jackson, may be taken as a strong confirmation, by analogy, of the same fact.

A very little consideration will show that these experimental results correspond exactly with what might have been foretold from the analogy of other ysiological conditions. Blood is supplied to the brain for two partly disnct purposes. (1.) It is supplied for mere nutrition's sake. (2.) It is necesry for bringing supplies of potential or active energy (*i.e.*, *combustible matter heat*) which may be transformed by the cerebral corpuscles into the various anifestations of nerve-force. During sleep blood is requisite for only the first these purposes; and its supply in greater quantity would be not only eless, but by supplying an excitement to work, when rest is needed, would be sitively harmful. In this respect the varying circulation of blood in the ain exactly resembles that which occurs in all other energy-transforming rts of the body; *e.g.*, *glands* or *muscles*.

At the same time, it is necessary to remember that the normal anæmia of e brain which accompanies sleep is probably a result, and not a cause of the iescence of the cerebral functions. What the immediate cause of this riodical partial abrogation of functions is, however, we do not know.

**Somnambulism and Dreams.**—What we term *sleep* occurs often in very differt degrees in different parts of the nervous system; and in some parts the pression cannot be used in the ordinary sense.

The phenomena of *dreams* and *somnambulism* are examples of differing grees of sleep in different parts of the cerebro-spinal nervous system. In the mer case the cerebrum is still partially active; but the mind-products of its tion are no longer corrected by the reception, on the part of the sleeping *sorium*, of impressions of objects belonging to the outer world; neither can cerebrum, in this half-awake condition, act on the centres of reflex action the voluntary muscles, so as to cause the latter to contract—a fact within painful experience of all who have suffered from nightmare.

In somnambulism the cerebrum is capable of exciting that train of reflex rvous action which is necessary for progression, while the nerve-centre of *scular sense* (in the cerebellum?) is, presumably, fully awake; but the *senium* is still asleep, and impressions made on it are not sufficiently *felt* to se the cerebrum to a comparison of the difference between mere ideas or mories and sensations derived from external objects.

*The centres for muscular co-ordinations.*—In asserting that the coination of complicated muscular movements is connected with the ddle parts of the brain below the cerebrum and above the bulb, we re stating a fact deduced from experiments upon animals. It is difficult to understand the exact way in which these parts of the brain are cerned. It appears, however, that co-ordinated movements such as nding, walking, and the maintenance of the equilibrium generally, uire to be guided and governed by afferent impulses, which tell of condition of the body and of its relations to its environment ("its ition in space"). The afferent impulses are *firstly* visual and tactile sations, *secondly* sensations by which we appreciate the condition of muscles (muscular sense), and *thirdly*, as appears from experiments pigeons and other animals, sensations produced by the pressure, in erent directions, of the fluid in the semicircular canals of the innal ear.

Experiments show that when the horizontal semicircular canal is divided in a pigeon, inco-ordination occurs, with a constant movement of the head from side to side, and similarly, when one of the vertical canals is operated upon, up and down movements of the head are observed. The bird is unable to fly in an orderly manner, flutters and falls when thrown into the air, and, moreover, is able to feed with difficulty. Hearing remains unimpaired. So that inco-ordination depends upon deficiency or disorder of normal ampullar influences. It will be recollected that the semicircular canals are supplied with a nerve, the vestibular branch of the auditory, which is connected with the bulb.

It is probable that the various afferent impulses upon which co-ordination and the maintenance of the equilibrium depend are gathered up, as it were, in the tegmental system from the bulb upward, since this region is so intimately connected with the bulb and cord posteriorly, and with the optic thalamus and corpora quadrigemina anteriorly. In addition to the tegmentum, however, the cerebellum and pons are in some way concerned, because of their intimate connection with the spinal cord and bulb, the cerebellum being further connected with the auditory nerve on the one hand, and with the gray matter in connection with the tegmentum on the other hand.

## Sensory Centres.

There is evidence that fibres from the nerves of special sense are specially connected with definite and distinct parts of the cerebrum.

*Visual or Optic Centre.*—The termination of the optic nerve in each eye, the retina, to the structure of which we shall return when treating of the eye, is so arranged that when we look at an object with both eyes, symmetrical parts of each retina are used. For example, if we look at an object to the left, an image of that object is focussed upon the right half of both retinæ, viz., upon the temporal side of the right retina, and upon the nasal side of the left retina. The optic nerve-fibres of these symmetrical parts of the retina are gathered together behind where the optic nerves decussate, viz., in the optic chiasma. The fibres which come from the right side of both eyes are contained in the optic tract of the same side, viz., the right, those from the right eye being outside of the others. In the same way the left optic tract contains internally fibres from the left side of the right eye and externally those from the left side of the left eye. On the inner border of the optic chiasma and tract there are also commissural fibres which pass from one side of the brain to the other; these are fibres which connect one median corpus geniculatum with the other. They are called the inferior or arcuate commissure. The optic tract thus formed then passes back-ard and terminates in three distinct nuclei, viz., the pulvinar of the ptic thalamus, the anterior corpus quadrigeminum and the lateral orpus geniculatum. These nuclei waste if the eyes are removed from n adult animal; and if from a newly born animal, they do not develop. he optic chiasma in its course gives off fibres which are connected with e nucleus of the third nerve.

It appears that some of the fibres of the optic tract pass directly into e cerebral cortex without joining with the optic thalamus, corpus quad- geminum or corpus geniculatum.

It was shown above that the fibres of the cerebral cortex, known as e optic radiation, pass from the occipital region to the three nuclei out which we are speaking, viz., into the pulvinar of the optic thala- us, the anterior corpus quadrigeminum and lateral corpus geniculatum,



Fig. 397.—The Cortical Centres.

d it is known that when the occipital cortex is removed, these three ste. It has been further shown that in a newly born animal the moval of such a region is followed by imperfect development of the rts in question.

If one optic nerve be divided, blindness of the corresponding eye sults, but if one optic tract be divided there is a half blindness, ich is called *hemianopsia*, *hemianopia*, *or hemiopia*, right or left, ording as the right or left field of vision is cut off. It is highly obable that the occipital lobe (figs. 393, 397), and particularly e cuneus, is concerned as a so-called visual centre, since not only is onnected with the optic nerves, as we have seen, but also because the moval of the right occipital lobe in an animal (monkey), is followed left hemiopia, removal of the left by right hemiopia, and removal of h occipital lobes by total blindness. Some have connected the angular gyrus also with vision as the centre, while others look upon it merely as an accessory centre.

*Olfactory centre.*—The olfactory nerve differs from the other cranial nerves. In reality it is a representative of the olfactory lobes of other animals, which are part of the cerebrum. It originates as an off-shoot from the cerebral vesicle, the front part of which is developed into the bulb of the olfactory nerve, while the back forms its peduncle. The nerve, the cavity of which is filled up in the fully developed condition with neurogliar substance, lies upon the cribriform plate of the ethmoid bone, and is contained in a groove of the frontal lobe on its under surface. On examination of the bulb it is found to be thus made up. Beneath the neurogliar layer is a layer of longitudinal fibres and a few nerve-cells, next to this is a layer of small cells (nuclear layer), fibres from the layer of nerve-fibres passing through it.

The nuclear layer is also separated into groups of cells by an interlacing of the fibres. The next layer is thick and is composed of neuroglia and some fibres, some of which are medullated, as well as of cells more or less pyramidal in shape. Below this layer is the layer of *olfactory glomeruli.* These glomeruli are small coils of olfactory fibres inclosing small cells and granular matter. A full description of the anatomy of these parts is given later (see **Olfactory nerve**).

Fibres of the olfactory nerve proper are found below this layer and pass to be distributed to the olfactory mucous membrane. They are thought to have origin in the glomeruli. The peduncle of the nerve or the *olfactory tract* as it is sometimes called, is made up of longitudinal fibres originating in the bulb, with neuroglia and some nerve-cells.

The fibres of the olfactory tract have been traced into the nucleus amygdalæ and its junction with the hippocampal gyrus in the temporal lobe (fig. 397). The hippocampus must be in some way connected with smell, since a lesion of it, leaving the olfactory tract uninjured, seriously interferes with that sense.

*Taste centre.*—It is very uncertain where the taste centre is situated, if such exist. It has been placed in the temporal lobe, not far from that of smell (fig. 397).

*Auditory Centre.*—This centre has been localized in the superior temporal convolution (fig. 393). Experiments have been made which connect auditory impulses on either side with the posterior corpus quadrigeminum and the median corpus geniculatum, for when the internal ear is destroyed there results atrophy of these bodies as well as of the lateral fillet of the opposite side; and on the other hand, destruction of the part of the temporal lobe above indicated is similarly followe atrophy of the nuclei of the same side. If these results be confirme additional experiments, it would make it plain that these nuclei much the same relation to the sense of hearing as do the anterior corpo rigeminum and the lateral corpus geniculatum to the sense of .

*entre for Cutaneous Sensations.*—Physiological experiments, as well nical and pathological observations, now show pretty certainly that ortical centre for sensations of touch, and probably of pain and erature, are essentially identical with the motor areas, that is to in the central convolutions. Owing, however, to the wide distribu- of afferent impulses, through the multiplication of their means of ng to the brain, the area of these sensory centres is not as strictly ed as that of other special centres.

*he Centre for Muscular Sensations.*—A great deal of evidence is ac- lated to show that the most important area in which these sensa- are brought to consciousness is in the inferior parietal lobule.

### FUNCTIONS OF CORPORA STRIATA AND OPTIC THALAMI.

*he Corpora Striata.*—The idea formerly held that the corpora a are concerned in the transmission of motor impulses, or that they he great motor ganglia at the base of the brain, rests upon insuffi- evidence. Lesions of the corpora striata produce hemiplegia only se of the pressure-effects they exercise upon the internal capsule by.

he caudate nucleus is connected with the opposite side of the cere- m by fibres which conduct downward, and the lenticular nucleus is ected with the cerebellum by fibres from the tegmentum and su- r cerebellar peduncles which conduct upward. It is suggested that orpora striata are central organs analogous to the cerebral cortex . "The analogy to those parts of the cortex that are connected the cerebellum is rendered still greater by the fact that a lesion, an extensive lesion, may exist in either the caudate or lenticular us, and so long as it does not interfere with the functions of the r or sensory parts of the internal capsules it causes no persistent toms." (Gowers.)

n the whole, however, it must be said that the functions of the ra striata are unknown, and it is possible that in man they are very liary, if not even rudimentary, bodies.

*he Optic Thalami.*—That the optic thalami are the great sensory es at the base of the brain—which was a view held by many until tly—does not seem to be based upon sufficiently accurate observa- The important relation to the tegmentum of its own side would it appear as being specially concerned with the sensory fibres pass- o the cerebrum, for which it probably forms a relay.

s connection with the optic nerves has been commented upon . Fibres connect the optic thalamus too with the superior pe- le of the cerebellum of the opposite side.

Lesions of the optic thalamus do not of themselves produce entire loss of sensation. If such a symptom follows, it is due to pressure upon, or injury to, the posterior limb of the internal capsule. The optic thalamus is connected with visual sensations and may be a reflex-centre for some of the higher reflex actions.

The optic thalamus is so closely connected with a large area of the cortex that it undoubtedly must have some function in connection with the mechanical or muscular movements and of expression. It is probable that it is the organ to which automatic activities are relegated in states of partial consciousness. The automatic walking, writing, speaking, and emotional expressions, for example, that are done by men in hypnotic states or in sleep, are very probably largely under the control of the optic thalamus in connection with the cerebellum and associated ganglia.



Fig. 398.—Cerebellum in section and fourth ventricle, with the neighboring parts. 1, Median groove of fourth ventricle, ending below in the *calamus scriptorius*, with the longitudinal eminences formed by the *fasciculi teretes*, one on each side; 2, the same groove, at the place where the white streaks of the auditory nerve emerge from it to cross the floor of the ventricle; 3, inferior crus or peduncle of the cerebellum, formed by the restiform body; 4, posterior pyramid; above this is the calamus scriptorius; 5, superior crus of cerebellum, or processus e cerebello ad cerebrum (or ad testes); 6, 6, fillet to the side of the crura cerebri; 7, 7, lateral grooves of the crura cerebri; 8, corpora quadrigemina. (From Sappey after Hirschfeld and Leveillé.)

Of the functions of the *external capsule* and of the *claustrum* nothing definite is known.

## The Cerebellum.

The cerebellum (7, 8, 9, 10, fig. 363) is composed of an elongated central portion or lobe, called the vermiform processes, and two hemispheres. Each hemisphere is connected with its fellow, not only by means of the vermiform processes, but also by a bundle of fibres called the *middle crus* or *peduncle* (the latter forming the greater part of the

Varolii), while the *superior crura* with the valve of Vieussens con- it with the cerebrum (5, fig. 398), and the *inferior crura* (formed ie prolonged restiform bodies) connect it with the medulla oblongata g. 398).

*tructure.*—The cerebellum is composed of white and gray matter, atter being external, like that of the cerebrum, and like it infolded, at a larger area may be contained in a given space. The convolu- of the gray matter, however, are arranged after a different pattern, own in fig. 387. Besides the gray substance on the surface, there ear the centre of the white substance of each hemisphere, a small ıle of gray matter called the *corpus dentatum* (fig. 388, *cd*), resem- ; very closely the *corpus dentatum* of the olivary body of the medulla ıgata (figs. 362, 388, *o*).



ig. 399.—Outline sketch of a section of the cerebellum, showing the corpus dentatum. The n has been carried through the left lateral part of the pons, so as to divide the superior pe- e and pass nearly through the middle of the left cerebellar hemisphere. The olivary body lso been divided longitudinally so as to expose in section its *corpus dentatum*. *c r*, crus ri; *f*, fillet; *q*, corpora quadrigemina; *s p*, superior peduncle of the cerebellum divided; middle peduncle or lateral part of the pons Varolii, with fibres passing from it into the stem; *a v*, continuation of the white stem radiating toward the arbor vitæ of the folia; orpus dentatum; *o*, olivary body with its corpus dentatum; *p*, anterior pyramid. (Allen son.) ⅔.

f a section be taken through the gray matter of the cerebellum, it be found to be composed of two layers, an outer, or molecular, and ner, or granular, layer. Each of these layers contains a large num- f peculiar shaped nerve-cells, and very rich plexuses of nerve-fibres. ıt studies of the cortex of the cerebellum by modern methods have led a most complex and beautiful arrangement of the parts, which all describe briefly here.

he molecular layer contains two kinds of cells, one large and known *ırkinjé's* cells, the other smaller and known as *stellate* cells. The of Purkinjé lie along the internal margin of the layer, being, ir practically at the boundary of the molecular and granular layers. measure 40x30 $\mu$, and have large, round nuclei. Each cell gives ı enormous number of branching dendrites, which run up toward ırface of the cerebellum in the shape of a bush. Each little branch off from the side small buds, which are called the *gemmules* or s. These branching dendrites do not pass up altogether like the hes of a round bush, but are flattened like a bush that has been pressed, so that if one cuts the cell in one direction, only the profile shown. The Purkinjé cells are arranged so that the axis of these fl tened branches is transverse to the longitudinal surface of the convol



Fig. 400.—The different constituent elements of the gray cortical layer of the cerebellum.



Fig. 401.—Longitudinal section of the gray substance of a cerebellar convolution. Schem gr, Granula; n, its nervous processes: n', divisions of the latter in the molecular layer and separating into two longitudinal fine fibres; p, cells of Purkinjé.

ion, and if one makes a section down through the centre of the convo-
tion, in its longitudinal course, a side view of the cell only is shown
fig. 401).

The cells of Purkinjé give off at their under surface a neuraxon hich runs down into the white matter of the cerebellum. Lying hroughout the molecular layer are the stellate cells, which are much maller in size, and which give off a number of dendrites (fig. 388).

Each cell has also an axis-cylinder (neuraxon) and this sends off col-
aterals which end in a fine basket-like network which surrounds the



Fig. 402.—A, Afferent fibre to basket (stellate) cell; B, neuraxon of Purkinjé cell; C, afferent fibre to Purkinjé cell; D, afferent (mossy) fibre to granule cell.

ody of the cells of Purkinjé (fig. 402). On this account they are some
mes called basket-cells. There are other stellate-shaped cells in the
olecular layer which lie more superficially, and do not have this partic-
ar connection with the Purkinjé cells, but appear, however, to belong
the same type.

The granular layer contains a large number of very small granular-
ke cells that Golgi was the first to show were really nerve cells. They
e only about 5μ in diameter, and they have a number of short den-
ites which end in clubbed extremities. They give off a very fine axis-
linder process (neuraxon) which runs up into the molecular layer and
ere divides in a T-shaped fashion, the fibres running parallel to the
rface of the convolution and passing in between the branches of the
lls of Purkinjé. There are, besides these granular cells, a few larger
lls, with axis-cylinders, that divide and subdivide, ending in a finely
mifying plexus. These are known as the *cells of Golgi*. They are
nd in other parts of the brain.

The white substance of the cerebellum consists of nerve-fibres, which are of three kinds: 1st, Descending fibres, that are made up of the axis-cylinders of the cells of Purkinjé carrying impulses down from the cerebellar cortex. 2d, Ascending fibres, which pass into the granular layer, and there end in a number of very short, finely split fibres, presenting a mossy appearance, so that these are known as the *mossy fibres*. These connect with the granular cells of this layer. 3d, Ascending fibres, which pass up through the granular into the molecular layer and there break up into a fine network, which interlaces with and coils among the protoplasmic branches of the cells of Purkinjé.

It will be seen that the arrangements for the transmission and diffusion of nerve-impulses and for the cooperation of different cells with each other are extremely complicated and delicate, as would be needed for so important an organ. It is not possible to indicate absolutely by any scheme the course of fibres and the course of impulses through the cerebellum, but, approximately, it is somewhat like that in the accompanying figure (fig. 402).

Impulses pass up along those ascending fibres called "mossy" to the granular cells. These cells, being stimulated, send the impulses by their axis-cylinders to the molecular layer, and through their T-shaped divisions to the dendrites of the cells of Purkinjé. Thence an impulse is send out by the axis-cylinder process of this cell. Other ascending impulses are brought up by those fibres which pass to the molecular layer and send their terminals winding around among the dendrites of the cells of Purkinjé. Probably impulses pass up also through the ascending fibres, and affect the stellate cells, and through them and their basket-like terminals the cells of Purkinjé.

### FUNCTIONS OF THE CEREBELLUM.

(1.) With the exception of its middle lobe, *the cerebellum is itself insensible to irritation* and may be all cut away without eliciting signs of pain (Longet). Its removal or disorganization by disease is also generally unaccompanied by loss or disorder of sensibility; animals from which it is removed can smell, see, hear, and feel pain, to all appearances, as perfectly as before (Flourens; Magendie). It cannot, therefore, be regarded as a principal organ of sensation. Yet, if any of its crura be touched, pain is indicated; and, if the restiform tracts of the medulla oblongata be irritated, the most acute suffering appears to be produced.

(2.) *Co-ordination of Movements.*—In reference to motion, the experiments of Longet and many others agree that no irritation of the cerebellum produces movement of any kind. Remarkable results, however, are produced by removing parts of its substance. Flourens (whose experiments have been confirmed by those of Bouillaud, Longet, and others) extirpated the cerebellum in birds by successive layers. Feebleness and

of harmony of muscular movements were the consequence of remov-
he superficial layers. When he reached the middle layers, the ani-
became restless without being convulsed; their movements were
nt and irregular, but their sight and hearing were perfect. By the
that the last portion of the organ was cut away, the animals had
ely lost the powers of springing, flying, walking, standing, and
rving their equilibrium. When an animal in this state was laid upon
ck, it could not recover its former posture, but it fluttered its
s, and did not lie in a state of stupor; it saw the blow that threatened
d endeavored to avoid it. Volition and sensation, therefore, were
st, but merely the faculty of combining the actions of the muscles;
he endeavors of the animal to maintain its balance were like those
lrunken man.

he experiments afforded the same results when repeated on all classes
imals; and from them and the others before referred to, Flourens
red that the cerebellum belongs neither to the sensory nor the intel-
al apparatus; and that it is not the source of voluntary movements,
ugh it belongs to the motor apparatus; but is the organ for the co-
ation of the voluntary movements, or for the excitement of the *com-*
action of muscles.

ch evidence as can be obtained from cases of disease of this organ
rms the view taken by Flourens: and, on the whole, it gains sup-
from comparative anatomy; animals whose natural movements
re most frequent and exact combinations of muscular actions being
whose cerebella are most developed in proportion to the spinal

e must remember, too, that the cerebellum is connected with the
rior columns of the cord as well as with the direct cerebellar tract,
of which probably convey to the middle lobe muscular sensations.
also connected with the auditory nerves and bulb by the internal and
nal acute fibres; and with the tegmentum through the red nuclei.
nnection with the efferent tracts from the different cerebral lobes
gh the pons is also highly important. Movements of the eyes also
r on direct stimulation of the middle lobe. It seems, therefore, to
nnected in some way with all of the chief sensory impulses which
to do with the maintenance of the equilibrium, and is generally
ded in the nervous apparatus which is supposed to govern this func-
of our bodies.

ville supposed that the cerebellum is the organ of *muscular sense*, *i.e.*, the
by which the mind acquires that knowledge of the actual state and
on of the muscles which is essential to the exercise of the will upon them;
t must be admitted that all the facts just referred to are as well explained
is hypothesis as on that of the cerebellum being the organ for combining

movements. A harmonious combination of muscular actions must depend as much on the capability of appreciating the condition of the muscles with regard to their tension, and to the force with which they are contracting, as on the power which any special nerve-centre may possess of exciting them to contraction. And it is because the power of such harmonious movement would be equally lost, whether the injury to the cerebellum involved injury to the seat of muscular sense, or to the centre for combining muscular actions, that experiments on the subject afford no proof in one direction more than the other.

**Forced Movements.**—The influence of each half of the cerebellum is directed to muscles on the opposite side of the body; and it would appear that for the right ordering of movements, the actions of its two halves must be always mutually balanced and adjusted. For if one of its crura, or if the pons on either side of the middle line, be divided, so as to cut off from the medulla oblongata and spinal cord the influence of one of the hemispheres of the cerebellum, strangely disordered movements ensue (forced movements). The animals fall down on the side opposite to that on which the crus cerebelli has been divided, and then roll over continuously and repeatedly; the rotation being always round the long axis of their bodies, and generally from the side on which the injury has been inflicted. The rotations sometimes take place with much rapidity; as often, according to Magendie, as sixty times in a minute, and may last for several days. Similar movements have been observed in men; as by Serres in a man in whom there was apoplectic effusion in the right crus cerebelli; and by Belhomme in a woman, in whom an exostosis pressed on the left crus. They may, perhaps, be explained by assuming that the division or injury of the crus cerebelli produces paralysis or imperfect and disorderly movements of the opposite side of the body; the animal falls, and then, struggling with the disordered side on the ground, and striving to rise with the other, pushes itself over; and so again and again, with the same act, rotates itself. Such movements cease when the other crus cerebelli is divided; but probably only because the paralysis of the body is thus made almost complete. Other varieties of forced movements have been observed, especially those named "circus movements," when the animal operated upon moves round and round in a circle; and again those in which the animal turns over and over in a series of somersaults. Nearly all these movements may result on section of one or other of the following parts; viz., crura cerebri, medulla, pons, cerebellum, corpora quadrigemina, corpora striata, optic thalami, and even, it is said, of the cerebral hemispheres.

### Functions of the Corpora Quadrigemina and Geniculata.

The corpora quadrigemina are the homologues of the optic lobes in birds, amphibia, and fishes. The anterior pair may be regarded as the incipal nerve-centres for visual sensations, the posterior possibly with ditory sensation.

*Functions.*—(1) The experiments show that removal of the anterior rpora quadrigemina wholly destroys the power of seeing; and diseases which they are disorganized are usually accompanied by *blindness.* rophy of them is also often a consequence of removal of the eyes. struction of one of the anterior corpora quadrigemina (or of one optic be in birds) produces hemiopia of opposite field of vision. This loss of ght is the only apparent injury of sensibility sustained by the removal the corpora quadrigemina.

The (2) removal of one of them affects the movements of the body, that animals rotate, as after division of the crus cerebri, only more wly: but this may be due to giddiness and partial loss of sight.

(3) The more evident and direct influence is that produced on the is. It contracts when the anterior corpora quadrigemina are irritated: is always dilated when they are removed: so that they may be regarded, some measure at least, as the nervous centres governing its move-ents, and adapting them to the impressions derived from the retina rough the optic nerves and tracts.

(4) The centre for the co-ordination of the movements of the eyes is so contained in them. This centre is closely associated with that for ntraction of the pupil, and so it follows that contraction or dilatation llows upon certain definite ocular movements.

As we have seen, the lateral corpus geniculatum is associated on ther side with the anterior corpus quadrigeminum, and the median rpus geniculatum with the posterior corpus quadrigeminum.

## MMARY OF THE COURSE OF MOTOR AND SENSORY IMPULSES WITHIN THE CEREBRO-SPINAL AXIS.

Impulses may be divided into (*a*) those which pass to the cerebro-nal axis from the periphery (afferent or centripetal impulses); (*b*) se which pass from the cerebro-spinal axis to the periphery (efferent centrifugal impulses; (*c*) those which pass between various parts of cerebro-spinal axis itself (connecting or intracentral impulses).

Afferent impulses, entering the cord from the periphery over the terior spinal nerve roots, may be brought into connection with effer- neurons at the same level or at higher or lower levels by collaterals the afferent neurons and connecting neurons. In this way cord re-es may be brought about. Part of the afferent impulses, entering cord, pass up, without interruption, first in the postero-lateral mn, and, later, in the postero-median, being forced into the postero-median column as new fibres enter the postero-lateral, to the nuclei gracilis and cuneatus, where their axones terminate.

Another part of the afferent impulses passes into the gray matter of the cord, and by means of another series of neurons, which takes them up, is passed over to the other side of the cord and thus up, either on the same side, or first on one side and then on the other, until the medulla is reached. Here in the nuclei gracilis and cuneatus, all axones which have conducted sensory impulses from the cord below terminate, and the impulses are carried up by new sets of fibres whose cell bodies of origin form these nuclei. A large strand of axones from these nuclei passes over to the opposite side of the medulla, forming the internal arcuate fibres of the formatio reticularis, and then passes up in the fillet of the posterior pyramids, behind the motor fibres of the anterior pyramids, which are carrying impulses down. The sensory impulses are continued up in the posterior part of the crura cerebri, a large part passing to the optic thalami, where they are transferred to another set of neurons, by which they are carried to the sensory areas of the cerebral cortex. Others are carried up to the sensorium, through the posterior limb of the internal capsule, and thence through the corona radiata, without further interruption.

The nuclei gracilis and cuneatus are also connected through the restiform body or inferior cerebellar peduncle with the gray matter of the cerebellum of the same side. By means of several relays of neurons, such sensory impulses as have passed to the cerebellum may eventually reach the cortex of the opposite cerebral hemisphere through the middle cerebellar peduncle and pons, and, also, through the superior cerebellar peduncle. Thus the cerebellum may form another indirect alternate pathway for the passage of sensory impressions to the cerebrum.

The cerebellum, also, is probably brought into relation with sensory impulses, reaching the cord from the periphery, by means of the cells of Clark's column and the direct cerebellar tract.

Motor impulses originating in the cells of the motor areas of the cerebral cortex are carried down without interruption by the axones of these cells, forming the motor pathways. These are found in the various portions of the brain, medulla, and cord in relation with other parts as follows: First, they form a part of the corona radiata which, converging between the optic thalamus and the caudate and lenticular nuclei of the corpus striatum, form the middle portion of the internal capsule. Below this point they are continued as the anterior part of the crura cerebri. Thence they pass behind and through the transverse fibres of the pons and in front of the fibres carrying sensory impulses up. Below the pons, the mass of fibres becomes visible as the anterior pyramids. At the lower portion of the medulla, the larger internal parts of these pyramidal fibres cross downward and backward to the opposite side, and are found below this point, as the crossed pyramidal tracts, in the lateral columns of the cord. The remaining smaller portions of the pyramidal fibres are continued down on the same side and converge to form the direct pyramidal tracts on each side of the anterior median fissure in the anterior columns of the cord.

The crossed pyramidal-tract fibres terminate at various levels of the cord and transfer their impulses, without further crossing, to the motor neurons, whose cell bodies of origin lie in the anterior horns of gray matter, and whose axones carry the impulses to the periphery. The direct pyramidal-tract fibres cross over at various levels of the cord by way of the anterior white commissure, and terminate, in the same way, about cell bodies of efferent neurons in the anterior horn of the opposite ide.

Although the large majority of motor impulses from either cerebral hemisphere cross, eventually, to the opposite side of the cord, a few are distributed by uncrossed fibres running in the lateral columns to the same side of the cord.

Other possible pathways, for motor impulses from the cerebrum, are y various relays of neurons through (*a*) the optic thalamus, the nucleus ubra, superior cerebellar peduncle, opposite cerebellar cortex and cord ia descending cerebellar fibres; (*b*) corpus striatum, pons, opposite erebellar hemisphere and cord. It is also possible that the cerebellum akes part in co-ordinated motor reflexes without the intervention of the erebrum.

## THE SYMPATHETIC SYSTEM.

Having in the preceding chapters completed the description of the erebro-spinal nervous system proper, there remain to be considered e structure and functions of the so-called Sympathetic nervous system, d to this it is now necessary to direct attention.

It should, however, be distinctly borne in mind that the cerebro-inal and sympathetic systems are not distinct from each other. The paration of the one from the other may be considered to be purely for e sake of convenience.

*Distribution.*—It consists of: (1) A double chain of ganglia and res, which extends from the cranium to the pelvis, along each side of e vertebral column, and from which branches are distributed both to e cerebro-spinal system, and to other parts of the sympathetic system. th these may be included the small ganglia in connection with those nches of the fifth cerebral nerve which are distributed in the neigh-hood of the organs of special sense: namely, the *Ophthalmic*, *Otic*, *Spheno-palatine* and *Submaxillary* ganglia. (2) Various ganglia and plexuses of nerve-fibres which give off branches to the thoracic and abdominal viscera, the chief of such plexuses being the *Cardiac*, *Solar*, and *Hypogastric;* but in intimate connection with these are many secondary plexuses, as the *Aortic*, *Spermatic*, and *Renal.* To these plexuses, fibres pass from the prævertebral chain of ganglia, as well as from cerebro-spinal nerves. (3) Various ganglia and plexuses in the substance of many of the viscera, as in the *Stomach*, *Intestines*, and *Urinary bladder.* These, which are, for the most part, microscopic, also freely communicate with other parts of the sympathetic system, as well as, to some extent, with the cerebro-spinal. (4) By many, the ganglia on the *Posterior roots of the spinal nerves*, on the *Glossopharyngeal* and *Vagus*, and on the *Sensory root* of the *Fifth cerebral nerve* (Gasserian ganglion), are also included as sympathetic-nerve structures.

*Classification.*—Gaskell's researches have suggested a convenient classification for the sympathetic ganglia into: (1.) The main sympathetic chain, extending from above downward, in the form of connected ganglia lying upon the bodies of the vertebræ, which may be called *lateral* or vertebral ganglia. (2.) A more or less distinct chain, prævertebral in position, consisting of the semi-lunar inferior mesenteric and similar plexuses, which may be called prævertebral or *collateral* ganglia. (3.) Ganglia situated in the organs and tissues themselves, called *terminal* ganglia. (4.) The *ganglia of the posterior roots* of the spinal nerves (see fig. 403).



Fig. 403.—Scheme of the constitution of the white ramus communicans of the sympathetic. The roots and trunks of a spinal nerve are shown, with the white ramus passing between the spinal nerve and a sympathetic ganglion, *Sy.* (Cunningham.)

The connection between these parts is as follows: the visceral branch or ramus communicans of each spinal nerve, which is one of the divisions of a typical spinal nerve—the others being the dorsal and ventral—passes first of all into the lateral chain; from this chain branches, *rami efferentes*, pass into the collateral ganglia, and from these again other branches pass off into the organs to end in the terminal ganglia. In the thoracic region the rami communicantes are composed of two parts, white and gray. The former can be traced backward into both spinal nerve-roots of their corresponding spinal nerve; and in the other ection partly in the lateral sympathetic chain, and partly into the at splanchnic nerves and so into the collateral ganglia without enter- the lateral chain at all. The upper *white* rami (from the 2nd to the ), however, proceed upward and join the superior cervical ganglion tead of passing downward into the splanchnics (see fig. 404). Other



Fig. 404.—Scheme of the constitution and connections of gangliated cord of the sympathetic. The liated cord is indicated on the right, with the arrangement of fibres arising from ganglion cells. he left, the roots and trunks of the spinal nerves are shown, with the arrangement of the white is communicans above and the gray ramus below. (Cunningham.)

nches go downward into the lumbar and sacral plexuses. The *gray* i of all the spinal nerves are the only apparent representatives of the eral branches in the regions above the 2nd thoracic nerve-root, and w the 2nd lumbar nerve-root, with the exception of the roots of the and 3rd sacral nerves, which have also white rami, and consist of non- dullated fibres, and pass from the ganglia to be distributed chiefly to the spinal column, to the spinal membranes and to the spinal nerve-roots themselves. We must look upon the white rami then as the visceral branches proper.

A peculiarity in the structure of these white medullated visceral nerves is the fineness of their fibres. They are a third or a fourth of the diameter of ordinary medullated fibres, measuring 1.8$\mu$ to 2.7$\mu$ instead of 14.4$\mu$ to 19$\mu$. Such fibres are a peculiarity of the spinal nerve-roots chiefly in the thoracic region, but they are also found in the second and third sacral nerves, and constitute there the *nervi erigentes* which pass directly to the hypogastric plexus, and not first of all into the lateral chain. From this plexus branches pass upward into the inferior mesenteric ganglia and downward to the bladder, rectum and generative organs. These nerves, called by Gaskell *pelvic splanchnic* nerves, differ from the rami viscerales of the thoracic region only in not communicating with the lateral ganglia; the branches which pass upward from the thoracic region to the neck, he calls *cervical splanchnics*, and the splanchnics proper *abdominal splanchnics*. The white rami viscerales of the upper cervical and cervico-cranial regions do not run with their corresponding gray rami, but form, Gaskell thinks, the internal branch of the spinal accessory nerve, which contains small medullated fibres similar to those of the visceral branches in the thoracic region. This branch passes into the ganglion of the trunk of the vagus. Small visceral fibres exist too in the roots of the vagus, and in those of the glosso-pharyngeal in connection with the ganglion of the trunk and ganglion petrosum, as well as in the chorda tympani, in the small petrosal and in other cranial visceral nerves.

*Functions.*—The researches of Gaskell have, however, done much to clear up the former confusion as to the functions of the sympathetic; and in the following account the description of the functions, as given by that observer, is followed.

The efferent *nerve fibres* of the sympathetic system supply (*a*) the **muscles of the vascular system,** to which they send vaso-motor fibres, *i.e.*, *vaso-constrictor* and *cardiac augmentor or accelerator*, and vaso-inhibitory fibres, *i.e.*, *vaso-dilator and cardiac inhibitory;* (*b*) the **visceral muscles,** to which they send both *viscero-motor* and *viscero-inhibitory* fibres. (*c*) The **secretory gland-cells.**

(*a*) i. *Vaso-motor or Vaso-constrictor* and *Cardio-augmentor Fibres.*—The vaso-motor nerves for all parts of the body come from the central nervous system, and pass out from the spinal cord in the white rami viscerales of the thoracic region from the second thoracic to the second lumbar nerve-roots inclusive, as fine medullated fibres; they then pass to the latera main sympathetic chain, become non-medullated, and are distribute their muscles either directly or through terminal ganglia. Thus the tor nerves of the heart arise in the thoracic rami, pass upward ugh the ganglion stellatum (first thoracic ganglion), the annulus of ssens and the inferior cervical ganglion, and are distributed to the t; the vaso-motor roots of the brachial plexus, in the anterior roots he second and lower thoracic nerves, and reach that plexus by the ganglion; the vaso-motor nerves of the foot leave the spinal cord up, and reach the sympathetic lateral ganglia above the origin of ciatic nerve, into which they pass through the abdominal sympa- c. In all cases the nerves lose their medulla in the ganglia. larly the vaso-motor nerve supply for the blood-vessels of the head neck and of the abdomen is derived from the cervical and abdominal chnics respectively, or from the corresponding rami efferentes of pper lumbar ganglia.

he lateral sympathetic chain Gaskell proposes to call the *chain of -motor ganglia.*

or the distribution of sympathetic fibres to the heart, see fig. 378.

i. *Vaso-inhibitory or Vaso-dilator, and Cardio-inhibitory Fibres.*—hese, which are doubtless as widely distributed as the vaso-motor s, we have distinct proof in the existence of fibres separate from -motor, *e.g.*, in the inhibitory nerve of the heart, the cardio-vagus; e chorda tympani; in the small petrosal, and in the nervi erigentes. hese nerve-fibres, as far as we know at present, leave the central ous system among the fine medullated nerves of the cervico-cranial sacral rami communicantes, do not enter the lateral ganglia, but without losing their medulla into the collateral or terminal lia.

b.) i. *Viscero-motor Fibres.*—These fibres, upon which depend the taltic movements of the thoracic portion of the œsophagus, and of tomach and intestines, arise from the central nervous system, as ine medullated fibres of the upper portion of the cervical region, not he spinal nerve-roots of that region, but as the bundles of fibres h may be called the rami viscerales of the vagus and accessory nerves. pass to the ganglion of the trunk of the vagus, where they lose medulla.

i. *Viscero-Inhibitory Fibres.*—It appears that the nerve supply to ircular muscles of the alimentary canal and its appendages, is con- d in the abdominal splanchnics, and consists of those fibres which not passed through the lateral chain, and which therefore retain medulla until they reach the proximal or collateral chain.

.) *Glandular Nerve-Fibres.*—A double nerve supply, in all proba- coinciding with the supply to the visceral muscles, has been nstrated in the cases of the submaxillary, parotid, and lachrymal ls, and in these cases the course of the fibres is very similar to of the corresponding fibres for the vaso-muscular supply. Thus the sympathetic supply for these glands passes along with the vaso-motor fibres from the cervical splanchnic (or sympathetic trunk), and superior cervical ganglion; while the cerebro-spinal supply comes from the rami viscerales of the cranial nerves in conjunction with the vaso-dilator fibres.

*Central Origin of the Rami Viscerales.*—There appears to be the strongest presumption that the white rami of the thoracic region arise in the spinal cord in, or are connected with, the cells of the posterior vesicular column of Clarke. This conclusion is based upon the fact that these special cells are found in the three regions already mentioned, and in those only where the white rami of fine medullated fibres exist, viz., in the cervico-cranial regions, in the spinal accessory, in the thoracic region, and in the sacral region. But it is probable that the fibres are also connected with the cells of the lateral horn of the gray matter of the spinal cord, and its representative in the medulla, the antero-lateral nucleus of Clarke.

In a paper supplementary to his first account of the sympathetic system, Gaskell traced the nerve fibres of the anterior nerve roots to the various groups of nerve cells in the spinal cord thus: (i.) Efferent nerves to somatic muscles arise from group of cells of anterior cornua; (ii.) efferent nerves to striated splanchnic muscles from cells of the tractus intermedio-lateralis. (iii.) Anabolic or inhibitory nerves to glands, muscles of viscera, and vessels of splanchnic system from cells of Clarke's column; (iv.) motor nerves to visceral muscles from solitary cells at the base of the posterior cornu; and (v.) motor or catabolic nerves to glands and vascular muscles from small cells of the lateral cornu.

**Structure and Functions of the Ganglia.**—The sympathetic ganglia all contain—(1.) nerve-fibres traversing them; (2.) nerve-fibres originating in them, (3.) nerve or ganglion-corpuscles, giving origin to these fibres; and (4.) other corpuscles that appear free. In the sympathetic ganglia of the frog, ganglion-cells of a very complicated structure have been described by Beale, and subsequently by Arnold. The cells are inclosed each in a nucleated capsule: they are pyriform in shape, and from the pointed end two fibres are given off, which gradually acquire the characters of nerve-fibres: one of them is straight, and the other (which sometimes arises from the cell by two roots) is spirally coiled around it.

According to Gaskell the functions of the main sympathetic ganglia are the following:—(1.) They effect the conversion of medullated into non-medullated fibres; (2.) They possess a nutritive influence over the nerves which pass from them to the periphery; (3.) They increase the number of fibres at the same time as they cause the removal of the medulla. As regards their possession of the usual properties of nerve-tres little or nothing is certainly known. It appears unlikely that y possess the reflex functions of the spinal centres.

As a contribution toward the explanation of the nervous mechanism nutrition comes in Gaskell's theory of *katabolic* and *anabolic* nerves. supposes that every tissue is supplied with two sets of nerves, the ner of which corresponds with the motor nerve, the viscero-motor the cardio-augmentor, by the stimulation of which an increase of metabolism takes place, and which is followed by exhaustion. It y be accompanied either by contraction of a muscle or by an increase ontraction. Such a nerve is excellently illustrated by the sympa-tic augmentor or accelerator nerve of the heart, on stimulation of ch an increase in the force and frequency of the heart takes place, owed after a time by exhaustion. A katabolic nerve stimulates the tructive metabolism which is always going on in a tissue. The bolic nerve is the exact opposite of the katabolic nerve in function. ubserves constructive metabolism. Stimulation of the nerve pro-es diminished activity, repair of tissue and building up. An exam- of this kind of nerve is seen in the cardiac vagus, stimulation of ch produces inhibition. Inhibition must generally be looked upon n anabolic process.

It will be seen that the results of stimulation of the nerves to the vary glands, discussed in a former chapter, appear to support the ry, that the processes of constructive and destructive metabolism under the control of separate nerve-fibres. In the case of the sub-illary gland for example, if the sympathetic fibres be stimulated, a bolic effect is produced, and the materials of secretion are formed at expense of the protoplasm (this action in the case of the gland denhain calls *trophic*); if on the other hand the chorda tympani or secretory nerve be stimulated, two things happen, one being the harge of water and the materials of secretion from the gland cells, the other the building up or reconstruction of the protoplasm of the s. A part of this action at any rate is anabolic, and similar to the on of inhibitory nerves.

# CHAPTER XVII.

## THE SENSES.

***General Considerations.***—Through the medium of the nervous system the mind obtains a knowledge of the existence both of the various parts of the body, and of the external world. This knowledge is based upon *sensations* resulting from the stimulation of certain centres in the brain, by irritations conveyed to them by afferent nerves. Under normal circumstances, the following structures are necessary for sensation: (*a*) A peripheral organ for the reception of the impression; (*b*) a nerve for conducting it; (*c*) a nerve-centre for feeling or perceiving it.

***Classification of Sensations.***—Sensations may be conveniently classed as (1) common and (2) special.

**(1.) Common Sensations.**—Under this head fall all those general sensations which cannot be distinctly localized in any particular part of the body, such as *fatigue*, *discomfort*, *faintness*, *satiety*, together with *hunger* and *thirst*, in which, in addition to a general discomfort, there is in many persons a distinct sensation referred to the stomach or fauces. In this class must also be placed the various irritations of the mucous membrane of the bronchi, which give rise to coughing, and also the sensations derived from various viscera indicating the necessity of expelling their contents; *e.g.*, the desire to defæcate, to urinate, and, in the female, the sensations which precede the expulsion of the fœtus. We must also include such sensations as itching, creeping, tickling, tingling, burning, aching, etc., some of which come under the head of *pain:* they will be again referred to in describing the tactile sense. It is impossible to draw a very clear line of demarcation between many of the common sensations above mentioned, and the sense of touch, which forms the connecting link between the general and special sensations. Touch is, indeed, usually classed with the special senses, and will be considered in the same group with them; yet it differs from them in being common to many nerves. Among common sensations some would rank the muscular sense, which has been already alluded to. It is by means of this sense that we become aware of the condition of the muscles, and thus obtain the information necessary for their adjustme various purposes—standing, walking, grasping, etc. This mus sensibility (to which we shall again refer) is shown in our power to

te the differences between weights by the different muscular efforts
essary to raise them. It must be carefully distinguished from the
se of contact and of pressure, of which the skin is the organ. When
nding erect, we can feel the ground (contact), and further there is a
se of pressure, due to our feet being pressed against the ground by
weight of the body. Both these are derived from the skin of the
of the foot. If now we raise the body on the toes, we are conscious
scular sense) of a muscular effort made by the muscles of the calf,
ch overcomes a certain resistance.

(2.) **Special Sensations.**—Including the sense of touch, the special
ses are five in number—Touch, Taste, Smell, Hearing, Sight.

The most important distinction between common and special sensa-
s is that by the former we are made aware of certain conditions of
ous parts of our bodies, while from the latter we gain our knowledge
he external world also. This difference will be clear if we compare
sensations of pain and touch, the former of which is a common, the
er a special sensation. "If we place the edge of a sharp knife on
skin, we feel the edge by means of our sense of touch; we perceive
nsation, and refer it to the object which has caused it. But as soon
e cut the skin with the knife, we feel pain, a feeling which we no
er refer to the cutting knife, but which we feel within ourselves,
which communicates to us the fact of a change of condition in our
body. By the sensation of pain we are neither able to recognize
object which caused it, nor its nature."

In studying the phenomena of sensation, it is important clearly to
erstand that the *sensorium*, or seat of sensation, is in the brain, and
in the particular organ through which the sensory impression is re-
ed. In common parlance we are said to see with the eye, hear with
ear, etc., but in reality these organs are only adapted to receive
ressions which, being conducted to the sensorium, through their re-
tive nerves give rise to sensation.

Hence, if the optic nerve is severed, vision is no longer possible:
e, although the image falls on the retina as before, the sensory im-
sion can no longer be conveyed to the sensorium. When any given
ation is felt, all that we can with certainty affirm is that some part
the brain is excited. The exciting cause may be some object of the
rnal world, producing an *objective sensation;* or the condition of the
orium may be due to some excitement within the brain itself, in
ch case the sensation is termed *subjective.* The mind habitually re-
sensations to external causes; and hence, whenever they are subjec-
we can hardly divest ourselves of the idea of an external cause, and
llusion is the result.

Numberless examples of such illusions might be quoted. As familiar cases may be mentioned, humming and buzzing in the ears caused by some irritation of the auditory nerve or centre, and even musical sounds and voices (sometimes termed auditory spectra); also so-called optical illusions: objects are described as seen, although not present. Such illusions are most strikingly exemplified in cases of delirium tremens or other forms of delirium, and may take the form of cats, rats, creeping loathsome forms, etc.

*Causes of Illusions.*—One uniform *internal* cause, which may act on all the nerves of the senses in the same manner, is capillary congestion. This one cause excites in the retina, while the eyes are closed, the sensations of light and luminous flashes; in the auditory nerve, the sensation of humming and ringing sounds; in the olfactory nerve, the sense of odors; and in the nerves of feeling, the sensation of pain. In the same way, also, a narcotic substance introduced into the blood, excites in the nerves of each sense peculiar symptoms: in the optic nerves, the appearance of luminous sparks before the eyes; in the auditory nerves, *tinnitus aurium;* and in the common sensory nerves, the sensations of creeping over the surface. So, also, among *external* causes, the stimulus of electricity, or the mechanical influence of a blow, concussion, or pressure, excites in the eye the sensation of light and colors; in the ear, a sense of a loud sound or of ringing; in the tongue, a saline or acid taste; and in the other parts of the body, a perception of peculiar jarring or of the mechanical impression, or a shock like it.

Experiments seem to have proved, however, that none of the nerves of special sense possess the faculty of common sensibility.

*Perceptions.*—The habit of constantly referring our sensations to external causes, leads us to interpret the various modifications which external objects produce in our sensations, as *properties* of the external bodies themselves. Thus we speak of certain substances as possessing a disagreeable taste and smell; whereas, the fact is, their taste and smell are only disagreeable to *us.* It is evident, however, that on this habit of referring our sensations to causes outside ourselves (perception), depends the reality of the external world to us; and more especially is this the case with the senses of touch and sight. By the co-operation of these two senses, aided by the others, we are enabled gradually to attain a knowledge of external objects which daily experience confirms, until we come to place unbounded confidence in what is termed the evidence of the senses.

*Judgments.*—We must draw a distinction between mere sensations and the judgments based, often unconsciously, upon them. Thus, in looking at a near object, we unconsciously estimate its distance and say it seems to be ten or twelve feet off: but the estimate of its distance is in reality a judgment based on many things besides the appearance of ct itself; among which may be mentioned the number of inter- objects, the number of steps which from past experience we e must take before we could touch it, and many others.

## The Special Senses.

### I. Touch.

.—The sense of touch is not confined to particular parts of the small extent, like the other senses; on the contrary, all parts of perceiving the presence of a stimulus by ordinary sensation a certain degrees, the seat of this sense; but touch should not be ed as a mere modification or exaltation of common sensation or ity. For although the nerves on which the sense of touch de- are the same as those which confer ordinary sensation on the t parts of the body, viz., those derived from the posterior roots nerves of the spinal cord, and the sensory cerebral nerves, yet it robable that the nerve-fibres which subserve the special sense of re provided with special end organs.

parts of the body supplied with sensory nerves are thus, in some organs of touch, yet the sense is exercised in perfection only in rts the sensibility of which is extremely delicate, *e.g.*, the skin, gue, and the lips, which are provided with abundant papillæ. iar and, of its own kind in each case, a very acute sense of touch sed through the medium of the nails and teeth. To a less extent may be reckoned an organ of touch; as in the case of the eye- The sense of touch renders us conscious of the presence of a s, from the slightest to the most intense degree of its action, by describable something which we call feeling, or common sensa- The modifications of this sense often depend on the extent of the ected. The sensation of pricking, for example, informs us that itive fibres are intensely affected in a small extent; the sensation ure indicates a slighter affection of the parts in the greater ex- d to a greater depth. It is by the depth to which the parts are that the feeling of pressure is distinguished from that of mere

*ieties.*—(*a*) The sense of touch proper, tactile sensibility or pres- ) temperature. These when carried beyond a certain degree are in the sensation of (*c*) pain.

**ch proper.**—In almost all parts of the body which have deli- tile sensibility the epidermis, immediately over the papillæ, is ely thin. When its thickness is much increased, as over the e sense of touch is very much dulled. On the other hand, when gether removed, and the cutis laid bare, the sensation of contact is replaced by one of pain. Further, in all highly sensitiv the papillæ are numerous and highly vascular, and the sensory are connected with special *end-organs* which have been describe *et seq.*

The special endings of the nerves which have to do with touc however, be here again mentioned. They are of two kinds, *touch corpuscles*, which are found chiefly in the hands and feet, larly on the palmar surface of the hands and fingers, but also under surface of the forearm, nipple, eyelids, lips, and genital Touch corpuscles are situated in the cutis vera. (b) *end bulbs* are found in conjunctivæ and other mucous membranes, the lips, organs, tongue, rectum, and elsewhere, but not in the skin prop regards the Pacinian corpuscles and similar end-organs, which widely distributed, and which may be in some way connected w sensation, when they are found in the skin they are situated very in the cutis vera or in the subcutaneous tissue. They are ex numerous on the nerves of the palmar surface of the fingers. I these endings, and in similar ones found in other animals, th ends, as in axis cylinder, in a special development of the connect sue sheath. In addition to these special nerve-endings, nerv appear to terminate everywhere in the skin between the cells Malpighian stratum of the epidermis in the ends, and in certain some of them appear to end in special and rather large cells.

It is practically impossible to distinguish between what is mere contact and touch in which the element of pressure co The acuteness of the sense of touch depends very largely on the ous circulation, which is of course largely influenced by external t ature. Hence the numbness, familiar to every one, produced application of cold to the skin.

*Acuteness of the Sense.*—The perfection of the sense of to different parts of the surface is proportioned to the power whic parts possess of distinguishing and isolating the sensations produ two points placed close together. This power depends, at least i on the number of primitive nerve-fibres distributed to the part; fewer the primitive fibres which an organ receives, the more like that several impressions on different contiguous points will act o one nervous fibre, and hence be confounded, and perhaps produ one sensation. Experiments have been made to determine the properties of different parts of the skin, as measured by this po distinguishing distances. These consist in touching the skin, wh eyes are closed, with the points of a pair of compasses sheathe cork, and in ascertaining how close the points of compasses mi brought to each other, and still be felt as two bodies.

**iations in the tactile sensibility of the different parts.**—*The mea- indicates the least distance at which the two blunted points of a ompasses could be separately distinguished.* (E. H. Weber.)

| | | |
|---|---|---|
| e . . . . . . . . . . . . | $\frac{1}{24}$ inch | 1 mm. |
| ce of third phalanx of forefinger . . | $\frac{1}{12}$ " | 2 " |
| ce of second phalanges of fingers . . | $\frac{1}{6}$ " | 4 " |
| of under-lip . . . . . . . . | $\frac{1}{6}$ " | 4 " |
| . . . . . . . . . . . | $\frac{1}{4}$ " | 6 " |
| rsum of tongue . . . . . . | $\frac{1}{3}$ " | 8 " |
| d . . . . . . . . . . . | $\frac{5}{12}$ " | 10 " |
| rd palate . . . . . . . . . | $\frac{1}{2}$ " | 12 " |
| e of first phalanges of fingers . . . . | $\frac{7}{12}$ " | 14 " |
| l . . . . . . . . . . | $1\frac{1}{6}$ " | 25 " |
| ot near toes . . . . . . . . | $1\frac{1}{2}$ " | 37 " |
| n . . . . . . . . . . | $1\frac{1}{2}$ " | 37 " |
| . . . . . . . . . . . | $1\frac{1}{2}$ " | 37 " |
| wer parts of forearm . . . . . | $1\frac{1}{2}$ " | 37 " |
| near occiput . . . . . . . | 2 " | 50 " |
| and mid-lumbar regions . . . . . | 2 " | 50 " |
| of forearm . . . . . . . . . | $2\frac{1}{2}$ " | 62 " |
| igh . . . . . . . . . . | $2\frac{1}{2}$ " | 62 " |
| region . . . . . . . . . . | $2\frac{1}{2}$ " | 62 " |
| egion . . . . . . . . . | $2\frac{1}{2}$ " | 62 " |

r, in the case of the limbs, it was found that before they ized as two, the points of the compasses had to be *further* hen the line joining them was in the long axis of the limb, n the transverse direction.

ng to Weber the mind estimates the distance between two e number of unexcited nerve-endings which intervene be- vo points touched. It would appear that a certain number ng unexcited nerve-endings are necessary before two points be recognized as separate, and the greater this number the y are the points of contact distinguished as separate. By delicacy of a sense of touch may be very much increased. llustration occurs in the case of the blind, who, by constant n acquire the power of reading raised letters the forms of lmost if not quite undistinguishable by the sense of touch to person.

*tion.*—The power of correctly localizing sensations of touch derived from experience. Thus infants when in pain sim- make no effort to remove the cause of irritation, as an older lt would, doubtless on account of their imperfect knowledge situation.

s.—The different degrees of sensitiveness possessed by differ- ay give rise to errors of judgment in estimating the distance points where the skin is touched. Thus, if blunted points f compasses (maintained at a constant distance apart) be n over the skin of the cheek toward the lips, it is almost im- esist the conclusion that the distance between the points is gradually increasing. When they reach the lips they seem to be considerably further apart than on the cheek. Thus, too, our estimate of the size of a cavity in a tooth is usually exaggerated when based upon sensation derived from the tongue alone. Another curious illusion may here be mentioned. If we close the eyes, and place a small marble or pea between the crossed fore and middle fingers, we seem to be touching two marbles. This illusion is due to an error of judgment. The marble is touched by two surfaces which, under ordinary circumstances, could only be touched by two separate marbles, hence the mind, taking no cognizance of the fact that the fingers are crossed, forms the conclusion that two sensations are due to two marbles.

**Temperature.**—The whole surface of the body is more or less sensitive to differences of temperature. The sensation of heat is distinct from that of touch: and it would seem reasonable to suppose that there are special nerves and nerve-endings for temperature. At any rate the power of discriminating temperature may remain unimpaired when the sense of touch is temporarily in abeyance. Thus if the ulnar nerve be compressed at the elbow till the sense of touch is very much dulled in the fingers which it supplies, the sense of temperature remains quite unaffected.

The sensations of heat and cold are often exceedingly fallacious, and in many cases are no guide at all to the absolute temperature as indicated by a thermometer. All that we can with safety infer from our sensations of temperature, is that a given object is warmer or cooler than the skin. Thus the temperature of our skin is the standard; and as this varies from hour to hour according to the activity of the cutaneous circulation, our estimate of the absolute temperature of any body must necessarily vary too. If we put the left hand into water at 5° C. (40° F.) and the right into water at 45° C. (110° F.), and then immerse both in water at 27° C. (80° F.), it will feel warm to the left hand but cool to the right. Again, a piece of metal which has really the same temperature as a given piece of wood will feel much colder, since it conducts away the heat much more rapidly. For the same reason air in motion feels very much cooler than air of the same temperature at rest.

In some cases we are able to form a fairly accurate estimate of absolute temperature. Thus, by plunging the elbow into a bath, a practised bath-attendant can tell the temperature sometimes within half a degree centigrade.

The temperatures which can be readily discriminated are between 10°–45° C. (50°–115° F.); very low and very high temperatures alike produce a burning sensation. A temperature appears higher according to the extent of cutaneous surface exposed to it. Thus, water of a temperature which can be readily borne by the hand, is quite intolerable if whole body be immersed. So, too, water appears much hotter to hand than to a single finger.

The delicacy of the sense of temperature coincides in the main with it of touch, and appears to depend largely on the thickness of the n; hence, in the elbow, where the skin is thin, the sense of tempera- e is delicate, though that of touch is not remarkably so. Weber has ther ascertained the following facts: two compass points so near to- her on the skin that they produce but a single impression, at once e rise to *two* sensations, when one is hotter than the other. More- r, of two bodies of equal weight, that which is the colder feels heavier n the other.

As every sensation is attended with an idea, and leaves behind it an a in the mind which can be reproduced at will, we are enabled to com- e the idea of a past sensation with another sensation really present. us we can compare the weight of one body with another which we l previously felt, of which the idea is retained in our mind. Weber s indeed able to distinguish in this manner between temperatures, erienced one after the other, better than between temperatures to ich the two hands were simultaneously subjected. This power of nparing present with past sensations diminishes, however, in propor- n to the time which has elapsed between them. *After-sensations* left impressions on nerves of common sensibility or touch are very vivid l durable. As long as the condition into which the stimulus has own the organ endures, the sensation also remains, though the excit- cause should have long ceased to act. Both painful and pleasurable sations afford many examples of this fact.

*Subjective sensations*, or sensations dependent on internal causes, are no sense more frequent than in the sense of touch. All the sensations pleasure and pain, of heat and cold, of lightness and weight, of fa- ne, etc., may be produced by internal causes. Neuralgic pains, the sation of rigor, formication or the creeping of ants, and the states of sexual organs occurring during sleep, afford striking examples of jective sensations. The mind has a remarkable power of exciting sations in the nerves of common sensibility: just as the thought of nauseous excites sometimes the sensation of nausea, so the idea of n gives rise to the actual sensation of pain in a part predisposed to numerous examples of this influence might be quoted.

**Pain.**—As regards painful sensations, three views can be taken: 1, t it is a special sensation provided with a special conducting apparatus ach part of the body; 2, that it is produced by an over-stimulation he special nerves concerned with touch or temperature, or of the r nerves of special sense; or 3, that it is an over-stimulation of the es of common sensation, which tell us of the condition of our own ies, both of the surface and also of the internal organs. There seems to be much in favor of all of these views. The weight of evidence is, however, rather against there being any special pain sense with a special end-organ and fibres. It is, however, certain that even if any variety of pain be a special sensation, some kind of pain may be produced by stimulation of the bare sensory nerves apart from any special form of nerve termination. It is said that the main difference between the common sensation which tells us of the condition of all parts of the body and of which thirst and hunger are but examples, the one informing us of the condition of the palate and the other of the state of our stomach, and the special sense of touch and temperature, is that the latter are provided with special apparatus. By means of this apparatus we are able to localize the sensation from which it is possible to form judgments. Such a special apparatus is evidently not absolutely essential for the sensation of pain, but this does not exclude the idea that pain may result from over-stimulation of a nerve of special sense or of its termination.

**The Muscular Sense.**—The estimate of a weight is usually based on *two* sensations: 1, of pressure on the skin, and 2, the muscular sense.

The estimate of weight derived from a combination of these two sensations (as in lifting a weight) is more accurate than that derived from the former alone (as when a weight is laid on the hand); thus Weber found that by the former method he could generally distinguish 19½ oz. from 20 oz., but not 19¾ oz. from 20, while by the latter he could at most only distinguish 14½ oz. from 15 oz.

It is not the absolute, but the relative, amount of the difference of weight which we have thus the faculty of perceiving.

It is not, however, certain, that our idea of the amount of muscular force used is derived solely from the muscular sense. We have the power of estimating very accurately beforehand, and of regulating, the amount of nervous influence necessary for the production of a certain degree of movement. When we raise a vessel, with the contents of which we are not acquainted, the force we employ is determined by the idea we have conceived of its weight. If it should happen to contain some very heavy substance, as quicksilver, we shall probably let it fall; the amount of muscular action, or of nervous energy, which we had exerted being insufficient. The same thing occurs sometimes to a person descending stairs in the dark; he makes the movement for the descent of a step which does not exist. It is possible that in the same way the idea of weight and pressure in raising bodies, or in resisting forces, may in part arise from a consciousness of the amount of nervous energy transmitted from the brain rather than from a sensation in the muscles themselves. The mental conviction of the inability longer to support weight must also be distinguished from the actual sensation of fatigu in the muscles.

So, with regard to the ideas derived from sensations of touch com-
ied with movements, it is doubtful how far the consciousness of the
ent of muscular movement is obtained from sensations in the muscles
mselves. The sensation of movement attending the motions of the
ad is very slight; and persons who do not know that the action of
ticular muscles is necessary for the production of given movements,
not suspect that the movement of the fingers, for example, depends
an action in the forearm. The mind has, nevertheless, a very definite
owledge of the changes of position produced by movements; and it
n this that the ideas which it conceives of the extension and form of
ody are in great measure founded.

There is no marked development of common sensibility to be made
in muscles: they may be cut without the production of pain. On the
er hand, there is no doubt that afferent impulses must pass upward
m muscles and tendons acquainting the brain with their condition.
is, then, must be a special sense. It has been suggested that the minute
-bulbs of Golgi found in tendons, and that the Pacinian corpuscles in
neighborhood of joints, are the terminal organs of this special sense.

*Judgment of the Form and Size of Bodies.*—By the sense of touch the
nd is made acquainted with the size, form, and other external char-
ers of bodies. And in order that these characters may be easily
ertained, the sense of touch is especially developed in those parts
ich can be readily moved over the surface of bodies. Touch, in its
re limited sense, or the act of examining a body by the touch, consists
rely in a voluntary employment of this sense combined with move-
nt, and stands in the same relation to the sense of touch, or common
sibility, generally, as the act of seeking, following, or examining
rs, does to the sense of smell. The hand is the best adapted for it,
reason of its peculiarities of structure,—namely, its capability of
nation and supination, which enables it, by the movement of rota-
, to examine the whole circumference of the body; the power it
sesses of opposing the thumb to the rest of the hand, and the relative
bility of the fingers; and lastly from the abundance of the sensory
ninal organs which it possesses. In forming a conception of the
re and extent of a surface, the mind multiplies the size of the hand
ingers used in the inquiry by the number of times which it is con-
ed in the surface traversed; and by repeating this process with
rd to the different dimensions of a solid body, acquires a notion of
cubical extent, but, of course, only an imperfect notion, as other
es, *e.g.*, the sight, are required to make it complete.

It is impossible in this consideration to say how much of our knowl-
e of the thing touched depends upon pressure and how much upon
muscular sense.

## II. Taste.

*Conditions necessary.*—The conditions for the perceptions of taste are:—1, the presence of a nerve and nerve-centre with special endowments; 2, the excitation of the nerve by the sapid matters, which for this purpose must be *in a state of solution;* 3, a temperature of about 37° to 40° C. (98° to 100° F.). The nerves concerned in the production of the sense of taste have been already considered (p. 349 *et seq.*) The mode of action of the substances which excite taste consists in the production of a change in the condition of the gustatory nerves, and the conduction of the stimulus thus produced to the nerve-centre; and, according to the difference of the susbtances, an infinite variety of changes of condition of the nerves, and consequently of stimulations of the gustatory centre, may be induced. The matters to be tasted must either be in solution or be soluble in the moisture covering the tongue; hence insoluble substances are usually tasteless, and produce merely sensations of touch. Moreover, for the perfect action of a sapid, as of an odorous substance, it is necessary that the sentient surface should be moist. Hence, when the tongue and fauces are dry, sapid substances, even in solution, are with difficulty tasted.

The nerves of taste, like the nerves of other special senses, may have their peculiar properties excited by various other kinds of irritation, such as electricity and mechanical impressions. Thus, a small current of air directed upon the tongue gives rise to a cool saline taste, like that of saltpetre; and a distinct sensation of taste similar to that caused by electricity, may be produced by a smart tap applied to the papillæ of the tongue. Moreover, the mechanical irritation of the fauces and palate produces the sensation of nausea, which is probably only a modification of taste.

*Seat.*—The principal seat (apparent seat, that is, to our senses) of the sense of taste is the tongue. But the result of experiments as well as ordinary experience show that the soft palate and its arches, the uvula, tonsils, and probably the upper part of the pharynx, are also endowed with taste. These parts, together with the base and posterior parts of the tongue, are supplied with branches of the glosso-pharyngeal nerve, and evidence has been already adduced that the sense of taste is conferred upon them by this nerve. In most, though not in all persons, the anterior parts of the tongue, especially the edges and tip, are endowed with the sense of taste. The middle of the dorsum is only feebly endowed with this sense, probably because of the density and thickness of the epithelium covering the filiform papillæ of this part of the tongue, which will prevent the sapid substances from penetrating to their sensitive parts.

*Other Functions.*—Beside the sense of taste, the tongue, by means

of its papillæ, is endued (2) especially at its side and tip, with a very
icate and accurate sense of touch, which renders it sensible of the
pressions of heat and cold, pain and mechanical pressure, and conse-
ntly of the form of surfaces. The tongue may lose its common sen-
ility, and still retain the sense of taste, and *vice versâ*. This fact
ders it probable that, although the senses of taste and of touch may
exercised by the same papillæ supplied by the same nerves, yet the
vous conductors for these two different sensations are distinct, just
the nerves for smell and common sensibility in the nostrils are dis-
ct; and it is quite conceivable that the same nervous trunk may con-
n fibres differing essentially in their specific properties. Facts already
ailed seem to prove that the lingual branch of the fifth nerve is the
ductor of sensations of taste in the anterior part of the tongue; and
is also certain, from the marked manifestations of pain to which its
ision in animals gives rise, that it is likewise a nerve of common sen-
ility. The glosso-pharyngeal also seems to contain fibres both of
mmon sensation and of the special sense of taste.

The functions of the tongue in connection with (3) speech, (4) mas-
ation, (5) deglutition, (6) suction, have been referred to in other
pters.

*Taste and Smell: Perceptions.*—The concurrence of common and two
ds of special sensibility, *i.e.*, touch and taste in the same part, makes
ometimes difficult to determine whether the impression produced by
bstance is perceived through the ordinary sensitive fibres, or through
se of the sense of taste. In many cases, indeed, it is probable that
h sets of nerve-fibres are concerned, as when irritating acrid substances
introduced into the mouth.

Much of the perfection of the sense of taste is often due to the sapid
stances being also odorous, and exciting the simultaneous action of
sense of smell. This is shown by the imperfection of the taste of
h substances when their action on the olfactory nerves is prevented
closing the nostrils. Many fine wines lose much of their apparent
ellence if the nostrils are held close while they are drunk.

*Varieties of Tastes.*—Among the most clearly defined tastes are the
*et* and *bitter* (which are more or less opposed to each other), the *acid*,
*line*, *salt*, and *metallic* tastes. Acid and alkaline taste may be ex-
d by electricity. If a piece of zinc be placed beneath and a piece of
per above the tongue, and their ends brought into contact, an acid
e (due to the feeble galvanic current) is produced. The delicacy of
sense of taste is sufficient to discern 1 part of sulphuric acid in 1000
ater; but it is far surpassed in acuteness by the sense of smell. Ex-
iments have shown that it is possible to entirely do away with the
er of tasting bitters and sweets while the taste for acids and salts

limited distribution in the human tongue.

Although the taste apparatus is bilateral the sensation is single, and in this respect taste resembles vision.

*After-taste.*—Very distinct sensations of taste are freque the substances which excited them have ceased to act on tl such sensations often endure for a long time, and modif other substances applied to the tongue afterward. Thus sweet substances spoils the flavor of wine, the taste of chees There appears, therefore, to exist the same relation betw between colors, of which those that are opposed or complem each other more vivid, though no general principles govern tion have been discovered in the case of tastes. In the art however, attention has at all times been paid to the conso mony of flavors in their combination or order of successio painting and music the fundamental principles of harmo employed empirically while the theoretical laws were unkn

Frequent and continued repetitions of the same taste re ception of it less and less distinct, in the same way that a more and more dull and indistinct the longer the eye is Thus, after frequently tasting first one and then the other of wine, it becomes impossible to discriminate between the

The simple contact of a sapid substance with the su gustatory organ seldom gives rise to a distinct sensation of t to be diffused over the surface, and brought into intimate the sensitive parts by compression, friction, and motion

## III. Smell.

*ecessary.*—(1.) The first conditions essential to the sense
pecial *nerve* and *nerve-terminations* in the form of special
es in whose condition stimulate a special nerve-centre,
ed in sensations of odor, for no other nervous structure
ese sensations, even though acted on by the same causes.
tance which excites the sensation of smell in the olfac-
cause another peculiar sensation through the nerves of
produce an irritating and burning sensation on the nerves
the sensation of odor is yet separate and distinct from
t may be simultaneously perceived. (2.) The material
are, usually, in the case of animals living in the air,



of the septum nasi, seen from the right side. ⅔.—I, the olfactory bulb;
es passing through the foramina of the cribriform plate, and descending to
septum; 2, the internal or septal twig of the nasal branch of the ophthal-
alatine nerves. (From Sappey, after Hirschfeld and Leveillé.)

spended in a state of extremely fine division in the atmos-
us exhalations often of so subtle a nature that they can
no other reagent than the sense of smell itself. The
r must, [illegible] cases, be dissolved in the mucus of the
ane bef[illegible] can be immediately applied to, or affect
erves; [illegible] a further [illegible] necessary for the
dors i[illegible] mucous m[illegible] of the nasal cavity
en the [illegible]rian membr[illegible] the sense of smell
ost; in [illegible] stage of ca[illegible] the secretion of
he nost[illegible]ened, the [illegible]erceiving odor is
endered [illegible] perfect. [illegible]als living in the
quisite [illegible]dorous m[illegible] be transmitted in
gh the [illegible] This is [illegible] inspiratory move-

ment, the mouth being closed; hence we have voluntary influence over the sense of smell; for by interrupting respiration we prevent the perception of odors, and by repeated quick inspiration, assisted, as in the act of *sniffing*, by the action of the nostrils, we render the impression more intense. An odorous substance in a liquid form injected into the nostrils appears incapable of giving rise to the sensation of smell; thus Weber could not smell the slightest odor when his nostrils were completely filled with water containing a large quantity of eau-de-Cologne.

The nose is not entirely an organ for the seat of smell. In fact the nasal cavities are divided into three districts called respectively—(*a*) *Regio vestibularis*, which is the entrance to the cavity. It is lined with a mucous membrane very closely resembling the skin, and contains hair (*vibrissæ*) with sebaceous glands. (*b*) *Regio respiratoria*, which includes the lower meatus of the nose, and all the rest of the nasal passages except (*c*); it is covered with mucous membrane covered by stratified columnar ciliated epithelium. The mucosa is thick and consists of fibrous connective tissue; it contains a certain number of tubular mucous and serous glands. (*c*) *Regio olfactoria*. This includes the anterior two-thirds of the superior meatus, the middle meatus, and the upper half of the septum nasi. It is of a yellowish color. It consists of a thicker mucous membrane than in (*b*), made up of loose areolar connective tissue covered by epithelium of a special variety, resting upon a basement membrane. The cells of the epithelium are of two principal kinds: (*a*) columnar epithelial cells whose function is to support (*b*) the bipolar olfactory cells. (*a*) The epithelial cells are prismatic in shape and have upon their surfaces facets into which the olfactory cells fit themselves. They are thus analogous to the cells of Müller of the retina (fig. 406 *e*). (*b*) The olfactory cells have an oblong or fusiform shape, which is mainly determined by the large nucleus. The thin protoplasmic body has two processes, an external and an internal. The external is large and passes up to the free surface to end in a small bunch of fibrils that are not vibratile. The internal process is very fine, often varicose, and passes through the mucous membrane to become continuous with the fibres of the olfactory bulb.



Fig. 406.—Bipolar olfactory cells from the nasal fossæ of the rat (full-term fœtus). *A*, Epithelium of the olfactory mucosa; *e*, epithelial cells; *f*, *f*, nerve-cells; *i*, nerve-fibres terminating freely on the epithelial surface; *h*, olfactory nerve-fibres; *g*, sensory nerve derived from the trigeminus. (Cajal.)

The **olfactory bulb** must be studied in relation with the nerve-bres and olfactory cells with which it is connected. These parts to-ether form a sensory end-organ which resembles in many respects the etina. The discovery of its true structure has thrown a flood of light n the architecture of the nerve-centres as a whole.

The olfactory bulb is not a nerve, but a modification of the brain ortex. A transection shows it to be made up of four layers:

1st. Peripheral fibres.
2d. Olfactory glomerules.
3d. Layer of mitral cells.



Fig. 407.—Principal constituent elements of the olfactory bulb of a mammal. (Van Gehuchten.)

4th. Layer of granular cells and deep nerve-fibres.

1st. The first and external layer is composed of the fine nerve-fibrils the olfactory nerves. They pass through the cribriform plate of the hmoid and continue on, ending in the olfactory cells.

2d. The glomerular layer contains numbers of small round bodies hose structure is now known to be nervous. They are made up of the pansions of the olfactory fibres on the one hand and of the "mitral" lls on the other. These are mingled in a close network, but do not astomose. It was by the study of these bodies in part that the fact of the non-continuity of the neurons was demonstrated (fig. 407). This layer also contains small fusiform cells with branching dendrites that extend outward to the glomeruli. Each has an axis-cylinder process which passes inward to join the fibres of the internal olfactory nerves.

3d. The layer of mitral cells contains large cells, some of them triangular and some in the shape of a mitre. They have numerous dendrites, one of which passes into a glomerule and then breaks up in a fine arborization. An axis-cylinder process (neuraxon) passes off from the inner surface and is continued as an internal olfactory nerve-fibre.

4th. The layer of granules and central fibres. This contains a large number of very small nerve-cells, which are peculiar in that they have *no axis-cylinder*. Their dendrites extend chiefly into the layer of mitral cells. They resemble the spongioblasts of the retina and probably have commissural functions. This layer has also some small star-shaped cells whose dendrites end in the mitral cell-layer. Among these cells run numerous fibres, chiefly from the mitral cells and the fusiform cells of the glomerular layer.



Fig. 408.—Nerves of the outer walls of the nasal fossæ. 3-5.—1, network of the branches of the olfactory nerve, descending upon the region of the superior and middle turbinated bones; 2, external twig of the ethmoidal branch of the nasal nerves; 3, spheno-palatine ganglion; 4, ramification of the anterior palatine nerves; 5, posterior, and 6, middle divisions of the palatine nerves; 7, branch to the region of the inferior turbinated bone; 8, branch to the region of the superior and middle turbinated bones; 9, naso-palatine branch to the septum cut short. (From Sappey, after Hirschfeld and Leveillé.)

The general arrangement is shown in fig. 407.

The sense of smell is derived exclusively through those parts of the nasal cavities in which the olfactory nerves are distributed; the accessory cavities or sinuses communicating with the nostrils seem to have no relation to it. Air impregnated with the vapor of camphor was injected

o the frontal sinus through a fistulous opening and odorous substances
e been injected into the antrum of Highmore; but in neither case
s any odor perceived by the patient. The purposes of these sinuses
ear to be that the bones, necessarily large for the action of the mus-
s and other parts connected with them, may be as light as possible,
l that there may be more room for the resonance of the air in vocaliz-
. The former purpose, which is in other bones obtained by filling
ir cavities with fat, is here attained, as it is in many bones of birds,
their being filled with air.

*Other Functions of the Nasal Region.*—All parts of the nasal cavi-
, whether or not they can be the seats of the sense of smell, are en-
ved with common sensibility by the nasal branches of the first and
ond divisions of the fifth nerve. Hence the sensations of cold, heat,
hing, tickling, and pain; and the sensation of tension or pressure in
nostrils. That these nerves cannot perform the function of the ol-
tory nerves is proved by cases in which the sense of smell is lost, while
mucous membrane of the nose remains susceptible of the various
difications of common sensation and of touch. But it is often difficult
istinguish the sensation of smell from that of mere feeling, and to
ertain what belongs to each separately. This is the case particularly
h the sensations excited in the nose by acrid vapors, as of ammonia,
se-radish, mustard, etc., which resemble much the sensations of the
ves of touch; and the difficulty is the greater when it is remembered
t these acrid vapors have nearly the same action upon the mucous
mbrane of the eyelids. It was because the common sensibility of the
e to these irritating substances remained after the destruction of the
ctory nerves that Magendie was led to the erroneous belief that the
nerve might exercise this special sense.

*Varieties of Odorous Sensations.*—Animals do not all equally perceive
same odors; the odors most plainly perceived by an herbivorous ani-
and by a carnivorous animal are different. The Carnivora have the
er of detecting most accurately by the smell the special peculiarities
nimal matters and of tracking other animals by the scent; but have
arently very little sensibility to the odors of plants and flowers. Her-
rous animals are peculiarly sensitive to the latter, and have a nar-
er sensibility to animal odors, especially to such as proceed from
r individuals than their own species. Man is far inferior to many
nals of both classes (which appear to have a special epithelial
ngement called *Jacobson's organ*, for the purpose of "*scent*"), in
ect of the acuteness of smell; but his sphere of susceptibility to various
s is more uniform and extended. The cause of this difference lies
ably in the endowments of the cerebral parts of the olfactory appa-
s. The delicacy of the sense of smell is most remarkable; it can dis-

cern the presence of bodies in quantities so minute as to be undiscoverable even by spectrum analysis; $\frac{3}{100,000,000}$ of a grain of musk can be distinctly smelt (Valentin). Opposed to the sensation of an agreeable odor is that of a disagreeable or disgusting odor, which corresponds to the sensations of pain, dazzling and disharmony of colors, and dissonance in the other senses. The cause of this difference in the effect of different odors is unknown; but this much is certain, that odors are pleasant or offensive in a relative sense only, for many animals pass their existence in the midst of odors which to us are highly disagreeable. A great difference in this respect is, indeed, observed amongst men: many odors, generally thought agreeable, are to some persons intolerable; and different persons describe differently the sensations that they severally derive from the same odorous substances. There seems also to be in some persons an insensibility to certain odors, comparable with that of the eye to certain colors; and among different persons, as great a difference in the acuteness of the sense of smell as among others in the acuteness of sight. We have no exact proof that a relation of harmony and disharmony exists between odors as between colors and sounds; though it is probable that such is the case, since it certainly is so with regard to the sense of taste; and since such a relation would account in some measure for the different degrees of perceptive power in different persons; for as some have no ear for music (as it is said), so others have no clear appreciation of the relation of odors, and therefore little pleasure in them.

*Subjective sensations.*—The sensations of the olfactory nerves, independent of the external application of odorous substances, have hitherto been little studied. The friction of the electric machine produces a smell like that of phosphorus. Ritter, too, has observed, that when a galvanic current is applied to the organ of smell, besides the impulse to sneeze, and the tickling sensation excited in the filaments of the fifth nerve, a smell like that of ammonia was excited by the negative pole, and an acid odor by the positive pole; whichever of these sensations were produced, it remained constant as long as the circle was closed, and changed to the other at the moment of the circle being opened. Subjective sensations occur frequently in connection with the sense of smell. Frequently a person smells something which is not present, and which other persons cannot smell; this is very frequent with nervous people, but it occasionally happens to every one. In a man who was constantly conscious of a bad odor, the arachnoid was found after death to be beset with deposits of bone, and a lesion in the middle of the cerebral hemispheres was also discovered. Dubois was acquainted with a man who, ever after a fall from his horse, which occurred several years before his death, believed that he smelt a bad odor.

## IV. Hearing.

*Anatomy of the Ear.*—For descriptive purposes, the Ear, or Organ f Hearing, is divided into three parts, (1) the external, (2) the middle, nd (3) the internal ear. The two first are only accessory to the third



Fig. 409.—Diagrammatic view from before of the parts composing the organ of hearing of e left side. The temporal bone of the left side, with the accompanying soft parts, has been tached from the head, and a section has been carried through it transversely, so as to remove e front of the meatus externus, half the tympanic membrane, the upper and anterior wall of e tympanum and Eustachian tube. The meatus internus has also been opened, and the bony byrinth exposed by the removal of the surrounding parts of the petrous bone. 1, the pinna d lobe; 2, 2′, meatus externus; 2′, membrana tympani; 3, cavity of the tympanum; 3′, its ening backward into the mastoid cells; between 3 and 3′, the chain of small bones; 4, Eustaian tube; 5, meatus internus, containing the facial (uppermost) and the auditory nerves; 6, aced on the vestibule of the labyrinth above the fenestra ovalis; *a*, apex of the petrous bone; internal carotid artery; *c*, styloid process; *d*, facial nerve issuing from the stylo-mastoid ramen; *e*, mastoid process; *f*, squamous part of the bone covered by integument, etc. (Arnold.)

internal ear, which contains the essential parts of an organ of hear- g. The accompanying figure shows very well the relation of these visions, one to the other (fig. 409).

**External Ear.**—The external ear consists of the *pinna* or *auricle* nd the *external auditory canal or meatus.*

The principal parts of the *pinna* (fig. 409) are two prominent rims closed one within the other (*helix* and *antihelix*), and inclosing a cen- al hollow named the *concha;* in front of the concha, a prominence rected backward, the *tragus*, and opposite to this one directed for- ard, the *antitragus.* From the concha, the auditory canal, with a slight arch directed upward, passes inward and a little forward to the membrana tympani, to which it thus serves to convey the vibrating air. Its outer part consists of fibro-cartilage continued from the concha; its inner part of bone. Both are lined by skin continuous with that of the pinna, and extending over the outer part of the *membrana tympani*.

Toward the outer part of the canal are fine hairs and sebaceous glands, while deeper in the canal are small glands, resembling the sweat-glands in structure, which secrete the *cerumen*.

**Middle Ear** or **Tympanum.**—The middle ear, or tympanum (3, fig. 409), is separated by the *membrana tympani* from the external auditory canal. It is a cavity in the temporal bone, opening through its anterior and inner wall into the Eustachian tube, a cylindriform flattened canal, dilated at both ends, composed partly of bone and partly of elastic cartilage, and lined with mucous membrane. This canal establishes communication between the tympanic cavity and pharynx, thus equalizing the air pressure on either side of the tympanic membrane, in some respects serving the same mechanical purpose as the vent-hole in a snare or bass drum. It opens into the cavity of the pharynx just behind the posterior aperture of the nostrils. The cavity of the tympanum communicates posteriorly with air cavities, the *mastoid cells* in the mastoid process of the temporal bone; but its only opening to the external air is through the Eustachian tube (4, fig. 409). The walls of the tympanum are osseous, except where apertures in them are closed with membrane, as at the fenestra rotunda and fenestra ovalis, and at the outer part where the bone is replaced by the membrana tympani. The cavity of the tympanum is lined with mucous membrane, the epithelium of which is ciliated and continuous with that of the pharynx. It contains a chain of small bones (*ossicula auditus*) which extends from the membrana tympani to the fenestra ovalis.



Fig. 410.



Fig. 411.



Fig. 412.

Fig. 410.—The hammer-bone or malleus, seen from the front. 1, the head; 2, neck; 3, short process; 4, long process. (Schwalbe.)

Fig. 411.—The incus, or anvil-bone. 1, body; 2, ridged articulation for the malleus; 4, processus brevis, with 5, rough articular surface for ligament of incus; 6, processus magnus, with articulating surface for stapes; 7, nutrient foramen. (Schwalbe.)

Fig. 412.—The stapes, or stirrup-bone. 1, base; 2 and 3, arch; 4, head of bone, which articulates with orbicular process of the incus; 5, constricted part of neck; 6, one of the crura. (Schwalbe.)

The *membrana tympani* is placed in a slanting direction at the bottom of the external auditory canal, its plane being at an angle of about 45° with the lower wall of the canal. It is formed chiefly of a tough and tense fibrous membrane, the edges of which are set in a bony groove;



Fig. 413.—Interior view of the tympanum, with membrana tympani and bones in natural osition. 1, Membrana tympani; 2, Eustachian tube; 3, tensor tympani muscle; 4, lig. mallei a per.; 6, corda-tympani nerve; *a*, *b*, and *c*, sinuses about ossicula. (Schwalbe.)

ts outer surface is covered with a continuation of the cutaneous lining f the auditory canal, its inner surface with part of the ciliated mucous membrane of the tympanum.

The *ossicles* are three in number; named malleus, incus, and stapes. The malleus, or hammer-bone, is attached by a long slightly-curved pro-ess, called its handle, to the membrana tympani; the line of attachment eing vertical, including the whole length of the handle, and extending rom the upper border to the centre of the membrane. The head of the malleus is irregularly rounded; its neck, or the line of boundary between t and the handle, supports two processes; a *short* conical one, which eceives the insertion of the *tensor tympani*, and a *slender* one, *processus racilis*, which extends forward, and to which the *laxator tympani* muscle s attached. The *incus*, or anvil-bone, shaped like a bicuspid molar tooth, s articulated by its broader part, corresponding with the surface of the rown of a tooth, to the malleus. Of its two fang-like processes, one, irected backward, has a free end lodged in a depression in the mastoid one; the other, curved downward and more pointed, articulates by means f a roundish tubercle, formerly called *os orbiculare*, with the stapes, a ttle bone shaped exactly like a stirrup, of which the base or bar fits into he fenestra ovalis. To the neck of the stapes, a short process, corresponding with the loop of the stirrup, is attached the *stapedius* muscle.

The bones of the ear are covered with mucous membrane reflected over hem from the wall of the tympanum; and are movable both altogether nd one upon the other. The malleus moves and vibrates with every ovement and vibration of the membrana tympani, and its movements-are communicated through the incus to the stapes, and through it to the membrane closing the fenestra ovalis. The malleus, also, is movable in its articulation with the incus; and the membrana tympani moving with it is altered in its degree of tension by the laxator and tensor tympani muscles. The stapes is movable on the process of the incus, when the stapedius muscle acting, draws it backward. The axis round which the malleus and incus rotate is the line joining the processus gracilis of the malleus and the posterior (short) process of the incus.

**The Internal Ear.**—The proper organ of hearing is formed by the distribution of the auditory nerve within the internal ear, or *labyrinth*, a set of cavities within the petrous portion of the temporal bone. The bone which forms the walls of these cavities is denser than that around it, and forms the *osseous labyrinth;* the membrane within the cavities forms the *membranous labyrinth.* The membranous labyrinth contains a fluid called *endolymph;* while outside it, between it and the osseous labyrinth, is a fluid called *perilymph.* This fluid is not pure lymph; as it contains mucin.

The **osseous labyrinth** consists of three principal parts, namely the *vestibule*, the *cochlea*, and the *semicircular canals.*

The *vestibule* is the middle cavity of the labyrinth, and the central organ of the whole auditory apparatus. It presents, in its inner wall, several openings for the entrance of the divisions of the auditory nerve; in its outer wall, the *fenestra ovalis* (2, fig. 414), an open-



Fig. 414.



Fig. 415.

Fig. 414.—Right bony labyrinth, viewed from the outer side. The specimen here represented is prepared by separating piecemeal the looser substance of the petrous bone from the dense walls which immediately inclose the labyrinth. 1, the vestibule; 2, fenestra ovalis; 3, superior semicircular canal; 4, horizontal or external canal; 5, posterior canal; *, ampullæ of the semicircular canals; 6, first turn of the cochlea; 7, second turn; 8, apex; 9, fenestra rotunda. The smaller figure in outline below shows the natural size. $\frac{2\frac{1}{2}}{1}$ (Sömmering.)

Fig. 415.—View of the interior of the left labyrinth. The bony wall of the labyrinth is removed superiorly and externally. 1, Fovea hemielliptica; 2, fovea hemispherica; 3, common opening of the superior and posterior semicircular canals; 4, opening of the aqueduct of the vestibule; 5, the superior, 6, the posterior, and 7, the external semicircular canals; 8, spiral tube of the cochlea (scala tympani); 9, opening of the aqueduct of the cochlea; 10, placed on the lamina spiralis in the scala vestibuli. $\frac{2\frac{1}{2}}{1}$ (Sömmering.)

g filled by the base of the stapes; in its posterior and superior
alls, five openings by which the *semicircular canals* communicate with
: in its anterior wall, an opening leading into the *cochlea*. The hinder
rt of the inner wall of the vestibule also presents an opening, the
ifice of the *aquæductus vestibuli*, a canal leading to the posterior mar-
n of the petrous bone, with uncertain contents and unknown purpose.

The *semicircular canals* (figs. 414, 415) are three arched cylindriform
ny canals, set in the substance of the petrous bone. They all open at
th ends into the vestibule (two of them first coalescing). The ends of
ch are dilated just before opening into the vestibule; and one end
ing more dilated than the other is called an *ampulla*. Two of the
nals form nearly vertical arches; of these the superior is also anterior;
e posterior is inferior; the third canal is horizontal, and lower and
orter than the others.

The *cochlea* (6, 7, 8, figs. 414 and 415), a small organ, shaped like a
mmon snail-shell, is situated in front of the vestibule, its base resting
the bottom of the internal meatus, where some apertures transmit
it the cochlear filaments of the auditory nerve. In its axis, the
chlea is traversed by a conical column, the *modiolus*, round which a
*ral canal* winds with about two turns and a half from the base to the
ex. At the apex of the cochlea the canal is closed; at the base it
esents three openings, of which one, already mentioned, communicates
th the vestibule; another called *fenestra rotunda*, is separated by a
mbrane from the cavity of the tympanum; the third is the orifice of
e *aquæductus cochleæ*, a canal leading to the jugular fossa of the
trous bone, and corresponding, at least in obscurity of purpose and
gin, to the aquæductus vestibuli. The spiral canal is divided into two
ssages, or scalæ, by a partition of bone and membrane, the *lamina*
*ralis*. The osseous part or *zone* of this lamina is connected with the
diolus.

The **Membranous Labyrinth.**—The membranous labyrinth corre-
nds generally with the form of the osseous labyrinth, so far as regards
e vestibule and semicircular canals, but is separated from the walls of
se parts by perilymph, except where the nerves enter into connection
thin it. The labyrinth is a closed membrane containing endolymph,
ich is of much the same composition as perilymph, but contains less
d matter. It is somewhat viscid, as is the perilymph, and it is
reted by the epithelium lining its cavity; all the sonorous vibrations
pressing the auditory nerves in these parts of the internal ear, are
ducted through fluid to a membrane suspended in and containing
d. In the cochlea, the membranous labyrinth completes the septum
ween the two *scalæ*, and incloses a spiral canal, previously mentioned,
led *canalis membranaceus* or *canalis cochleæ* (fig. 417). The fluid in

the *scalæ* of the cochlea is continuous with the perilymph in the vestibule and semicircular canals, and there is no fluid external to its lining membrane. The vestibular portion of the membranous labyrinth comprises two, probably communicating cavities, of which the larger and upper is named the *utriculus;* the lower, the *sacculus.* They are lodged in depressions in the bony labyrinth, termed respectively *fovea hemielliptica* and *fovea hemispherica.* Into the former open the orifices of the membranous semicircular canals; into the latter the *canalis cochleæ.* The membranous labyrinth of all these parts is laminated, transparent, very vascular, and covered on the inner surface with nucleated cells, of which those that line the ampullæ are prolonged into stiff hair-like processes; the same appearance, but to a much less degree, being visible in the utricule and saccule. In the cavities of the utriculus and sacculus are small masses of calcareous particles, *otoconia* or *otoliths;* and the same, although in more minute quantities, are to be found in the interior of some other parts of the membranous labyrinth.



Fig. 416.—View of the osseous cochlea divided through the middle. 1, central canal of the modiolus; 2, lamina spiralis ossea; 3, scala tympani; 4, scala vestibuli; 5, porous substance of the modiolus near one of the sections of the canalis spiralis modioli. × 5. (Arnold.)

*Auditory Nerve.*—All the organs now described are provided for the appropriate exposure of the filaments of the auditory nerve to sonorous vibrations. It is characterized as a nerve of special sense by its softness (whence it derived its name of *portio mollis* of the seventh pair), and by the fineness of its component fibres. It enters the bony canal (the *meatus auditorius internus*), with the facial nerve and the nervus intermedius, and, traversing the bone, enters the labyrinth at the angle between the base of the cochlea and the vestibule, in two divisions; one for the vestibule and semicircular canals, and the other for the cochlea.

There are two branches for the vestibule, one, superior, distributed to the utricule and to the superior and horizontal semicircular canals, and the other, inferior, ending in the saccule and posterior semicircular canal. Where the nerve comes in connection with the utricule and saccule, the structure of the membrane is modified somewhat and the places are called *maculæ acusticæ.* The epithelium in this region is, as we shall see directly, considerably specialized, and where the nerve is in connection with the ampullæ of the semicircular canals, too, the structure is altered, becoming elevated into a horse-shoe ridge, which projects to the interior of the cavity, forming the *crista acustica.* Here, too, e epithelium is of a special kind. The nerve fibres spread out and diate on the inner surface of the membranous labyrinth: their exact mination is uncertain. The distribution of the other division of the ditory nerve, the cochlear, will be more clearly understood after the scription of the cochlea itself.

*Structure.*—The structure of the membranous labyrinth consists of ee coats, externally a layer of areolar tissue, next a hyaloid membrane, vated into minute papillæ, and internally a layer of flattened epilium. At the position where the branches of the vestibular branch the auditory nerve join it, viz., at the saccule, utricule, and ampullæ the semicircular canals, there is a marked difference in the structure, external and middle layers are thicker and the epithelium becomes umnar. The epithelium in which the fibres of the vestibular nerve said to terminate are of two kinds, called *cylinder* or *hair cells*, and *cells.* The hair cells occupy only one-half of the thickness of the mbrane; from their inner end hair-like processes project into the ity of the labyrinth. Their outer end is rounded and contains a ge round nucleus. To these cells the primitive fibrillæ of the axis inders pass up, some of them being distinctly varicose. The exact ation of the nerve fibrillæ to the hair-cells is unknown; by some they believed actually to enter the cells, by others they are stated to form ind of nest of fibrillæ into which the cells fit. The rod-cells are of newhat varying form. They are elongated cells extending from the face to the basement membrane, broad at the upper or surface end, containing oval nuclei toward their attached end, but not exactly at same level in all cases. These nuclei, therefore, form a distinct ad nuclear layer on a vertical section of the membrane, as the cells numerous, much more so, indeed, than the other variety of cell. e lower or attached part of the cell may be branched.

The membranous part of the cochlea, with a muscular zone, forming outer margin, is attached to the outer wall of the canal. Commenc- at the base of the cochlea, between its vestibular and tympanic opens, it forms a partition between these apertures; the two scalæ are, refore, in correspondence with this arrangement, named *scala vesti-* and *scala tympani* (fig. 417). At the apex of the cochlea, the ina spiralis ends in a small *hamulus*, the inner and concave part of ch, being detached from the summit of the modiolus, leaves a small rture named *helicotrema*, by which the two scalæ, separated in all the of their length, communicate.

Besides the scala vestibuli and scala tympani, there is a third space ween them, called *scala media* or *canal membranaceus* (CC, fig. 417). section it is triangular, its external wall being formed by the wall of the cochlea, its upper wall (separating it from the scala vestibuli) by the membrane of Reissner, and its lower wall (separating it from the scala tympani) by the basilar membrane, these two meeting at the outer edge of the bony lamina spiralis. Following the turns of the cochlea to its apex, the scala media there terminates blindly; while toward the base of the cochlea it is also closed with the exception of a very narrow passage (canalis reuniens) uniting it with the sacculus. The scala media (like the rest of the membranous labyrinth) contains *endolymph.*

*Organ of Corti.*—Upon the basilar membrane are arranged cells of various shapes. About midway between the outer edge of the lamina spiralis and the outer wall of the cochlea are situated the *rods of Corti.* Viewed sideways, they are seen to consist of an external and internal pillar, each rising from an expanded foot or *base* on the basilar membrane (*o*, *n*, fig. 418). They slant inward toward each other, and each ends in a swelling termed the head; the head of the inner pillar overlying that of the outer (fig. 418). Each pair of pillars forms, as it were, a pointed roof arching over a space, and by a succession of them a little tunnel is formed.



Fig. 417.—Section through one of the coils of the cochlea (diagrammatic). *ST*, scala tympani; *SV*, scala vestibuli; *CC*, canalis cochleæ or canalis membranaceus; *R*, membrane of Reissner; *lso*, lamina spiralis ossea; *lls*, limbus laminæ spiralis; *ss*, sulcus spiralis; *nc*, cochlear nerve; *gs*, ganglion spirale; *t*, membrana tectoria (below the membrana tectoria is the lamina recticularis); *b*, membrana basilaris; *Co*, rods of Corti; *lsp*, ligamentum spirale. (Quain.)

It has been estimated that there are about 3000 of these pairs of pillars, in proceeding from the base of the cochlea toward its apex. They are found progressively to increase in length, and become more oblique; in other words the tunnel becomes wider, but diminishes in height as we approach the apex of the cochlea. Leaning, as it were, against these external and internal pillars are certain other cells, of which the external ones, *hair cells*, terminate in small hair-like processes. Most of the above details are shown in the accompanying figure (fig. 418). This complicated structure rests, as we have seen, upon the basilar membrane; it is roofed in by a remarkable fenestrated membrane or lamina reticuris into the fenestræ of which the tops of the various rods and cells re received. When viewed from above, the organ of Corti shows a emarkable resemblance to the key-board of a piano. In close relation



Fig. 418.—Vertical section of the organ of Corti from the dog. 1 to 2, Homogeneous layer the so-called membrana basilaris; *u*, vestibular layer; *v*, tympanal layer, with nuclei and toplasm; *a*, prolongation of tympanal periosteum of lamina spiralis ossea; *c*, thickened mmencement of the membrana basilaris near the point of perforation of the nerves *h*; *d*, od-vessel (vas spirale); *e*, blood-vessel; *f*, nerves; *g*, the epithelium of the sulcus spiralis ernus; *i*, internal or tufted cell, with basil process *k*, surrounded with nuclei and protoplasm the granular layer), into which the nerve-fibres radiate; *l*, hairs of the internal hair-cell; *n*, e or foot of inner pillar of organ of Corti; *m*, head of the same uniting with the correspond- part of an external pillar, whose under half is missing, while the next pillar beyond, *o*, pre- ts both middle portion and base; *r s d*, three external hair-cells; *t*, bases of two neighboring r or tufted cells; *x*, so-called supporting cell of Hensen; *w*, nerve-fibre terminating in the first the external hair-cells; *l l* to *l*, lamina reticularis. × 800. (Waldeyer.)

th the rods of Corti and the cells inside and outside them, and proba- y projecting by free ends into the little tunnel containing fluid (roofed by them), are filaments of the auditory nerve. These are derived om the cochlear division already mentioned. This passes up the axis the cochlea, and in its course gives off fibres to the lamina spiralis. ese fibres are thick at their origin, but thin out peripherally, and ntaining bipolar ganglion cells form the *ganglion spirale*. Beyond e ganglion at the edge of the lamina the fibres pass up and become nnected with the organ of Corti.

### The Physiology of Hearing.

All the acoustic contrivances of the organ of hearing are means for nducting sound. Since all matter is capable of propagating sonorous rations, the simplest conditions must be sufficient for mere hearing; all substances surrounding the auditory nerve would stimulate it. e whole development of the organ of hearing, therefore, can have for its ect merely the rendering more perfect the propagation of the sono- s vibrations, and their multiplication by resonance; and, in fact, the ole of the acoustic apparatus may be shown to have reference to these nciples.

The external auditory passages influence the propagation of sound to the tympanum in three ways:—1, by causing the sonorous undulations, entering directly from the atmosphere, to be transmitted by the air in the passage immediately to the membrana tympani, and thus preventing them from being dispersed; 2, by the walls of the passage conducting the sonorous undulations imparted to the external ear itself, by the shortest path to the attachment of the membrana tympani, and so to this membrane; 3, by the resonance of the column of air contained within the passage; 4, the external ear, especially when the tragus is provided with hairs, is also, doubtless, of service in protecting the meatus and membrana tympani against dust, insects, and the like.

Regarding the cartilage of the external ear, therefore, as a conductor of sonorous vibrations, all its inequalities, elevations, and depressions, become of evident importance; for those elevations and depressions upon which the undulations fall perpendicularly, will be affected by them in the most intense degree; and, in consequence of the various form and position of these inequalities, sonorous undulations, in whatever direction they may come, must fall perpendicularly upon the tangent of some one of them. This affords an explanation of the extraordinary form given to this part.

In animals living in the atmosphere, the sonorous vibrations are conveyed to the auditory nerve by three different media in succession; namely, the air, the solid parts of the body of the animal and of the auditory apparatus, and the fluid of the labyrinth. Sonorous vibrations are imparted too imperfectly from air to solid bodies, for the propagation of sound to the internal ear to be adequately effected by that means alone; yet already an instance of its being thus propagated has been mentioned. In passing from air directly into water, sonorous vibrations suffer also a considerable diminution of their strength; but if a tense membrane exists between the air and the water, the sonorous vibrations are communicated from the former to the latter medium with very great intensity. This fact, of which Müller gives experimental proof, furnishes at once an explanation of the use of the fenestra rotunda, and of the membrane closing it. They are the means of communicating, in full intensity, the vibrations of the air in the tympanum to the fluid of the labyrinth. This peculiar property of membranes is the result, not of their tenuity alone, but of the elasticity and capability of displacement of their particles; and it is not impaired when, like the membrane of the fenestra rotunda, they are not impregnated with moisture.

Sonorous vibrations are also communicated without any perceptible loss of intensity from the air to the water, when to the membrane forming the medium of communication, there is attached a short, solid body, which occupies the greater part of its surface, and is alone in contact ith the water. This fact elucidates the action of the fenestra ovalis, nd of the plate of the stapes which occupies it, and, with the preceding ct, shows that both fenestræ—that closed by membrane only, and that ith which the movable stapes is connected—transmit very freely the norous vibrations from the air to the fluid of the labyrinth.

A small, solid body, fixed in an opening by means of a border of embrane, so as to be movable, communicates sonorous vibrations from r on the one side, to water, or the fluid of the labyrinth, on the other de, much better than solid media not so constructed. But the propa-ation of sound to the fluid is rendered much more perfect if the solid nductor thus occupying the opening, or fenestra ovalis, is by its other d fixed to the middle of a tense membrane, which has atmospheric air both sides. A tense membrane is a much better conductor of the brations of air than any other solid body bounded by definite surfaces: d the vibrations are also communicated very readily by tense mem-anes to solid bodies in contact with them. Thus, then, the membrana mpani serves for the transmission of sound from the air to the chain ossicles. Stretched tightly in its osseous ring, it vibrates with the r in the auditory passage, as any thin tense membrane will, when the r near it is thrown into vibrations by the sounding of a tuning-fork a musical string. And, from such a tense vibrating membrane, the brations are communicated with great intensity to solid bodies which uch it at any point. If, for example, one end of a flat piece of wood applied to the membrane of a drum, while the other end is held in e hand, vibrations are felt distinctly when the vibrating tuning-fork held over the membrane without touching it; but the wood alone, lated from the membrane, will only very feebly propagate the vibra-ns of the air to the hand.

In comparing the membrana tympani to the membrane of a drum, wever, it is necessary to point out certain important differences.

When a drum is struck, a certain definite tone is elicited (funda-ntal tone); similarly a drum is thrown into vibration when certain nes are sounded in its neighborhood, while it is quite unaffected by hers. In other words it can only take up and vibrate in response to ose tones whose vibrations nearly correspond in number with those of own fundamental tone. The tympanic membrane can take up an mense range of tones produced by vibrations ranging from 30 to 4000 5000 per second. This would be clearly impossible if it were an nly stretched membrane.

The fact is, that the membrana tympani is by no means evenly etched, and this is due partly to its slightly funnel-like form, and rtly to its being connected with the chain of auditory ossicles. Fur-er, if the membrane were quite free in its centre, it would go on vibrating as a drum does some time after it is struck, and each sound would be prolonged, leading to considerable confusion. This evil is obviated by the ear-bones, which check the continuance of the vibrations like the "dampers" in a pianoforte.

The ossicles of the ear are the better conductors of the sonorous vibrations communicated to them, on account of being isolated by an atmosphere of air, and not continuous with the bones of the cranium; for every solid body thus isolated by a different medium, propagates vibrations with more intensity through its own substance than it communicates them to the surrounding medium, which thus prevents a depression of the sound; just as the vibrations of the air in the tubes used for conducting the voice from one apartment to another are prevented from being dispersed by the solid walls of the tube. The vibrations of the membrana tympani are transmitted, therefore, by the chain of ossicula to the fenestra ovalis and fluid of the labyrinth, their dispersion in the tympanum being prevented by the difficulty of the transition of vibrations from solid to gaseous bodies.

The necessity of the presence of air on the inner side of the membrana tympani, in order to enable it and the ossicula auditus to fulfil the objects just described, is obvious. Without this provision, neither would the vibrations of the membrane be free, nor the chain of bones isolated, so as to propagate the sonorous undulations with concentration of their intensity. But while the oscillations of the membrana tympani are readily communicated to the air in the cavity of the tympanum, those of the solid ossicula will not be conducted away by the air, but will be propagated to the labyrinth without being dispersed in the tympanum.

The propagation of sound through the ossicula tympani to the labyrinth, must be affected either by oscillations of the bones, or by a kind of molecular vibration of their particles, or, most probably, by both these kinds of motion.

It has been shown that the existence of the membrane over the fenestra rotunda will permit approximation and removal of the stapes to and from the labyrinth. When by the stapes the membrane of the fenestra ovalis is pressed toward the labyrinth, the membrane of the fenestra rotunda may, by the pressure communicated through the fluid of the labyrinth, be pressed toward the cavity of the tympanum.



Fig. 419.—Diagram to illustrate the action of the ossicles of the middle ear in the conduction of sound to the internal ear.

The long process of the malleus receives the undulations of the mem-

rana tympani (fig. 419, *a*, *a*) and of the air in a direction indicated by
e arrows, nearly perpendicular to itself. From the long process of
e malleus they are propagated to its head (*b*): thence into the incus (*c*),
e long process of which is parallel with the long process of the malleus.
rom the long process of the incus the undulations are communicated
the stapes (*d*), which is united to the incus at right angles. The
everal changes in the direction of the chain of bones have, however, no
fluence in changing the character of the undulations, which remain the
me as in the meatus externus. From the long process of the malleus,
e undulations are communicated by the stapes to the fenestra ovalis
a perpendicular direction.

Increasing tension of the membrana tympani diminishes the facility
transmission of sonorous undulations from the air to it.

The dry membrana tympani, on the approach of a body emits a loud
und, rejects particles of sand strewn upon it more strongly when lax
an when very tense; and it has been inferred, therefore, that hearing
rendered less acute by increasing the tension of the membrana tym-
ni.

The pharyngeal orifice of the Eustachian tube is usually shut; dur-
g swallowing, however, it is opened; this may be shown as follows:—
the nose and mouth be closed and the cheeks blown out, a sense of
essure is produced in both ears the moment we swallow; this is due,
ubtless, to the bulging out of the tympanic membrane by the com-
essed air, which at that moment enters the Eustachian tube.

Similarly the tympanic membrane may be pressed in by rarefying
e air in the tympanum. This can be readily accomplished by closing
e mouth and nose, and making an inspiratory effort and at the same
ne swallowing. In both cases the sense of hearing is temporarily
lled; proving that equality of pressure on both sides of the tympanic
embrane is necessary for its full efficiency.

The principal office of the Eustachian tube has relation to the pre-
ntion of these effects of increased tension of the membrana tympani.
existence and openness will provide for the maintenance of the equi-
rium between the air within the tympanum and the external air, so
to prevent the inordinate tension of the membrana tympani which
uld be produced by too great or too little pressure on either side.
ile discharging this office, however, it will serve to render sounds
arer, as the apertures in violins do; to supply the tympanum with
and to be an outlet for mucus. If the tube were *permanently* open,
sound of one's own voice would probably be greatly intensified, a
dition which would of course interfere with the perception of other
nds. At any rate, it is certain that sonorous vibrations can be prop-

agated up the tube to the tympanum by means of a catheter inserted into the pharyngeal orifice of the Eustachian tube.

The influence of the tensor tympani muscle in modifying hearing may also be probably explained in connection with the regulation of the tension of the membrana tympani. If, through reflex nervous action, it can be excited to contraction by a very loud sound, then it is manifest that a very intense sound would, through the action of this muscle, induce a deafening or muffling of the ears. In favor of this supposition we have the fact that a loud sound excites, by reflection, nervous action, winking of the eyelids, and, in persons of irritable nervous system, a sudden contraction of many muscles.

The exact influence of the stapedius muscle in hearing is unknown. It acts upon the stapes in such a manner as to make it rest obliquely in the fenestra ovalis, depressing that side of it on which it acts, and elevating the other side to the same extent. It prevents too great a movement of the bone.

The fluid of the labyrinth is the most general and constant of the acoustic provisions of the labyrinth. In all forms of organs of hearing, the sonorous vibrations affect the auditory nerve through the medium of liquid—the most convenient medium, on many accounts, for such a purpose.

The otoliths in the labyrinth would reinforce the sonorous vibrations by their resonance, even if they did not actually touch the membranes upon which the nerves are expanded; but, inasmuch as these bodies lie in contact with the membranous parts of the labyrinth, and the vestibular nerve-fibres are imbedded in them, they communicate to these membranes and the nerves, vibratory impulses of greater intensity than the fluid of the labyrinth can impart. This appears to be their office. Sonorous undulations in water are not perceived by the hand itself immersed in the water, but are felt distinctly through the medium of a rod held in the hand. The fine hair-like prolongations from the epithelial cells of the ampullæ have, probably, the same function.

The function of the semicircular canals in the co-ordination of movements necessary to the maintenance of the equilibrium of the body has already been indicated.

The cochlea seems to be constructed for the spreading out of the nerve-fibres over a wide extent of surface, upon a solid lamina which communicates with the solid walls of the labyrinth and cranium, at the same time that it is in contact with the fluid of the labyrinth, and which, besides exposing the nerve-fibres to the influence of sonorous undulations, by two media, is itself insulated by fluid on either side.

The connection of the lamina spiralis with the solid walls of the byrinth, adapts the cochlea for the perception of the sonorous undulaions propagated by the solid parts of the head and the walls of the labyinth. The membranous labyrinth of the vestibule and semicircular anals is suspended free in the perilymph, and is destined more particuarly for the perception of sounds through the medium of that fluid, whether the sonorous undulations be imparted to the fluid through the enestræ, or by the intervention of the cranial bones, as when sounding odies are brought into communication with the head or teeth. The piral lamina on which the nervous fibres are expanded in the cochlea, s, on the contrary, continuous with the solid walls of the labyrinth, and eceives directly from them the impulses which they transmit. This is n important advantage; for the impulses imparted by solid bodies, ave, *cæteris paribus*, a greater absolute intensity than those communiated by water. And, even when a sound is excited in the water, the onorous undulations are more intense in the water near the surface of e vessel containing it, than in other parts of the water equally distant om the point of origin of the sound; thus we may conclude that, *eteris paribus*, the sonorous undulations of solid bodies act with greater tensity than those of water. Hence, we perceive at once an important se of the cochlea.

This is not, however, the sole office of the cochlea; the spiral lamina, well as the membranous labyrinth, receives sonorous impulses through e medium of the fluid of the labyrinth from the cavity of the vestibule, d from the fenestra rotunda. The lamina spiralis is, indeed, much tter calculated to render the action of these undulations upon the ditory nerve efficient, than the membranous labyrinth is; for as a solid dy insulated by a different medium, it is capable of resonance.

The rods of Corti are probably arranged so that each is set to vibrate unison with a particular tone, and thus strike a particular note, the sation of which is carried to the brain by those filaments of the audiy nerve with which the little vibrating rod is connected. The disctive function, therefore, of these minute bodies is, probably, to der sensible to the brain the various musical notes and tones, one of m answering to one tone, and one to another; while perhaps the er parts of the organ of hearing discriminate between the intensities different sounds, rather than their qualities.

"In the cochlea we have to do with a series of apparatus adapted for forming sympathetic vibrations with wonderful exactness. We have e before us a musical instrument which is designed, not to create sical sounds, but to render them perceptible, and which is similar in struction to artificial musical instruments, but which far surpasses m in the delicacy as well as the simplicity of its execution. For, while in a piano every string must have a separate hammer by means of which it is sounded the ear possesses a single hammer of an ingenious form in its ear bones, which can make every string of the organ of Corti sound separately." (Bernstein.)

Since about 3000 rods of Corti are present in the human ear, this would give about 400 to each of the seven octaves which are within the compass of the ear. Thus about 32 would go to each semi-*tone*. Weber asserts that accomplished musicians can appreciate differences in pitch as small as $\frac{1}{64}$th of a tone. Thus on the theory above advanced, the delicacy of discrimination would, in this case, appear to have reached its limits.

## Sounds.

Any elastic body, *e.g.*, air, a membrane, or a string performing a certain number of regular vibrations in the second, gives rise to what is termed a musical sound or *tone*. We must, however, distinguish between a musical sound and a mere noise; the latter being due to irregular vibrations.

Musical sounds are distinguished from each other by three qualities. 1. *Strength* or intensity, which is due to the amplitude or length of the vibrations. 2. *Pitch*, which depends upon the number of vibrations in a second. 3. *Quality*, *Color*, or *Timbre*. It is by this property that we distinguish the same note sounded on two instruments, *e.g.*, a piano and a flute. It has been proved by Helmholtz to depend on the number of secondary tones, termed *harmonics*, which are present with the predominating or fundamental tone.

It would appear that two impulses, which are equivalent to four single or half vibrations, are sufficient to produce a definite note, audible as such through the auditory nerve.

The maximum and minimum of the intervals of successive impulses still appreciable through the auditory nerve as determinate sounds, have been determined by Savart. If their intensity is sufficiently great, sounds are still audible which result from the succession of 48,000 half vibrations, or 24,000 impulses in a second; and this, probably, is not the extreme limit in acuteness of sounds perceptible by the ear. For the opposite extreme, he has succeeded in rendering sounds audible which were produced by only fourteen or eighteen half vibrations, or seven or eight impulses in a second; and sounds still deeper might probably be heard, if the individual impulses could be sufficiently prolonged.

*Direction.*—The power of perceiving the *direction of sounds* is not a faculty of the sense of hearing itself, but is an act of the mind judging on experience previously acquired. From the modifications which the

sation of sound undergoes according to the direction in which the
nd reaches us, the mind infers the position of the sounding body.
e only true guide for this inference is the more intense action of the
nd upon one than upon the other ear. But even here there is room
much deception, by the influence of reflexion or resonance, and by
propagation of sound from a distance, without loss of intensity,
ough curved conducting tubes filled with air. By means of such tubes,
of solid conductors, which convey the sonorous vibrations from their
rce to a distant resonant body, sounds may be made to appear to orig-
te in a new situation. The direction of sound may also be judged
by means of one ear only; the position of the ear and head being
ied, so that the sonorous undulations at one moment fall upon the
in a perpendicular direction, at another moment obliquely. But
en neither of these circumstances can guide us in distinguishing the
ection of sound, as when it falls equally upon both ears, its source
ng, for example, either directly in front or behind us, it becomes
possible to determine whence the sound comes.

*Distance.*—The distance of the source of sounds is not recognized by
sense itself, but is inferred from their intensity. The sense itself is
ays seated but in one place, namely, in our ear; but it is interpreted
oming from an exterior soniferous body. When the intensity of the
e is modified in imitation of the effect of distance, it excites the
a of its originating at a distance. Ventriloquists take advantage of
difficulty with which the direction of sound is recognized, and also
influence of the imagination over our judgment, when they direct
ir voice in a certain direction, and at the same time pretend, them-
es, to hear the sounds as coming from thence.

*Intensity.*—By removing one or several teeth from the toothed wheel
fact has been demonstrated that in the case of the auditory nerve,
n that of the optic nerve, the sensation continues longer than the im-
ssion which causes it; for a removal of a tooth from the wheel pro-
ed no interruption of the sound. The gradual cessation of the sen-
on of sound renders it difficult, however, to determine its exact
ation beyond that of the impression of the sonorous impulses.

So we see that the effect of the action of sonorous undulations upon
nerve of hearing, endures somewhat longer than the period during
ch the undulations are passing through the ear. If, however, the
ressions of the same sound be very long continued, or constantly
ated for a long time, then the sensation produced may continue for
ry long time, more than twelve or twenty-four hours even, after the
inal cause of the sound has ceased.

*Binaural Sensations.*—Corresponding to the double vision of the same object with the two eyes, is the double hearing with the two ears; and analogous to the double vision with one eye, dependent on unequal refraction, is the double hearing of a single sound with one ear, owing to the sound coming to the ear through media of unequal conducting power. The first kind of double hearing is very rare; instances of it, however, have been recorded. The second kind which depends on the unequal conducting power of two media through which the same sound is transmitted to the ear, may easily be experienced. If a small bell be sounded in water, while the ears are closed by plugs, and a solid conductor be interposed between the water and the ear, two sounds will be heard differing in intensity and tone; one being conveyed to the ear through the medium of the atmosphere, the other through the conducting-rod.

*Subjective Sensations.*—Subjective sounds are the result of a state of irritation or excitement of the auditory nerve produced by other causes than sonorous impulses. A state of excitement of this nerve, however induced, gives rise to the sensation of sound. Hence the ringing and buzzing in the ears heard by persons of irritable and exhausted nervous system, and by patients with cerebral disease, or disease of the auditory nerve itself; hence also the noise in the ears heard for some time after a long journey in a rattling, noisy vehicle. Ritter found that electric currents also excite sounds in the ears. From the above truly subjective sound we must distinguish those dependent, not on a state of the auditory nerve itself merely, but on sonorous vibrations excited in the auditory apparatus. Such are the buzzing sounds attendant on vascular congestion of the head and ear, or on aneurismal dilatation of the vessels. Frequently even the simple pulsatory circulation of the blood in the ear is heard. To the sounds of this class belong also the buzz or hum, heard during the contraction of the palatine muscles in the act of yawning, during the forcing of air into the tympanum so as to make tense the membrana tympani, and in the act of blowing the nose, as well as during the forcible depression of the lower jaw.

Irritation or excitement of the auditory nerve is capable of giving rise to movements in the body, and to sensations in other organs of sense. In both cases it is probable that the laws of reflex action, through the medium of the brain, come into play. An intense and sudden noise excites, in every person, closure of the eyelids, and, in nervous individuals, a start of the whole body or an unpleasant sensation, like that produced by an electric shock, throughout the body, and sometimes a particular feeling in the external ear. Various sounds cause in many people a disagreeable feeling in the teeth, or a sensation of cold tickling through the body, and, in some people, intense sounds are said to make the saliva collect.

## V. Sight.

*natomy of the Optical Apparatus.*—The *eyelids* consist of two mov- folds of skin, each of which is kept in shape by a thin plate of elastic tissue. Along their free edges are inserted a number of d hairs (*eyelashes*), which, when the lids are half closed, serve tect the eye from dust and other foreign bodies: their tactile sen- y is also very delicate.

the inner surface of the elastic tissue are disposed a number of racemose glands (Meibomian), whose ducts open near the free edge lid.

e orbital surface of each lid is lined by a delicate, highly sensitive s membrane (*conjunctiva*), which is continuous with the skin at ee edge of each lid, and after lining the inner surface of the eyelid ected on to the eyeball, being somewhat loosely adherent to the ic coat. The epithelial layer is continued over the cornea at its or epithelium. At the inner edge of the eye the conjunctiva es continuous with the mucous lining of the lachrymal sac and which again is continuous with the mucous membrane of the or meatus of the nose.

e *lachrymal gland*, composed of several lobules made up of acini bling the serous salivary glands, is lodged in the upper and outer of the orbit. Its secretion, which issues from several ducts on ner surface of the upper lid, under ordinary circumstances just s to keep the conjunctiva moist. It passes out through two small gs (puncta lachrymalia) near the inner angle of the eye, one in id, into the lachrymal sac, and thence along the nasal duct into ferior meatus of the nose. The excessive secretions poured out the influence of any irritating vapor or painful emotion overflows wer lid in the form of tears.

e eyelids are closed by the contraction of a sphincter muscle *ularis*), supplied by the facial nerve; the upper lid is raised by the *palpebræ superioris*, which is supplied by the third nerve.

## The Eyeball.

e eyeball or the organ of vision (fig. 420) consists of a variety of ures which may be thus enumerated:—

e *sclerotic*, or outermost coat, envelops about five-sixths of the eye- continuous with it, in front, and occupying the remaining sixth, is the *cornea*. Immediately within the sclerotic is the *choroid* coat, and within the choroid is the *retina*.

The crystalline lens, its suspensory ligament and the ciliary body, divides the interior of the eyeball into two cavities: the larger, behind these structures extending to the retina, the *vitreous chamber*, and the smaller in front of these structures and extending to the cornea, the *aqueous chamber*.

*The Chambers of the Eye.*—The chamber of the aqueous is the space behind the cornea and the front of the lens, its suspensory ligament and the ciliary body. It is filled with the aqueous humor, which is essentially a diluted lymph with a small amount of proteid in it, viz., of fibrinogen, serum globin, and septum albumin. It is seldom spontaneously coagulable. It contains salts, principally sodium chloride; sometimes, also, a substance which reduces copper sulphate, but is not sugar, and a trace of urea and sarcolactic acid. There are no formed elements in the fluid. It is produced by the iris and ciliary processes, the latter playing the more important part, for in cases of congenital or acquired deficiency of the iris, the aqueous is still produced in the normal amount. The aqueous chamber is drained principally through the spaces of Fontana into the canal of Schlemm at the corneal-scleral junction. The iris, a contractile and perforated muscular and vascular curtain, partially divides the aqueous chamber into two parts: the *anterior*, the larger and the posterior, *smaller* and triangular-shaped. These are freely communicable with each other by means of the pupil. The *anterior chamber* is the



Fig. 420.—Section of the anterior four-fifths of the eyeball.

between the cornea and the iris, and therefore comprises by much ırger portion of the aqueous chamber. The *posterior chamber* lies ıen the posterior surface of the iris and the anterior surface of the its suspensory ligament and ciliary body. Its existence is due to ıct that the iris is not in contact with the capsule of the lens by hole posterior surface, but only at its pupillary margin. Thus a gular-shaped space is left between the base of the iris and the ciliary

As has been said before, this second division of the aqueous ber communicates with the anterior, or first division, by means of upil. The *vitreous chamber*, or that behind the lens, contains the *us humor*, which is a semi-fluid substance contained in the meshes indistinct connective tissue. It is enclosed in a distinct mem-, called *membrana hyaloidea;* from the anterior surface of this ɔrane, at the ora serrata, fibres pass off to the back of the lens cap- forming an incomplete canal, called the *Canal of Petit*, the mem- itself being the *Zonule of Zinn.* The hyaloid membrane separates itreous from the retina.

*tructure of the Sclerotic Coat.*—The sclerotic coat is composed of fibrous tissue, with some elastic fibres near the inner surface, ged in variously disposed and interlacing layers. Many of the les of fibres cross the others almost at right angles. It is strong, ı, and opaque, and not very elastic. It is separated from the ıid by a considerable lymphatic space (*perichoroidal*), and this is in ection with smaller spaces lined with endothelium in the sclerotic itself. There is a lymphatic space also outside the sclerotic sepa- g it from a loose investment of connective tissue called the *capsule non.* The innermost layer is made up of loose connective tissue ɔigment-cells, and is called the *lamina fusca.*

*tructure of the Cornea.*—The cornea is a transparent membrane h forms a segment of a smaller sphere than the rest of the eyeball,



ꞩ. 421.—Vertical section of rabbit's cornea. *a*, Anterior epithelium, showing the different of the cells at various depths from the free surface; *b*, portion of the substance of (Klein.)

s let in, as it were, into the sclerotic with which it is continuous und. It is covered by laminated epithelium (*a*, fig. 421), consisting of seven or eight layers of cells, of which the superficial ones flattened and scaly, and the deeper ones more or less columnar. Im diately beneath this is the anterior elastic lamina of Bowman, w



Fig. 422.—Horizontal preparation of cornea of frog; showing the network of branched corpuscles. The ground substance is completely colorless. × 400. (Klein.)

differs, only in being more condensed tissue, from the general stru of the cornea or cornea proper.

This latter tissue, as well as its epithelium is, in the adult, pletely destitute of blood-vessels; it consists of an intercellular gr substance of rather obscurely fibrillated flattened bundles of conn tissue, arranged parallel to the free surface, and forming the bound of branched anastomosing spaces in which the cornea-corpuscle These branched cornea-corpuscles have been seen to creep by amo



Fig, 423.—Surface view of part of lamella of kitten's cornea, prepared first with c potash and then with nitrate of silver. (By this method the branched cornea-corpuscle their granular protoplasm and large oval nuclei are brought out.) × 450. (Klein and Smith.)

movement from one branched space into another. At its posterior face the cornea is limited by the *posterior elastic lamina*, or *memb* *of Descemet*, similar in structure to the anterior elastic lamina, the in layer of which consists of a single stratum of epithelial cells (fig. 424,

*Nerves.*—The nerves of the cornea are both large and numerous: t

rived from the ciliary nerves. They traverse the substance of the
a, in which some of them near the anterior surface break up into axis
lers, and their primitive fibrillæ. The latter form a plexus imme-
y beneath the epithelium, from which delicate fibrils pass up
en the cells anastomosing with horizontal branches, and forming a
ntra-epithelial plexus, from which still finer fibres ascend, till near
rface they form a superficial intra-epithelial net-work. Most of
imitive fibrillæ have a beaded or varicose appearance. The cornea



Fig. 424.



Fig. 425.

424.—Vertical section of rabbit's cornea, stained with gold chloride. *e*, Laminated
epithelium. Immediately beneath this is the anterior elastic lamina of Bowman. *n*,
orming a delicate sub-epithelial plexus, and sending up fine twigs between the epithelial
end in a second plexus on the free surface; *d*, Descemet's membrane, consisting of a
tic layer, and a single layer of epithelial cells; the substance of the cornea, *f*, is seen
rillated, and contains many layers of branched corpuscles, arranged parallel to the free
and here seen edgewise. (Schofield.)

425.—Section through the choroid coat of the human eye. 1, elastic membrane, struc-
or finely fibrillated; 2, chorio-capillaris or tunica Ruyschiana; 3, Proper substance of
oid with large vessels cut through; 4, suprachoroidea; 5, sclerotic. (Schwalbe.)

blood-vessels penetrating its structure, nor yet lymphatic vessels
. It is nourished by the circulation of lymph in the spaces in
the cornea corpuscles lie. These communicate freely and form a
-canalicular system.

*ucture of the Choroid Coat* (*tunica vasculosa*).—This coat is
ed to the inner layer of the sclerotic in front at the corneo-scleral
on and behind at the entrance of the optic nerve, elsewhere it is

connected to it only by loose connective tissue. Its external formed chiefly of elastic fibres and large pigment corpuscles arranged and containing lymphatic spaces lined with endothelium. is the *suprachoroidea.* More internally is a layer of arteries and arranged in a system of venous whorls, together with elastic fibr



Fig. 426.—Section through the eye carried through the ciliary processes. 1, Cornea; brane of Descemet; 3, sclerotic; 3′, corneo-scleral junction; 4, canal of Schlemm; 5, nucleated network on inner wall of canal of Schlemm; 7, lig. pectinatum iridis, *ab* stroma; 9, pigment of iris; 10, ciliary processes; 11, ciliary muscle; 12, choroid tis meridional and 14, radiating fibres of ciliary muscle; 15, ring muscle of Müller; 16, cir angular bundles of ciliary muscle. (Schwalbe.)

pigment cells. The lymphatics, too, are well developed aroun blood-vessels, and there are besides distinct lymph spaces lined wi dothelium. Internally to this is a layer of fine capillaries, very den derived from the arteries of the outer coat and ending in veins i coat. It contains corpuscles without pigment, and lymph spaces surround the blood-vessels (*membrana chorio-capillaris*). It is sep from the retina by a fine elastic membrane (*membrane of Bruch*), is either structureless or finely fibrillated.

The choroid coat ends in front in what are called the *ciliary pro* (fig. 426). These consist of from 70 to 80 meridionally arr radiating plaits, which consist of blood-vessels, fibrous connective t and pigment corpuscles. They are lined by a continuation of the brane of Bruch. The ciliary processes terminate abruptly at the m of the lens. The ciliary muscle (13, 14 and 15, fig. 426), which m considered to form part of the processes, is situated between sclerotic (at the corneo-scleral junction) and the folds of the ci processes. It is a ring of muscle, 3 mm. broad and 8 mm. thick, up of fibres running in two or three directions. (*a*) Meridional f near the sclerotic and passing to the choroid; (*b*) radial fibres, pas toward the centre; and (*c*) circular fibres, more internal, and consti ing the so-called ciliary sphincter.

*The Iris.*—The iris is a continuation of the choroid inward bey iliary processes. It is a fibro-muscular membrane perforated by a al aperture, the pupil. It is made up chiefly of blood-vessels and ective tissue with pigment and unstriated muscle.

osteriorly are two layers of pigment cells (*uvea*), in which are repred the two layers of cells of which the optic vesicle is originally ed, and behind which are the retina proper and its pigment layer. e iris representatives of both layers are deeply pigmented. The ture of the iris proper is made of connective tissue in front with scles which may or may not be pigmented, and behind of similar supporting blood-vessels inclosed in connective tissue. The pigcells are usually well developed here, as are also many nerve-fibres ting toward the pupil. Surrounding the pupil is a layer of circunstriped muscle, the *sphincter pupillæ*. In some animals there are nuscle-fibres which radiate from the sphincter in the substance of ris forming the *dilator pupillæ*. The iris is covered anteriorly by er of endothelium continued upon it from the posterior surface of ornea; posteriorly there is a very fine layer which is a continuation e membrana limitans interna of the retina.

*he Lens.*—The lens is situated behind the iris, being inclosed in a act capsule, the posterior surface of which is less thick than the ior. It is supported in place by the suspensory ligament, fused e anterior surface of the capsule. The suspensory ligament is ed from the hyaloid membrane, which incloses the vitreous humor.

*tructure.*—The lens is made up of a series of concentric laminæ 428), which when it has been hardened, can be peeled off like the



Fig. 427.



Fig. 428.

. 427.—Ciliary processes, as seen from behind. 1, posterior surface of the iris, with the ter muscle of the pupil; 2, anterior part of the choroid coat; 3, one of the ciliary processes, ch about seventy are represented. ½.

. 428.—Laminated structure of the crystalline lens. The laminæ are split up after hardin alcohol. 1, the denser central part or nucleus; 2, the successive external layers. × 4. d.)

s of an onion. The laminæ consist of long ribbon-shaped fibres, h in the course of development have originated from cells.

The lens itself is made up of transparent longitudinal fibres, hexagonal and prismatic, thickened posteriorly. Those fibres at the cortex have nuclei and are smooth, those near the centre are without nuclei and have serrated edges. The fibres are united together by a scanty amount of cement substance.

The arrangement is such that no fibres run the whole half of the lens, from front to back, since, if a fibre starts near the anterior pole, its other end is far from the posterior pole (fig. 429.)

The epithelium of the lens consists of a layer of cubical cells anteriorly, which merges at the equator into the lens fibres. The development of the lens explains this transition. The lens at first consists of a closed sac composed of a single layer of epithelium. The cells of the posterior part soon elongate forward and obliterate the cavity, the anterior cells do not grow, but at the edge they become continuous with the posterior cells, which are gradually developed into fibres. The lens contains globulin or crystallin, but no native-albumin; it also contains cholesterin. The capsule is a homogeneous transparent elastic membrane. The hardest portion of the lens is that which is most internal. It forms the so-called *nucleus* of the lens (fig. 428, 1).



Fig. 429.—Meridional section through the lens of a rabbit. 1, Lens capsule; 2, epithelium of lens; 3, transition of the epithelium into the fibres; 4, lens fibres. (Bubuchin.)

*Corneo-scleral junction.*—At this junction the relation of parts (fig. 426) is so important as to need a short description. In the neighborhood, the iris and ciliary processes join with the cornea. The proper substance of the cornea and the posterior elastic lamina become continuous with the iris, at *the angle of the iris*, and the iris sends forward processes toward the posterior elastic lamina, forming the *ligamentum pectinatum iridis*, and these join with fibres of the elastic lamina. The endothelial covering of the posterior surface of the cornea is, as we have seen, continuous over the front of the iris. At the iridic angle, the compact inner substance of the cornea is looser, and between the bundles are lymph spaces filled with fluid, called the *spaces of Fontana*. They are little developed in the human cornea. Where the cornea and sclerotic join, there is an intermediate part which resembles both, but which is still not transparent, as the internal part remains scleral in structure.

The spaces which are present in the broken up bundles of corneal tissue at the angle of the iris, are continuous with the larger lymphatic f the anterior chamber. Above the angle at the corneo-scleral ı is a canal, which is called the *canal of Schlemm.* It is a lym- hannel, but appears to be in communication with blood-vessels, y be under certain circumstances filled with blood.

*cture of the Retina.*—The retina (fig. 430) is a delicate membrane, with the concavity directed forward and apparently ending in ear the outer part of the ciliary processes, in a finely notched the *ora serrata*, but really represented to the very margin of the Semitransparent when fresh, it soon becomes clouded and opaque, inkish tint from the blood in its minute vessels. It results from den spreading out or expansion of the optic nerve, of whose ter-



0.—A section of the retina, choroid, and part of the sclerotic, moderately magnified. ına limitans interna; *b*, nerve-fibre layer traversed by Müller's sustentacular fibres; ı-cell layer; *d*, molecular layer; *e*, internal nuclear layer; *f*, internuclear layer; *g*, ex- ear layer; *h*, membrana limitans externa, running along the lower part of *i*, the layer l cones; *k*, pigment-cell layer; *lm*, internal and external vascular portions of the chor- st containing capillaries, the second larger blood-vessels, cut in transverse section; *n*, (W. Pye.)

ores, apparently deprived of their external white substance, to- vith nerve cells, it is essentially composed.

tly in the centre of the retina is a round yellowish elevated spot, of an inch (1 mm.) in diameter, having a minute depression in tre, called after its discoverer the macula lutea, or *yellow spot of* ing. The minute depression in its centre is called the *fovea* s. About $\frac{1}{10}$ of an inch (2.5 mm.) to the inner side of the yel-

nerve to support the fibres. The fibres of the nerve ther
ceedingly fine, and are surrounded by the myelin sheat
possess the ordinary external nerve-sheath. As they pass
they lose their myelin sheaths and proceed as axis-cylinde
supports the nerve-fibres in the optic nerve-trunk. In th
nerve is a small artery, the *arteria centralis retinæ*. T
fibres in the optic nerve is said to be upward of 500,0
cylinders pass on to the retina, turning over the edge
*opticus*, to be distributed on the inner surface of the retin
ora serrata, as a layer of optic nerve-fibres, and separ
hyaloid membrane which contains the vitreous humor t
described, by a very thin layer, the membrana limitans int

The retina consists of certain nervous elements arran
layers and supported by a very delicate connective tissue.

The researches of Cajal upon the structure of the r
brates has shown that this membrane is a much simpler
has heretofore been described. Cajal's observations being
other observers and accepted by neuro-anatomists, it will
the descriptions here, as representing our present kno
structure of this membrane.

The retina is a nervous tissue formed essentially of
nerve-cells. From without inward they are: the layer of v
layer of bipolar cells, and the layer of ganglionic cells. Th
is shown in the diagram (fig. 431). These different laye
divided so as to give the following layers from without inw

1. The layer of rods and cones. } Forming the layer of visual cell

This is, however, practically a layer made up simply of bipolar :lls with prolongations more or less long which run to the ex- urface of the retina and there form a series of bodies known as ; and cones.

*'he rods and cones* are really a kind of secretion from the pro- of the bipolar cell beneath, and are not distinct nerve-cells. nsist of bodies more or less alike, which extend up through the limiting membrane from the cells beneath.



1.—Transverse section of a mammalian retina. *A*, Layer of rods and cones; *B*, bodies ells (external granular); *C*, external molecular layer; *E*, layer of bipolar cells (internal *F*, internal molecular layer; *G*, layer of ganglionic cells; *H*, layer of optic-nerve fibres; cone; *c*, body of the cone cell; *d*, body of the rod cell; *e*, bipolar rod cells; *f*, bipolar cone *i*, *j*, *k*, ganglionic cells ramifying in the various strata of the internal molecular zone; arborization of the bipolar rod cells, connecting with the ganglionic cells; $r_1$, inferior ar- of the bipolar cone cells; *t*, epithelial or Müller cells; *x*, point of contact between the ieir bipolar cells; *z*, point of contact between the cones and their bipolar cells; *s*, centri- e-fibre. (Cajal.)

*Rods.*—Each rod (fig. 431, *a*) is made up of two parts, very differ- tructure, called the outer and inner limbs. The outer limb of the about $30\mu$ $\frac{1}{800}$ inch long and $2\mu$ broad, is transparent, and doubly ve. It is said to be made up of fine superimposed discs. It re- in some ways the myelin sheath of a medullated nerve. It p on exposure to light, and is part of the layer in which the t called *visual purple* is found. The inner limb is about as t slightly broader than the outer, is longitudinally striated at r and granular at its inner part. Each rod is connected by air-like process to a nerve-cell in the external granular layer be- s. 431, *d*; 432, 2).

*Cones.*—Each cone (fig. 431, *c*), like the rods, is made up of two uter and inner. The outer limb is tapering and not cylindrical corresponding part of the rod, and about one-third only of its length, but it resembles this in structure. There is, however, no vis purple found in the cone. The inner limb of the cone is broader in centre; each cone is in connection by its internal end with a cone fi which has much the same structure as the rod fibre, but is much stou This connects with a nerve-cell of the layer below (fig. 432, 4).

In the rod and cone layer of birds, the cones usually predomi



Fig. 432.—Schematic diagram of the elementary structure of the retina. sz, Rods and co se, membrana limitans externa; gr, external granules; e, external molecular layer); bz, inte granular layer; i, internal molecular layer; mz, multipolar cell layer (ganglion optici); nf, ne fibre layer; li, membrana limitans interna.

1, Rod; 2, rod granule; 3, cone; 4, cone granule; 1-1′, rod visual cell; 3-3′, cone visual cell central termination of the visual cells and peripheral terminal arborization of the bipolar c 6, 6, two bipolar cells for rods; 6, one bipolar cell for cone; 7, 7, 7, 7, 7, 7, the central process bipolar cells with the terminal arborizations situated in the various layers of the internal molec layer; 7′, central process of a bipolar cell for cone; 8, multipolar cells with their peripheral d drites and central neuraxons; 9, 9, 9, nerve-fibres and terminal arborizations of remote cells.

largely in number, whereas in man the rods are by far the more nume ous, except in the fovea centralis, where cones only are present, as is th case at the anterior part of the retina near the ora serrata. The num ber of cones has been estimated at 3,000,000. In nocturnal birds, how ever, such as the owl, only rods are present, and the same appears to the case in many nocturnal and burrowing mammalia, *e.g.*, bat, hedge hog, mouse, and mole. The rods are absent in reptiles.

*External Limiting Membrane.*—A delicate membrane lies beneath he rods and cones and separates them from the layer beneath. This s called the *external limiting membrane* (fig. 432, *le*).

2. *External Granular Layer.*—The cells of the external granular ayer are the bipolar or *visual* cells which contain the protoplasm not yet ransformed into rods and cones in the layer above. The cells whose odies are continued upward as cones are different in shape from those hich are connected with the rods. The cells of the cones are situted close to the external limiting membrane. They have a large ovoid ucleus. From the inner side of the cell-body a process descends ward the external molecular layer where it ends in a slight dilatation see fig. 431). On its outer side a process of the body ascends through to the external limiting membrane and swells into a cone (fig. 431, *c*).

The bipolar cells giving birth to the rods lie at deeper levels in the



Fig. 433.—The posterior half of the retina of the left eye, viewed from before; *s*, the cut e of the sclerotic coat; *ch*, the choroid; *r*, the retina; in the interior at the middle the ula lutea with the depression of the fovea centralis is represented by a slight oval shade; ard the left side the light spot indicates the colliculus or eminence at the entrance of the c nerve, from the centre of which the arteria centralis is seen spreading its branches into retina, leaving the part occupied by the macula comparatively free. (After Henle.)

nular layer. They contain an ovoid nucleus of a smaller volume than se of the cone cells. The protoplasm of the cell-body gives off two es, one ascending, and the other descending. The ascending fibre s up through the limiting membrane and is continued as a rod. The cending fibre goes into the molecular layer and ends here in a small ule. According to Cajal, these cells of the visual layer have no di- anatomical continuity with the cells of the bipolar layer below, gh Dogiel and others have denied this.

3. *The external molecular layer* or external plexiform layer (fig. 431, *C*) omposed of numerous protoplasmic processes (dendrites) which come n the cells of the internal granular layer below and from the visual s above. Some subdivisions of this layer are made, there being an r part in which the rod cells meet the branching fibres of the bi-

polar layer, and a slightly deeper layer i
in contact with the dendrites of the bipolar
4. *The internal granular layer* (fig. 431,
layer of bipolar cells, and is the most compli
retina. It is made up, however, mainly of
form in shape, vertical in arrangement, an
cending and the other descending. The de
and ends at different levels in the internal
where it forms flattened and brush-like
process is often multiple, and it ends in
branches, which arrange themselves in som
in the lower part of the external molecular



Fig. 434. —Perpendicular section of the retina of a ma
rods; *B*, bodies of cones; *a*, horizontal external or small c
c, horizontal internal cell with descending protoplasmic ap
of the large cells; *f*. *g*, *h*, *j*. *l*, spongioblasts ramifying in th
zone; *m*, *n*, diffuse spongioblasts; *o*, ganglionic cell; 1, ex
cular zone. (Cajal.)

Besides these vertical bipolar cells th
cells lying just beneath the external molecul
parallel to the periphery and ending in nu
which come in contact with the different
cone cells. Their general arrangement is h
appear to have as their function the conne
each other (fig. 434, *c*, *b*). There are oth
these, but having practically the same sha
somewhat more deeply in the layer; these c
cells with each other and have thus an asso
addition, in this layer, a series of larger cell
which lie deep in the internal granular la
a horizontal direction and appear to have t
cells of the ganglionic layer below (see fig.

5. *The internal molecular layer* is composed of a plexus of fibres med by the processes of the bipolar cells from above and of the gan- onic cells below, and of fibres from the spongioblasts.

6. The most internal of the nervous layers is a layer of ganglionic s, consisting of large multipolar nerve-cells, with large round nuclei. some parts of the retina, especially near the macula lutea, this layer ery thick and consists of several distinct strata of nerve-cells. These s lie in the spaces of the connective-tissue framework. They are ar- ged with their single neuraxon or axis-cylinder processes directed in- d. These pass into and are continuous with the layer of optic fibres. ernally the cells send up numerous branching processes or dendrites ich interlace with the fibres of the bipolar cells and the horizontal cesses of the spongioblasts.

All the elements of the retina are sustained and isolated by large s lying vertically which are known as the *fibres of Müller*, or epi- lial retinal cells. Like the corresponding cells of the olfactory cous membrane, these fibres have upon their sides an infinite number facets which serve as receptacles to the nerve-corpuscles and fibres the retina. The nucleus of the fibre of Müller is found at the l of the internal granular layer, and the two extremities of the proto- sm or cell-body are condensed in two homogeneous layers, known as *external* and *internal limiting layer*. The external limiting layer is ed, as already described, just between the layer of rods and cones that of the visual cells. The other is situated upon the internal ace of the retina. The fibres of Müller are completely independent each other, having between themselves and the nerve elements only relation of contact. It is believed that their function is that of porting the nerve-tissues and also isolating them.

It will be seen now that the retina is composed essentially of three rs of vertical cells, whose processes have a vertical direction, and ch are connected with each other by contact of these processes; that re are also two other sets of cells which form horizontal layers of ve-processes, these being in the inner and outer parts of the internal nular layer. There are, therefore, strictly speaking, five layers of ve-cells, three vertical and two horizontal. Two other layers are le up by the modification of the protoplasm of the fibres of Müller are purely mechanical in function. They are the external and in- al limiting layers.

*Pigment-cell layer*, which was formerly considered part of the choroid, sists of cells which cover and entirely surround the outer limbs of the s and cones.

The further subdivisions of the retina are more for purposes of fine tomy than of functional importance.

*ifferences in Structure of Different Parts.*—Toward the centre of the macula lutea all the layers of the retina become greatly thinned out and almost disappear, except the rod and cone layer, which considerably increases in thickness but at the fovea centralis comes to consist almost entirely of long slender cones and cone-fibres, which curve toward the periphery. They are supported by neuroglia, which is also found internally as a thin layer, the rods being absent. There are capillaries here, but none of the larger branches of the retinal arteries.

Toward the edge of the macula lutea, not only are all the layers present, but the ganglionic layer consists of many strata of cells (7 or 8), and with this increase there is also an increase in the thickness of the inner granular layer. The cells are generally bipolar. Toward the centre the layers diminish in this order: optic nerve-fibres, ganglionic layer, inner molecular layer, and inner granular layer. The rods grow scanty and then are absent.

At the ora serrata the layers are not perfect and disappear in this order: nerve-fibres and ganglion cells, then the rods, leaving only the inner limbs of the cones, these cease, then the inner molecular layer. The Müllerian fibres persist.

At the pars-ciliaris retinæ, the retina is represented by a layer of columnar cells, derived from the fusion of the nuclear layers. The cells are covered by the membrana limitans interna, and externally are in contact with the pigment layers of the retina, which is continued over the ciliary processes.

**Blood-vessels of the Eyeball.**—The eye is very richly supplied with blood-vessels. In addition to the conjunctival vessels which are derived from the palpebral and lachrymal arteries, there are at least two other distinct sets of vessels supplying the tunics of the eyeball. (1) The vessels of the sclerotic, choroid, and iris, and (2) the vessels of the retina.



Fig. 435.—Section through the macula lutea and fovea centralis of human retina. a, fovea; b, descent of the macula toward fovea. The numbers indicate the layers of the retina. (Kuhnt.)

(1.) These are the short and long *posterior* ciliary arteries which pierce the sclerotic in the posterior half of the eyeball, and the *anterior* ciliary which enter near the insertions of the recti. These vessels anastomose and form a very rich choroidal plexus; they also supply the iris and liary processes, forming a very highly vascular circle round the outer argin of the iris and adjoining portion of the sclerotic.

The distinctness of these vessels from those of the conjunctiva is ell seen in the difference between the bright red of blood-shot eyes onjunctival congestion), and the pink zone surrounding the cornea hich indicates deep seated ciliary congestion.

(2.) The *retinal vessels* (fig. 433) are derived from the *arteria cenalis retinæ*, which enters the eyeball along the centre of the optic erve. They ramify all over the retina, chiefly in its inner layers. hey can be seen by direct ophthalmoscopic examination.

## The Optical Apparatus.

The optical apparatus may be supposed, for the sake of description, consist of several parts. *Firstly*, of a system of transparent refractg surfaces and media by means of which images of external objects are ought to a focus upon the back of the eye; and *secondly*, of a sensitive reen, the retina, which is a specialized termination of the optic nerve, pable of being stimulated by luminous objects, and of sending through e optic nerve, such an impression as to produce in the brain visual nsations. To these main parts may be added, *thirdly*, an apparatus r focussing objects at different distances from the eye, called *accommotion*. Even this does not complete the description of the whole organ vision, since both eyes are usually employed in vision, and *fourthly*, arrangement exists by means of which the eyes may be turned in e same direction by a system of muscles, so that binocular vision is ssible.

The arrangement of the optic nerve-fibres, and of the continuation these backward in the optic chiasma, and thence to special districts of e brain, have already been discussed.

The eye may be compared to a photographic *camera*, and the transrent media corresponds to the photographic lens. In such a camera ages of external objects are thrown upon a ground-glass screen at the ck of a box, the interior of which is painted black. In the eye, the mera proper is represented by the eyeball with its choroidal pigment, e screen by the retina, and the lens by the refracting media. In the se of the camera, the screen is enabled to receive clear images of objects different distances, by an apparatus for focussing. The corresponding ntrivance in the eye is the accommodation.

The iris, which is capable of allowing more or less light to pass into e eye, corresponds with the different sized diaphragms used in the otographic apparatus.

*Refractive media and surfaces.*—At first sight it would seem as if the refracting apparatus of the eye were very complicated, seeing that it consists of so many parts. These parts are: the anterior surface of the cornea itself, the posterior surface of the cornea, the aqueous humor, the anterior surface of the lens, the substance of the lens itself (which is also unequally refractive), the posterior surface of the lens, and the vitreous humor. Thus there are four surfaces, and at least including the air, five media. For all practical purposes, however, these may be resolved into a somewhat simpler form, and the cornea may be considered as one surface, the anterior, and one medium; the aqueous and vitreous humors as one medium; the lens, as two surfaces and one medium. It will be as well to consider the laws which govern the refraction of light under such circumstances.

In its simplest form, we may consider the refraction through a simple transparent spherical surface, separating two media of different density.

The rays of light which fall upon the surface exactly perpendicularly do not suffer refraction, but pass through, cutting the optic axis (O A, fig. 436), a line which passes exactly through the centre of the surface, at a certain point, the *nodal point* (fig. 436, N), or centre of curvature. Any rays which do not so strike the curved surface are refracted toward the optical axis. Rays which impinge upon the spherical surface parallel to the optical axis, will meet at a point behind, upon the said axis which is called the *chief posterior focus* (fig. 436, $F_1$); and again there is a point in the optical axis in front of the surface, rays of light from which so strike the surface that they are refracted in a line parallel with the axis $df''$; such a point (fig. 436, $F_2$) is called the *chief anterior focus*. The optic axis cuts the surface at what is called the *principal point*.

It is quite obvious that the eye, even in the simplified form above indicated, is a much more complicated optical apparatus than the one described in the figure. It is, however, possible to reduce the refractive surfaces and media to a simpler form when the refractive indices of the



Fig. 436.—Diagram of a simple optical system (after M. Foster). The curved surface, b, d, is supposed to separate a less refractive medium toward the left from a more refractive medium toward the right.

fferent media and the curvature of each surface are known. All of ese data have been very carefully collected. They are as follows:—

Index of refraction of aqueous and vitreous = 1.3365
" " lens . . . . . = 1.4371
Radius of curvature of cornea . . . . = 7.829 mm.
" " anterior surface of lens = 10 "
" " posterior " = 6 "
Distance from anterior surface of cornea and anterior surface of lens . . . . . = 3.6 "
Distance from posterior surface of cornea and posterior surface of lens . . . . . = 7.2 "

With these data, it has been found comparatively easy to reduce by lculation the different surfaces of different curvatures, into one mean rved surface of known curvature, and the differently refracting media to one mean medium the refractive power of which is known.

The simplest so-called schematic eye formed upon this principle, ggested by Listing as *the reduced eye*, has the following dimensions:—

From anterior surface of cornea to the principal point . . . . . . . . = 2.3448 mm.
From the nodal point to the posterior surface of lens . . . . . . . . . = .4764 "
Posterior chief focus lies behind cornea . . = 22.8237 "
Anterior chief focus in front of cornea . . = 12.8326 "
Radius of curvature of ideal surface . . = 5.1248 "

In this reduced or simplified eye the principal posterior focus, about 3 mm. behind the spherical surface, would correspond to the position the retina behind anterior surface of cornea. The refracting surface ould be situated about midway between the posterior surface of the rnea and the anterior surface of the lens.

The *optical axis* of the eye is a line drawn through the centres of rvature of the cornea and lens, prolonged backward to touch the retina tween the porus opticus and fovea centralis, and this differs from the sual axis which passes through the nodal point of the reduced eye to



Fig. 437.—Diagram of the optical angle.

e fovea centralis; this forms an angle of 5° with the optical axis. some the optical axis and the *visual axis* are considered to be idencal. The visual or optical angle is included between the lines drawn om the borders of any object to the nodal point; if the lines be prolonged backward they include an equal angle. It has been shown by Helmholtz that the smallest angular distance between two points which can be appreciated = 50 seconds, the size of the retinal image being 3.65$\mu$; this practically corresponds to the diameter of the cones at the fovea centralis which = 3$\mu$, the distance between the centres of two adjacent cones being = 4$\mu$.



Fig. 498.—Diagram of the method of the formation of an inverted image exactly focussed upon the retina. The dotted line is the ideal surface of curvature.

The image of an object, then, is thus formed upon the retina. An object may be considered as a series of points, from each of which a pencil of light diverges to the eye, and this pencil has for its centre or axis, a ray which impinging upon the refractive surface perpendicularly to the surface is not refracted, but passes through the nodal point, and is prolonged backward to the retina, whereas the diverging rays are also made to converge to a principal posterior focus behind the lens, or the chief axis of the pencil of light proceeding from the point in question, and this focus, if the image is to be clear, should fall on the retina.



Fig. 499.—Diagram of the course of a ray of light, to show how a blurred or indistinct image is formed if the object be not exactly focussed upon retina. The surface C C should be supposed to represent the ideal curvature. The nodal point should be nearer the posterior surface of lens as in fig. 498.

Thus from each point of an object a corresponding image is formed on the retina, so that an image of the distal object is produced. It is an inverted image. Whether the image is blurred or not depends upon the refractive power of the media, and upon the distance of the anterior surface of the cornea from the retina. If the refractive media are powerful, or the eye too long, the image is formed in front of the reti ig. 439); if the reverse, the image is formed behind the retina, and in oth cases an indistinct and blurred image is the result.

## ACCOMMODATION.

The distinctness of the image formed upon the retina, is mainly deendent on the rays emitted by each luminous point of the object being rought to a perfect focus upon the retina. If this focus occur at a oint either in front of, or behind the retina, indistinctness of vision nsues, in the way we have already described, with the production of a alo. The *focal distance*, *i.e.*, the distance from a lens of the point at hich the luminous rays are collected, besides being regulated by the egree of convexity and density of the lens, varies with the distance of he object from the lens, being greater as this is shorter, and *vice versâ*. ence, since objects placed at various distances from the eye can within certain range, different in different persons, be seen with almost equal istinctness, there must be some provision by which the eye is enabled to dapt itself, so that whatever length the focal distance may be, the focal oint may always fall exactly upon the retina.

This power of accommodation, or the *adaptation of the eye to vision f different distances*, has received the most varied explanations. It is bvious that the effect might be produced in either of two ways, viz., (*a*) y altering the convexity, and thus the refracting power, either of the rnea or of the lens; or (*b*) by changing the position either of the tina or of the lens, so that whether the object be near or distant, the cal points to which the rays are converged by the lens may always fall xactly on the retina. The amount of either of these changes, which ould be required in even the widest range of vision, would be extremely mall. For, from the refractive powers of the media of the eye, the difrence between the focal distances of the images of an object at a distance, nd of one at the distance of four inches, is only about 0.143 of an inch .5 mm.). On this calculation the change in the distance of the retina om the lens required for vision at all distances, supposing the cornea nd lens to remain the same, would not be more than about one line.

The adaptation of the eye for objects at different distances is priarily due to a varying shape of the lens, its front surface becoming ore or less convex, according as the distance of the object looked at is ear or far. The nearer the object, the more convex, up to a certain mit, the front surface of the lens, and *vice versâ;* the back surface takg little or no share in the production of the effect required. And this rface, which during rest is more convex than the anterior, becomes e less convex of the two during accommodation. The following simple periment illustrates this point: If a lighted candle be held a little to

one side of a person's eye, an observer looking
side sees three distinct images of the flame (
brightest is (1) a small erect image formed by th



Fig. 440.—Diagram showing three reflections of a candle.
cornea; 2, from the anterior surface of lens; 3, from the poste
explanation, see text. The experiment is best performed by e
by Helmholtz, termed a *Phakoscope*.

of the cornea; the second (2) is also erect, but la
the preceding, and is formed at the anterior c
the third (3) is smaller, inverted, and indisti
posterior surface of the lens, which is concave



Fig. 441.



Fig. 441. —Diagram of Sanson's images. A, when the ey
focussed for near objects. The fig. to the right in A and B is
terior surface of the lens.

Fig. 442.—Phakoscope of Helmholtz. At *B B'* are two prism
is concentrated on the eye of the person experimented with
eye of the observer. The observer notices three double images
eye under examination when the eye is fixed upon a distant ob
having been noticed, the eye is then made to focus a near obje
*C;* the images from the anterior surface of the lens will be obs
in consequence of the lens becoming more convex.

e all concave mirrors, gives an inverted image. If now the eye under
servation be made to look at a near object, the second image becomes
aller, clearer, and approaches the first. If the eye be now adjusted
a far point, the second image enlarges again, becomes less distinct,
d recedes from the first. In both cases alike the first and third images
nain unaltered in size, distinctness, and relative position. This
oves that during accommodation for near objects the curvature of the
rnea, and of the *posterior* of the lens, remains unaltered, while the
*terior* surface of the lens becomes more convex and approaches the
rnea.

The experiment (fig. 441) is more striking when two candles are
ed, and the images of the two candles from the front surface of the
s during accommodation not only approach those from the cornea,
t also approach one another, and become somewhat smaller. (*San-*
*'s images.*)

*The mechanism of accommodation.*—Accommodation is the act or
ocess of focussing the rays of light from any object, whether near or
stant, upon the retina. Its mechanism depends primarily upon the
herent tendency of the lens to approximate the shape of a sphere.
e elasticity of the latter can make itself apparent when the tension of
e suspensory ligament is relaxed. This takes place completely after a



**. 443.—Diagram representing by dotted lines the alteration in the shape of the lens on accommodation for near objects. (E. Landolt.)**

vision of the fibres of the zonula. When we remove the lens from the
e of a young person, we see it assume the spherical shape immediately
on the division of its connections. In life this slackening of the ten-
n of the suspensory ligament of the lens is brought about by the con-
ction of the annular fibres of the ciliary body. This relaxation allows
e anterior surface of the lens to become more convex, by its own
stic powers, thus focussing entering rays of light, say from a near
ject, upon the retina; in other words, accommodation (fig. 443). It

therefore appears that when the eye is at rest
objects, inasmuch as the suspensory ligament
surface of the lens is more flattened. In accom
nular fibres of the ciliary muscle contract, it
choroid, and by so doing slackens the tension
ment. Hence, the ciliary muscle is sometimes ca
The iris acts in co-ordination with accommoda
objects the pupil contracts and dilates upon view

*Range of Distinct Vision. Near-point.*—In
to the power of accommodation. If a book
nearer to the eye, the type at last becomes in
brought into focus by any effort of accommo
This, which is termed the ***near-point***, can be de
ing experiment (*Scheiner*). Two small holes ar
a pin not more than a twelfth of an inch (2
their distance from each other must not exceed
pil. The card is held close in front of the
viewed through the pin-holes. At a moderate
focussed, but when brought nearer, beyond a
appears double or at any rate blurred. This
ceases to appear single is the near-point. Its
of course be readily measured. It is usually
cm.). In the accompanying figure (fig. 444)



Fig. 444.—Diagram of experiment to ascertain the minimu

eye; *ef* the two pin-holes in the card, *nn* the ret
sition of the needle. When the needle is at
two pencils of light coming from *e* and *f*, are foc
the retina *nn*. If the needle be brought nearer
strongest effort of accommodation is not sufficie
cils, they meet at a point behind the retina.
as if the retina were shifted forward to *mm*.
formed, one from each hole. It is interesting
images are produced, the lower one *g* really ap
while the upper one appears in the position
verified by covering the holes in succession.

During accommodation two other changes take place in the eyes, *The eyes converge* by the action of the extra-ocular muscles chiefly he internal and inferior recti, or internal and superior recti. The rior oblique and the inferior oblique may also be used to turn the upward or downward.

**Movements of the Eye.**—The eyeball possesses movement around three axes cated in fig. 445, viz., an antero-posterior, a vertical, and a transverse, ing through a centre of rotation a little behind the centre of the optic axis. movements are accomplished by pairs of muscles.



45.—Diagram of the axes of rotation to the eye. The thin lines indicate axes of rotation, the thick the position of muscular attachment.

| Direction of Movement. | By what muscles accomplished. |
|---|---|
| rd | Internal rectus. |
| ward | External rectus. |
| ard | Superior rectus.<br>Inferior oblique. |
| nward | Inferior rectus.<br>Superior oblique. |
| rd and upward | Internal and superior rectus.<br>Inferior oblique. |
| rd and downward | Internal and inferior rectus.<br>Superior oblique. |
| ward and upward | External and superior rectus.<br>Inferior oblique. |
| ward and downward | External and inferior rectus.<br>Superior oblique. |

(2) The second change which takes place in the eyes is, that *the ils contract.* The contraction of all of the muscles which have to do accommodation, viz., of the ciliary muscle, of the recti muscles,

and of the sphincter pupillæ is under the co
But the superior oblique may also be employed,
nerve is also concerned.

*Contraction* of the pupil may also occur un
stances: (1) On exposure of the eye to a brig
application of eserine (active principle of Ca
administration internally of opium, aconite, a
chloroform and alcohol poisoning; (4) on
sympathetic or stimulation of the third nerve, a
occurs (1) in a dim light; (2) when the eye i
jects; (3) on the local application of atropine
(4) on the internal administration of atropi
the later stages of poisoning by chloroform, c
(6) on paralysis of the third nerve; (7) on s
sympathetic, or of its centre in the floor of the
Sylvius. The contraction of the pupil appear
of a centre in the bulb or in the corpora q
reflexly stimulated by a bright light, and the c
centre is not in action is due to the more pow
but in addition, it appears that both contracti
produced by a local mechanism, upon which cer
is independent of and probably often antagonis
central apparatus of the third and sympathetic n
fifth nerve upon the pupil is not well understoo
in producing dilatation is due to the mixtu
with its nasal branch. The sympathetic influ
fibres is believed to be conveyed not by the long
nerve, but by the short ciliary branches from th

The close sympathy subsisting between the t
shown than by the condition of the pupil. If
hand its pupil will of course dilate; but the pu
also dilate, though it is unshaded.

### DEFECTS IN THE OPTICAL AP

**Defects in the Refracting Media.**—Und
sider the defects known as (1) Myopia, (2) H
matism, (4) Spherical Aberration, (5) Chroma

The normal (emmetropic) eye is so adjust
brought exactly to a focus on the retina withou
dation (1, fig. 446). Hence all objects except
objects more than twenty feet off) are seen wit
modation; in other words, the far-point of the n
distance. In viewing near objects we are consci

on of the ciliary muscle) by which the anterior surface of the lens is red more convex, and rays which would otherwise be focussed *behind* tina are converged upon the retina (see dotted lines 2, fig. 446).



446.—Diagram showing—1, normal (emmetropic) eye bringing parallel rays exactly to on the retina; 2, normal eye adapted to a near point; without accommodation the rays be focussed behind the retina, but by increasing the curvature of the anterior surface of s (shown by a dotted line) the rays are focussed on the retina (as indicated by the meet- the two dotted lines); 3, *hypermetropic* eye, in this case the axis of the eye is shorter, lens flatter, than normal; parallel rays are focussed behind the retina; 4, *myopic* eye; case the axis of the eye is abnormally long, and the lens too convex; parallel rays are d in front of the retina.

*Myopia* (short-sight) (4, fig. 446), is that refractive condition of ye in which parallel rays are brought to a focus *in front* of the . It is due either to an abnormal elongation of the eyeball, anteroriorly, or to an increase in the convexity of the refracting surfaces, both of these conditions. The retina is too far from the lens and quently parallel rays are focussed in front of the retina, and, cross-form little circles on the retina; thus the images of distant objects lurred and indistinct. The eye is, as it were, permanently adjusted near-point. Rays from a point near the eye are exactly focussed retina. But those which issue from any object beyond a certain distance (*far-point*) cannot be distinctly focussed. This defect is corrected by *concave* glasses which cause the rays entering the eye to diverge; hence they do not come to a focus so soon. Such glasses of course are only needed to give a clear vision of distant objects. For near objects, except in extreme cases, they are not required.

*Hypermetropia* (long-sight) (3, fig. 446), is that refractive condition of the eye in which parallel rays are brought to a focus *behind* the retina. It is the opposite of myopia, and is due either to an abnormal shortening of the eyeball, antero-posteriorly, or to a decrease in the convexity of the refracting surfaces, or both. Parallel rays are focussed *behind* the retina: an effort of accommodation is required to focus even parallel rays on the retina; and when they are divergent, as in viewing a near object, the accommodation is insufficient to focus them. Thus in well-marked cases distant objects require an effort of accommodation and near ones a very powerful effort. Thus the ciliary muscle is constantly acting. This defect is obviated by the use of *convex* glasses, which renders the pencils of light more convergent. Such glasses are of course especially needed for near objects, as in reading, etc. They rest the eye by relieving the ciliary muscle from excessive work.

3. *Astigmatism.*—This defect, which was first discovered by Airy, is due to a greater curvature of the eye in one meridian than in others. The eye may be even myopic in one plane and hypermetropic in others. Thus vertical and horizontal lines crossing each other cannot both be focussed at once; one set stands out clearly and the others are blurred and indistinct. This defect, which is present in a slight degree in all eyes, is generally seated in the cornea, but occasionally in the lens as well; it may be corrected by the use of cylindrical glasses (*i.e.*, curved only in one direction).

4. *Spherical Aberration.*—The rays of a cone of light from an object situated at the side of the field of vision do not meet all in the same point, owing to their unequal refraction; for the refraction of the rays which pass through the circumference of a lens is greater than that of those traversing its central portion. This defect is known as *spherical aberration*, and in the camera, telescope, microscope, and other optical instruments, it is remedied by the interposition of a screen with a circular aperture in the path of the rays of light, cutting off all the marginal rays and only allowing the passage of those near the centre. Such correction is effected in the eye by the iris, which forms an annular diaphragm to cover the circumference of the lens, and to prevent the rays from passing through any part of the lens but its centre which corresponds to the pupil. The posterior surface of the iris is coated with pigment, to prevent the passage of rays of light through its substance. The image of an object will be most defined and distinct when the

is narrow, the object at the proper distance for vision, and the abundant; so that, while a sufficient number of rays are admitted, ırrowness of the pupil may prevent the production of indistinctness ı image by *spherical aberration*. But even the image formed by ays passing through the circumference of the lens, when the pupil ıch dilated, as in the dark, or in a feeble light, may, under certain nstances, be well defined.

istinctness of vision is further secured by the pigment of the outer e of the retina, the posterior surface of the iris and the ciliary sses, which absorbs any rays of light that may be reflected within re, and prevents their being thrown again upon the retina so as to ere with the images there formed. The pigment of the retina is ially important in this respect; for with the exception of its outer the retina is very transparent, and if the surface behind it were not dark color, but capable of reflecting the light, the luminous rays ı had already acted on the retina would be reflected again through d would fall upon other parts of the same membrane, producing dazzling from excessive light, and indistinctness of the images.

*Chromatic Aberration.*—In the passage of light through an ordiconvex lens, decomposition of each ray into its elementary colored commonly ensues, and a colored margin appears around the image, ; to the unequal refraction which the elementary colors undergo. tical instruments this, which is termed *chromatic aberration*, is cond by the use of two or more lenses, differing in shape and density, econd of which continues or increases the refraction of the rays ıced by the first, but by recombining the individual parts of each ıto its original white light, corrects any chromatic aberration which ıave resulted from the first. It is probable that the unequal refracower of the transparent media in front of the retina may be the by which the eye is enabled to guard against the effect of chromatic ıtion. The human eye is achromatic, however, only so long as nage is received at its focal distance upon the retina, or so long as ye adapts itself to the different distances of sight. If either of conditions be interfered with, a more or less distinct appearance ors is produced.

ı ordinary ray of white light in passing through a prism, is refract-., bent out of its course, but the different colored rays which go ıke up white light are refracted in different degrees, and therefore r as colored bands fading off into each other: thus a colored band ı as the "spectrum" is produced, the colors of which are arranged lows—red, orange, yellow, green, blue, indigo, violet; of these d ray is the least, and the violet the most refracted. Hence, as holtz has shown, a small white object cannot be accurately focussed

on the retina, for if we focus for the red rays,
and *vice versâ*: such objects, if not exactly fo
rounded by a pale yellowish or bluish fringe.

For similar reasons a red surface looks nea
equal distance, because, the red rays being
effort of accommodation is necessary to focus th
as if for a nearer object, and therefore the red

From the insufficient adjustment of the in
ject, it appears surrounded by a sort of halo c
enon is termed *Irradiation*. It is from this
on a black ground appears larger than a black
a white ground.

As an optical instrument, *the eye is supe*
following, among many other particulars, whi
detail. 1. The correctness of images even in
The simplicity and efficiency of the means by
tion is avoided. 3. The perfect efficiency of i
distances.[1] In the photographic camera, it is w
paratively small object can be accurately focus
of a large object near at hand, the upper an
more or less hazy, and vertical lines appear cu
fact that the image produced by a convex lens is
can only be received without distortion on
screen, hence the distortion on a *flat* surfac
different with the eye, since it possesses a c
which the field of vision is depicted, and with
the image coincides exactly. Thus, the defe
is entirely avoided; for the eye is able to emb
the margins of which are depicted distinctly a
the retina had a plane surface like the groun
it must necessarily be much larger than is re
see as much; moreover, the central portion o
would give a good clear picture (Bernstein).

*Presbyopia* is the diminution of the rang
takes place with perfect uniformity from yout
disease, but a physiological process which ev
owner grows older. It is due to a gradual s
the periphery of the lens, which begins even in
so slowly that it is not until the age of tw
though small, nucleus is present. With adv
goes on until, finally, the lens becomes inelasti
a shape convex enough to focus rays, from

tina, as in reading. The defect is remedied by the use of convex nses equivalent to the loss in accommodation.

## VISUAL SENSATIONS.

**Excitation of the Retina.**—Light is the normal agent in the ex-tation of the retina. The only layer of the retina capable of reacting the stimulus is the rods and cones. The proofs of this statement ay be summed up thus:—

(1.) The point of entrance of the optic nerve into the retina, where e rods and cones are absent, is insensitive to light and is called the *ind spot.* The phenomenon itself is very readily demonstrated. If e direct one eye, the other being closed, upon a point at such a dis-nce to the side of any object, that the image of the latter must fall pon the retina at the point of entrance of the optic nerve, this image lost either instantaneously, or very soon, If, for example, we close the ft eye, and direct the axis of the right eye steadily toward the circular



ot here represented, while the page is held at a distance of about six ches from the eye, both dot and cross are visible. On gradually in-easing the distance between the eye and the object, by removing the ok farther and farther from the face, and still keeping the right eye eadily on the dot, it will be found that suddenly the cross disappears om view, while on removing the book still farther, it suddenly comes sight again. The cause of this phenomenon is simply that the por-on of retina which is occupied by the entrance of the optic nerve, is ite blind; and therefore that when it alone occupies the field of vision, jects cease to be visible. (2.) In the fovea centralis and macula tea which contain rods and cones but no optic nerve-fibres, light pro-ces the greatest effect. In the latter, cones occur in large numbers, d in the former cones without rods are found, whereas in the rest of the tina which is not so sensitive to light, there are fewer cones than rods. e may conclude, therefore, that cones are even more important to sion than rods. (3.) If a small lighted candle be moved to and fro the side of and close to one eye in a dark room while the eyes ok steadily forward into the darkness, a remarkable branching ure (*Purkinje's figures*) is seen floating before the eye, consisting of rk lines on a reddish ground. As the candle moves, the figure moves the opposite direction, and from its whole appearance there can be no ubt that it is a reversed picture of the retinal vessels projected before e eye. The two large branching arteries passing up and down from e optic disc are clearly visible together with their minutest branches.

A little to one side of the disc, in a part free
yellow spot in the form of a slight depression.
ance is due to shadows of the retinal vessels c
branches of these vessels are chiefly distribute
ganglionic layers; and since the light of the c
vessels from in front, the shadow is cast behin
elements of the retina which perceive the shad
the vessels. Here, then, we have a clear proof
elements of the retina are not the fibres of th
innermost layer of the retina, but the external
and cones, which indeed appear to be the spe
optic nerve-fibres.

*Duration of Visual Sensations.*—The durat
duced by a luminous impression on the retina i
of the impression which produces it. However
sion, the effect on the retina always lasts for abou
Thus, supposing an object in motion, say a ho
dark night by a flash of lightning. The object
for an eighth of a second, but it would not ap
although the image remained on the retina fo
revealed for such an extremely short period (a
almost instantaneous) that no appreciable m
the object could have taken place in the per
revealed to the retina of the observer. And th
reverse way. The spokes of a rapidly revolvi
distinct objects, because at every point of the f
the revolving spokes pass, a given impression ha
comes to replace it. Thus every part of th
appears occupied.

The duration of the *after-sensation*, produc
in a direct ratio with the duration of the imp
Hence the image of a bright object, as of the p
which the light is shining, may be perceived i
siderable period, if we have previously kept ou
on it. But the image in this case is *negati*
shutting the eyes for some time, we open them
an instant, and again close them, the after-ima

*Intensity of Visual Sensations.*—It is quit
luminous a body the more intense is the sensati
intensity of the sensation is not *directly* prop
of the luminosity of the object. It is necessar
tain intensity before it can excite the retina, bu
arbitrary limit to the power of excitability.
also in visual sensations, a stimulus may be too

tion. If it be increased in amount sufficiently it begins to produce an fect which is increased on the increase of the stimulation; this in-ease in the effect is not *directly* proportional to the increase in the citation, but, according to *Fechner's law*, "as the logarithm of the imulus," *i.e.*, in each sensation, there is a constant ratio between the crease in the stimulus and the increase in the sensation, this constant tio for each sensation expresses the least perceptible increase in the nsation or minimal increment of excitation.

This law, which is true only within certain limits, may be best nderstood by an example. When the retina has been stimulated by the ght of one candle, the light of two candles will produce a difference in nsation which can be distinctly felt. If, however, the first stimulus ad been that of an electric light, the addition of the light of a candle ould make no difference in the sensation. So, generally, for an addi-onal stimulus to be felt, it may be proportionately small if the original imulus have been small, and must be greater if the original stimulus ave been great. The stimulus increases as the ordinary numbers, while e sensation increases as the logarithm.

Part of the light which enters the eye is absorbed and produces some hange in the retina, of which we shall treat further on; the rest is eflected.

Every one is perfectly familiar with the fact, that it is quite impos-ble to see the *fundus* or back of another person's eye by simply looking to it. The interior of the eye forms a perfectly black background to he pupil. The same remark applies to an ordinary photographic amera, and may be illustrated by the difficulty we experience in seeing to a room from the street through the window, unless the room be ghted within. In the case of the eye this fact is partly due to the ebleness of the light reflected from the retina, most of it being absorbed y the retinal pigment, as mentioned above; but far more to the fact that ery such ray is reflected straight to the source of light (*e.g.*, candle), and annot, therefore, be seen by the unaided eye without intercepting the cident light from the candle, as well as the reflected rays from the tina. This difficulty is surmounted by the use of the *ophthalmoscope*.

**The ophthalmoscope,** brought into use by Helmholtz, consists in its simplest rm of a mirror with a hole in it. The one about to be described is one of e less intricate of the modern instruments. It consists of *a*, a slightly con-ve mirror of metal or silvered glass perforated in the centre, and fixed to a handle; and *b*, a biconvex lens of about 2½-3 inches focal length. wo methods of examining the eye with this instrument are in common use -the *direct* and the *indirect:* both methods of investigation should be em-oyed. A normal eye should be examined; a drop of a solution of atropia wo grains to the ounce) or of homatropia hydrobromate, should be instilled out twenty minutes before the examination is commenced; the ciliary mus-e is thereby paralyzed, the power of accommodation is abolished, and the pupil is dilated. This will materially facilitate the examination; but it is quite possible to observe all the details to be presently described without the use of this drug. The room being now darkened, the observer seats himself in front of the person whose eye he is about to examine, placing himself upon a somewhat higher level. A brilliant and steady light is placed close to the left ear of the patient. The atropia having been put into the right eye *only* of the patient, this eye is examined. Taking the mirror in his right hand, and looking through the central hole, the operator directs a beam of light into the eye of the patient. A red glare, known as *the reflex*, is seen; it is due to the illumination of the retina. The patient is then told to look at the little finger of the observer's right hand as he holds the mirror; to effect this the eye is rotated somewhat inward, and at the same time the reflex changes from red to a lighter color, owing to the reflection from the optic disc. The observer now approximates the mirror, and with it his eye to the eye of the patient, taking care to keep the light fixed upon the pupil, so as not to lose the reflex. At a certain point, which varies with different eyes, but is usually when there is an interval of about two or three inches between the observed and the observing eye, *the vessels of the retina* will become visible as lines running in different directions. Distinguish the smaller and brighter red arteries from the larger and darker colored veins. Examine carefully the fundus of the eye, *i.e.*, the red surface—until *the optic disc* is seen; trace its circular outline, and observe the small central white spot, the porus opticus, *physiological pit:* near the centre is the central artery of the retina breaking up upon the disc into branches; veins also are present, and correspond roughly to the course of the arteries. Trace the vessels over the disc on to the retina. The optic disc is bounded by two delicate rings, the more external being the choroidal, while the more internal is the sclerotic opening. Somewhat to the outer side, and only visible



Fig. 447.—Diagram to illustrate the action of the Ophthalmoscope, when a plane concave glass is used. *c*, observer's eye. The light reflected from any point, *d*, on retina of *a*, would naturally be focussed at *e*; if the lens *b* is used it would be focussed at *i*, in other words, at back of *c*. The image would be enlarged, as though of *g*, and would be inverted. (After McGregor Robertson.)



Fig. 448.—Diagram to illustrate action of ophthalmoscope when a bi-convex glass is used. The fig. *d* on retina of *a* is under ordinary conditions focussed at *f* and inverted. If the lens *b* be placed between eyes, the image *h* is seen by the eye *c* as an enlarged image. (After McGregor Robertson.)

ter some practice, is the *yellow spot*, with the smaller lighter-colored *fovea* ntralis in its centre. This constitutes the direct method of examination (fig. 7); by it the various details of the fundus are seen s they really exist, and it is this method which hould be adopted for ordinary use.

If the observer is ametropic, *i.e.*, is myopic or ypermetropic, he will be unable to employ the irect method of examination until he has remedied is defective vision by the use of proper glasses.

In the indirect method (fig. 448) the patient is laced as before, and the operator holds the mirror his right hand at a distance of twelve to eighteen ches from the patient's right eye. At the same me he rests his left little finger lightly upon the ght temple, and holding the lens between his umb and forefinger, two or three inches in front the patient's eye, directs the light through the ns into the eye. The red reflex, and subsequently e white one, having been gained, the operator owly moves his mirror, and with it his eye, toward away from the face of the patient, until the outne of one of the retinal vessels becomes visible, hen very slight movements on the part of the perator will suffice to bring into view the details the fundus above described, but the image will much smaller and inverted. The lens should be ept fixed at a distance of two or three inches, the irror being alone moved until the disc becomes isible: should the image of the mirror, however, scure the disc, the lens may be slightly tilted.



Fig. 449.—The ophthalmoscope. The small upper mirror is for direct, the larger for indirect illumination.

**Visual Purple.**—The method by which a ray of light is able to imulate the endings of the optic nerve in the retina in such a manner at a visual sensation is perceived by the cerebrum is not yet under-ood. It is supposed that the change effected by the agency of the ght which falls upon the retina is in fact a chemical alteration in the otoplasm, and that this change stimulates the optic nerve-endings. he discovery of a certain temporary reddish-purple pigmentation of the ter limbs of the retinal rods in certain animals (*e.g.*, frogs) which had en killed in the dark, forming the so-called *rhodopsin or visual purple*, peared likely to offer some explanation of the matter, especially as it as also found that the pigmentation disappeared when the retina was posed to light, and reappeared when the light was removed, and also at it underwent distinct changes of color when other than white ght was used. It was also found that if the operation were performed ickly enough, the image of an object (*optogram*) might be fixed in the gment on the retina by soaking the retina of an animal, which has en killed in the dark, in alum solution.

The visual purple cannot however be absolutely essential to the due production of visual sensations, as it is absent from the retinal cones, and from the macula lutea and fovea centralis of the human retina, and does not appear to exist at all in the retinæ of some animals, *e.g.*, bat, dove, and hen, which are, nevertheless, possessed of good vision.

However the fact remains that light falling upon the retina (*a*) *bleaches the visual purple*, and this must be considered as one of its effects. It has been found that certain pigments, also sensitive to light, are contained in the inner segments of the cones. These colored bodies are said to be oil globules of various colors, red, green, and yellow, called *chromophanes*, and are found only in the retinas of animals not mammals. The rhodopsin at any rate appears to be derived in some way from the retinal pigment, since the color is not renewed after bleaching if the retina be detached from its pigment layer. (*b*) The second change produced by the action of the light upon the retina is the *movement of the pigment cells*. On the stimulation of light the granules of pigment in the cells which overlie the outer part of the rod and cone layer of the retina become diffused in the parts of the cells between the rods and cones, the *melanin* or *fuscin* granules, as they are called, passing down into the processes of the cells. (*c*) A *movement of the cones* and possibly of the rods is also said to occur, as has been already incidentally mentioned; on the stimulus of light the outer parts of the cones, which in an eye protected from light extend to the pigment layer, are retracted. It is even thought that the contraction is under the control of the nervous system; and finally, according to the careful researches of Dewar and McKendrick, and of Holmgren, it appears that the stimulus of light is able to produce (*d*) a *variation of the natural electrical currents of the retina*. The current is at first increased and then diminished. McKendrick believes that this is the electrical expression of those chemical changes in the retina of which we have already spoken.

## VISUAL PERCEPTIONS AND JUDGMENTS.

**Reversion of the Image.**—It will be as well to repeat here that the direction given to the rays by their refraction is regulated by that of the central ray, or axis of the cone, toward which the rays are bent. The image of any point of an object is, therefore, as a rule (the exceptions to which need not here be stated), always formed in a line identical with the axis of the cone of light, as in the line of B *b*, or A *a* (fig. 450), so that the spot where the image of any point will be formed upon the retina may be determined by prolonging the central ray of the cone of light, or that ray which traverses the centre of the pupil. Thus A *a* is the axis or central ray of the cone of light issuing from A; B *b* the central ray of the cone of light issuing from B; the image of A is formed at *a*, the image of B at *b*, in the inverted position: therefore what in the object was above is in the image below, and *vice versâ*,—the right-hand part of the object is in the image to the left, the left-hand to the right. If an opening be made in an eye at its superior surface, so that the retina can be seen through the vitreous humor, this image of any bright object, such as the windows of the room, may be perceived inverted upon the retina. Or still better, if the eye of any albino animal, such as a white rabbit, in which the coats, from the absence of pigment, are transparent, is dissected clean, and held with the cornea toward the window, a very distinct image of the window completely inverted is seen depicted on the posterior translucent wall of the eye. Volkmann has also shown that a similar experiment may be successfully performed in a living person possessed of large prominent eyes, and an unusually transparent sclerotic.



Fig. 450.—Diagram of the formation of the image on the retina.

An image formed at any point on the retina is referred to a point outside the eye, lying on a straight line drawn from the point on the retina outward through the centre of the pupil. Thus an image on the left side of the retina is referred by the mind to an object on the right side of the eye, and *vice versâ*. Thus all images on the retina are mentally, as it were, projected in front of the eye, and the objects are seen *erect* though the image on the retina is inverted. Much needless confusion and difficulty have been raised on this subject for want of remembering that when we are said to *see* an object, the mind is merely conscious of the picture on the retina, and when it refers it to the external object, or "projects" it outside the eye, it *necessarily* reverses it and sees the object as erect, though the retinal image is inverted. This is further corroborated by the sense of touch. Thus an object whose picture falls on the left half of the retina is reached by the right hand, and hence is said to lie to the *right*. Or, again, an object whose image is formed on the upper part of the retina is readily touched by the feet, and is therefore said to be in the *lower* part of the field, and so on.

Hence it is also, that no discordance arises between the sensations of inverted vision and those of touch, which perceives everything in its erect position; for the images of all objects, even of our own limbs, on the retina, are equally inverted, and therefore maintain the same relative position.

Even the image of our hand, while used in touch, is seen inverted. The position in which we see objects, we call, therefore, the erect position. A mere lateral inversion of our body in a mirror, where the right hand occupies the left of the image, is indeed scarcely remarked: and there is but little discordance between the sensations acquired by touch in regulating our movements by the image in the mirror, and those of sight, as, for example, in tying a knot in the cravat. There is some want of harmony here, on account of the inversion being only lateral, and not complete in all directions.

The perception of the erect position of objects appears, therefore, to be the result of an act of the mind. And this leads us to a consideration of the several other properties of the retina, and of the co-operation of the mind in the several other parts of the act of vision. To these belong not merely the act of sensation itself and the perception of the changes produced in the retina, as light and colors, but also the conversion of the mere images depicted in the retina into ideas of an extended field of vision, of proximity and distance, of the form and size of objects, of the reciprocal influence of different parts of the retina upon each other, the simultaneous action of the two eyes, and some other phenomena.

**Field of Vision.**—The actual size of the field of vision depends on the extent of the retina, for only so many images can be seen at any one time as can occupy the retina to the same time; and thus considered, the retina, the conditions of which are perceived by the brain, is itself the field of vision. But to the mind of the individual the size of the field of vision has no determinate limits; sometimes it appears very small, at another time very large; for the mind has the power of projecting images on the retina toward the exterior. Hence the mental field of vision is very small when the sphere of the action of the mind is limited to impediments near the eye: on the contrary, it is very extensive when the projection of the images on the retina toward the exterior, by the influence of the mind, is not impeded. It is very small when we look into a hollow body of small capacity held before the eyes; large when we look out upon the landscape through a small opening; more extensive when we look at the landscape through a window; and most so when our view is not confined by any near object. In all these cases the idea which we receive of the size of the field of vision is very different, although its absolute size is in all the same, being dependent on the extent of the retina. Hence it follows, that the mind is constantly co-operating in the acts of vision, so that at last it becomes difficult to say what belongs to mere sensation, and what to the influence of the mind.

By a mental operation of this kind, we obtain a correct idea of the size f individual objects, as well as of the extent of the field of vision. To illustrate this, it will be well to refer to fig. 451.

The angle $x$, included between the decussating central rays of two ones of light issuing from different points of an object, is called the



Fig. 451.

ptical angle—*angulus opticus seu visorius*. This angle becomes larger, he greater the distance between the points A and B; and since the angles and $y$ are equal, the distance between the points $a$ and $b$ in the image n the retina increases as the angle becomes larger. Objects at different istances from the eye, but having the same optical angle $x$—for examle, the objects, $c$, $d$, and $e$,—must also throw images of equal size upon he retina; and, if they occupy the same angle of the field of vision, heir image must occupy the same spot in the retina.

Nevertheless, these images appear to the mind to be of very unequal ze when the ideas of distance and proximity come into play; for, from he image $a$ $b$, the mind forms the conception of a visual space extendng to $e$, $d$, or $c$, and of an object of the size which that represented by he image on the retina appears to have when viewed close to the eye, or nder the most usual circumstances.

**Estimation of Size.**—Our estimate of the size of various objects is ased partly on the visual angle under which they are seen, but much ore on the estimate we form of their distance. Thus a lofty mountain any miles off may be seen under the same visual angle as a small hill ear at hand, but we infer that the former is much the larger object ecause we know it is much further off than the hill. Our estimate of istance is often erroneous, and consequently the estimate of size also. hus persons seen walking on the top of a small hill againts a clear wilight sky appear unusually large, because we over-estimate their disnce, and for similar reasons most objects in a fog appear immensely agnified. The same mental process gives rise to the idea of depth in he field of vision; this idea being fixed in our mind principally by the rcumstance that, as we ourselves move forward, different images in ccession become depicted on our retina, so that we seem to pass etween these images, which to the mind is the same thing as passing etween the objects themselves.

The action of the sense of vision in relation to external objects is, therefore, quite different from that of the sense of touch. The objects of the latter sense are immediately present to it; and our own body, with which they come in contact, is the measure of their size. The part of a table touched by the hand appears as large as the part of the hand receiving an impression from it, for a part of our body in which a sensation is excited, is here the measure by which we judge of the magnitude of the object. In the sense of vision, on the contrary, the images of objects are mere fractions of the objects themselves realized upon the retina, the extent of which remains constantly the same. But the imagination, which analyzes the sensations of vision, invests the images of objects, together with the whole field of vision in the retina, with very varying dimensions; the relative size of the image in proportion to the whole field of vision, or of the affected parts of the retina to the whole retina, alone remaining unaltered.

**Estimation of Direction.**—The direction in which an object is seen, depends on the part of the retina which receives the image, and on the distance of this part from, and its relation to, the central point of the retina. Thus, objects of which the images fall upon the same parts of the retina lie in the same visual direction; and when, by the action of the mind, the images or affections of the retina are projected into the exterior world, the relation of the images to each other remains the same.

**Estimation of Form.**—The estimation of the form of bodies by sight is the result partly of the mere sensation, and partly of the association of ideas. Since the form of the images perceived by the retina depends wholly on the outline of the part of the retina affected, the sensation alone is adequate to the distinction of only superficial forms of each other, as of a square from a circle. But the idea of a solid body as a sphere, or a body of three or more dimensions, *e.g.*, a cube, can only be attained by the action of the mind constructing it from the different superficial images seen in different positions of the eye with regard to the object, and, as shown by Wheatstone and illustrated in the *stereoscope*, from two different perspective projections of the body being present simultaneously to the mind by the two eyes. Hence, when, in adult age, sight is suddenly restored to persons blind from infancy, all objects in the field of vision appear at first as if painted flat on one surface; and no idea of solidity is formed until after long exercise of the sense of vision combined with that of touch.

The *clearness* with which an object is perceived irrespective of accommodation, would appear to depend largely on the number of rods and cones which its retinal image covers. Hence the nearer an object is to the eye (within moderate limits) the more clearly are all its details een. Moreover, if we want carefully to examine any object, we always direct the eyes straight to it, so that its image shall fall on the yellow spot where an image of a given area will cover a larger number of cones than anywhere else in the retina. It has been found that the images of two points must be at least $3\mu$ apart on the yellow spot in order to be distinguished separately; if the images are nearer together, the points appear as one. The diameter of each cone in this part of the retina is about $3\mu$.

**Estimation of Movement.**—We judge of the *motion* of an object, partly from the motion of its image over the surface of the retina, and partly from the motion of our eyes following it. If the image upon the etina moves while our eyes and our body are at rest, we conclude that he object is changing its relative position with regard to ourselves. In uch a case the movement of the object may be apparent only, as when we are standing upon a body which is in motion, such as a ship. If, on he other hand, the image does not move with regard to the retina, but emains fixed upon the same spot of that membrane, while our eyes folow the moving body, we judge of the motion of the object by the sensaion of the muscles in action to move the eye. If the image moves over he surface of the retina while the muscles of the eye are acting at the ame time in a manner corresponding to this motion, as in reading, we nfer that the object is stationary, and we know that we are merely ltering the relations of our eyes to the object. Sometimes the object ppears to move when both object and eye are fixed, as in vertigo.

The mind can, by the faculty of *attention*, concentrate its activity more or less exclusively upon the sense of sight, hearing, and touch alternately. When exclusively occupied with the action of one sense, it is carcely conscious of the sensations of the others. The mind, when deeply mmersed in contemplations of another nature, is indifferent to the acions of the sense of sight, as of every other sense. We often, when eep in thought, have our eyes open and fixed, but see nothing, because f the stimulus of ordinary light being unable to excite the brain to erception, when otherwise engaged. The attention which is thus ecessary for vision, is necessary also to analyze what the field of vision resents. The mind does not perceive all the objects presented by the eld of vision at the same time with equal acuteness, but directs itself rst to one and then to another. The sensation becomes more intense, ccording as the particular object is at the time the principal object of ental contemplation. Any compound mathematical figure produces a ifferent impression according as the attention is directed exclusively to ne or the other part of it. Thus in fig. 542, we may in succession ave a vivid perception of the whole, or of distinct parts only; of the x triangles near the outer circle, of the hexagon in the middle, of the three large triangles. The more numerous and varied the parts of which a figure is composed the more scope does it afford for the play of the attention. Hence it is that architectural ornaments have an enlivening



Fig. 452.

effect on the sense of vision, since they afford constantly fresh subject for the action of the mind.

**Color Sensations.**—If a ray of sunlight be allowed to pass through a prism, it is decomposed by its passage into rays of different colors, which are called the colors of the spectrum; they are red, orange, yellow, green, blue, indigo, and violet. The red rays are the least turned out of their course by the prism, and the violet the most, while the other colors occupy in order places between these two extremes. The differences in the color of the rays depend upon the number of vibrations producing each, the red rays being the least rapid and the violet the most. In addition to the colored rays of the spectrum, there are others which are invisible, but which have definite properties, those to the left of the red, and less refrangible, being the calorific rays which act upon the thermometer, and those to the right of the violet, which are called the actinic or chemical rays, which have a powerful chemical action. The rays which can be perceived by the brain, *i.e.*, the colored rays, must stimulate the retina in some special manner in order that colored vision may result, and two chief explanations of the method of stimulation have been suggested.

(1.) The one, originated by Young and elaborated by Helmholtz, holds that there are three primary colors, viz., *red*, *green*, and *violet*, and that in the retina are contained rods or cones which answer to each of these primary colors, whereas the innumerable intermediate shades of color are produced by stimulation of the three primary color terminals in different degrees, the sensation of white being produced at the same time when the three elements are equally excited. Thus if the retina be stimulated by rays of certain wave length, at the red end of the spectrum, the terminals of the other colors, green and violet, are hardly stimulated at all, but the red terminals are strongly stimulated, the resulting sensation being red. The orange rays excite the red terminals considerably, the green rather more, and the violet slightly, the resulting sensation being that of orange, and so on (fig. 453).

(2.) The second theory of color (Hering's) supposes that there are six primary color sensations, of three pair of antagonistic or complemental colors, black and white, red and green, and yellow and blue, and that these are produced by the changes either of disintegration or of assimilation taking place in certain substances, somewhat it may be supposed of the nature of the visual purple, which (the theory supposes to) exist in the retina. Each of the substances corresponding to a pair of colors, being capable of undergoing two changes, one of construction and the other of disintegration, with the result of producing one or other color. For instance, in the white-black substance, when disintegration is in excess of construction or assimilation, the sensation is white, and when assimilation is in excess of disintegration the reverse is the case; and similarly with the red-green substance, and with the yellow-blue substance. When the repair and disintegration are equal with the first



Fig. 453.



Fig. 454.

Fig. 453.—Diagram of the three primary color sensations. (Young-Helmholtz theory) 1, is the red; 2, green, and 3, violet, primary color sensations. The lettering indicates the colors of the spectrum. The diagram indicates by the height of the curve to what extent the several rimary sensations of color are excited by vibrations of different wave lengths.

Fig. 454.—Diagram of the various simple and compound colors of light, and those which are omplemental of each other, i.e., which, when mixed, produce a neutral gray tint. The three imple colors, red, yellow, and blue, are placed at the angles of an equilateral triangle, which re connected together by means of a circle; the mixed colors, green, orange, and violet, are laced intermediate between the corresponding simple or homogeneous colors; and the complemental colors, of which the pigments, when mixed, would constitute a gray, and of which the rismatic spectra would together produce a white light, will be found to be placed in each case pposite to each other, but connected by a line passing through the centre of the circle. The figre is also useful in showing the further shades of color which are complementary of each ther. If the circle be supposed to contain every transition of color between the six marked own, those which, when united, yield a white or gray color, will always be found directly opposite to each other; thus, for example, the intermediate tint between orange and red is comlemental of the middle tint between green and blue.

ubstance, the visual sensation is gray; but in the other pairs when this s the case, no sensation occurs. The rays of the spectrum to the left roduce changes in the red-green substance only, with a resulting sensaion of red, while the (orange) rays further to the right affect both the ed-green and the yellow-blue substances; blue rays cause constructive hanges in the yellow-blue substances but none in the red-green and so n. These changes produced in the visual substances in the retina are erceived by the brain as sensations of color.

The spectra left by the images of white or luminous objects are rdinarily white or luminous; those left by dark objects are dark. Someimes, however, the relation of the light and dark parts in the image may, under certain circumstances, be reversed in the spectrum; what was bright may be dark, and what was dark may appear light. This occurs whenever the eye, which is the seat of the spectrum of a luminous object, is not closed, but fixed upon another bright or white surface, as a white wall, or a sheet of white paper. Hence the spectrum of the sun, which, while light is excluded from the eye, is luminous, appears black or gray when the eye is directed upon a white surface. The explanation of this is, that the part of the retina which has received the luminous image remains for a certain period afterward in an exhausted or less sensitive state, while that which has received a dark image is in an unexhausted, and therefore much more excitable condition.

The ocular spectra which remain after the impression of colored objects upon the retina are always colored; and their color is not that of the object, or of the image produced directly by the object, but the opposite, or *complemental* color. The spectrum of a red object is, therefore, green; that of a green object, red; that of violet, yellow; that of yellow, violet, and so on. The reason of this is obvious. The part of the retina which receives, say, a red image, is wearied by that particular color, but remains sensitive to the other rays which with red make up white light; and, therefore, these by themselves reflected from a white object produce a green hue. If, on the other hand, the first object looked at be green, the retina being tired of green rays, receives a red image when the eye is turned to a white object. And so with the other colors; the retina while fatigued by yellow rays will suppose an object to be violet, and *vice versâ;* the size and shape of the spectrum corresponding with the size and shape of the original object looked at. The colors which thus reciprocally excite each other in the retina are those placed at opposite points of the circle in fig. **454.** The peripheral parts of the retina do not react to rays of *red.* The area of the retina which is capable of receiving impressions of color, and therefore the field of vision, is slightly different for each color.

*Color Blindness or Daltonism.*—Daltonism or color-blindness is a by no means uncommon visual defect. One of the commonest forms is the inability to distinguish between red and green. The simplest explanation of such a condition is, that the elements of the retina which receive the impression of red, etc., are absent, or very imperfectly developed, or, according to the other theory, that the red-green substance is absent from the retina. Other varieties of color blindness in which the other color-perceiving elements are absent have been shown to exist occasionally.

### THE RECIPROCAL ACTION OF DIFFERENT PARTS OF THE RETINA.

Although each elementary part of the retina represents a distinct portion of the field of vision, yet the different elementary parts, or sensipoints of that membrane, have a certain influence on each other; particular condition of one influencing the other, so that the image ived by one part is modified by the image depicted in the other. phenomena which result from this relation between the different of the retina, may be arranged in two classes: the one including where the condition existing in the greater extent of the retina is rted to the remainder of that membrane; the other, consisting of in which the condition of the larger portion of the retina excites, e less extensive portion, the opposite condition.

. When two opposite impressions occur in contiguous parts of an e on the retina, the one impression is, under certain circumstances, fied by the other. If the impressions occupy each one-half of the e, this does not take place; for in that case, their actions are equally ced. But if one of the impressions occupies only a small part of etina, and the other the greater part of its surface, the latter may, ng continued, extend its influence over the whole retina, so that pposite less extensive impression is no longer perceived, and its becomes occupied by the same sensation as the rest of the field of n. Thus, if we fix the eye for some time upon a strip of colored r lying upon a white surface, the image of the colored object, espe- y when it falls on the lateral parts of the retina will gradually dis- ar, and the white surface be seen in its place.

. In the second class of phenomena, the affection of one part of the a influences that of another part, not in such a manner as to ob- ate it, but so as to cause it to become the contrast or opposite of . Thus a gray spot upon a white ground appears darker than the tint of gray would do if it alone occupied the whole field of vision, shadow is always rendered deeper when the light which gives rise to comes more intense, owing to the greater contrast.

he former phenomena ensue gradually, and only after the images been long fixed on the retina; the latter are instantaneous in their uction, and are permanent.

n the same way, also, colors may be produced by contrast. Thus, a small dull gray strip of paper, lying upon an extensive surface of bright color, does not appear gray, but has a faint tint of the color h is the complement of that of the surrounding surface. A strip ray paper upon a green field, for example, often appears to have t of red, and when lying upon a red surface, a greenish tint; it has range-colored tint upon a bright blue surface, and a bluish tint an orange-colored surface; a yellowish color upon a bright violet, violet tint upon a bright yellow surface. The color excited thus, as trast to the exciting color, being wholly independent of any rays of orresponding color acting from without upon the retina, must arise as an opposite or antagonistic condition of that membrane; and the opposite conditions of which the retina thus becomes the subject would seem to balance each other by their reciprocal reaction. A necessary condition for the production of the contrasted colors is, that the part of the retina in which the new color is to be excited, shall be in a state of comparative repose; hence the small object itself must be gray. A second condition is, that the color of the surrounding surface shall be very bright, that is, shall contain much white light.

## BINOCULAR VISION.

Although the sense of sight is exercised by the two eyes, yet the impression of an object conveyed to the mind is single. Various theories have been advanced to account for this phenomenon.

By Gall it was supposed that we do not really employ both eyes simultaneously in vision, but always see with only one at a time. This especial employment of one eye in vision certainly occurs in persons whose eyes are of very unequal focal distance, but in the majority of individuals both eyes are simultaneously in action, in the perception of the same object; this is shown by the double images seen under certain conditions. If two fingers be held up before the eyes, one in front of the other, and vision be directed to the more distant, so that it is seen singly, the nearer will appear double; while, if the nearer one be regarded, the most distant will be seen double; and one of the double images in each case will be found to belong to one eye, the other to the other eye.

**Diplopia.**—Single vision results only when certain parts of the two retinæ are affected simultaneously; if different parts of the retinæ receive the image of the object, it is seen double. This may be readily illustrated as follows:—the eyes are fixed upon some near object, and one of them is pressed by the thumb so as to be turned slightly in or out; two images of the object (Diplopia) are at once perceived, just as is frequently the case in persons who squint. This diplopia is due to the fact that the images of the object do not fall on corresponding points in the two retinæ.

The parts of the retinæ in the two eyes which thus correspond to each other in the property of referring the images which affect them simultaneously to the same spot in the field of vision, are, in man, just those parts which would correspond to each other, if one retina were placed exactly in front of, and over the other (as in fig. 455). Thus, as we have noticed in speaking of the distribution of the optic nerve-fibres, the temporal portion of one eye corresponds to, or, to use a better term, is identical with the nasal portion of the other eye; or *a* of the eye A (fig. 455), with $a'$ of the eye B. The upper part of one retina is also identical with the upper part of the other; and the lower parts of the two eyes are identical with each other. The distribution of the optic nerve-fibres correspond with their distribution. The identical points on the upper and lower parts of the retinæ may also be shown by the folowing simple experiment.

Pressure upon any part of the ball of the eye, so as to affect the retina, produces a luminous circle, seen at the opposite side of the field of vision o that on which the pressure is made. If, now, in a dark room, we press with the finger at the upper part of one eye, and at the lower part f the other, two luminous circles are seen, one above the other; so, lso, two figures are seen when pressure is made simultaneously on the wo outer or the two inner sides of both eyes. It is certain, therefore, hat neither the upper part of one retina and the lower part of the other re identical, nor the outer lateral parts of the two retinæ, nor their nner lateral portions. But if pressure be made with the fingers upon both eyes simultaneously at their lower part, one luminous ring is seen at the middle of the upper part of the field of vision; if the pressure be pplied to the upper part of both eyes a single luminous circle is seen in he middle of the field of vision below. So, also, if we press upon the uter side $a$ of the eye A, and upon the inner side $a'$ of the eye B, a ingle spectrum is produced, and is apparent at the extreme right of the eld of vision; if upon the point $b$ of one eye, and the point $b'$ of the ther, a single spectrum is seen to the extreme left.



Fig. 455.—Diagram to show the corresponding parts of both retina.

The spheres of the two retinæ may, therefore, be regarded as lying ne over the other, as in C, fig. 455; so that the left portion of one eye lies ver the identical left portion of the other eye, the right portion of one ye over the identical right portion of the other eye; and with the pper and lower portions of the two eyes, $a$ lies over $a'$, $b$ over $b'$, and $c$ ver $c'$. The points of the one retina intermediate between $a$ and $c$ are gain identical with the corresponding points of the other retina between ' and $c'$; those between $b$ and $c$ of the one retina, with those between $b'$ nd $c'$ of the other. If the axes of the eyes, A and B (fig. 456), be so irected that they meet at $a$, an object at $a$ will be seen singly, for the

point *a* of the one retina, and *a'* of the other a
the object β be so situated that its image falls
distance from the central point of the retina,—
eye, and at *b'* in the other,—β will be seen sin
parts of the two retinæ. The same will apply

In quadrupeds, the relation between the id
parts of the retina cannot be the same as in m
eyes generally diverge, and can never be made
an object. When such an animal regards an o
front of it, the image of the object must fall, i
portion of the retinæ. Thus the image of the
at *a'* in one, and at *a''* in the other: and these
identical. So, also, for distinct and single visi



Fig. 456.

Fig. 456.—Diagram to show the simultaneous action of the
ferent directions.

Fig. 457.—Diagram to show the corresponding parts of the

points *b'* and *b''* or *c' c''*, in the two retinæ, on
objects fall, must be identical. All points o
which receive rays of light from lateral objects
sponding identical points in the retina of the
two objects, one situated to the right and the
appear to lie in the same spot of the field o
therefore, that there are in the eyes of anin
which are identical, and parts which are not id
which have no corresponding parts in the othe
of the two retinæ to each other in the field of
as in fig. 458.

The cause of the impressions on the identica
giving rise to but one sensation, and the perc

ither lie in the structural organization of the deeper or cere- rtion of the visual apparatus, or be the result of a mental opera- or in no other case is it the property of the corresponding nerves wo sides of the body to refer their sensations as one to one spot.



Fig. 458.

ly attempts have been made to explain this remarkable relation the eyes, by referring it to anatomical relation between the erves. The circumstance of the inner portion of the fibres of the ic nerves decussating at the commissure, and passing to the eye pposite side, while the outer portion of the fibres continue their to the eye of the same side, so that the left side of both retinæ is from one root of the nerves, and the right side of both retinæ e outer root, naturally led to an attempt to explain the phenomenon distribution of the fibres of the nerves. And this explanation is by cases in which the entire of one side of the retina, as far as tral point in both eyes, sometimes becomes insensible. But has endeavored to show the inadequateness of this theory to ex- e phenomenon, unless it be supposed that each fibre in each cere- rtion of the optic nerves divides in the optic commissure into two



-Diagrams to illustrate three theories to explain the action of symmetrical parts of the retina.

s for the identical points of the two retinæ, as is shown in A, . But there is no foundation for such supposition.

nother theory it is assumed that each optic nerve contains exactly e number of fibres as the other, and that the corresponding fibres wo nerves are united in the sensorium (as in fig. 459, B). But theory no account is taken of the partial decussation of the fibres erves in the optic commissure.

According to a third theory, the fibres *a* and *a'*, fig. 459, C, coming from identical points of the two retinæ, are in the optic commissure brought into one optic nerve, and in the brain either are united by a loop, or spring from the same point. The same disposition prevails in the case of the identical fibres *b* and *b'*. According to this theory, the left half of each retina would be represented in the left hemisphere of the brain, and the right half of each retina in the right hemisphere.

Another explanation is founded on the fact, that at the anterior part of the commissure of the optic nerve, certain fibres pass across from the distal portion of one nerve to the corresponding portion of the other nerves, as if they were commissural fibres forming a connection between the retinæ of the two eyes. It is supposed, indeed, that these fibres may connect the corresponding parts of the two retinæ, and may thus explain their unity of action; in the same way that corresponding parts of the cerebral hemispheres are believed to be connected together by the commissural fibres of the corpus callosum, and so enabled to exercise unity of function.

**Judgment of Solidity.**—On the whole, it is probable, that the power of forming a single idea of an object from a double impression conveyed by it to the eyes is the result of a mental act. This view is supported by the same facts as those employed by Wheatstone to show that this power is subservient to the purpose of obtaining a right perception of bodies raised in relief. When an object is placed so near the eyes that to view it the optic axes must converge, a different perspective projection of it is seen by each eye, these perspectives being more dissimilar as the convergence of the optic axes becomes greater. Thus, if any figure of three dimensions, an outline cube, for example, be held at a moderate distance before the eyes, and viewed with each eye successively while the head is kept perfectly steady, A (fig. 460) will be the picture presented to the right eye, and B that seen by the left eye. Wheatstone has shown that on this circumstance depends in a great measure our conviction of the solidity of an object, or of its projection in relief. If different perspective drawings of a solid body, one representing the image seen by the right eye, the other that seen by the left (for example, the drawing



Fig. 460.—Diagrams to illustrate how a judgment of a figure of three dimensions is obtained.

f a cube, A, B, fig. 460) be presented to corresponding parts of the two etinæ, as may be readily done by means of the stereoscope, the mind ill perceive not merely a single representation of the object, but a body rojecting in relief, the exact counterpart of that from which the drawngs were made.

By transposing two stereoscopic pictures a reverse effect is produced; ne elevated parts appear to be depressed, and *vice versâ*. An instruent contrived with this purpose is termed a *pseudoscope*. Viewed with nis instrument a bust appears as a hollow mask, and as may readily be nagined the effect is most bewildering.

There can be no doubt in order that the image of an object should fall pon corresponding points in the two retinæ, it is essential that the movements of the eyes should be accurately co-ordinated, and the method of is co-ordination is not so easily understood when examined carefully. hus, suppose the eyes be directed downward and to the left. On the left de, the inferior rectus, the external rectus, and the superior oblique ould contract, and, on the right side the inferior rectus, internal rectus, d superior oblique. In other words, a different set of muscles on ther side, and supplied to a certain extent by different nerves. There ust be some co-ordinating centre for these binocular movements. It is ought that this centre is localized in the anterior corpus quadrigemim, since stimulation of it causes conjugal lateral movement of the visual es to the opposite side, and stimulation at another spot produces movements downward and inward. The posterior longitudinal bundle of fibres scribed as found in the pons and crus, appears to be concerned in some y with the simultaneous movement of the eyes; it appears to unite the clei of the three nerves to the ocular muscles, the sixth, fourth, and rd. In it are said to be contained fibres from the sixth nerve of the posite side which go to the nucleus of the third nerve of the same side; d this would serve to connect the nerve supply of the internal rectus one side, and the external rectus of the other side. It appears, hower, that there is no evidence to assume that the fibres of the sixth rve decussate, but those of the fourth nerve do entirely, and those of e third, partially.

# CHAPTER XVIII.

## THE REPRODUCTIVE ORGANS.

**Before** describing the method of Reproduction, or the way which the species is propagated, it will be advisable to describe

### The Genital Organs of the Female.

The female organs of generation (fig. 461) consist of two *ovaries*, the function of which is the formation of *ova;* of a *Fallopian tube*, or *oviduct*, connected with each ovary, for the purpose of conducting the ovum from the ovary to the *uterus* in the cavity of which, if impregnated, it is retained until the embryo is fully developed, and fitted to maintain its existence independently of internal connection with the parent; and, lastly, of a canal, or *vagina*, with its appendages, for the reception of a male organ in the act of copulation, and for the subsequent discharge of the fœtus.



Fig. 461.—Diagrammatic view of the uterus and its appendages, as seen from behind. The uterus and upper part of the vagina have been laid open by removing the posterior wall; the Fallopian tube, round ligament, and ovarian ligament have been cut short, and the broad ligament removed on the left side; *u*, the upper part of the uterus; *c*, the cervix opposite the os internum; the triangular shape of the uterine cavity is shown, and the dilatation of the cervical cavity with the rugæ termed arbor vitæ; *v*, upper part of the vagina; *od*, Fallopian tube or oviduct; the narrow communication of its cavity with that of the cornu of the uterus on each side is seen; *l*, round ligament; *lo*, ligament of the ovary; *o*, ovary; *i*, wide outer part of the right Fallopian tube; *fi*, its fimbriated extremity; *po*, parovarium; *h*, one of the hydatids frequently found connected with the broad ligament. ½. (Allen Thomson.)

**The Ovaries.**—The ovaries are two oval compressed bodies, situated in the cavity of the pelvis, one on each side, and are adherent to the posterior surface of the broad ligament by their anterior border. This rder of the ovary is called the hilum, and it is at this point that the ood-vessels and nerves enter it. Each ovary measures about an inch d a half in length (3.75 cm.), three quarters of an inch in width .86 cm.), and nearly half an inch (1.25 cm.) in thickness, and is tached to the uterus by a narrow fibrous cord (the ligament of the ary), and, more slightly, to the Fallopian tubes, by one of the fimbriæ to which the walls of the extremity of the tube expand.

*Structure.*—A layer of condensed connective tissue, called the *tunica buginea*, surrounds the ovary, and this is covered on the outside by epielium (germ-epithelium), the cells of which although continuous with,



Fig. 462.—View of a section of the ovary of the cat. 1, outer covering and free border of e ovary; 1', attached border; 2, the ovarian stroma, presenting a fibrous and vascular structe; 3, granular substance lying external to the fibrous stroma; 4, blood-vessels; 5, ovigerms in ir earliest stages occupying a part of the granular layer near the surface; 6, ovigerms which ve begun to enlarge and to pass more deeply into the ovary; 7, ovigerms round which the aafian follicle and tunica granulosa are now formed, and which have passed somewhat deeper o the ovary and are surrounded by the fibrous stroma; 8, more advanced Graafian follicle th the ovum imbedded in the layer of cells constituting the proligerous disc; 9, the most adnced follicle containing the ovum, etc.; 9', a follicle from which the ovum has accidentally aped; 10, corpus luteum. × 6. (Schrön.)

d originally derived from, the squamous epithelium of the peritoneum, e short columnar (A, fig. 463).

The internal structure of the organ consists of a peculiar soft fibrous ssue—a kind of undeveloped connective tissue, with long nuclei osely resembling unstriped muscle (C, fig. 463)—or *stroma*, abundantly pplied with blood-vessels, and having embedded in it, in various stages development, numerous minute follicles or vesicles, the **Graafian llicles**, or sacculi, containing the ova (fig. 463).

If the ovary be examined at any period between early infancy and vanced age, but especially during that period of life in which the wer of conception exists, it will be found to contain a number of ese vesicles. Immediately after the tunica albuginea (fig. 463) they e small and numerous, either arranged as a continuous layer, as in the t or rabbit, or in groups, as in the human ovary. These small follicles embedded in the soft stroma of fine connective tissue and unstriped muscle form here the *cortical layer;* they are sometimes called *ovisacs.*

Each of the small follicles of this layer has an external membranous envelope, or *membrana propria.* This envelope or tunic is lined with a layer of nucleated cells, forming a kind of epithelium or internal tunic, and named the *membrana granulosa.* The cavity of the follicle is filled up by a nucleated mass of protoplasm inclosed in a very delicate membrane, which is the **Ovum.** The large spherical nucleus contains one or more nucleoli. The nucleus is known as the *germinal vesicle,* and the nucleolus as the *germinal spot.*



Fig. 463.—Section of the ovary of a cat. A, germinal epithelium; B, immature Graafian follicle; C, stroma of ovary; D, vitelline membrane containing the ovum; E, Graafian follicle showing lining cells; F, follicle from which the ovum has fallen out. (V. D. Harris.)

The central portion of the stroma of the ovary extends from the cortical layer to the hilum of the organ, at which enter the numerous arteries, fibrous tissue, and unstriped muscle, forming a highly vascular zona vasculosa. Within this central zone are contained the fully-developed Graafian follicles, varying in size however, but considerably larger than those of the cortical layer. In these follicles the cavity is not nearly filled by the ovum, which is attached at one side to the zona granulosa by a collection of small cells, the *discus proligerus,* the remainder of the cavity being filled with fluid, the *liquor folliculi.* The envelope of the ovum, or *zona pellucida,* is much thicker. The *zona granulosa* is formed of several layers of cells, instead of one only. Its membrana propria is much thicker, so as to form a distinct fibrous investment; the *membrana fibrosa* and the blood-vessels surrounding it are numerous, and may be said to form a *membrana vasculosa* about it.

The human ovum measures about $\frac{1}{120}$ of an inch (about .2 mm.) in diameter. Its external investment, or the *zona pellucida,* or *vitelline* *mbrane*, is a transparent membrane, about $\frac{1}{2500}$ of an inch (10$\mu$) in ickness, which under the microscopic appears as a bright ring (fig. 4), bounded externally and internally by a dark outline. Within this ansparent investment or zona pellucida, and usually in close contact th it, lies the *yolk or vitellus*, which is composed of granules and glob- es of various sizes, imbedded in a more or less fluid substance. The naller granules, which are the more numerous, resemble in their appear- nce, as well as their constant motion, pigment-granules. The larger ranules or globules, which have the aspect of fat-globules, are in reatest number at the periphery of the yolk. The number of the gran- les is greatest in the ova of carnivorous animals. In the human ovum heir quantity is comparatively small.

In the substance of the yolk is imbedded the *germinal vesicle*, or ves- cula germinativa, $\frac{1}{500}$ of an inch (.05 mm.) (fig. 464). The vesicle is of reatest relative size in the smallest ova, and is in them surrounded losely by the yolk, nearly in the centre of which it lies. During the evelopment of the ovum, the germinal vesicle increases in size much less apidly than the yolk, and comes to be placed near to its surface. It onsists of a fine, transparent, structureless membrane, containing a clear, atery fluid, in which are sometimes a few granules; and at that part of he periphery of the germinal vesicle which is nearest to the periphery of he yolk is situated the *germinal spot*, or macula germinativa, of a finely ranulated appearance and of a yellowish color, strongly refracting the ys of light.


Nucleus or germinal vesicle.
Nucleolus or germinal spot.
Space left by retraction of yolk.
Yolk or vitellus.
Vitelline membrane.

g. 464.—Semidiagrammatic representation of a human ovum, showing the parts of an animal cell. (Cadiat.)

Such are the parts of which the Graafian follicle and its contents, cluding the ovum, are composed. With regard to the mode and order f development of these parts there is considerable uncertainty.

The Graafian follicles are formed in the following manner:—The em- ryonic ovary is covered with short columnar cells, or the so-called germ- al epithelium. The cells of this layer undergo proliferation, so as to rm several strata, and grow into the ovarian stroma as longer or shorter

columns or tubes. By degrees these tubes bec
epithelium, and form cell nests, small, if ne
the depth of the stroma. The nests increase
of their cells, and may even give off new nests
them in various directions. Certain of t
epithelium enlarge, and form ova; and the f
place in the nests within the stroma. The o
by division. The small cells of a nest surrou
membrana granulosa, and the stroma growing
ova into so many Graafian follicles. The oth
brana fibrosa and the membrana vasculosa, ar

The smallest follicles are formed at the su
tical layer. It is said by some that the super
become more deeply placed in the ovarian st
they increase in size, they make their way tow

When mature, they form little prominen
ovary, covered only by a thin layer of condens
lium. Only a few follicles ever reach maturi

From the earliest infancy, and through th
life, there appears to be a constant formation,



Fig. 465.—Germinal epithelium of the surface of the ovary
blasts; *b*, larger ovoblasts. (C

tion of Graafian vesicles, with their contained
puberty, however, the process is comparativel
this period, the ovaries are small and pale, th
are very minute, and probably never attain
shrivel and disappear, instead of bursting,
the contained ova are also incapable of being
cident with the other changes which occur
puberty, the ovaries enlarge, and become ve
of Graafian vesicles is more abundant, the size
attained by them are greater, and the ova ar
dated.

The **Fallopian Tubes** (*Oviducts*).—The
four inches in length (10 cm.), and extend b

er angles of the uterus. At the point of attachment to the uterus, tube is very narrow; but in its course to the ovary it increases to t an eighth of an inch (3 mm.) in thickness; at its distal extremity, h is free and floating, it bears a number of *fimbriæ*, one of which, er than the rest, is attached to the ovary. The canal by which each is traversed is narrow, especially at its point of entrance into the us, at which it will scarcely admit a bristle; its other extremity is er, and opens into the cavity of the abdomen, surrounded by the zone mbriæ. Externally, the Fallopian tube is invested with peritoneum; rnally, its canal is lined with mucous membrane, which is apt to be wn into numerous longitudinal folds, covered with ciliated epithe-: between the peritoneal and mucous coats the walls are composed, those of the uterus, of fibrous tissue and unstriped muscular fibres, fly circular in arrangement.

The **Uterus.**—The uterus (*u. c*, fig. 461) is a somewhat pyriform ed organ, and in the unimpregnated state is about three inches (7.5 in length, two (5 cm.) in breadth at its upper part or *fundus*, but at ower pointed part, *neck* or *cervix*, only about half an inch (1.25 cm.). part between the fundus and neck is termed the *body* of the us: it is about an inch (2.5 cm.) in thickness.

*Structure.*—The uterus is constructed of three principal layers, or s—serous, fibrous and muscular, and mucous. (*a*) The *serous* coat, h has the same general structure as the peritoneum, covers the n before and behind, but is absent from the front surface of the . (*b*) The *middle* coat is composed of unstriped muscle, arranged he human uterus in three layers from without inward, longitudinal, lar, oblique and circular. They become enormously developed dur-pregnancy. The arteries and veins are found in large numbers in outer part of their coat, so as to form almost a special vascular coat.

The *mucous* membrane of the uterus is lined by columnar ciliated elium, which extends also to the interior of the tubular glands, of h the mucous membrane is largely made up.

n the cervix uteri the mucous membrane is arranged in permanent itudinal folds, *palmæ plicatæ*. The glands of this part are of the lo-racemose type, branching repeatedly and extending deeply into substance of the cervix. They are lined by columnar epithelium, open on the ridges and furrows of the mucous membrane. They te a thick glairy mucus, resembling unboiled white of egg.

The mucous membrane of the cavity of the body of the uterus s a thin membrane about $\frac{1}{25}$ inch (1 mm.) thick, and is covered on its ce by columnar ciliated epithelium. Imbedded in its substance are erous simple tubular glands set somewhat obliquely and lined with nnar ciliated epithelium. These glands often bifurcate at their

cm.) long, extending obliquely downward and forward
of the uterus, which it embraces, to the external organs
It is lined with mucous membrane, covered with strat
epithelium, which in the ordinary contracted state of the
into transverse folds. External to the mucous membra
the vagina are constructed of unstriped muscle and
within which in the submucosa, especially around the lo
tube, is a layer of erectile tissue. This exists also in the
lower extremity of the vagina is embraced by an orbicu
*sphincter vaginæ;* its external orifice, in the virgin, is pa
a fold or ring of mucous membrane, termed the *hymen.*
organs of generation consist of the *clitoris*, a small e
situated above and in the middle line, and constructed
masses or corpora cavernosa. They are not perforated b
of two folds of mucous membrane, termed *labia interna*, o
in front of these,of two other folds, the *labia externa*, or *p*
of the external integument, and lined internally by muc
Between the nymphæ and beneath the clitoris is an angul
the vestibule, at the centre of whose base is the orifice
*urinarius.* Numerous mucous follicles are scattered bene
membrane composing these parts of the external organs
and at the side of the lower part of the vagina are two l
glands, vulvo-vaginal or Duverney's glands, which are an
per's glands in the male. The ducts of these glands ar
(12.5 mm.) long and open immediately external to the

well as the urine is discharged. The *Prostate gland*, the ion of which is not understood, is generally included in the

estes.—The secreting structure of the testicle and its duct d of in two contiguous, parts (1) the body of the testicle proper, ithin a thick and tough white fibrous membrane, the *tunica* on the outer surface of which is the serous covering formed by *vaginalis*, and (2) the *epididymis* and *vas deferens.*

**as deferens,** or duct of the testicle, which is about two feet in length, is constructed externally of connective tissue, and is lined by a mucous membrane, covered with columnar epithe- le between these two coats is a middle coat, very firm and tough, f unstriped muscle, chiefly arranged longitudinally, but also some circular fibres. When followed back to its origin, the as is found to pass to the lower part of the *epididymis*, with

Fig. 466.



Fig. 467.

Plan of a vertical section of the testicle, showing the arrangement of the ducts. h and diameter of the ducts have been disregarded. *a a*, tubuli seminiferi coiled rate lobes; *b*, tubuli recti or vasa recta; *c*, rete testis; *d*, vasa efferentia ending culosi; *l*, *e*, *g*, convoluted canal of the epididymis; *h*, vas deferens; *f*, section of of the tunica albuginea; *i*, *i*, fibrous processes running between the lobes; *s*, me-

Section of the epididymis of a dog.—The tube is cut in several places, both trans- liquely; it is seen to be lined by a ciliated epithelium, the nuclei of which are c, connective tissue. (Schofield.)

directly continuous (fig. 466), and assumes there a much smaller ith an exceedingly tortuous course.

**pididymis,** which is lined, except at its lowest part, by columnar ciliated epithelium (fig. 466), is commonly described as consisting (fig. 466) of a *globus minor* (*g*), the *body* (*e*), and the *globus major* (*l.*) When unravelled it is found to be constructed of a single tube, measuring about twenty feet in length.

At the globus major this duct divides into ten or twelve small branches, the convolutions of which form coniform masses, named *Coni vasculosi;* and the ducts continued from these, the *Vasa efferentia*, after anastomosing, one with another in what is called the *Rete testis*, lead finally as the *Tubuli recti* or *Vasa recta* to the seminal tubules (*tubuli seminiferi*), which form the proper substance of the testicle. The epithelium lining the coni vasculosi and vasa efferentia is columnar and ciliated; that of the rete testis is squamous.

The seminal tubules are arranged in lobules, separated from one another by incomplete fibrous septa or cords, which pass from the front of the tunica albuginea internally to a firm incomplete vertical septum of thick extending fibrous tissue at the posterior border, from the upper to near the lower part, called the *corpus Highmori*, or *mediastinum testis*. Through this very firm fibrous tissue pass the seminal tubes from the vasa recta. The tunica albuginea is covered by a very fine plexus of blood-vessels internally, derived from the spermatic vessels. The fibrous cords which may contain unstriped muscle are also covered with a similar capillary plexus.

*Tubuli Seminiferi.*—The seminal tubes, which compose the parenchyma of the testicle, are loosely arranged in lobules between the connective tissue septa.

They are relatively large, very wavy, and much convoluted; and they possess a few lateral branches, by which they become connected into a network. They form terminal loops, and in the peripheral portion of the testis the tubules are possessed of minute lateral cæcal branchlets.



Fig. 468.—From a section of the testis of dog, showing portions of seminal tubes. A, seminal epithelial cells, and numerous small cells loosely arranged; B, the small cells or spermatoblasts converted into spermatozoa; groups of these in a further stage of development. (Klein.)

Each seminal tubule in the adult testis is limited by a membrana ropria, which appears as a hyaline elastic membrane, but which is eally made up of several incomplete layers of flattened cells, containng oval flattened nuclei at regular intervals. Inside this membrana ropria are several layers of epithelial cells, the *seminal cells* (fig. 468). hese consist of two or more layers, the outermost being situated next he membrana propria. These cells are of two kinds, those that are in



Fig 469.—Section of a tubule of the testicle of a rat, to show the formation of the spermtozoa; *a* spermatozoa; *b*, seminal cells; *c*, spermatoblasts, to which the spermatozoa are still herent; *d*, membrana propria; *e*, fibro-plastic elements of the connective tissue. (Cadiat.)

resting state, which generally form a complete layer, and those that re in a state of division, of which there may be two layers. The latter re called mother cells, and the smaller cells resulting from their division re called daughter cells or spermatoblasts. From these the spermazoa are formed, their head corresponding with the nuclei of the aughter cells; and during their development they lie in groups (figs. 68,469), and are supported by irregular masses of so-called nutritive lls; but when fully formed, they become detached, and fill the lumen the seminiferous tubule (fig. 469). This detachment is effected by e liquefaction of the nutritive cells in which the groups of spermatozoa e imbedded.

In the fine connective tissue which supports the tubules of the testis, e to be found flattened and nucleated epithelial cells, probably the mains of the Wolffian body. The lymphatics of the testes are numers, and may be injected by inserting the needle of an injecting syringe to the tunica albuginea, and pressing in the injection with slight ort.

The **Vesiculæ Seminales.**—The vesiculæ seminales have the appearce of outgrowths from the vasa deferentia. Each vas deferens, just

before it enters the prostate gland, through
terminate in the urethra, gives off a side
from it at an acute angle: and this branch di
and pursuing in both itself and its branche
the vesicula seminalis.

*Structure.*—Each vesicula may be unravel
tube sacculated, convoluted, and folded up.

The structure resembles closely that of
mucous membrane, like that of the gall-blac
and set with folds and ridges arranged so as
lated appearance.

**The Penis.**—The penis is composed o
cylindrical masses, inclosed in remarkabl



Fig. 470.—Dissection of the base of the bladder and prc
seminales and vasa deferentia. *a*, lower surface of the blad
peritoneum; *b*, the part above covered by the peritoneum; *i*,
ejaculatory duct; the vas deferens has been divided near
tion has been taken away; *s*, left vesicula seminalis joining
deferens and right vesicula seminalis, which has been unrav
gland; *m*, part of the urethra; *u*, *u*, the ureters (cut sh
(Haller.)

which two, the *corpora cavernosa*, are alik
together, and receive below and between then
*spongiosum*. The urethra passes through the
penis is attached to the symphysis pubis by it
tremity or glans penis is continuous with the
integument covering the penis forms a loose
the glans with the body, called the *prepuce* or

*ture.*—(*a.*) *The urethra* is lined by stratified pavement epithe- the prostatic portion; in front of the bulb the epithelium columnar, while at the fossa navicularis it is again lined ıtified pavement epithelium. The mucous membrane consists fibrous connective-tissue, intermixed with which are many elastic [t is surrounded by unstriped muscular tissue. In the inter-



.—Erectile tissue of the human penis. *a*, fibrous trabeculæ with their ordinary *b*, section of the venous sinuses; *c*, muscular tissue. (Cadiat.)

portion many large veins run amongst the bundles of muscular Many mucous glands, *glands of Littré*, are present.

*The corpora cavernosa*, a true erectile structure, are surrounded se fibrous and elastic sheath, and from the inner surface of this, ı the septum which separates the two corpora cavernosa, pass s bundles of fibrous, elastic, and plain muscular fibres, called , and these by their anastomosis form a series of irregular These spaces are lined with endothelium, and are filled with lood. The inter-trabecular spaces or sinuses of one corpus ım anastomose with those of the other, especially in front where ing septum is incomplete.

[he corpus spongiosum urethræ consists of an inner portion or longitudinal veins, and of an outer or really cavernous portion in structure with that which has just been described. *The* *:s* of the penis are very numerous, both superficially and also he urethra. They join the inguinal glands.

*ıerves*, derived from the pudic nerves and hypogastric plexus, ibuted to the skin and mucous membrane and to the corpora ı and spongiosum respectively. The nerves are provided with s and Pacinian corpuscles in the glans penis, and form also a »epithelial plexus.

*er's glands* are two small glands, the ducts of which open into

*Relation of Menstruation to the Discharge of Ova.*—The human female is subject to the same law as the females of other mammiferous animals; her ova are matured and discharged from the ovary *independent of sexual union.* This maturation and discharge occur, moreover, periodically at or about the epochs of menstruation.

The evidence of the periodical discharge of ova at the menstrual periods is that in most cases in which signs of menstruation have been found in the uterus, follicles in a state of maturity or of rupture have been seen in the ovary; and although conception is not confined to the periods of menstruation, yet it is more likely to occur about a menstrual epoch than at other times.

The exact relation between the discharge of ova and menstruation is not very clear. It was formerly believed that the monthly flux was the result of a congestion of the uterus arising from the enlargement and rupture of a Graafian follicle; but though a Graafian follicle is, as a rule, ruptured at each menstrual epoch, yet several instances are recorded in which menstruation has occurred where no Graafian follicle can have been ruptured, and on the other hand cases are known where ova have been discharged in amenorrhæic women. It must therefore be admitted that menstruation is not dependent on the maturation and discharge of ova.

It was, moreover, formerly understood that ova were discharged toward the close or soon after the cessation of a menstrual flow. Observations made after death, and facts obtained by clinical investigation, however, do not support this view. Rupture of a Graafian follicle does not happen on the same day of the monthly period in all women. It may occur toward the close or soon after the cessation of a flow; but only in a small minority of the subjects examined after death was this the case. On the other hand, in almost all such subjects of which there is record, rupture of the follicle appears to have taken place before the commencement of the catamenial flow. Moreover, the custom of the Jews—a prolific race, to whom by the Levitical law sexual intercourse during the week following menstruation was forbidden—militates strongly in favor of the view that conception usually occurs before and not soon after a menstrual epoch, and necessarily, therefore, for the view that ova are usually discharged before the catamenial flow. This, together with the anatomical condition of the uterus just before the catamenia, seems to indicate that the ovum fertilized is that which is discharged in connection with the first absent, and not that with the last present menstruation.

Though menstruation does not appear to depend upon the discharge of ova, yet the presence of the ovaries seems necessary for the performance of the function; for women do not menstruate when both ovaries

The muscular tissue of the prostate not only forms the chief part of
e stroma of the gland, but also forms a continuous layer inside the
rous sheath, as well as a layer surrounding the urethra, which is con-
ous with the sphincter vesicæ.

## PHYSIOLOGY OF THE SEXUAL ORGANS.

**Of the Female.**—In the process of development in the ovary of
ividual Graafian vesicles, it has been already observed, that as each
reases in size, it gradually approaches the surface of the ovary, and
en fully ripe or mature, forms a little projection on the exterior.
incident with the increase in size, caused by the augmentation of its
uid contents, the external envelope of the distended vesicle becomes
y thin and eventually bursts. By these means, the ovum and fluid
ntents of the vesicle are liberated, and escape on the exterior of the
ry, whence they pass into the Fallopian tube or oviduct, the fimbri-
d processes of the extremity of which are supposed coincidentally to
sp the ovary, while the aperture of the tube is applied to the part
responding to the matured and bursting vesicle.

In animals whose special capability of being impregnated occurs at
ular periods, as in the human subject, and most mammalia, the
aafian vesicles and their contained ova appear to arrive at maturity,
l the latter to be discharged at such periods only. But in other
imals, *e.g.*, the common fowl, the formation, maturation, and dis-
rge of ova appear to take place almost constantly.

It has long been known, that in the so-called oviparous animals, the
aration of ova from the ovary may take place independently of im-
gnation by the male, or even of sexual union. And it is now
ablished that a like maturation and discharge of ova, independently
coition, occurs in mammalia, the periods at which the matured ova
separated from the ovaries and received into the Fallopian tubes
ng indicated in the lower mammalia by the phenomena of *heat* or
in the human female, although not always with exact coincidence,
the phenomena of *menstruation*. If the union of the sexes take
ce, the ovum may be fecundated, and if no union occur it perishes.

That this maturation and discharge occur periodically, and only
ing the phenomena of heat in the lower mammalia, is made probable
the facts that, in all instances in which Graafian vesicles have been
nd presenting the appearance of recent rupture, the animals were at
time, or had recently been, in heat; that on the other hand, there is no
hentic and detailed account of Graafian vesicles being found ruptured
the intervals of the period of heat; and that female animals do not
nit the males, and never become impregnated, except at those periods.

the second part of the urethra. They are small round bodies, of the size of a pea, yellow in color, resembling the sublingual gland; in structure they are compound tubular mucous glands.

The **Prostate Gland.**—The prostate is situated (fig. 470) at the neck of the urinary bladder, and incloses the commencement of the urethra. It is somewhat chestnut-shaped. It measures an inch and a half in breadth, and an inch and a quarter long, and half an inch in thickness.

*Structure.*—The prostate is made up of small compound tubular glands imbedded in an abundance of muscular fibres and connective tissue.

The glandular substance, which is nearly absent from the front part of the organ, consists of numerous small saccules, opening into elongated ducts, which unite into a smaller number of excretory ducts. *The acini* of the upper part of the prostate are small and hemispherical; while in the middle and lower parts the tubes are longer and more convoluted. The acini are of two kinds, namely, those ($a$) lined with a single layer of thin and long columnar cells, each with an oval nucleus in outer part of wall; and those ($b$) acini resembling the foregoing, but with a second layer of small cortical, polyhedral, or fusiform cells between the membrana propria and the columnar cells. *The ducts*, twelve to twenty in number, open into the urethra. They are lined by a layer of columnar cells, beneath which is a layer of small polyhedral cells.



Fig. 472.—Section of a small portion of the prostate. $a$, gland duct cut across obliquely; $b$, gland structure; $c$, prostatic calculus. (Cadiat.)

The tunica adventitia consists of dense fibrous tissue of two layers, between which is situated a plexus of veins. Large *vessels* pass into the interior of the organ, to form a broad, meshed, capillary s
with numerous large ganglion-cells surround the co
bodies are sometimes found in the substance of the orga

lobules projecting from the opposite walls of the Graafian follicle appear in a section to be separated by the thinnest possible lamina of semi-transparent tissue.

When a follicle is about to burst and expel the ovum, it becomes highly vascular and opaque; and, immediately before the rupture takes place, its walls appear thickened on the interior by a reddish glutinous or fleshy-looking substance. Immediately after the rupture, the inner layer of the wall of the vesicle appears pulpy and flocculent. It is thrown into wrinkles by the contraction of the outer layer, and, soon, red fleshy mammillary processes grow from it, and gradually enlarge till they nearly fill the vesicle, and even protrude from the orifice in the external covering of the ovary. Subsequently this orifice closes, but the fleshy growth within still increases during the earlier period of pregnancy, the color of the substance gradually changing from red to yellow, and its consistence becoming firmer.

The human corpus luteum (fig. 476) differs from that of the domestic quadruped in being of a firmer texture, and having more frequently a persistent cavity at its centre, and in the stelliform cicatrix, which remains in the cases where the cavity is obliterated, being proportionately of much larger bulk. The quantity of yellow substance formed is also much less: and although the deposit increases after the vesicle has burst, yet it does not usually form mammillary growths projecting into the cavity of the vesicle, and never protrudes from the orifice, as is the case in other Mammalia. It maintains the character of a uniform, or nearly uniform, layer, which is thrown into wrinkles, in consequence of the contraction of the external tunic of the vesicle. After the orifice of the vesicle has closed, the growth of the yellow substance continues during the first half of pregnancy, till the cavity is reduced to a comparatively small size, or is obliterated; in the latter case, merely a white stelliform cicatrix remains in the centre of the corpus luteum.



Fig. 476.—Corpora lutea of different periods. B, corpus luteum of about the sixth week after impregnation, showing its plicated form at that period. 1, substance of the ovary; 2, substance of the corpus luteum; 3, a grayish coagulum in its cavity. (Paterson.) A, corpus luteum two days after delivery; D, in the twelfth week after delivery. (Montgomery.)

An effusion of blood generally takes place into the cavity of the follicle at the time of its rupture, especially in the human subject, but it has no share in forming the yellow body; it gradually loses its coloring matter. The serum of the blood sometimes remains included within a cavity in the centre of the coagulum, and then the decolorized fibrin forms a membraniform sac, lining the corpus luteum. At other times the serum is removed, and the fibrin constitutes a solid stelliform mass.

The yellow substance of which the corpus luteum consists, both in the human subject and in the domestic animals, is a growth from the inner surface of the ruptured follicle, the result of an increased development of the membrana granulosa.

The first changes of the internal coat of the Graafian vesicle in the process of formation of a corpus luteum seem to occur in every case in which an ovum escapes; as well in the human subject as in the domestic quadrupeds. If the ovum is impregnated, the growth of the yellow substance continues during nearly the whole period of gestation and forms the large corpus luteum commonly described as a characteristic mark of impregnation. If the ovum is not impregnated, the growth of yellow substance on the internal surface of the vesicle proceeds, in the human ovary, no further than the formation of a thin layer, which shortly disappears; but in the domestic animals it continues for some time after the ovum has perished, and forms a corpus luteum of considerable size. The fact that a structure, in its essential characters similar to, though smaller than, a corpus luteum observed during pregnancy, is formed in the human subject, independent of impregnation or of sexual union, coupled with the varieties in size of corpora lutea formed during pregnancy, necessarily renders unsafe all evidence of previous impregnation founded on the existence of a corpus luteum in the ovary.

The following table by Dalton, expresses well the differences between the corpus luteum of the pregnant and unimpregnated condition respectively:—

| | **Corpus Luteum of Menstruation.** | **Corpus Luteum of Pregnancy.** |
|---|---|---|
| *At the end of three weeks* | Three-quarters of an inch in diameter; central clot reddish; convoluted wall pale. | |
| *One month* . | Smaller; convoluted wall bright yellow; clot still reddish. | Larger; convoluted wall bright yellow; clot still reddish. |
| *Two months* | Reduced to the condition of an insignificant cicatrix. | Seven-eighths of an inch in diameter; convoluted wall bright yellow; clot perfectly decolorized. |
| *Six months* . | Absent. | Still as large as at end of second month; clot fibrinous; convoluted wall paler. |
| *Nine months* | Absent. | One-half an inch in diameter; central clot converted into a radiating cicatrix; the external wall tolerably thick and convoluted but without any bright yellow color. |

**Of the Male.**—In order that the ovum should be fecundated, it is necessary that it should meet with the seminal fluid of the male. This is accomplished by the junction of the sexes in the act of coition, whereby the seminal fluid is discharged into the neighborhood of, if not within, the cervix uteri. Before considering the changes which are produced in the ovum by impregnation, it will be as well to describe the nature of the seminal fluid. This consists essentially of the semen secreted by the *testes*, and to this are added a material secreted by the vesiculæ seminales, as well as the secretion of the prostate gland, and of Cowper's glands. Portions of these several fluids are discharged, together with the proper secretion of the testicles.

The semen is a viscid, whitish, albuminous fluid of a peculiar odor. It contains epithelium, granules or colorless particles, and large numbers of *spermatozoa*, which are the characteristic and essential elements.





Fig. 477.

Fig. 478.

Fig. 477.—Spermatic filaments from the human vas deferens. 1, magnified 300 diameters; 2, magnified 800 diameters; *a*, from the side; *b*, from above. (From Kölliker.)

Fig. 478.—Spermatozoa. 1, Of salamander; 2, human. (H. Gibbes.)

The spermatozoa are minute bodies each consisting of a flattened oval head and attached to it a long slender tapering mobile flagellum or tail.

In some forms of spermatozoa there is a small middle piece interposed between the head and the tail. The head is about $\frac{1}{6000}$th inch (about 4$\mu$) long and $\frac{1}{10000}$th inch (about 2.5$\mu$) broad. The tail is about $\frac{1}{5000}$th to $\frac{1}{4000}$th inch (5$\mu$–6$\mu$) long. The spermatozoa possess the power of active movement, and it is by this sinuous, cilia-like movement that they are propelled in the female and so helped in their progress to meet the ovum. The lashing cilium-like movement of a spermatozoon may go on for hours or days in the alkaline fluids of the body. It is stopped by any of the agencies which stop ciliary movement, *e.g.*, acids, or strong alkalies, alcohol, chloroform, cold to 0° C., and heat above 50° C.

On examining the spermatozoon of Triton cristatus, one of the amphibia which possess the largest spermatozoa of all vertebrate animals, H. Gibbes found that the organism consisted of (*a*) a long pointed head, at the base of which is (*b*), an elliptical structure joining the head to (*c*), a long filiform body; (*d*), a fine filament, much longer than the body, is connected with this latter by (*e*), a homogeneous membrane.

The head, as it appears in the fresh specimen, has a different refractive power from that of the rest of the organism, and with a high power appears to be a light green color; there is also a central line running up it, from which it appears to be hollow.

The elliptical structure at the base of the head connects it with the long threadlike body, and the filament springs from it.

While the spermatozoon is living, this filament is in constant motion; at first this is so quick that it is difficult to see it, but as its vitality becomes impaired the motion gets slower, and it is then easily perceived to be a continuous waving from side to side.

The spermatozoa of all mammalia examined, consisting of *man*, *bull*, *dog*, *horse*, *cat*, *pig*, *mouse*, *rat*, *guinea-pig*, had instead of the long-pointed head of the amphibian, a blunt thick process of different shapes in the different animals; and from the root or neck of this proceeded the long filament just as in the amphibia, only so delicate as to be invisible except with very high powers.

In man the head (fig. 478) is club-shaped, and from its base springs the very delicate filament, which is three or four times as long as the body; and the membrane which attaches it to the body is much broader, and allows it to lie at a greater distance from the body than in the spermatozoa of any other Mammal examined.

From his investigation, Gibbes concluded:—1st, that the head of the spermatozoon is inclosed in a sheath, which is a continuation of the membrane which surrounds the filament, and connects it to the body, acting in fact the part of a mesentery. 2ndly. That the substance of the head is quite distinct in its composition from the elliptical structure, the filament and the long body, and that it is readily acted on by alkalies; these reagents have no effect, however, on the other part, exempting the membraneous sheath. 3rdly. That this elliptical structure has its analogue in the mammalian spermatozoon; in the one case the head is drawn out as a long pointed process, in the other it is of a globular form, and surrounds the elliptical structure. 4thly. That the motive power lies, in a great measure, in the filament and the membrane attaching it to the body.

The spermatozoa are derived from the breaking up of the seminal ells or daughter cells. They must be looked upon as modified cells.

The occurrence of spermatozoa in the impregnating fluid of nearly ll classes of animals, proves that they are essential to the process of mpregnation, and their actual contact with the ovum is necessary for ts development.

The seminal fluid is, probably, after the period of puberty secreted constantly, though, except under excitement, very slowly, in the tubules of the testicles. From these it passes along the vasa deferentia into the vesiculæ seminales, whence, if not expelled in emission, it may be discharged, as slowly as it enters them, either with the urine, which may remove minute quantities, mingled with the mucus of the bladder and the secretion of the prostate, or from the urethra in the act of defæcation.

To the vesiculæ seminales a double function may be assigned; for they both secrete some fluid to be added to that of the testicles, and serve as reservoirs for the seminal fluid. The former is their most constant and probably most important office; for in the horse, bear, guinea-pig, and several other animals, in whom the vesiculæ seminales are large and of apparently active functions, they do not communicate with the vasa deferentia, but pour their secretions, separately, though it may be simultaneously, into the urethra.

There is a complete want of information respecting the nature and purposes of the secretions of the prostate and Cowper's glands. That they contribute to the right composition of the impregnating fluid, is shown both by the position of the glands and by their enlarging with the testicles at the approach of an animal's breeding time. But that they contribute only a subordinate part is shown by the fact, that, when the testicles are lost, though these other organs be perfect, all procreative power ceases.

The fluid part of the semen or liquor seminis has not been satisfactorily analyzed: but Henle says it contains fibrin, because shortly after being discharged, flocculi form in it by spontaneous coagulation, and leave the rest of it thinner and more liquid, so that the filaments move in it more actively. The chief constituents of the semen are said to be a variety of *nuclein*, which does not contain sulphur; certain *proteids*, one of which contains four per cent. of sulphur; *lecithin; cholesterin; fat*, and *extractives*.

# CHAPTER XIX.

## DEVELOPMENT.

### Changes which occur in the Ovum.

Of the changes which take place in the ovum, some occur before and are as it were preparatory to impregnation, and others ensue after impregnation. It will be as well to consider the respective changes separately.

*Changes prior to Impregnation.*—These changes especially concern the germinal vesicle, and have been observed chiefly in the ova of low types. The ovum when ripe and detached from the ovary consists, it will be remembered, of a granular yolk inclosed within the protoplasmic zona pellucida, and containing the germinal vesicle and germinal spot situated eccentrically. The yolk granules are of different sizes, from the minutest molecules up to a diameter of $\frac{1}{1000}$th to $\frac{1}{1500}$th of an inch (about $25\mu$). The germinal vesicle consists of reticulated protoplasm inclosed in a distinct membrane, and containing one or more nucleoli or germinal spots. The primary change observed in the ovum consists in the travelling of the germinal vesicle to the surface, and the disappearance of its inclosing membrane, with a consequent indentation and indistinctness of its outline. Its protoplasm becomes to a considerable extent confounded with the yolk substance, and its germinal spot disappears. The next step in the process is the appearance in the yolk of two *stars* in a clear space near the poles of the vesicle elongated to a certain extent, and from this results a *nuclear spindle*, with the stars at either end lying near the surface of the yolk. This spindle next becomes vertical, the nucleus divides into two parts, and that nearer the surface protrudes from the ovum enveloped in a protoplasmic mass, which by constriction forms the first *polar cell.* A second polar cell arises in the same way. The remaining daughter nucleus again divides—one-half of it is extruded from the ovum, forming a second polar cell; the other half remains behind and is called the *female pro-nucleus.* This is clearly derived from the original germinal vesicle. It must be remembered that these changes have been so far observed only in a certain number of instances. It is very possible, not to say probable, that such changes are universal in the animal kingdom (Balfour).

Balfour's view as to the formation of the polar bodies may be given his own words:—" My view amounts to the following, viz., that after e formation of the polar-cells, the remainder of the germinal vesicle thin the ovum (the female pro-nucleus) is incapable of further devel- ment without the addition of the nuclear part of the male element permatozoon), and that if polar-cells were not formed, parthenogenesis ight normally occur."

**Changes following Impregnation.**—The process of impregnation the ovum has been observed most accurately in the lower types. In ammalia, although spermatozoa pass in numbers through the yolk velope, yet their further progress is only inferred from observations on e lower animals. The process in *asterias glacialis*, according to Bal- ur, is as follows:—The head of a single spermatozoon joins with an evation of the yolk substance, the tail remaining motionless, and then isappearing. The head enveloped in the protoplasm then sinks into the olk and becomes a nucleus, from which the yolk substance is arranged n radiating lines. This is the *male pro-nucleus*. At first, at some dis- ance from the female pro-nucleus, it after a while approaches nearer, nd the female pro-nucleus, which was before inactive, becomes active. The nuclei at last meet and unite. The result of their union is the *first gmentation sphere*, or *blasto-sphere*. It is a nucleated protoplasmic cell. he changes which have resulted in the formation of the blasto-sphere r primitive segmentation germ are followed by the process known as gmentation of the yolk.

This process and the earlier stages in development are so fundamen- lly similar in all vertebrate animals, from fishes up to man, that the ps existing in our knowledge of the process in the higher mammalia, ch as man, may be, in part, at any rate, filled up by the more accu- te knowledge which we possess of the development of the ovum in ch animals as the trout, frog, and fowl.

One important distinction between the ova of various vertebrata should be membered. In the hen's egg, besides the shell and the white or albumen, two her structures are to be distinguished—the *germ*, often called the cicatricula r "tread," and the *yolk*, inclosed in its vitelline membrane.

The *germ* is (as was mentioned in the description already given) essentially cell, consisting of protoplasm inclosing a nucleus and nucleolus. It alone articipates in the process of *segmentation*, the great mass of the yolk (food- olk) remaining quite unaffected by it. Since only the germ, which forms but small portion of the yolk, undergoes segmentation, the ovum is called *mero- lastic*.

In the mammalia, on the other hand, there is no large unsegmented mass orresponding to the food-yolk of birds; the entire ovum undergoes segmenta- ion, and is hence termed *holoblastic*.

The eggs of fishes, reptiles, and birds, are meroblastic, while those of am- hibia and mammalia are *holoblastic*.

Of the changes which the mammalian ovum undergoes previous to

the formation of the embryo, those which occur while it is sti
ovary are independent of impregnation: others take place aft
reached the Fallopian tube. The knowledge we possess of these
is derived almost exclusively fro
vations on the ova of the bitch an
but it may be inferred that s
changes ensue in the human ovu



Fig. 479.—Diagrams of the various stages of cleavage of the yolk. (Dalton.)

As the ovum approaches the r
the Fallopian tube, it begins to
new investment, consisting of a
transparent albuminous or gluti
stance, which forms upon the e
the zona pellucida. It is at firs
ingly fine, and owing to this, a
transparency, is not easily re
but at the lower part of the
tube it acquires considerable thic

*Segmentation.*—The first visi
of fertilization is a slight amœbo
ment in the protoplasm of th
this has been observed in some fis
frog, and in some mammals. Im
succeeding to this the process of
tation commences, and is compl
ing the passage of the ovum thr
Fallopian tube. In mammals, i
the process is an example of *com*
mentation, the yolk becomes co
in the middle, and is surround
furrow which, gradually deepe
length cuts it in half, while the s
cess begins almost immediately
half of the yolk, and cuts it also
The same process is repeated in
the quarters, and so on, until at
continual cleavings, the whole
changed into a mulberry-like
small and more or less rounded
sometimes called *vitelline sphe*
whole still inclosed by the zona pellucida (fig. 479). Each of t
tle spherules contains a transparent vesicle, like an oil-globule,
seen with difficulty, on account of its being enveloped by the yol
ules which adhere closely to its surface.

The cause of this singular subdivision of the yolk is quite obscure: though the immediate agent in its production seems to be the central vesicle contained in each division of the yolk. Originally there was probably but one vesicle, situated in the centre of the entire granular mass of the yolk, and probably derived in the manner already described from the germinal vesicle. This divides and subdivides: each successive division and subdivision of the vesicle being accompanied by a corresponding division of the yolk.

About the time at which the mammalian ovum reaches the uterus, the process of division and subdivision of the yolk appears to have ceased, its substance having been resolved into its ultimate and smallest divisions, while its surface presents a uniform finely-granular aspect, instead of its late mulberry-like appearance. The ovum, indeed, appears at first sight to have lost all trace of the cleavage process, and, with the exception of being paler and more translucent, almost exactly resembles the ovarian ovum, its yolk consisting apparently of a confused mass of finely granular substance. But on a more careful examination, it is found that these granules are aggregated into numerous minute spheroidal masses, each of which contains a clear vesicle or nucleus in its centre, and is, in fact, an *embryonal cell.* The zona pellucida, and the layers of albuminious matter surrounding it, have at this time the same character as when at the lower part of the Fallopian tube.

The passage of the ovum, from the ovary to the uterus, occupies probably eight or ten days in the human female.

When the peripheral cells, which are formed first, are fully developed, they arrange themselves at the surface of the yolk into a kind of membrane, and at the same time assume a polyhedral shape from mutual pressure, so as to resemble pavement epithelium. The deeper cells of the interior pass gradually to the surface and accumulate there, thus increasing the thickness of the membrane already formed by the more superficial layer of cells, while the central part of the yolk remains filled only with a clear fluid. By this means the yolk is shortly converted nto a kind of secondary vesicle, the walls of which are composed externally of the original vitelline membrane, and within by the newly formed cellular layer, the *blastoderm* or *germinal* membrane, as it is called.

*Segmentation in the Chick.*—The embryo chick affords an illustraion of what is known as incomplete or partial segmentation, or meroblastic segmentation. In the youngest ova the germinal vesicle is situted subcentrally, but as development proceeds it passes to the periphery, nd the protoplasm surrounding it remaining free from yolk granules, he *germinal disc* is formed. This germinal disc is not marked out by ny sharp line from the remaining protoplasm, but passes insensibly nto it. The first change consists in the appearance of a furrow running across the disc dividing it into two; it does not extend across the whole breadth. A second furrow, at right angles, cutting the first a little eccentrically, next appears, and the disc is thus cut into four quadrants. The furrows do not extend through the whole thickness of the disc, and the segments are not separated out on the lower aspect. The quadrants are next bisected by radiating furrows, and the disc is thus divided into eight parts. The central portion of each segment is now cut off from the peripheral furrow, so that a number of smaller central and larger peripheral portions result. As the primary division was eccentric and the succeeding followed the same plan, there results a bilateral symmetry; but the relation of the axis of symmetry and the long axis of the embryo is not known. Rapid division of the segments by furrows in various directions now ensues, and the small central portions are more rapidly broken up than the larger, and therefore become more numerous. During this superficial segmentation a similar process goes on throughout the whole mass, and division goes on not only by vertical but also by horizontal furrows. The result of this process of segmentation is that the original germinal disc is cut into a large number of small rounded protoplasmic cells, small in the centre, larger to the periphery, and that the superficial cells are smaller than those below: the two original layers of the blastoderm are thus early represented.

The process of segmentation proceeds at the periphery of the germinal disc, and at the same time further division of the cells at the centre proceeds. The nucleus of the original cell divides coincidently with the protoplasm, and so it comes that the protoplasmic masses are nucleated; and besides this, nuclei derived from the original nucleus are found in the ovum below the area of segmentation, and from these by the protoplasm which surrounds them being constricted off with them, supplementary segmentation masses come to be formed. The blastoderm is thus formed as the result of segmentation, and between it and the subjacent white yolk is a cavity containing fluid. The segmentation having been completed toward the centre, although it still proceeds at the periphery, the superficial layer of the blastoderm becomes



Fig. 480.—Vertical section of area pellucida and area opaca (left extremity of figure) of blastoderm of a fresh-laid egg (unincubated). *S*, superficial layer corresponding to epiblast; *D*, deeper layer, corresponding to hypoblast, and probably in part to mesoblast; *M*, large "formative cells," filled with yolk granules, and lying on the floor of the segmentation cavity; *A*, the white yolk immediately underlying the segmentation cavity. (Stricker.)

a layer of columnar nucleated cells, and the lower layer consists of larger masses indistinctly nucleated, still granular and rounded, irregularly disposed. In the segmentation cavity are the supplementary segmentation masses or formative cells.

When the egg is incubated, rapid changes take place in the blastoderm, resulting in the formation first of all of two, then of the three layers, which have been already mentioned in the first chapter. The superficial, or **epiblast,** does not at first enter into these changes, but



Fig. 481.—Impregnated egg, with commencement of formation of embryo; showing the area erminativa or embryonic spot, the area pellucida, and the primitive groove or trace. Dalton.)

ontinues to be a layer of nucleated columnar cells. But in the lower ayer of larger rounded cells certain of the cells become flattened horiontally, their granules disappear, and the nuclei become distinct. A embrane of flattened nucleated cells is then formed, first of all toward he centre of the area, afterward peripherally also: this is the **hypoblast.** etween the two layers some cells, not belonging to either layer, remain. hese cells are almost entirely at the back part of the area. The foration of the intermediate layer of **mesoblast** is more complicated, nd will now be described.

At this period it is necessary to return to the surface view of the lastoderm. Before incubation it is seen to consist of a more or less ircular transparent area, the **area pellucida,** surrounded by an opaque im, which is called the **area opaca.** The area opaca rests upon the hite yolk: beneath the area pellucida is a cavity containing fluid. In he centre of the area pellucida is a white shining spot, or *nucleus of ander*, shining through. This is the upper dilated extremity of the ask-shaped accumulation of white yolk upon which the blastoderm ests.

The yellow yolk consists of spheres 25μ to 100μ in diameter, filled with ighly refractive granules of an albuminous nature, and the white yelk eing distinguished from the yellow not only by its lighter color, but lso because its vesicles are smaller than those of the yellow. Each contains a highly refractive body. Some large spheres contain a number of spherules. Some of these are vacuolated. The white yolk not only envelopes the yellow yolk in a thin layer, and merges with the central flask-shaped mass, already mentioned, but also is found in the yellow yolk, forming with it alternate layers.

Except that the central shining opacity of the pellucid area has disappeared, that the size of the area has increased, and that the opaque area has also increased, no other change can be remarked up to the formation of the two complete layers. There is, however, a slight ill-defined opacity at the posterior part of the area pellucida, known as the *embryonic shield.* This opacity is probably due to the intermediate cells already mentioned as existing between the epiblast and hypoblast.



Fig. 482.—Transverse section through embryo chick (26 hours). *a*, epiblast; *b*, mesoblast; *c*, hypoblast; *d*, central portion of mesoblast, which is here fused with epiblast; *e*, primitive groove; *f*, dorsal ridge. (Klein.)

In the posterior part of the area pellucida now appears an opaque streak which extends about a third of the diameter of the area toward the middle line. This is the **Primitive streak.** It is found on transverse section of the blastoderm in this neighborhood to be due to a proliferation downward of cells two or more deep from the epiblast. The area pellucida now becomes oval. As the primitive streak becomes more defined the area pellucida changes its oval for a pear shape, but the streak increases in size faster than the area, and so after a time is about two-thirds of its length. In the primitive streak a groove, the **primitive groove,** runs along its axis. From the primitive streak the cells from the under surface of the epiblast now extend as lateral wings to the edge of the pellucid area; they are not joined with the hypoblast. The



Fig. 483.—Diagram of transverse section through an embryo before the closing-in of the medullary groove. *m*, cells of epiblast lining the medullary groove which will form the spinal cord; *h*, epiblast; *d*, hypoblast; *ch*, notochord; *u*, protovertebra; *sp*, mesoblast; *w*, edge of lamina dorsalis, folding over medullary groove. (Kölliker.)

intermediate layer of cells in this position producing the primitive streak is a portion of the intermediate layer or **mesoblast.** It is formed chiefly from the epiblast, but laterally, especially in the front part of the primitive streak, it appears to be derived at any rate in part from the cells of the primitive lower layer. At the most anterior part of the primitive streak, at the point which corresponds to the future posterior end of the embryo, the three layers are all joined together. The next important change which occurs is found in the hypoblast in front of the primitive streak. The irregular layer of primitive cells of which it is composed, split into two layers, the lower consisting of flattened cells which forms the hypoblast proper and an upper consisting of several layers of stellate cells, the mesoblast.



Fig. 484.—Portion of the germinal membrane, with rudiments of the embryo; from the ovum of a bitch. The primitive groove, A, is not yet closed, and at its upper or cephalic end presents three dilatations, B, which correspond to the three divisions or vesicles of the brain. At its lower extremity the groove presents a lancet-shaped dilatation (sinus rhomboidalis) C. The margins of the groove consist of clear pellucid nerve-substance. Along the bottom of the groove is observed a faint streak, which is probably the chorda dorsalis. D. Vertebral plates. (Bischoff.)

In the preceding account of the formation of the blastodermic layers, Balfour's description has been chiefly followed. It differs somewhat from that which was formerly given. The mesoblast was described as arising from the hypoblast, together with some of the large formative cells, which migrate by amœboid movement round the edge of the hypoblast (fig. 485, *M*), and no difference was made in the formation of the mesoblast in the primitive streak and elsewhere.

There now appears in the middle line extending forward from the primitive streak an opaque line, which proceeds almost to the anterior edge of the area pellucida, stopping short at a transverse crescent-shaped line, the future headfold. This line is the commencing **notochord.** It is a collection of mesoblastic cells from the hypoblast in the middle line, and remains connected with the latter after the lateral portions of the mesoblast have become quite detached from it. The notochord and the hypoblast from which it arises are continued posteriorly into the primitive streak. Thus the mesoblast of the area on either side of the middle line in which the embryo is formed arises from the hypoblast, as does also the notochord. In the formation of the **medullary plate** which now appears, the epiblast is concerned. In the middle line above the collection of cells that will become the notochord that layer becomes thickened. The sides of the central thickened portion are elevated somewhat to form the **medullary folds** inclosing between them the **medullary groove.** From this medullary plate is formed the central nervous system. Although behind the groove is a shallow one, if it be traced forward it becomes deeper and narrower, and at the headfold the folds curve round and meet in the middle line. Anterior to the headfold is a second fold parallel to it, which is the commencing amnion.



Fig. 485.—Vertical section of blastoderm of chick (1st day of incubation). *S*, epiblast consisting of short columnar cells; *D*, hypoblast, consisting of a single layer of flattened cells; *M*, "formative cells." They are seen on the right of the figure, passing in between the epiblast and hypoblast to form the mesoblast; *A*, white yolk granules. Many of the large "formative cells" are seen containing these granules. (Stricker.)

The medullary canal is bounded by its two folds or longitudinal elevations, **laminæ dorsales,** which are folds consisting entirely of cells of the epiblast: these grow up and arch over the medullary groove (fig. 483) till after some time they coalesce in the middle line, converting it from an open furrow into a closed tube—the **neural canal** or the primitive cerebro-spinal axis. Over this closed tube, the walls of which consist of more or less cylindrical cells, the superficial layer of the epiblast is now continued as a distinct membrane.

The union of the medullary folds or laminæ dorsalis takes place first about the neck of the future embryo; they soon after unite over the region of the head, while the closing in of the groove progresses much more slowly toward the hinder extremity of the embryo. The medullary groove is by no means of uniform diameter throughout, but even before the dorsal laminæ have united over it, is seen to be dilated at the anterior extremity and obscurely divided by constrictions into the three primary cerebral vesicles.



Fig. 486.—Embryo chick (36 hours), viewed from beneath as a transparent object (magnified). *pl*, outline of pellucid area, *FB*, fore-brain, or first cerebral vesicle: from its sides project *op*, the optic vesicle; *SO*, backward limit of somatopleure fold, "tucked in" under head; *a*, head-fold of true amnion; *a'*, reflected layer of amnion, sometimes termed "false amnion;" *sp*, backward limit of splanchnopleure folds, along which run the omphalomesaraic veins uniting to form *h*, the heart, which is continued forward into *ba*, the bulbus arteriosus; *d*, the fore-gut, lying behind the heart, and having a wide crescentic opening between the splanchnopleure folds; *HB*, hind-brain; *MB*, mid-brain; *pv*, protovertebræ lying behind the fore-gut; *mc*, line of junction of medullary folds and of notochord; *vpl*, vertebral plates; *pr*, the primitive groove at its caudal end. (Foster and Balfour.)

The part from which the spinal cord is formed is of nearly uniform calibre, while toward the posterior extremity is a lozenge-shaped dilatation, **sinus rhomboidalis,** which is the last part to close in (fig. 484).

While the changes which have been described are taking place in the area pellucida, which has enlarged to a certain extent, the area opaca has also considerably extended. The hypoblast and mesoblast have also been prolonged laterally, not by mere extension, but also from the **germinal wall,** which is made up of the thickened edge of the blastoderm, together with formative cells of the yolk; on each side of the notochord and medullary canal, the mesoblast remains as a longitudinal thickening.

It now however splits horizontally into two layers or laminæ (*parietal* and *visceral*): of these the former, when traced out from the central axis, is seen to be in close apposition with the epiblast, and gives origin to the parietes of the trunk, while the latter adheres more or less closely to the hypoblast, and gives rise to the serous and muscular walls of the alimentary canal and several other parts.

The united *parietal* layer of the mesoblast with the epiblast is termed **somatopleure,** the united *visceral* layer and hypoblast, **splanchnopleure.** The space between them is the **pleuro-peritoneal cavity,** which becomes subdivided by subsequent partitions into pericardium, pleura, and peritoneum.

The splitting of the mesoblast extends almost to the medullary canal, but a portion on either side (*P. v.* fig. 487) remains undivided, the **vertebral plate.** The divided portion is known as the **lateral plate.** The longitudinal thickening of the vertebral plate is seen after a while to be divided at right angles to the medullary canal by bright transverse lines into a number of square segments. These seg-

ments, which are the surface appearance of c
**mesoblastic somites** or **protovertebræ.**
the protovertebræ make their appearance in
one or two more are formed in front of this
continued backward till the whole medullary



Fig. 487.—Transverse section through dorsal region of embr
section is represented; if completed it would extend as far to t
of the medullary canal (*Mc*). *A*, epiblast; *C*, hypoblast, consis
cells; *Mc*, medullary canal; *Pv*, protovertebra; *Wd*, Wolffi
splanchnopleure; *pp*, pleuro-peritoneal cavity; *ch*, notochor
blood cells; *v*, blood-vessels of the yolk-sac. (Foster and Balf

(fig. 486). That which is first formed corresp
cal vertebra. From these somites the vertebra
are derived.

*Head and Tail Folds. Body Cavity.*—Eve
sists essentially of a longitudinal axis (vertebr
canal above it, and a body-cavity (containin
beneath.

We have seen how the earliest rudiments of
neural canal are formed; we must now consid



Fig. 488.—Diagrammatic longitudinal section through the
has commenced, but the tail-fold has not yet appeared. *FSo*,
fold of the splanchnopleure; the line of reference, *Fso*, lies o
which marks off the overhanging head from the amnion; *D*,
which is to become the fore-gut: *Fso* and *Fsp*, are both parts o
left of the figure as development proceeds; *pp*, space between so
pleuro-peritoneal cavity; *Am*, commencing head-fold of amn
chord; *Ht*, heart: *A*, *B*, *C*, epiblast, mesoblast, hypoblast. (

cavity is developed. In the earliest stages the
surface of the yolk, and is not clearly marke
blastoderm: but gradually the head-fold or cr

its concavity backward) is formed in the blastoderm, limiting the head of the embryo; the blastoderm is, as it were, tucked in under the head, which thus comes to project above the general surface of the membrane: a similar tucking in of blastoderm takes place at the caudal extremity, and thus the head and tail folds are formed.

Similar depressions mark off the embryo laterally, until it is completely surrounded by a sort of moat which it overhangs on all sides, and which clearly defines it from the yolk.

This moat runs in further and further all round beneath the overhanging embryo, till the latter comes to resemble a canoe turned upside-down, the ends and middle being, as it were, decked in by the folding or tucking in of the blastoderm, while on the ventral surface there is still a large communication with the yolk, corresponding to the *well* or undecked portion of the canoe.



Fig. 489.—Diagrammatic section showing the relation in a mammal between the primitive alimentary canal and the membranes of the ovum. The stage represented in this diagram corresponds to that of the fifteenth or seventeenth day in the human embryo, previous to the expansion of the allantois; *c*, the villous chorion; *a*, the amnion; *a'*, the place of convergence of the amnion and reflection of the false amnion *a'* *a'*, or outer or corneous layer; *e*, the head and trunk of the embryo, comprising the primative vertebræ and cerebro-spinal axis; *i*, *i*, the simple alimentary canal in its upper and lower portions. Immediately beneath the right hand *i* is seen the fœtal heart, lying in the anterior part of the pleuro-peritoneal cavity; *v*, the yolk-sac or umbilical vesicle; *v i*, the vitello-intestinal opening; *u*, the allantois connected by a pedicle with the anal portion of the alimentary canal. (Quain.)

This communication between the embryo and the yolk is gradually contracted by the further tucking in of the blastoderm from all sides, till it becomes narrowed down, as by an invisible constricting band, to a mere pedicle which passes out of the body of the embryo at the point of the future umbilicus.

The downwardly folded portions of blastoderm are termed the **visceral plates.**

Thus we see that the body-cavity is formed by the downward folding of the visceral plates, just as the neural cavity is produced by the upward growth of the dorsal laminæ, the difference being that, in the visceral or ventral laminæ, all three layers of the blastoderm are concerned.

The folding in of the splanchnopleure, lined by hypoblast, pinches off, as it were, a portion of the yelk-sac, inclosing it in the body-cavity. This forms the rudiment of the alimentary canal, which at this period ends blindly toward the head and tail, while in the centre it communicates freely with the cavity of the yolk-sac through the canal termed **vitelline** or **omphalo-mesenteric duct.**

The yolk-sac thus becomes divided into two portions which communicate through the vitelline duct, that portion within the body giving



Fig. 490. Fig. 491. Fig. 492.

Figs. 490, 491 and 492.—Diagrams showing three successive stages of development. Transverse vertical sections. The yolk-sac, *ys*, is seen progressively diminishing in size. In the embryo itself the medullary canal and notochord are seen in section. *a'*, in middle figure, the alimentary canal, becoming pinched off, as it were, from the yolk-sac; *a'* in right-hand figure, alimentary canal completely closed; *a*, in last two figures, amnion; *ac*, cavity of amnion filled with amniotic fluid; *pp*, space between amnion and chorion continuous with the pleuro-peritoneal cavity inside the body; *vt*. vitelline membrane; *ys*, yolk-sac, or umbilical vesicle. (Foster and Balfour.)

rise, as above stated, to the digestive canal, and that outside the body remaining for some time as the *umbilical vesicle* (fig. 492, *ys*.). The hypoblast forming the epithelium of the intestine is of course continuous with the lining membrane of the umbilical vesicle, while the visceral plate of the mesoblast is continuous with the outer layer of the umbilical vesicle.

All the above details will be clear on reference to the accompanying diagrams.

At the posterior end of the embryo chick, when the amniotic fold is commencing to be formed, and the hind fold of the splanchnopleure has commenced, there remains for a time a communication between the neural canal and the hind gut, which is called the **neurenteric canal.**

It passes in at the point where the notochord falls into the primitive streak. The anterior part of the primitive streak becomes the tail swelling, the posterior part atrophies, and the corresponding lateral part of the blastoderm forms part of the body-wall of the embryo.

The anterior part of the medullary canal having been completely roofed in, the foremost portion undergoes dilatation, and a bulb, the **first** or **anterior cerebral vesicle,** results. From either side of this dilatation a process, the cavity of which is in communication with it, is separated off, which is called the **optic vesicle.**

Behind the first cerebral vesicle two other vesicles now arise, the **second** or **middle,** and the **third** or **posterior cerebral vesicle,** and at the posterior part of the head two small pits, the **auditory vesicles** or **pits,** are to be seen. The folding of the head, it should be recollected, is the cause of the inclosure below the neural canal (fig. 488) of a canal ending blindly, which has in front the splanchnopleure, and which is just as long as the involution of that membrane. This canal is the **fore-gut.** In the interior of the splanchnopleure fold below it (as seen in fig. 488) in the pleuro-peritoneal cavity the heart is formed, at the point where the splanchnopleure makes its turn forward. It arises as a thickening of the mesoblast on either side as the two splanchnopleure folds diverge, and of a thickening of the mesoblast at the point of divergence. So that at first the rudiment of the heart is like an inverted V, which by the gradual coming together of the diverging cords is converted into an inverted Y.

The cylinders become hollowed out, and are thus converted into tubes, which then coalesce. Layers are separated off toward the interior, which become the epithelial lining, and the mass of the mesoblast surrounding this, afterward form the muscle and serous covering, while at first the rudimentary organ is attached to the gut by a mesoblastic mesentery, the *mesocardium.*

## FŒTAL MEMBRANES.

**Umbilical Vesicle** (*Yolk-sac*).—The splanchnopleure, lined by hypoblast, forms the yolk-sac in reptiles, birds, and mammals; but in amphibia and fishes, since there is neither *amnion* nor *allantois*, the wall of the yolk-sac consists of all three layers of the blastoderm, inclosed, of course, by the original vitelline membrane.

The body of the embryo becomes in great measure detached from the yolk-sac or umbilical vesicle, which contains, however, the greater part of the substance of the yolk, and furnishes a source whence nutriment is derived for the embryo. This nutriment is absorbed by the numerous vessels (omphalo-mesenteric) which ramify in the walls of the yolk-sac, forming what in birds is termed the **area vasculosa.** In

a mere pedicle which passes out of
of the future umbilicus.

The downwardly folded portion
**ceral plates.**

Thus we see that the body-cavity
of the visceral plates, just as the
ward growth of the dorsal laminæ,
ceral or ventral laminæ, all three la
The folding in of the splanchn
off, as it were, a portion of the yel
This forms the rudiment of the al
ends blindly toward the head and
cates freely with the cavity of the
**vitelline** or **omphalo-mesenteric**

The yolk-sac thus becomes divid
cate through the vitelline duct,



Fig. 490.

Figs. 490, 491 and 492.—Diagrams show
verse vertical sections. The yolk-sac,
embryo itself the medullary canal and
alimentary canal, becoming pinched off.
alimentary canal completely closed; *a.*
with amniotic fluid; *pp*, space between
neal cavity inside the body; *vt.* vitelline
and Balfour.)

rise, as above stated, to the
remaining for some time as
hypoblast forming the epitheli
with the lining membrane
plate of the mesoblast is conti
vesicle.

All the above details will
diagrams.

At the posterior end of
commencing to be formed,
commenced, there remains
neural canal and the hind

while the outer or reflected layer,
coalesces with the inner surface of
rm the **subzonal membrane** or
amniotic folds must of course be
ilar process, already described, by
s of the neural canal are formed.
n and the external surface of the
the *amniotic cavity* (*ac*, fig. 492).
the embryo, but it becomes grad-
*ii*), which, as pregnancy advances,

ning small quantities of albumen
g gestation appears to be the me-
rt to the embryo on all sides, and
om the effects of blows and other
r.
egnancy is thus immersed in fluid,
mportant purpose of gradually and
to allow of the passage of the fœtus:
ic sac bursts, and the *waters* escape.
d 492, it will be obvious that the
and the false amnion, is continu-
at the umbilicus. This cavity is
h, and contains a small quantity of
arturition either before, or at the

itoneal space the allantois sprouts
g the development of the amnion.
der portion of the intestinal canal
cates, the allantois is at first a solid
e; but becoming vesicular by the
rowth of hypoblast, and very soon
insinuates itself between the amni-
s into close contact and union with
s itself, as before said, become one
ane of the egg. As it grows, the
n its external wall and becomes ex-
6) it envelops the whole embryo—
outer investing membrane of the
shell with a vascular membrane,
rface in which the blood may
other mammalia, the vessels
only to a special part of the

outer membrane or false *chorion*, where, by interlacement with the vascular system of the mother, a structure called the *placenta* is developed.

In mammalia, as the visceral laminæ close in the abdominal cavity, the allantois is thereby divided at the umbilicus into two portions; the outer part, extending from the umbilicus to the *chorion*, soon shrivelling; while the inner part remaining in the abdomen, is in part converted into the urinary bladder; the portion of the inner part not so converted, extending from the bladder to the umbilicus, under the name of the *urachus*. After birth the umbilical cord, and with it the external and shrivelled portion of the allantois, are cast off at the umbilicus, while the *urachus* remains as an impervious cord stretched from the top of the urinary bladder to the umbilicus, in the middle line of the body, immediately beneath the parietal layer of the peritoneum. It is sometimes enumerated among the ligaments of the bladder.



Fig. 495.



Fig. 496.

Fig. 495.—Diagram of fecundated egg. *a*, umbilical vesicle; *b*, amniotic cavity; *c*, allantois (Dalton.)

Fig. 496.—Fecundated egg with allantois nearly complete. *a*, inner layer of amniotic fold; *b*, outer layer of ditto; *c*, point where the amniotic folds come in contact. The allantois is seen penetrating between the outer and inner layers of the amniotic folds. This figure, which represents only the amniotic folds and the parts within them, should be compared with figs. 497, 498, in which will be found the structures external to these folds. (Dalton.)

It must not be supposed that the phenomena which have been successively described, occur in any regular order one after another. On the contrary, the development of one part is going on side by side with that of another.

**The Chorion.**—It has been already remarked that the allantois is a structure which extends from the body of the fœtus to the outer investing membrane of the ovum, that it insinuates itself between the two layers of the amniotic fold, and becomes fused with the outer layer, which has itself become previously joined with the vitelline membrane. By these means the external investing membrane of the ovum, or the true chorion, as it is now called, represents three layers, namely, the original vitelline membrane, the outer layer of the amniotic fold, and the allantois.

Very soon after the entrance of the ovum into the uterus, in the human subject, the outer surface of the chorion is found beset with fine cesses, the so-called *chorion villi* (*a*, figs. 497, 498), which give it ugh and shaggy appearance. At first only cellular in structure, these e outgrowths subsequently become vascular by the development in



Fig. 497. Fig. 498.

'igs. 497 and 498.—*a*, chorion with villi. The villi are shown to be best developed in the of the chorion to which the allantois is extending: this portion ultimately becomes the enta; *b*, space between the two layers of the amnion; *c*, amniotic cavity; *d*, situation of the tine, showing its connection with the umbilical vesicle; *e*, umbilical vesicle; *f*, situation of t and vessels; *g*, allantois.

m of loops of capillaries (fig. 499); and the latter at length form the ute extremities of the blood-vessels which are, so to speak, conducted n the fœtus to the chorion by the allantois. The function of the i of the chorion is evidently the absorption of nutrient matter for fœtus; and this is probably supplied to them at first from the fluid ter, secreted by the follicular glands of the uterus, in which they soaked. Soon, however, the fœtal vessels of the villi come into re intimate relation with the vessels of the rus. The part at which this relation between vessels of the fœtus and those of the parent ues, is not, however, over the whole surface of chorion; for, although all the villi become cular, yet they become indistinct or disappear ept at one part where they are greatly devel- d, and by their branching give rise, with the sels of the uterus, to the formation of the *centa*.



Fig. 499.

To understand the manner in which the *fœtal* l *maternal* blood-vessels come into relation h each other in the placenta, it is necessary efly to notice the changes which the uterus undergoes after impreg- ion. These changes consist especially of alterations in structure of superficial part of the mucous membrane which lines the interior of uterus, and which forms, after a kind of development to be immediately described, the *membrana decidua*, so called on account of its being discharged from the uterus at birth.

## Formation of the Placenta.

The mucous membrane of the human uterus, which consists of a matrix of connective tissue containing numerous corpuscles, and is lined internally by columnar ciliated epithelium, is abundantly beset with tubular glands, arranged perpendicularly to the surface (fig. 500). These follicles are very small in the unimpregnated uterus; but when examined shortly after impregnation, they are found elongated, enlarged, and much wayed and contorted toward their deep and closed extremity, which is planted at some depth in the tissue of the uterus, and may dilate into two or three closed sacculi.



Fig. 500.—Section of the lining membrane of a human uterus at the period of commencing pregnancy showing the arrangement and other peculiarities of the glands, *d*, *d*, *d*, with their orifices, *a*, *a*, *a*, on the internal surface of the organ. Twice the natural size.

The glands are lined by columnar ( (?) ciliated) epithelium and they open on the inner surface of the mucous membrane by small round orifices set closely together (*a*, *a*, fig. 500).

On the internal surface of the mucous membrane may be seen the circular orifices of the glands, many of which are, in the early period of pregnancy, surrounded by a whitish ring, formed of the epithelium which lines the follicles.

Coincidently with the occurrence of pregnancy, important changes occur in the structure of the mucous membrane of the uterus. The epithelium and sub-epithelial connective tissue, together with the tubular glands, increase rapidly, and there is a greatly increased vascularity of the whole mucous membrane, the vessels of the mucous membrane becoming larger and more numerous; while a substance composed chiefly of nucleated cells fills up the interfollicular spaces in which the blood-vessels are contained. The effect of these changes is an increased thicknes, softness, and vascularity of the mucous membrane, the superficial part of which itself forms the **membrana decidua.**

The object of this increased development seems to be the production of nutritive materials for the ovum; for the cavity of the uterus shortly becomes filled with secreted fluid, consisting almost entirely of nucleated cells in which the chorion villi are imbedded.

When the ovum first enters the uterus it becomes imbedded in the structure of the decidua, which is yet quite soft, and in which soon afterward three portions are distinguishable. These have been named the *decidua vera*, the *decidua reflexa*, and the *decidua serotina*.

The first of these, the decidua vera, lines the cavity of the uterus; the second, or decidua reflexa, is a part of the decidua vera which grows up around the ovum, and wrapping it closely, forms its immediate investment.

The third, or decidua serotina, is the part of the decidua vera which becomes especially developed in connection with those villi of the chorion, which, instead of disappearing, remain to form the fœtal part of the *placenta*.

In connection with these villous processes of the chorion, there are developed *depressions* or *crypts* in the decidual mucous membrane, which correspond in shape with the villi they are to lodge; and thus the chorionic villi become more or less imbedded in the maternal structures. These uterine crypts, it is important to note, are not, as was once supposed, merely the open mouths of the uterine follicles.



Fig. 501.—Diagram of an early stage of the formation of the human placenta. *a*, embryo; *b*, amnion; *c*, placental vessels; *d*, decidua reflexa; *e*, allantois; *f*, placental villi; *g*, mucous membrane. (Cadiat.)

As the ovum increases in size, the decidua vera and the decidua reflexa gradually come into contact, and in the third month of pregnancy the cavity between them has almost disappeared. Though the two layers come into contact at the third month, they are not closely amalgamated until the end of the sixth month.

**The Placenta.**—During these changes the deeper part of the mucous membrane of the uterus, at and near the region where the placenta is placed, becomes hollowed out by sinuses, or cavernous spaces, which communicate on the one hand with arteries and on the other with veins of the uterus. Into these sinuses the villi of the chorion protrude, pushing the thin wall of the sinus before them, and so come into intimate relation with the blood contained in them. *There is no direct communication between the blood-vessels of the mother and those of the fœtus;* but the layer or layers of membrane intervening between the blood of the one and of the other offer no obstacle to a free interchang of matters between them by diffusion and osmosis. Thus the villi of th chorion containing fœtal blood, are bathed or soaked in maternal bloo contained in the uterine sinuses. The arrangement may be roughl compared to filling a glove with fœtal blood, and dipping its finger into a vessel containing maternal blood. But in the fœtal villi there is constant stream of blood into and out of the loop of capillary blood-vessel contained in it, as there is also into and out of the maternal sinuses.



Fig. 502.—Diagrammatic view of a vertical transverse section of the uterus at the sevent or eighth week of pregnancy. *c, c, c'*, cavity of uterus, which becomes the cavity of the decidu opening at *c, c*, the cornua, into the Fallopian tubes, and at *c'* into the cavity of the cervi which is closed by a plug of mucus; *d v*, decidua vera; *d r*, decidua reflexa, with the sparse villi imbedded in its substance; *d s*, decidua serotina, involving the more developed chorioni villi of the commencing placenta. The fœtus is seen lying in the amniotic sac; passing up fro the umbilicus is seen the umbilical cord and its vessels, passing to their distribution in the vil of the chorion; also the pedicle of the yolk-sac, which lies in the cavity between the amnio and chorion. (Allen Thomson.)

It would seem that, at the villi of the placental tufts, where the fœtal and maternal portions of the placenta are brought into close relation with each other, the blood in the vessels of the mother is separated from that in the vessels of the fœtus by the intervention of two distinct sets of nucleated cells (fig. 503). One of these (*b*) belongs to the maternal portion of the placenta, is placed between the membrane of the villus and that of the vascular system of the mother, and is probably designed to separate from the blood of the parent the materials destined for the blood of the fœtus; the other (*f*) belongs to the fœtal portion of the placenta, is situated between the membrane of the villus and the loop of vessels contained within, and probably serves for the absorption of the material secreted by the other sets of cells, and for its conveyance into the blood-vessels of the fœtus. Between the two sets of cells with their investing membrane there exists a space (*d*), into which it is possible that the materials secreted by the one set of cells of the villus are poured in order that they may be absorbed by the other set, and thus conveyed into a fœtal vessel.

Not only, however, is there a passage of materials from the blood of the mother into that of the fœtus, but there is a mutual interchange of materials between the blood both of fœtus and of parent; the latter supplying the former with nutriment, and in turn abstracting from it materials which require to be removed.



Fig. 503.—Extremity of a placental villus. *a*, lining membrane of the vascular system of the mother; *b*, cells immediately lining *a*; *d*, space between the maternal and fœtal portions of the villus; *e*, internal membrane of the villus, or external membrane of the chorion; *f*, internal cells of the villus, or cells of the chorion; *g*, loop of umbilical vessels. (Goodsir.)

The placenta, therefore, of the human subject is composed of a *fœtal* part and a *maternal* part,—the term placenta properly including all that entanglement of fœtal villi and maternal sinuses, by means of which the blood of the fœtus is enriched and purified after the fashion necessary for the proper growth and development of those parts which it is designed to nourish.

The whole of this structure is not, as might be imagined, thrown off immediately after birth. The greater part, indeed, comes away at that time, as the *after-birth;* and the separation of this portion takes place by a rending or crushing through of that part at which its cohesion is least strong, namely, where it is most burrowed and undermined

by the cavernous spaces before referred to. I
with the fœtal membrane and the decidua ve
with a part of the decidua serotina. The re
and disappears by being gradually either absorb
uterine discharges or the *lochia*, which occur at

A new mucous membrane is of course gra
old one, by its transformation into the decidu
original functions.

The *umbilical cord*, which in the latter pa
solely composed of the two arteries and the single
convey fœtal blood to and from the placenta, c
other structures which in the early stages of
embryo were, as already related, of great compar
in early fœtal life, it is composed of the following
a layer of the amnion, reflected over it from the
bilical vesicle with its duct and appertaining o
vessels. (3.) The remains of the allantois, an
urachus. (4.) The umbilical vessels, which, as j
form the greater part of the cord.

## THE DEVELOPMENT OF THE C

Before considering very briefly* the main p
of the chief organs and tissues of the body,
before us the following table, compiled by Schä
ent parts derived from the three blastodermic l

From the *Epiblast*.—The whole of the ne
not only the central organs (brain and spinal
pheral nerves and sympathetic.

The epithelial structures of the organs of sp

The epidermis and its appendages, including

The epithelium of all the glands opening
skin, including the mammary glands, the sweat
glands. The muscular fibres of the sweat gland

The epithelium of the mouth (except that c
the adjacent posterior part of the floor of the m
from the hypoblast), and that of the glands ope

The enamel of the teeth.

The epithelium of the nasal passages, of the a
pharynx and of all the cavities and glands open
sages.

---

* For a more detailed account the reader is referre
embryology.

† Quain's Anatomy, Xth Ed., Vol. I., Part I., p.

From the *Mesoblast.*—The urinary and generative organs (except the epithelium of the urinary bladder and urethra).

All the voluntary and involuntary muscles of the body (except the muscular fibres of the sweat glands).

The whole of the vascular and lymphatic system, including the serous membranes and spleen.

The skeleton and all the connective tissues and structures of the body.

From the *Hypoblast.*—The epithelium of the alimentary canal from the back of the mouth to the anus, and that of all the glands which open into this part of the alimentary tube.

The epithelium of the Eustachian tube and tympanum.

The epithelium of the bronchial tubes and air sacs of the lungs.

The epithelium lining the vesicles of the thyroid body.

The epithelial nests of the thymus.

The epithelium of the urinary bladder and urethra.

It remains now to consider in succession the development of the several organs and systems of organs in the further progress of the embryo. The accompanying figure (fig. 504) shows the chief organs of the body in a moderately early stage of development.



Fig. 504.—Embryo chick (4th day), viewed as a transparent object, lying on its left side (magnified). *C H*, cerebral hemispheres; *F B*, fore-brain or vesicle of third ventricle, with *Pn*, pineal gland projecting from its summit; *M B*, mid-brain; *Cb*, cerebellum; *IV. V*, fourth ventricle; *L*, lens; *c h s*, choroidal slit; *Cen V*, auditory vesicle; *s m*, superior maxillary process; 1*F*, 2*F*, etc., first, second, third, and fourth visceral folds; *V*, fifth nerve, sending one branch (ophthalmic) to the eye, and another to the first visceral arch; *VII*, seventh nerve, passing to the second visceral arch; *G Ph*, glosso-pharyngeal nerve, passing to the third visceral arch; *P g*, pneumogastric nerve, passing toward the fourth visceral arch; *i v*, investing mass; *c h*, notochord; its front end cannot be seen in the living embryo, and it does not end as shown in the figure, but takes a sudden bend downward, and then terminates in a point; *Ht*, heart seen through the walls of the chest; *M P*, muscle plates; *W*, wing, showing commencing differentiation of segments, corresponding to arm, forearm, and hand; *H L*, hind-limb, as yet a shapeless bud, showing no differentiation. Beneath it is seen the curved tail. (Foster and Balfour.)

**The Vertebral Column and Cranium.**—The primitive part of the vertebral column in all the vertebrata is the chorda dorsalis or noto-

chord, which consists entirely of soft cellul
tapers to a point at the cranial and caudal ex
In the progress of its development, it is found
membranous sheath, which at length acquires
posed of transverse annular fibres. The chord
as the azygos axis of the spinal column, and, ir
bodies of the vertebræ, although it never itself
hyaline cartilage or bone, but remains inclosec
persistent parts of the vertebral column whi
it. It is permanent, however, only in a few
only traces of it persist in the adult animal.

In many fish no true vertebræ are devel
graduation from the *amphioxus*, in which
through life and there are no vertebræ, throu
there are a few scattered cartilaginous verte
which many of the vertebræ are partly ossifiec
as the cod and herring, in which the verteb
number of distinct ossified vertebræ, with re
between them. In amphibia, reptiles, birds,
distinct vertebræ, which are formed as follows:

The mesoblastic somites, which have bee
794), send processes downward and inward to
and also upward between the medullary canal
it. In the former situation, the cartilaginou
make their appearance, in the latter their a
neural canal.

The vertebræ do not exactly correspond in
protovertebræ: but each permanent vertebra is
tiguous halves of two protovertebræ. The ori
protovertebræ disappears and a fresh subdivisi
that a permanent invertebral disc is develop
each protovertebra. Meanwhile the protover
and ventral portion. The former is termed the
and from it are developed all the muscles of th
cutis of the dorsal region (the epidermis being
The ventral portions of the protovertebræ,
give rise to the vertebræ and heads of the ribs.

The chorda is now inclosed in a case, form
vertebræ, but it gradually wastes and disappear
ance of the chorda, the ossification of the bodie
bræ begins at distinct points.

The ossification of the body of a vertebr
point where the two primitive elements of t

inferiorly. Those vertebræ which do not bear ribs, such as the cervical vertebræ, have generally an additional centre of ossification in the transverse process, which is to be regarded as an abortive rudiment of a rib. In the fœtal bird, these additional ossified portions exist in all the cervical vertebræ, and gradually become so much developed in the lower part of the cervical region as to form the upper false ribs of this class of animals. The same parts exist in mammalia and man; those of the last cervical vertebræ are the most developed, and in children may, for a considerable period, be distinguished as a separate part on each side like the root or head of a rib.

The true cranium is a prolongation of the vertebral column, and is developed at a much earlier period than the facial bones. Originally, it is formed of but one mass, a cerebral capsule, the chorda dorsalis being continued into its base, and ending there with a tapering point. At an early period the head is bent downward and forward round the end of the chorda dorsalis in such a way that the *middle* cerebral vesicle, and not the anterior, comes to occupy the highest position in the head.

**Pituitary Body.**—In connection with this must be mentioned the development of the pituitary body. It is formed by the meeting of two outgrowths, one from the fœtal brain, which grows downward, and the other from the epiblast of the buccal cavity, which grows up toward it. The surrounding mesoblast also takes part in its formation. The connection of the first process with the brain becomes narrowed, and persists as the infundibulum, while that of the other process with the buccal cavity disappears completely at a spot corresponding with the future position of the body of the sphenoid.

**Cranium.**—The first appearance of a solid support at the base of the cranium observed by Muller in fish, consists of two elongated bands of cartilage (trabeculæ cranii), one on the right and the other on the left side, which are connected with the cartilaginous capsule of the auditory apparatus, and which diverge to inclose the pituitary body uniting in front to form the septum nasi beneath the anterior end of the cerebral capsule. Hence, in the cranium, as in the spinal column, there are at first developed at the sides of the chorda dorsalis two symmetrical elements, which subsequently coalesce, and may wholly inclose the chorda.

The brain-case consists of three segments: occipital, parietal, and frontal, corresponding in their relative position to the three primitive cerebral vesicles; it may also be noted that in front of each segment is developed a sense-organ (auditory, ocular, and olfactory, from behind forward). The basis cranii consists at an early period of an unsegmented cartilaginous rod, developed round the notochord, and continued forward beyond its termination into the *trabeculæ cranii*, which bound the pituitary fossa on either side.

In this cartilaginous rod three centres of ossification appear: basi-occipital, basi-sphenoid, and pre-sphenoid, one corresponding to each segment.

The bones forming the vault of the skull, viz., the frontal, parietal, squamous portion of temporal and the squamo-occipital, are ossified i membrane.

## The Visceral Clefts and Arches.

As the embryo enlarges, the heart, which at first occupied a positio close to the cranial flexure, is carried further and further backward until considerable part, in which the mesoblast is undivided, intervenes between



Fig. 505.—A. Magnified view from before of the head and neck of a human embryo of abo three weeks (from Ecker.)—1, anterior cerebral vesicle or cerebrum; 2, middle ditto; 3, middl or fronto-nasal process; 4, superior maxillary process; 5, eye; 6, inferior maxillary process first visceral arch, and below it the first cleft; 7, 8, 9, second, third, and fourth arches and clefts B. Anterior view of the head of a human fœtus of about the fifth week (from Ecker, as before fig. IV.). 1, 2, 3, 5, the same parts as in A; 4, the external nasal or lateral frontal process; the superior maxillary process; 7, the lower jaw; ×, the tongue; 8, first branchial cleft becom ing the meatus auditorius externus.

it and the head. This becomes the neck. On section it is seen that i it the whole three layers are represented in order, and that there is n interval between them. In the neck thus formed soon appear the **visceral** or **branchial clefts** on either side, in series, across the axis the gut not quite at right angles. They are four in number, the mo anterior being first found. At their edges the hypoblast and the epiblast are continuous. The anterior border of each cleft forms a fo or lip, the **branchial** or **visceral fold.** The posterior border of the la cleft is also formed into a fold, so that there are four clefts and five fold but the three most anterior are far more prominent than the others, an of these the second is the most conspicuous. The first fold nearly meets i fellow in the middle line, the second less nearly, and the others in orde still less so. Thus in the neck there is a triangular interval, into whic by the splitting of the mesoblast at that part the pleuroperitoneal cavit extends. The branchial clefts and arches are not all permanent. Th first arch gives off a branch from its front edge, which passes forward t meet its fellow, but these offshoots do not quite meet, being separate y a process which grows downward from the head. Between the ranches and the main first fold is the cavity of the mouth. The branches epresent the superior maxilla, and the main folds the mandible or lower aw. The central process, which grows down, is the fronto-nasal pro-ess.

In this way the so-called visceral *arches* and *clefts* are formed, four n each side (fig. 505, A).

From or in connection with these arches the following parts are devel-ped:—

The first arch (mandibular) contains a cartilaginous rod (Meckel's artilage), around the distal end of which the lower jaw is developed, hile the malleus is ossified from the proximal end.

When the maxillary processes on the two sides fail partially or com-letely to unite in the middle line, the well-known condition termed *eft palate* results. When the integument of the face presents a similar eficiency, we have the deformity known as *hare-lip*. Though these two



Fig. 506.—Embryo chick (4th day), viewed as a transparent object, lying on its left side magnified). *C H*, cerebral hemispheres; *F B*, fore-brain or vesicle of third ventricle, with *Pn*, ineal gland projecting from its summit; *M B*, mid-brain; *C b*, cerebellum; *IV. V*, fourth ven-ricle; *L*, lens; *c h s*, choroidal slit; *Cen. V*, auditory vesicle; *s m*, superior maxillary process; *F*, *2F*, etc., first, second, third, and fourth visceral folds; *V*, fifth nerve, sending one branch ophthalmic) to the eye, and another to the first visceral arch; *VII*, seventh nerve, passing to e second visceral arch; *G. Ph*, glosso-pharyngeal nerve, passing to the third visceral arch; *g*, pneumogastric nerve, passing toward the fourth visceral arch; *i v*, investing mass; *c h*, otochord; its front end cannot be seen in the living embryo, and it does not end as shown in e figure, but takes a sudden bend downward, and then terminates in a point; *Ht*, heart seen rough the walls of the chest; *M P*, muscle-plates; *W*, wing, showing commencing differentia-on of segments, corresponding to arm, forearm, and hand; *S S*, somatic stalk; *Al*, allantois; *L*, hind-limb, as yet a shapeless bud, showing no differentiation. Beneath it is seen the urved tail. (Foster and Balfour.)

eformities frequently co-exist, they are by no means always necessarily ssociated.

The upper part of the face in the middle line is developed from the o-called *frontal-nasal* process (A, 3, fig. 505). From the *second* arch

are developed the *incus*, *stapes*, and *stapedius*
of the *temporal* bone, the *stylo-hyoid* ligamen
the *hyoid* bone. From the *third* visceral arch,
of the hyoid bone. In man and other mamm
is indistinct. It occupies the position wher
developed.

A distinct connection is traceable between
certain cranial nerves: the trigeminal, the fa
and the vagus. The ophthalmic division of t
fronto-nasal process; the superior and inferior
the maxillary and mandibular arches respecti

The facial nerve distributes one branch
first visceral arch, and others to the secon
divides, inclosing the first visceral cleft.

Similarly, the glosso-pharyngeal divides to
cleft, its lingual branch being distributed
pharyngeal branch to the third arch.

The vagus, too, sends a branch (pharynge
and in fishes it gives off paired branches, whic
successive branchial clefts.

## The Extremities.

The extremities are developed in a unif
brate animals. They appear in the form of le



Fig. 507.—A human embryo of the fourth week, 3½ lines
of the amnion; 4, umbilical vesicle with its long pedicle
heart; 8, the liver; 9, the visceral arch destined to form the
other visceral arches separated by the branchial clefts; 10, ru
that of the lower extremity; 12, the umbilical cord; 15, the
spheres; 18, optic lobes, corpora quadrigemina. (Müller.)

parieties of the trunk (see fig. 507), at points
arch will be produced for them within. T
extremity is nearly the same in all vertebrata,

swimming, crawling, walking, or flying. In the human fœtus the fingers are at first united, as if webbed for swimming; but this is to be regarded not so much as an approximation to the form of aquatic animals, as the primitive form of the hand, the individual parts of which subsequently become more completely isolated.

The fore-limb always appears before the hind-limb, and for some time continues in a more advanced state of development. In both imbs alike, the distal segment (hand or foot) is separated by a slight notch from the proximal part of the limb, and this part is subsequently divided again by a second notch (knee or elbow-joint).

**The Vascular System.**—At an early stage in the development of the embryo-chick, the so-called *area vasculosa* begins to make its appearance. A number of branched cells in the mesoblast send out processes which unite so as to form a network of protoplasm with nuclei at the nodal points. A large number of nuclei acquire red color; these form the red blood-corpuscles. The protoplasmic processes become hollowed out in the centre so as to form a closed system of branching canals, in the walls of which the rest of the nuclei remain imbedded. In the blood-vessels thus formed, the circulation of the embryonic blood commences.

According to Klein, the first blood-vessels in the chick are developed from embryonic cells of the mesoblast, which swell up and become vacuolated, while their nuclei undergo segmentation. These cells send out protoplasmic processes, which unite with corresponding ones from other cells, and become hollowed, give rise to the capillary wall composed of endothelial cells; the blood corpuscles being budded off from the endothelial wall by a process of gemmation.

*Heart.*—About the same early period the heart makes its appearance as a solid mass of cells of the splanchnopleure in the manner before indicated.

At this period the anterior part of the alimentary tube ends blindly beneath the notochord. It is beneath the posterior end of this *fore-gut* that the heart begins to be developed. The heart when first formed is made up of two not quite complete tubes which coalesce to form one, and so when the cavity is hollowed out in the mass of cells, the central cells float freely in the fluid, which soon begins to circulate by means of the rhythmic pulsations of the embryonic heart.

These pulsations take place even before the appearance of a cavity, and immediately after the first laying down of the cells from which the heart is formed, and long before muscular fibres or ganglia have been formed in the cardiac walls. At first they seldom exceed from fifteen to eighteen in the minute. The fluid within the cavity of the heart shortly assumes the characters of blood. At the same time, the cavity itself forms a communication with the great vessels in contact with it, and the cells of which its walls are comprised are transformed into fibrous and muscular tissues, and into epithelium. In the developing chick



Fig. 508.



Fig. 509.



Fig. 510.

Fig. 508.—Capillary blood-vessels of the tail of a young larval frog. *a*, capillaries permeable to blood; *b*, fat granules attached to the walls of the vessels, and concealing the nuclei; c hollow prolongation of a capillary, ending in a point; *d*, a branching cell with nucleus and fat granules; it communicates by three branches with prolongation of capillaries already formed *e*, *e*, blood corpuscles still containing granules of fat. × 350 times. (Kölliker.)

Fig. 509.—Development of capillaries in the regenerating tail of a tadpole. *a b c d*, sprout and cords of protoplasm. (Arnold.)

Fig. 510.—The same region after the lapse of 24 hours. The "sprouts and cords of protoplasm" have become channelled out into capillaries. (Arnold.)

it can be observed with the naked eye as a minute red pulsating littl mass before the end of the second day of incubation.

*Blood-vessels.*—Blood-vessels appear to be developed in two ways, according to their size. In the formation of large blood-vessels, masses o embryonic cells similar to those from which the heart and other structures of the embryo are developed, arrange themselves in the position form, and thickness of the developing vessel. Shortly afterward the cell in the interior of a column of this kind seem to be developed into blood corpuscles, while the external layer of cells is converted into the walls of the vessel.

In the development of *capillaries* another plan is pursued. This has been well illustrated by Kölliker, as observed in the tails of tadpoles. The first lateral vessels of the tail have the form of simple arches, passing between the main artery and vein, and are produced by the junction of prolongations, sent from both the artery and vein, with certain elongated or star-shaped cells, in the substance of the tail. When these arches are formed and are permeable to blood, new prolongations pass from them, join other radiated cells, and thus form secondary arches. In this manner, the capillary network extends in proportion as the tail increases in length and breadth, and it, at the same time, becomes more dense by the formation, according to the same plan, of fresh vessels within its meshes. The prolongations by which the vessels communicate with the star-shaped cells, consist at first of narrow pointed projections from the side of the vessels, which gradually elongate until they come in contact with the radiated processes of the cells. The thickness of such a prolongation often does not exceed that of a fibril of fibrous tissue, and at first it is perfectly solid; but, by degrees, especially after its junction with a cell, or with another prolongation, or with a vessel already permeable to blood, it enlarges, and a cavity then forms in its interior (see figs. 510, 511). This tissue is well calculated to illustrate the various steps in the development of blood-vessels from elongating and branching cells.

In many cases a whole network of capillaries is developed from a network of branched, embryonic connective-tissue corpuscles by the joining of their processes, the multiplication of their nuclei, and the vacuolation of the cell-substance. The vacuoles gradually coalesce till all the partitions are broken down, and the originally solid protoplasmic cell-substance is, so to speak, tunnelled out into a number of tubes.



Fig. 511.—Capillaries from the vitreous humor of a fœtal calf. Two vessels are seen connected by a "cord" of protoplasm, and clothed with an adventitia, containing numerous nuclei. *a*, insertion of this "cord" into the primary walls of the vessels. (Frey.)

Capillaries may also be developed from cells which are originally spheroidal, vacuoles form in the interior of the cells gradually becoming united by fine protoplasmic processes: by the into them, capillary tubes are gradually forme

*Morphology. Heart.*—When it first appea mately tubular in form, being at first a *double* receives at its two posterior angles the two om line veins, and gives off anteriorly the primiti junction of the two veins which pass into the farther and farther away from the heart, and called sinus venosus near to the auricle, and away, or if it be called by one name that of *me*

It soon, however, becomes curved somewhat shoe, with the convexity toward the right, the same time drawn up toward the head, so that somewhat to the right, of the arterial. It also constrictions into three cavities.

Of these three cavities which are developed the venous end is the simple auricle, with the arterial end the bulbus arteriosus, and the mid tricle.

These three parts of the heart contract in and the bulbus arteriosus at this period lie



Fig. 512.—Fœtal heart in successive stages of development. 1 tremity; 3, 3, pulmonary branches; 4, ductus ar

horse-shoe. The bulging out of the middle po first indication of the future form of the ventri curvature of the horse-shoe by the same me developed than the smaller curvature between and the two extremities, the auricle and bu superiorly, so as to produce a greater resembl the heart, while the ventricle becomes more iorly. The heart of fishes retains these cavities, no further division internal septa into right and left chambers taking place. In phibia, also, the heart throughout life consists of the three muscular isions which are so early formed in the embryo and the sinus venosus; the auricle is divided internally by a septum into a pulmonary and emic auricle. In reptiles, not merely the auricle is thus divided into cavities, but a similar septum but incomplete is more or less developed



513.—Heart of the chick at the 45th, 65th, and 85th hours of incubation. 1, the venous trunks; 2, the auricle; 3, the ventricle; 4, the bulbus arteriosus. (Allen Thomson.)

he ventricle. In birds and mammals, both auricle and ventricle ergo complete division by septa; while in these animals as well as in tiles, the bulbus aortæ is not permanent, but becomes lost in the venles. The septum dividing the ventricle commences at the apex and nds upward. The subdivision of the auricles is very early foredowed by the outgrowth of the two auricular appendages, which ırs before any septum is formed externally. The septùm of the icles is developed from a semilunar fold, which extends from above nward. In man, the septum between the ventricles, according to kel, begins to be formed about the fourth week, and at the end of ıt weeks is complete. The septum of the auricles, in man and all nals which possess it, remains imperfect throughout fœtal life. When partition of the auricles is first commencing, the two venæ cavæ have erent relations to the two cavities. The superior cava enters, as in adult, into the right auricle; but the inferior cava is so placed that ppears to enter the left auricle, and the posterior part of the septum the auricles is formed by the Eustachian valve, which extends from point of entrance of the inferior cava. Subsequently, however, the um, growing from the anterior wall close to the upper end of the venular septum, becomes directed more and more to the left of the vena inferior. During the entire period of fœtal life, there remains pening in the septum, which the valve of the foramen ovale, develd in the third month, imperfectly closes.

The *bulbus arteriosus*, which is originally a single tube, becomes dually divided into two by the growth of an internal septum, which ngs from the posterior wall, and extends forward toward the front and downward toward the ventricles. This partition takes a somet spinal direction, so that the two tubes (aorta and pulmonary artery) which result from its completion, do not run side by side, but ar twisted round each other.

As the septum grows down toward the ventricles, it meets and co lesces with the upwardly growing ventricular septum, and thus fro the right and left ventricles, which are now completely separate, ari respectively the pulmonary artery and aorta, which are also quite di tinct. The auriculo-ventricular and semi-lunar valves are formed by t folds of the endocardium.

At its first appearance, as we have seen, the heart is placed ju beneath the head of the fœtus, and is very large relatively to the who body; but with the growth of the neck it becomes further and furth removed from the head, and is lodged in the cavity of the thorax.

Up to a certain period the auricular is larger than the ventricular di sion of the heart; but this relation is gradually reversed as developme proceeds. Moreover, all through fœtal life, the walls of the right ve tricle are of very much the same thickness as those of the left, whi may probably be explained by the fact that in the fœtus the right ve tricle has to propel the blood from the pulmonary artery into the aort and thence into the placenta, while in the adult it only drives the blo through the lungs.

*Arteries.*—The primitive aorta arises from the bulbus arteriosus a divides into two branches which arch backward, one on each side of foregut and unite again behind it, and in front of the notochord into single vessel.

This gives off the two omphalo-mesenteric arteries, which distribu branches all over the yolk-sac; this *area vasculosa* in the chick attaini a large development, and being limited all round by a vessel known the sinus terminalis.

The blood is collected by the venous channels, and returned throu the omphalo-mesenteric veins to the heart.

Behind this pair of primitive aortic arches, four more pairs mak their appearance sucessively, so that there are five pairs in all, each o running along one of the visceral arches.

These five are never all to be seen at once in the embryo of high animals, for the two anterior pairs gradually disappear, while the po terior ones are making their appearance, so that at length only thr remain.

In fishes, however, they all persist throughout life as the branchi arteries supplying the gills, while in amphibia three pairs persist throug out life.

In reptiles, birds, and mammals, further transformations occur.

In reptiles the fourth pair remains throughout life as the permanen right and left aorta; in birds the right one remains as the permanen aorta, curving over the right bronchus instead of the left as in mammals.

In mammals the left fourth aortic arch develops into the permanent aorta, the right one remaining as the subclavian artery of that side. Thus the subclavian artery on the right side corresponds to the aortic arch on the left, and this homology is further confirmed by the fact that the recurrent laryngeal nerve hooks under the subclavian on the right side, and the aortic arch on the left.



Fig. 514.—Diagram of the aortic arches in a mammal, showing transformations which give rise to the permanent arterial vessels. *A*, primitive arterial stem or aortic bulb, now divided into *A*, the ascending part of the aortic arch, and *p*, the pulmonary; *a a'*, right and left aortic roots; *A'*, descending aorta; 1, 2, 3, 4, 5, the five primitive aortic or branchial arches; *I*, *II*, *III*, *IV*, the four branchial clefts which, for the sake of clearness, have been omitted on the right side. The permanent systemic vessels are deeply, the pulmonary arteries lightly, shaded; the parts of the primitive arches which are transitory are simply outlined; *c*, placed between the permanent common carotid arteries; *c e*, external carotid arteries; *c i*, internal carotid arteries; *s*, right subclavian, rising from the right aortic root beyond the fifth arch; *v*, right vertebral from the same, opposite the fourth arch; *v' s'*, left vertebral and subclavian arteries rising together from the left or permanent aortic root, opposite the fourth arch; *p*, pulmonary arteries rising together from the left fifth arch; *d*, outer or back part of the left fifth arch, forming ductus arteriosis; *p n*, *p n'*, right and left pneumogastric nerves descending in front of aortic arch, with their recurrent branches represented diagrammatically as passing behind, to illustrate the relations of these nerves respectively to the right subclavian artery (4) and the arch of the aorta and ductus arteriosus (*d*). (Allen Thomson, after Rathke.)

The third aortic arch remains as the internal carotid artery, while the fifth disappears on the right side, but on the left forms the pulmonary artery. The distal end of this arch originally opens into the descending aorta, and this communication (which is permanent throughout life in many reptiles on both sides of the body) remains throughout fœtal life under the name of *ductus arteriosus:* the branches of the pulmonary artery, to the right and left lung, are very small, and most of the blood which is forced into the pulmonary artery passes through the wide ductus arteriosus into the descending aorta. All these points will become clear on reference to the accompanying diagram (fig. 514).

As the umbilical vesicle dwindles in size, the portion of the omphalo-mesenteric arteries outside the body gradually disappears, the part inside the body remaining as the mesenteric arteries.

Meanwhile with the growth of the allantois two new arteries (*umbilical*) appear, and rapidly increase in size till they are the largest branches of the aorta: they are given off from the internal iliac arteries, and for a long time are considerably larger than the external iliacs which supply the comparatively small hind-limbs.

*Veins.*—The chief veins in the early embryo may be divided into two groups, visceral and parietal: the former includes the omphalo-mesenteric and umbilical, the latter the jugular and cardinal veins. The former may be first considered.



Fig. 515.



Fig. 516.

Fig. 515.—Diagram of young embryo and its vessels, showing course of circulation in the umbilical vesicle; and also that of the allantois (near the caudal extremity), which is just commencing. (Dalton.)

Fig. 516.—Diagram of embryo and its vessels at a later stage, showing the second circulation. The pharynx, œsophagus, and intestinal canal have become further developed, and the mesenteric arteries have enlarged, while the umbilical vesicle and its vascular branches are very much reduced in size. The large umbilical arteries are seen passing out in the placenta. (Dalton.)

The earliest veins to appear in the fœtus are the omphalo-mesenteric or vitelline, which return the blood from the yolk-sac to the developing auricle. As soon as the placenta with its umbilical veins is developed, these unite with the omphalo-mesenteric, and thus the blood which reaches the auricle comes partly from the yolk-sac and partly from the placenta. The right omphalo-mesenteric and the right umbilical veins soon disappear, and the united left omphalo-mesenteric and umbilical veins pass through the developing liver on the way to the auricle. Two sets of vessels make their appearance in connection with the liver (venæ hepaticæ advehentes, and revehentes), both opening into the united omphalo-mesenteric and umbilical veins, in such a way that a portion of the venous blood traversing the latter is diverted into the developing liver, and, having passed through its capillaries, returns to the umbilical vein through the venæ hepaticæ revehentes at a point nearer the heart (see fig. 517). The portion of vein between the afferent and efferent veins of the liver becomes the ductus venosus. The venæ hepaticæ



Fig. 517.—Diagrams illustrating the development of veins about the liver. *B*, *d c*, ducts of Cuvier, right and left; *c a*, right and left cardinal veins; *o*. left omphalo-mesenteric vein; *o'*, right omphalo-mesenteric vein, almost shrivelled up; *u u'*, umbilical veins, of which *u'*, the right one, has almost disappeared. Between the venæ cardinales is seen the outline of the rudimentary liver with its venæ hepaticæ advehentes, and revehentes. *D*, ductus venosus; *l'*, hepatic veins; *c i*, vena cava inferior; *P*, portal vein; *P'P'*, venæ advehentes; *m*, mesenteric veins. (Kölliker.)

advehentes become the right and left branches of the portal vein, the venæ hepaticæ revehentes become the hepatic veins, which open just at the junction of the ductus venosus with another large vein (vena cava inferior), which is now being developed. The mesenteric portion of the omphalo-mesenteric vein returning blood from the developing intestines remains as the mesenteric vein, which, by its union with the splenic vein, forms the portal.

Thus the fœtal liver is supplied with venous blood from two sources, through the umbilical and portal vein respectively. At birth the circulation through the umbilical vein of course completely ceases and the vessel begins at once to dwindle, so that now the only venous supply of the liver is through the portal vein. The earliest appearance of the *parietal* system of veins is the formation of two short transverse veins (ducts of Cuvier) opening into the auricle on either side, which result from the union of an anterior cardinal, afterward forming a jugular, vein, collecting blood from the head and neck, and a posterior cardinal vein which returns the blood from the Wolffian bodies, the vertebral column, and the parieties of the trunk. This arrangement persists throughout life in fishes, but in mammals the following transformations occur.

As the kidneys are developing a new vein appears (vena cava inferior), formed by the junction of their efferent veins. It receives branches from the legs (iliac) and increases rapidly in size as they grow; further up it receives the hepatic veins, which by now have lost their original opening into the ductus venosus. The heart gradually descends into the thorax, causing the ducts of Cuvier to become oblique instead transverse. As the fore-limbs develop, the subclavian veins are forme

A transverse communicating trunk now unites the two ducts Cuvier, and gradually increases, while the left duct of Cuvier becor almost entirely obliterated (all its blood passing by the communicati trunk to the right side) (fig. 518, C.D.). The right duct of Cuv remains as the right innominate vein, while the communicating bran forms the left innominate. The remnant of the left duct of Cuv generally remains as a fibrous band, running obliquely down to the co nary vein, which is really the proximal part of the left duct of Cuvi In front of the root of the left lung, another relic may be found in t



Fig. 518.—Diagrams illustrating the development of the great veins. d c, ducts of Cuvie jugular veins; h, hepatic veins; c, cardinal veins; s, subclavian vein; j i, internal jugular v j e, external jugular vein; a z, azygos vein; c i, inferior vena cava; r, renal veins; i l, iliac ve h i j, hypogastric veins. (Gegenbaur.)

form of the so-called *vestigial fold* of Marshall, which is a fold of p cardium running in the same direction.

In many of the lower mammals, such as the rat, the left duct Cuvieri remains as a left superior cava.

Meanwhile, a transverse branch carries across most of the blood the left posterior cardinal vein into the right; and by this union th great azygos vein is formed.

The upper portions of the left poste[illegible] linal [illegible] o th left superior intercostal and vena azyg

CIRCULATION OF

The circulation of blood in t of the adult. It will be well, pe he course of the blood, which, after being carried out to the pla- by the two umbilical arteries, has returned, cleansed and replen-, to the fœtus by the umbilical vein.

is at first conveyed to the under surface of the liver, and there the n is divided,—a part of the blood passing straight on to the in-



Fig. 519.—Diagram of the Fœtal Circulation.

vena cava, through a venous canal called the *ductus venosus*, while em[illegible] into the portal vein, and reaches the inferior vena onl[illegible] circul[illegible]ng through the liver. Whether, however, by ire[illegible] the [illegible] ductus venosus or by the roundabout way gh [illegible] r,—[illegible] od which is returned from the placenta by mb[illegible] inferior vena cava at last, and is carried to th[illegible] heart, into which cavity is also pouring the blood that has circulated in the head and neck and arms, and has been brought to the auricle by the superior vena cava. It might be naturally expected that the two streams of blood would be mingled in the right auricle, but such is not the case, or only to a slight extent. The blood from the superior vena cava—the less pure fluid of the two—passes almost exclusively into the right ventricle, through the auriculo-ventricular opening, just as it does in the adult; while the blood of the inferior vena cava is directed by a fold of the lining membrane of the heart, called the *Eustachian valve*, through the foramen ovale into the left auricle, whence it passes into the left ventricle, and out of this into the aorta, and thence to all the body, but chiefly to the head and neck. The blood of the superior vena cava, which, as before said, passes into the right ventricle, is sent out thence in *small amount* though the pulmonary artery to the lungs, and thence to the left auricle, as in the adult. The greater part, however, by far, does not go to the lungs, but instead, passes through a canal, the *ductus arteriosus*, leading from the pulmonary artery into the aorta just below the origin of the three great vessels which supply the upper parts of the body; and there meeting that part of the blood of the inferior vena cava which has not gone into these large vessels, it is distributed with it to the trunk and lower parts, —a portion passing out by way of the two umbilical *arteries* to the placenta. From the placenta it is returned by the umbilical *vein* to the under surface of the liver, from which the description started.

**Changes after Birth.**—After birth the foramen ovale closes, and so do the ductus arteriosus and ductus venosus, as well as the umbilical vessels; so that the two streams of blood which arrive at the right auricle by the superior and inferior vena cava respectively, thenceforth mingle in this cavity of the heart, and passing into the right ventricle, go by way of the pulmonary artery to the lungs, and through these after purification, to the left auricle and ventricle, to be distributed over the body.

## The Nervous System.

*The Cranial and Spinal Nerves.*—The cranial nerves are derived from a continuous band, called the neural band. They are formed before the neural canal is complete. The neural band is made up of two laminæ going from the dorsal edges of the neural groove to the external epiblast. It becomes separated from the epiblast, and then forms a crest attached to the upper surface of the brain. The posterior roots of the spinal nerves arise as outgrowths of median processes of cells from the dorsal side of the spinal cord, which become attached laterally to the spinal cord as their original point of attachment disappears. The anterior roots probably arise from the ventral part of the cord as a number of strands for each nerve. They appear later than the posterior roots. The rudiment of the posterior root is differentiated into a proximal round nerve connected to the cord, a ganglionic portion and a distal portion. To the last the anterior nerve-root becomes attached.

*The Spinal Cord.*—The spinal cord consists at first of the undifferentiated epiblast of the walls of the neural canal, the cavity of which is large, with almost parallel sides. The walls are at first composed of elongated irregular nucleated columnar cells, arranged in a radiate manner. The cavity then becomes narrow in the middle and of an hour-glass shape (fig. 520). When the spinal nerves make their first appearance, about the fourth day in the chick, the epiblastic walls become differentiated into three parts: (*a*) the epithelium lining the central canal; (*b*) the gray matter; (*c*) the external white matter. The last is derived from the outermost part of the epiblastic walls by the conversion of the cells into longitudinal nerve-fibres. The fibres being without any myelin sheath, are for a time gray in appearance. The white matter corresponds in position to the anterior and posterior nerve-roots, and are the anterior and posterior white columns. It is at first a very thin layer, but increases in thickness until it covers the whole cord. The gray matter too arises from the cells by their being prolonged into fibres. The change in the central cells is sufficiently obvious. The anterior and posterior cornua of gray matter and the anterior gray commissure then appear. The anterior fissure is formed on the fifth day by the growth downward of the anterior cornua of gray matter toward the middle line. The posterior fissure is formed later. The whole cord now becomes circular. The posterior gray commissure is then formed.



**Fig. 520.**—Diagram of development of spinal cord, *c c*, central canal; *af*, anterior fissure; *pf*, posterior fissure; *g*, gray matter; *w*, white matter. *For further explanation, see text.*

When it first appears, the spinal cord occupies the whole length of the medullary canal, but as development proceeds, the spinal column grows more rapidly than the contained cord, so that the latter appears as if drawn up till, at birth, it is opposite the third lumbar vertebra, and in the adult opposite the first lumbar. In the same way the increasing obliquity of the spinal nerves in the neural canal, as we approach the lumbar region, and the *cauda equina* at the lower end of the cord, are accounted for.

**Brain.**—We have seen that the front portion of the medullary canal is almost from the first widened out and divided into three vesicles. From the anterior vesicle (thalamencephalon) the two primary optic vesicles are budded off laterally: their further history will be traced in the next section. Somewhat later, from the same vesicle the rudiments of the hemispheres appear in the form of two outgrowths at a higher level, which grow upward and backward. These form the *prosencephalon.*

In the walls of the posterior (third) cerebral vesicle, a thickening appears (rudimentary cerebellum) which becomes separated from the rest of the vesicle by a deep inflection.

At this time there are two chief curvatures of the brain (fig. 521). (1.) A sharp bend of the whole cerebral mass downward round the end of the notochord, by which the anterior vesicle, which was the highest of the three, is bent downward, and the middle one comes to occupy the highest position. (2.) A sharp bend, with the convexity forward, which runs in from behind beneath the rudimentary cerebellum separating it from the medulla.



Fig. 521.—Early stages in development of human brain (magnified). 1, 2, 3, are from an embryo about seven weeks old; 4, about three months old. *m*, middle cerebral vesicle (mesencephalon); *c*, cerebellum; *m o*, medulla oblongata; *i*, thalamencephalon; *h*, hemispheres; *i'*, infundibulum; Fig. 3 shows the several curves which occur in the course of development; Fig. 4 is a lateral view, showing the great enlargement of the cerebral hemispheres which have covered in the thalami, leaving the optic lobes, *m*, uncovered. (Kölliker.)

N. B.—In Fig. 2 the line *i* terminates in the right hemisphere; it ought to be continued into the thalamencephalon.

Thus, five fundamental parts of the fœtal brain may be distinguished, which, together with the parts developed from them, may be presented in the following tabular view:—

TABLE OF PARTS DEVELOPED FROM FUNDAMENTAL PARTS OF BRAIN.

| | | | |
|---|---|---|---|
| I. Anterior Primary Vesicle, or Fore-brain. | First Secondary Vesicle of Prosencephalon. | Anterior end of third ventricle, foramen of Monro, lateral ventricles, cerebral hemispheres, corpora striata, corpus callosum, fornix, lateral ventricles, olfactory bulb. | |
| | Second Secondary Vesicle or Thalamencephalon (Diencephalon). | Thalami optici, pineal gland, part of pituitary body, third ventricle, optic nerve and retina, infundibulum. | |
| II. Middle Primary Vesicle, or Mid-brain. | Third Secondary Vesicle or Mesencephalon. | Corpora quadrigemina, crura cerebri, aqueduct of Sylvius. | |
| III. Posterior Primary Vesicle, or Hind-brain. | Fourth Secondary Vesicle or Epencephalon.<br>Fifth Secondary Vesicle or Metencephalon. | Fourth ventricle. | Cerebellum, pons, medulla oblongata. |

(*Quain.*)

The cerebral hemispheres grow rapidly upward and backward, while from their inferior surface the olfactory bulbs are budded off, and the prosencephalon, from which they spring, remains to form the third ventricle and optic thalami. The middle cerebral vesicle (mesencephalon) for some time is the most prominent part of the fœtal brain, and in fishes, amphibia, and reptiles, it remains uncovered through life as the optic lobes. But in birds the growth of the cerebral hemispheres thrusts the optic lobes down laterally, and in mammalia completely overlaps them.

In the lower mammalia the backward growth of the hemispheres ceases as it were, but in the higher groups, such as the monkeys and man, they grow still further back, until they completely cover in the cerebellum, so that on looking down on the brain from above, the cerebellum is quite concealed from view. The surface of the hemispheres is at first quite smooth, but as early as the third month the great Sylvian fissure begins to be formed (fig. 522).



Fig. 522.—Side view of fœtal brain at six months, showing commencement of formation of the principal fissures and convolutions. *F*, frontal lobe; *P*, parietal; *O*, occipital; *T*, temporal; *a a a*, commencing frontal convolutions; *s*, Sylvian fissure; *s'*, its anterior division; *c*, within it the central lobe or island of Reil; *r*, fissure of Rolando; *p*, perpendicular fissure. (R. Wagner.)

The next to appear is the parieto-occipital or perpendicular fissure; these two great fissures, unlike the rest of the sulci, are formed by a curving round of the whole cerebral mass.

In the sixth month the fissure of Rolando appears: from this time till the end of fœtal life the brain grows rapidly in size, and the convolutions appear in quick succession; first the great primary ones are sketched out, then the secondary, and lastly the tertiary ones in the sides of the fissures. The commissures of the brain (anterior, middle, and posterior), and the corpus callosum, are developed by the growth of fibres across the middle line.

The Hippocampus major is formed by the folding in of the gray matter from the exterior into the lateral ventricles. The essential points in the structure and arrangement of the various parts of the brain, are diagrammatically shown in the two accompanying figures (figs. 521, 522).

## THE SPECIAL SENSE ORGANS.

**The Eye.**—Soon after the first three cerebral vesicles have become distinct from each other, the anterior one sends out a lateral vesicle from each side (primary optic vesicle), which grows out toward the free surface, its cavity of course communicating with that of the cerebral vesicle through the canal in its pedicle. It is soon met and invaginated by an ingrowing process from the epiblast (fig. 523), very much as the growing tooth is met by the process of epithelium which produces the enamel organ. This process of the epiblast is at first a depression, which ultimately becomes closed in at the edges so as to produce a hollow ball, which is thus completely severed from the epithelium with which it was originally continuous. From this hollow ball the crystalline lens is developed. The way in which this occurs has been indicated in a previous chapter under the head of structure of the lens. By the ingrowth of the lens the anterior wall of the primary optic vesicle is forced back nearly into contact with the posterior, and thus the primary optic vesi-



Fig. 523.—Longitudinal section of the primary optic vesicle in the chick magnified (from Remak).—A, from an embryo of sixty-five hours; B, a few hours later; C, of the fourth day; c, the corneous layer or epidermis, presenting in A the open depression for the lens, which is closed in B and C; *l*, the lens follicle and lens; *pr*, the primary optic vesicle; in A and B, the pedicle is shown; in C, the section being to the side of the pedicle, the latter is not shown; *v*, the secondary ocular vesicle and vitreous humor.

cle is almost obliterated. The cells in the anterior wall are much longer than those of the posterior wall; from the former the retina proper is developed, from the latter the retinal pigment.

The cup-shaped hollow in which the lens is now lodged is termed the secondary optic vesicle: its walls grow up all round, leaving, however, a slit at the lower part.

*Choroidal Fissure.*—Through this slit (fig. 525), often termed the *choroidal fissure*, a process of mesoblast containing numerous blood-vessels projects, and occupies the cavity of the secondary optic vesicle behind the lens, filling it with vitreous humor and furnishing the lens capsule and the capsulo-pupillary membrane. This process in mammals projects, not only into the secondary optic vesicle, but also into the pedicle of the primary optic vesicle invaginating it for some distance from beneath, and thus carrying up the *arteria centralis retinæ* into its permanent position in the centre of the optic nerve.



Fig. 524.



Fig. 525.

Fig. 524.—Diagrammatic sketch of a vertical longitudinal section through the eyeball of a human fœtus of four weeks. The section is a little to the side, so as to avoid passing through the ocular cleft; *c*, the cuticle where it becomes later the corneal epithelium; *l*, the lens; *op*, optic nerve formed by the pedicle of the primary optic vesicle; *vp*, primary medullary cavity or optic vesicle; *p*, the pigment layer of the retina; *r*, the inner wall forming the retina proper; *vs*, secondary optic vesicle containing the rudiment of the vitreous humor. × 100. (Kölliker.)

Fig. 525.—Transverse vertical section of the eyeball of a human embryo of four weeks. The anterior half of the section is represented: *pr*, the remains of the cavity of the primary optic vesicle; *p*, the inner part of the outer layer forming the retinal pigment; *r*, the thickened inner part giving rise to the columnar and other structures of the retina; *v*, the commencing vitreous humor within the secondary optic vesicle; *v'*, the ocular cleft through which the loop of the central blood-vessel, *a*, projects from below; *l*, the lens with a central cavity. × 100. (Kölliker.)

This invagination of the optic nerve does not occur in *birds*, and consequently no arteria centralis retinæ exists in them. But they possess an important permanent relic of the original protrusion of the mesoblast through the choroidal fissure, in the *pecten*, while a remnant of the same fissure sometimes occurs in man under the name coloboma iridis. The cavity of the primary optic vesicle becomes completely obliterated, and the rods and cones growing up from the external limiting membrane, get into apposition with the pigment layer of the retina.

The inner segments of the rods become the first formed, then the outer. The cavity of its pedicle disappears and the solid optic nerve is formed. Meanwhile the cavity which existed in the centre of the primitive lens becomes filled up by the growth of fibres from its posterior wall. The epithelium of the cornea is developed from the epiblast, while the corneal tissue proper is derived from the mesoblast which intervenes between the epiblast and the primitive lens which was originally continuous with it. The *sclerotic* coat is developed round the eyeball from the general mesoblast in which it is embedded. The *choroid* is developed from the mesoblast on the outside of the optic cup and the iris by the growing forward of the anterior edge of the optic cup, both layers of which becoming pigmented remain as the uvea. Externally the choroidal mesoblast grows inward to form the main structure. The ciliary processes arise from the hypertrophy of the edge of the optic cup which forms folds into which the choroidal mesoblast grows, and in which blood-vessels and pigment-cells develop.

The iris is formed rather late, as a circular septum projecting inward, from the fore part of the choroid, between the lens and the cornea. In the eye of the fœtus of mammalia, the pupil is closed by a delicate membrane, the *membrana pupillaris*, which forms the front portion of a highly vascular membrane that, in the fœtus, surrounds the lens, and is named the *membrana capsulo-pupillaris* (fig. 526). It is supplied with blood by a branch of the *arteria centralis retinæ*, which, passing forward to the back of the lens, there subdivides. The membrana capsulo-pupillaris withers and disappears in the human subject a short time before birth.



Fig. 526.—Blood-vessels of the capsulo-pupillary membrane of a new-born kitten, magnified. The drawing is taken from a preparation injected by Tiersch, and shows in the central part the convergence of the net-work of vessels in the pupillary membrane. (Kölliker.)

The eyelids of the human subject and mammiferous animals, like those of birds, are first developed in the form of a ring. They then extend over the globe of the eye until they meet and become firmly agglutinated to each other. But before birth, or in the carnivora after birth, they again separate.

**The Ear.**—Very early in the development of the embryo a depression or ingrowth of the epiblast occurs on each side of the head which deepens and soon becomes a closed follicle. This *primary optic vesicle*, which closely corresponds in its formation to the lens follicle in the eye, sinks down to some distance from the free surface; from it are developed the epithelial lining of the *membranous* labyrinth of the internal ear, consisting of the vestibule and its semicircular canals and the scala media of the cochlea. The surrounding mesoblast gives rise to the various fibrous bony and cartilaginous parts which complete and inclose this membranous labyrinth, the bony semicircular canals, the walls of the cochlea with its scala vestibuli and scala tympani. In the mesoblast between the primary optic vesicle and the brain, the auditory nerve is gradually differentiated and forms its central and peripheral attachments to the brain and internal ear respectively. According to some authorities, however, it is said to take its origin from and grow out of the hind brain.

The Eustachian tube, the cavity of the tympanum, and the external auditory passage, are remains of the first branchial cleft. The membrana tympani divides the cavity of this cleft into an internal space, the tympanum, and the external meatus. The mucous membrane of the mouth, which is prolonged in the form of a diverticulum through the Eustachian tube into the tympanum, and the external cutaneous system come into relation with each other at this point; the two membranes being separated only by the proper membrane of the tympanum.

The pinna or external ear is developed from a process of integument in the neighborhood of the first and second visceral arches, and probably corresponds to the gill-cover (operculum) in fishes.

**The Nose.**—The nose originates like the eye and ear in a depression of the superficial epiblast at each side of the fronto-nasal process (primary olfactory groove), which is at first completely separated from the cavity of the mouth, and gradually extends backward and downward till it opens into the mouth.

The outer angles of the fronto-nasal process, uniting with the maxillary process on each side, convert what was at first a groove into a closed canal.

### THE ALIMENTARY CANAL.

The alimentary canal in the earliest stages of its development consists of three distinct parts—the fore and hind gut ending blindly at each end of the body, and a middle segment which communicates freely on its ventral surface with the cavity of the yolk-sac through the vitelline or omphalo-mesenteric duct.

From the fore-gut are formed the pharynx, œsophagus, and stomach; from the hind-gut, the lower end of the colon and the rectum. The mouth is developed by an involution of the epiblast between the maxillary and mandibular processes, which becomes deeper and deeper till it reaches the blind end of the fore-gut, and at length communicates freely with the pharynx by the absorption of the partition between the two.

At the other end of the alimentary canal the anus is formed in a precisely similar way by an involution from the free surface, which at length opens into the hind-gut. When the depression from the free surfac does not reach the intestine, the condition known as imperforate anu results. A similar condition may exist at the other end of the alimentary canal from the failure of the involution which forms the mouth, t meet the fore-gut. The middle portion of the digestive canal become more more and closed in till its originally wide communication with th yolk-sac becomes narrowed down to a small duct (vitelline). This duc usually completely disappears in the adult, but occasionally the proximal portion remains as a diverticulum from the intestine. Sometimes a fibrous cord attaching some part of the intestine to the umbilicus, remains to represent the vitelline duct. Such a cord has been known to cause in after-life strangulation of the bowel and death.



Fig. 527.—Outlines of the form and position of the alimentary canal in successive stages c its development. A, alimentary canal, etc., in an embryo of four weeks; B, at six weeks; C, a eight weeks; D, at ten weeks; *l*, the primitive lungs connected with the pharynx; *s*, the stomach *d*, duodenum; *i*, the small intestine; *i'*, the large; *c*, the cæcum and vermiform appendage; *r*, th rectum; *cl*, in A, the cloaca; *a*, in B, the anus distinct from *s i*, the sinus uro-genitalis; *s*, th yolk-sac; *v i*, the vitello-intestinal duct; *u*, the urinary bladder and urachus leading to the a lantois; *g*, genital ducts. (Allen Thomson.)

The alimentary canal lies in the form of a straight tube close beneath the vertebral column, but it gradually becomes divided into its special parts, stomach, small intestine, and large intestine (fig. 527), and at the same time comes to be suspended in the abdominal cavity by means of a lengthening mesentery formed from the splanchnopleure which attaches it to the vertebral column. The stomach originally has the same direction as the rest of the canal; its cardiac extremity being superior, its pylorus inferior. The changes of position which the alimentary canal undergoes may be readily gathered from the accompanying figures (fig. 527).

**Pancreas and Salivary Glands.**—The principal glands in connection with the intestinal canal are the salivary, pancreas, and the liver. In mammalia, each salivary gland first appears as a simple canal with bud-like processes (fig. 528), lying in a gelatinous nidus or blastema, and communicating with the cavity of the mouth. As the development of the gland advances, the canal becomes more and more ramified, increasing at the expense of the blastema in which it is still inclosed. The branches or salivary ducts constitute an independent system of closed tubes (fig. 528). The pancreas is developed exactly as the salivary glands, but is developed from the hypoblast lining the intestine, while the salivary glands are formed from the epiblast lining the mouth.



Fig. 528.—Lobules of the parotid, with the salivary ducts, in the embryo of the sheep, at a more advanced stage.

**The Liver.**—The liver is developed by the protrusion, as it were, of a part of the walls of the fore-gut, in the form of two conical hollow branches, which embrace the common venous stem (figs. 529, 530). The outer part of these cones involves the omphalo-mesenteric vein, which breaks up in its interior into a plexus of capillaries, ending in venous trunks for the conveyance of the blood to the heart. The inner portion of the cones consists of a number of solid cylindrical masses of cells, derived probably from the hypoblast, which become gradually hollowed by the formation of the hepatic ducts, and among which blood-vessels are rapidly developed. The gland cells of the organ are derived from the hypoblast, the connective tissue and vessels without doubt from th mesoblast. The gall-bladder is developed as a diverticulum from th hepatic duct. The spleen, lymphatic, and thymus glands are develope from the mesoblast: the thyroid partly also from the hypoblast, which grows into it as a diverticulum from the fore-gut.



Fig. 529.—Diagram of part of digestive tract of a chick (4th day). The black line represen hypoblast, the outer shading mesoblast; *lg*, lung diverticulum with expanded end forming pri mary lung-vesicle; *St*, stomach; *l*, two hepatic diverticula, with their terminations united b solid rows of hypoblast cells; *p*, diverticulum of the pancreas with the vesicular diverticul coming from it. (Gotte.)



Fig. 530.—Rudiments of the liver on the intestine of a chick at the fifth day of incubatio 1, heart; 2, intestine; 3, diverticulum of the intestine in which the liver (4) is developed; 5, pa of the mucous layer of the germinal membrane. (Müller.)

## THE RESPIRATORY APPARATUS.

**The Lungs,** at their first development, appear as small tubercles or diverticula from the abdominal surface of the œsophagus.

The two diverticula at first open directly into the œsóphagus, but as they grow, a separate tube (the future trachea) is formed at their point of fusion, opening into the œsophagus on its anterior surface. These primary diverticula of the hypoblast of the alimentary canal send off secondary branches into the surrounding mesoblast, and these again give off tertiary branches, forming the air-cells. Thus we have the lungs formed: the epithelium lining their air-cells, bronchi, and trachea being derived from the hypoblast, and all the rest of the lung-tissue, nerves, lymphatics, and blood-vessels, cartilaginous rings, and muscular fibres of the bronchi from the mesoblast. The diaphragm is early developed.



Fig. 531 illustrates the development of the respiratory organs. A, is the œsophagus of a chick on the fourth day of incubation, with the rudiments of the trachea on the lung of the left side, viewed laterally; 1, the inferior wall of the œsophagus; 2, the upper portion of the same tube; 3, the rudimentary lung; 4, the stomach; B, is the same object seen from below, so that both lungs are visible. C, shows the tongue and respiratory organs of the embryo of a horse; 1, the tongue; 2, the larynx; 3, the trachea; 4, the lungs viewed from the upper side. (After Rathke.)

## THE GENITO-URINARY APPARATUS.

The **Wolffian bodies** are organs peculiar to the embryonic state, and may be regarded as temporary, rather than rudimental, kidneys; for although they seem to discharge the functions of these latter organs, they are not developed into them.

The Wolffian duct makes its appearance at an early stage in the history of the embryo, as a cord running longitudinally on each side in the mass of mesoblast, which lies just externally to the intermediate cell-mass (*ung*, fig. 532). This cord, at first solid, becomes gradually hollowed out to form a tube (Wolffian) which sinks down till it projects beneath the lining membrane into the pleuro-peritoneal cavity.

The primitive tube thus formed sends off secondary diverticula at frequent intervals which grow into the surrounding mesoblast: tufts of vessels grow into the blind ends of these tubes, invaginating them and producing Malpighian bodies very similar in appearance to those of the permanent kidney, which constitute the substance of the Wolffian body. Meanwhile another portion of mesoblast between the Wolffian body and the mesentery projects in the form of a ridge, covered on its free surface



Fig. 532.—Transverse section of embryo chick (third day). *mr*, rudimentary spinal cord; the primitive central canal has become constricted in the middle; *c h*, notochord; *u w h*, primordial vertebral mass; *m*, muscle-plate; *dr*, *df*, hypoblast and visceral layer of mesoblast lining groove, which is not yet closed in to form the intestines; *a o*, one of the primitive aortæ; *u n*, Wolffian body; *u n g*, Wolffian duct; *v c*, vena cardinalis; *h*, epiblast; *h p*, somatopleure and its reflection to form *a f*, amniotic fold; *p*, pleuro-peritoneal cavity. (Kölliker.)

with epithelium termed *germ epithelium*. From this projection is developed the reproductive gland (ovary or testis as the case may be).

Simultaneously, on the outer wall of the Wolffian body, between it and the body-wall on each side, an involution is formed from the pleuroperitoneal cavity in the form of a longitudinal furrow, whose edges soon close over to form a duct (Müller's duct).

All the above points are shown in the accompanying figures, 532, 533.

The Wolffian bodies, or temporary kidneys, as they may be termed, give place at an early period in the human fœtus to their successors, the permanent kidneys, which are developed behind them. They diminish rapidly in size, and by the end of the third month have almost entirely disappeared. In connection, however, with their upper part, in the male, there are developed from a new mass of blastema, the *vasa efferentia*, *coni vasculosi*, and *globus major* of the epididymis; and thus is brought about a direct connection between the secreting part of the testicle and its duct. The Wolffian *ducts* persist in the male, and are developed to form the body and globus minor of the epididymis, the vas deferens, and ejaculatory duct on each side, the vesiculæ seminales forming diverticula from their lower part. In the female a small relic of the Wolffian body persists as the *parovarium*; in the male a similar relic is termed the *organ of Giraldès*. The lower end of the Wolffian duct remains in the female as the *duct of Gaertner* which descends toward, and is lost upon, the anterior wall of the vagina.

From the lower end of the Wolffian duct a diverticulum grows back along the body of the embryo toward its anterior extremity, and ultimately forms the ureter. Secondary diverticula are given off from it and grow into the surrounding blastema of blood-vessels and cells.

Malpighian bodies are formed just as in the Wolffian body, by the invagination of the blind knobbed end of these diverticula by a tuft of vessels. This process is precisely similar to the invagination of the primary optic vesicle by the rudimentary lens. Thus the kidney is developed, consisting at first of a number of separate lobules; this condition remaining throughout life in many of the lower animals, *e.g.*, seals and whales, and traces of this lobulation being visible in the human fœtus at birth. In the adult all the lobules are fused into a compact solid organ.



Fig. 533.—Section of intermediate cell-mass on the fourth day. *m*, mesentery; *L*, somatopleure; *a*, germinal epithelium, from which *z*, the duct of Müller, becomes involuted; *a*, thickened part of germinal epithelium in which the primitive ova *O* and *o*, are lying; *E*, modified mesoblast, which will form the stroma of the ovary; *WK*, Wolffian body; *y*, Wolffian duct; × 160. (Waldeyer.)

The supra-renal capsules originate in a mass of mesoblast just above the kidneys; soon after their first appearance they are very much larger than the kidneys (see fig. 535), but by the more rapid growth of the latter this relation is soon reversed.

The first appearance of the generative gland has been already described: for some time it is impossible to determine whether an ovary or testis will be developed from it; gradually however the special characters belonging to one of them appear, and in either case the organ soon begins to assume a relatively lower position in the body; the ovaries being ultimately placed in the pelvis; while toward the end of fœtal existence the testicles descend into the scrotum, the testicle entering the internal inguinal ring in the seventh month of fœtal life, and completing its descent through the inguinal canal and external ring into the scrotum by the end of the eighth month. A pouch of peritoneum, the *processus vaginalis*, precedes it in its descent, and ultimately forms



Fig. 534.—Diagram showing the relations of the female (the left-hand figure ♀) and of the male (the right-hand figure ♂) reproductive organs to the general plan (the middle figure of these organs in the higher vertebrata (including man). *C l*, cloaca: *R*, rectum: *B l*, urinary bladder; *U*, ureter; *K*, kidney; *U h*, urethra; *G*, genital gland, ovary, or testis; *W*, Wolffian body; *W d*, Wolffian duct; *M*, Müllerian duct; *P s t*, prostate gland; *C p*, Cowper's gland; *C sp*, corpus spongiosum; *C c*, corpus cavernosum.

*In the female.—V*, vagina; *U t*, uterus; *F p*, Fallopian tube; *G t*, Gaertner's duct; *P v*, parovarium; *A*, anus; *C c*, *C s p*, clitoris.

*In the male.—C s p*, *C c*, penis; *U t*, uterus masculinis; *V s*, vesicula seminalis; *V d*, vas deferens. (Huxley.)

the tunica vaginalis or serous covering of the organ; the communication between the tunica vaginalis and the cavity of the peritoneum being closed only a short time before birth. In its descent, the testicle or ovary of course retains the blood-vessels, nerves, and lymphatics, which were supplied to it while in the lumbar region, and which are compelled to accompany it, so to speak, as it assumes a lower position in the body. Hence the explanation of the otherwise strange fact of the origin of these parts at so considerable a distance from the organ to which they are distributed.

*Descent of the Testicles into the Scrotum.*—The means by which the descent of the testicles into the scrotum is effected are not fully and exactly known. It was formerly believed that a membraneous and partly muscular cord, called the *gubernaculum testis*, which extends while the testicle is yet high in the abdomen, from its lower part, through the abdominal wall (in the situation of the inguinal canal) to the front of the pubes and lower part of the scrotum, was the agent by the contraction of which the descent was effected. It is now generally thought, however, that such is not the case, and that the descent of the testicle and ovary is rather the result of a general process of development in these and neighboring parts, the tendency of which is to produce this change in the relative position of these organs. In other words, the descent is not the result of a mere mechanical action, by which the organ is dragged down to a lower position, but rather one change out of many which attend the gradual development and re-arrangement of these organs. It may be repeated, however, that the details of the process by which the descent of the testicle into the scrotum is affected are not accurately known.

The homologue, in the female, of the gubernaculum testis is a structure called the *round ligament of the uterus*, which extends through the inguinal canal, from the outer and upper part of the uterus to the subcutaneous tissue in front of the symphysis pubis.

At a very early stage of fœtal life, the Wolffian ducts, ureters, and Müllerian ducts, open into a receptacle formed by the lower end of the allantois, or rudimentary bladder; and as this communicates with the lower extremity of the intestine, there is for the time, a common receptacle or *cloaca* for all these parts, which opens to the exterior of the body through a part corresponding with the future anus, an arrangement which is permanent in reptiles, birds, and some of the lower mammalia. In the human fœtus, however, the intestinal portion of the cloaca is cut off from that which belongs to the urinary and generative organs; a separate passage or canal to the exterior of the body, belonging to these parts, being called the *sinus uro-genitalis*. Subsequently, this canal is divided, by a process of division extending from before backward or from above downward, into a 'pars urinaria' and a 'pars genitalis.' The former, continuous with the *urachus*, is converted into the urinary bladder.

The Fallopian tubes, the uterus, and the vagina are developed from the Müllerian ducts (fig. 535, *m*), whose first appearance has been already described. The two Müllerian ducts are united below into a single cord, called the *genital cord*, and from this are developed the vagina, as well as the cervix and the lower portion of the body of the uterus; while the ununited portion of the duct on each side forms the upper part of the uterus, and the Fallopian tube. In certain cases of arrested or abnormal development, these portions of the Müllerian ducts may not become fused together at their lower extremities, and there is left cleft or horned condition of the upper part of the uterus resembling condition which is permanent in certain of the lower animals.

In the male, the Müllerian ducts have no special function, and ar but slightly developed. The hydatid of Morgagni is the remnant of th upper part of the Müllerian duct. The small prostatic pouch, *uteru masculinus*, or *sinus pocularis*, forms the atrophied remnant of the dis



Fig. 535.—Diagram of the Wolffian bodies, Müllerian ducts and adjacent parts previous t sexual distinction, as seen from before. *sr*, the supra-renal bodies; *r*, the kidneys; *ot*, commo blastema of ovaries or testicles; W, Wolffian bodies; *w*, Wolffian ducts; *m m*, Müllerian ducts *g c*, genital cord; *u g*, sinus urogenitalis; *i*, intestine; *cl*, cloaca. (Allen Thomson.)

tal end of the genital cord, and is, of course, therefore, the homologue in the male, of the vagina and uterus in the female.

The external parts of generation are at first the same in both sexes.

The opening of the genito-urinary apparatus is, in both sexes, bounde by two folds of skin, while in front of it there is formed a penis-lik body surmounted by a glans, and cleft or furrowed along its under sur face. The borders of the furrows diverge posteriorly, running at th sides of the genito-urinary orifice internally to the cutaneous folds jus mentioned. In the female, this body becoming retracted, forms th clitoris, and the margins of the furrow on its under surface are converte into the nymphæ or labia minora, the labia majora pudendæ being con stituted by the great cutaneous folds. In the male fœtus, the margin of the furrow at the under surface of the penis unite at about the fourteenth week, and form that part of the urethra which is included in the penis. The large cutaneous folds form the scrotum, and later (in the eighth month of development), receive the testicles, which descend into them from the abdominal cavity. Sometimes the urethra is not closed, and the deformity called hypospadias then results. The appearance of hermaphroditism may, in these cases, be increased by the retention of the testes within the abdomen.

# INDEX.

Abducens nerve, 619
Absorption, 422
  blood-vessels in, 437
  conditions for, 424
  lymphatic system in, 425
  methods of, 422
  places for, 438
  rapidity of, 423
  through the lungs, 440
    the skin, 439
Accelerator centres for heart, 610
Accessory olives, 606
Accommodation of vision, 731
Achromatic spindle, 15
Achromatin, 12
Achroödextrin, 351
Acid albumin, 115
  hydrochloric, 372
Addison's disease, 827
Adenin, 122, 125
Adenoid tissue, 46
Adipose tissue, 48
  development of, 49
  uses of, 50
Adrenals, 827
Afferent impulses, 568
After-birth, the, 803
  -images, 742
  -sensations, 681
Agglutinative substances, 175
Air cells, 272
Akinesis, 13
Albumin, acid, 115
  alkali, 116
  native, 114
  serum, 115
Albuminates, 115
Albuminoids, 120
  effect of diet of, 444
Albumose, 375
Alimentary canal, development of, 831
Alkali albumin, 116
Allantoin, 125, 493
Allantois, 799
Alloxan, 122
Aluminum, 135
Amides, 122
Amido-acids, 122
Amidulin, 352
Amines, 122
Amitosis, 18
Amitotic division, 18
Ammonium carbamate, 445
  carbonate, 444
  sulphate reaction, 113
Amnion, 798
Amœboid movement, 4
Amylolytic ferments, 127
Amylopsin, 396
Anabolism, 441
Anacrotic wave, 231
Anaphases, 17
Anelectrotonus, 545
Animal heat, 463
  kingdom, classification of, xii
Anode, 544
Ano-spinal centre, 594
Anterior pyramids, 603
  decussation of, 604
Antipeptone, 395
Apnœa, 299
Appendices epiploicæ, 390
Aqueduct of Sylvius, 599
Area opaca, 789
  pellucida, 789
  vasculosa, 797
Areolar tissue, 45
Aromatic series, 132
Arterial flow, 224
Arteries, 191
  development of, 818
  nerves of, 193

- Arteries, structure of, 191
- Articulate sounds, 564
- Asphyxia, 305
  - cause of death in, 307
- Astigmatism, 738
- Atmosphere, composition of, 284
- Attraction sphere, 13
- Auditory centre, 656
  - nerve, 621, 698
  - vesicles, 797
- Auerbach's plexus, 384
- Augmentation function of nerve centres, 573
- Augmentor nerve, 251
- Auricles, action of, 200
- Axis cylinder, 94
- Axone, 91

- BASOPHIL, 154
- Beef, composition of, 340
- Bezold's ganglion, 246
- Bidder's ganglion, 246
- Bile, chemic composition of, 403
  - discharge of, 408
  - disposal of, 409
  - excretory function of, 410
  - fatty substances of, 406
  - functions of, 406, 407
  - gases of, 406
  - inorganic constituents of, 406
  - mode of secretion of, 408
  - mucus in, 406
  - nervous influence on, 410
  - pigments of, 404
  - preparation of, 404
  - salts, 403
  - test for, 404, 405
- Bilifulvin, 405
- Bilifuscin, 126
- Bilihumin, 126
- Bilin, 403
- Biliprasin, 126
- Bilirubin, 125, 404
- Biliverdin, 126, 405
- Binaural sensations, 709
- Binocular vision, 756
- Bioplasm, 2
- Biuret reaction, 113
- Bladder, urinary, 483
- Blastema, 2
- Blastoderm, 22, 787
- Blastosphere, 785
- Blind spot, 741
- Blood, 140
  - arterial flow, 224
  - buffy coat, 143
  - capillary flow, 234
  - carbon dioxide of, 171
  - chemical composition of, 157
  - circulation of, 182
    - in fœtus, 822
  - coagulation of, 142
    - fibrin in, 142
    - theories of, 145
  - corpuscles of, 148
    - chemical composition of, 16
    - colored, 148
    - colored, action of reagents 151
    - colored, development of, 1
    - colored, enumeration of, 15
    - colored, origin of, 178
    - colored, varieties of, 150
    - colorless, 153
    - colorless, action of reagent 156
    - colorless, amœboid move of, 155
    - colorless, origin of, 179
    - colorless, varieties of, 154
  - defibrination of, 144
  - differences between arterial and nous, 246
  - flow, regulation of, 243
  - gases of, 161
  - laking of, 140
  - oxygen of, 162
  - plasma, 140
  - plates, 156
  - pressure, 216
    - in man, 233
  - proofs of circulation of, 262
  - quantity of, 141
  - respiratory changes in, 289
  - serum, chemical composition of,
  - specific gravity of, 140
  - uses of, 140
  - variations in composition of, 1
  - velocity of flow, 237
  - venous flow, 237
- Blood-vessels, development of, 814
- Blushing, 260
- Body, chemical composition of, 110
- Bone, 55

- Bone, canaliculi of, 57
  - development of, 60
  - functions of, 69
  - growth of, 68
  - Haversian canals of, 58
  - lacunæ of, 57, 59
  - marrow, 56
  - ossification in cartilage, 62
    - in membrane, 61
  - periosteum of, 57
- Bowman's theory of urine secretion, 500
- Brain, 596
  - development of, 825
  - distinctive characters of human, 640
  - fore-, 600, 827
  - gray matter in, 685
  - gyri of, 683
  - hind-, 600, 827
  - lobes of, 682
  - mid-, 600, 827
  - motor areas of, 641
    - areas of human, 644
    - areas of monkey's, 642
    - tracts in, 645
  - relation of different parts, 596
  - sulci of, 685
  - weight of, 689
- Branchial clefts, 810
  - folds, 810
- Bronchi, 267
- Brownian movement, 8
- Brunner's glands, 387
- Buffy coat, 143
- Bulb, the, 597, 602
  - centres in, 609
  - connections with cerebrum and cerebellum, 607
  - functions of, 608
- Bulbus arteriosus, 817
- Burdach, column of, 580

- CÆCUM, 389
- Calcium fluoride, 134
- Calorimeter, 466
- Cane sugar, 130
- Capillaries, development of, 815
  - purpose of, 236
  - structure of, 194
- Capillary electrometer, 255
  - flow, 234
- Carbohydrates, 118
  - as foods, 448
  - effect of excess as food, 452
- Carbon dioxide, secretion of, 285
- Carbonates, 134
- Cardiac cycle, 204
  - nerves, 251
- Cardio-accelerator centres, 610
- Cardiogram, 209
- Cardiograph, 209
- Cardio-inhibitory centre, 251, 610
- Carotid gland, 338
- Cartilage, 51
  - development of, 55
  - functions of, 55
  - hyaline, 51
  - white fibre, 54
  - yellow elastic, 53
- Casein, 120, 324
  - insoluble calcium, 119
  - soluble, 119
- Caseinogen, 119, 323
- Caudate nucleus, 680
- Cell, difference between plant and animal, 17
  - division of, 13
  - functions of, 18
  - nucleus of, 11
  - reticulum of, 9
  - structure of, 9
- Cells, decay and death of, 28
  - fixed, 40
  - functions of, 22
  - migratory, 41
  - modes of connection, 27
  - plasma, 41
  - shapes of, 26
- Cellulose, 351
- Central lobe of brain, 633
  - canal of cord, 575
- Centre for lymph hearts, 595
  - for muscle tone, 595
- Centres, motor, 641
  - sensory, 654
- Centrifugal nerves, 568
- Centripetal nerves, 568
- Centrosome, 16
- Cerebellum, 658
  - connection with bulb, 658
  - functions of, 662
- Cerebral ventricles, 598
- Cerebrin, 125

Cerebro-spinal axis, summary of impulses in, 665
  fluid, 575
  nervous system, 569
Cerebrum, 634
  arrangement of parts of, 638
  chemical composition of, 638
  connection with bulb, 607
  effects of removal of, 649
  functions of, 648
  motor areas of cortex, 641
  unilateral action of, 651
  weight of, 639
Cerumen, 507
Cheyne-Stokes breathing, 305
Chlorides, estimation of, 139
Chlorophyll, 18
Choletelin, 492
Chondrin, 121
Chorda tympani, 355, 620
Chordæ tendineæ, 202
Chorion, 800
Chorionic villi, 801
Choroidal fissure, 829
Choroid plexus, 598
Chromatin, 12
Chromophanes, 746
Chromoplasm, 15
Chromo-proteids, 118
Chromosome, 16
Chyle, 434
  corpuscles, 434
Chyme, 374
Cilia, 35
Ciliary motion, 36
Circulation, coronary, 256
  effect of respiration on, 300
  in brain, 241
  in erectile structures, 243
  local peculiarities of, 241
  of blood, 182
  proofs of, 262
  regulation of flow, 243
  time of, 240
  velocity of, 237
Clark's column, 579
Claustrum, 631
Clitoris, 768
Coagulation, calcium salts in, 146
  conditions affecting, 147
  of blood, 142
    theories of, 145
Coccygeal gland, 338
Cochlea, 697
Cohnheim's fields, 85
Cold, influence of extreme, 473
Collagen, 55, 120
Collaterals, 98
Colloids, 179
Colon, 389
Color blindness, 754
  complemental, 754
  Hering's theory of, 752
  sensations of, 752
  Young's and Helmholtz's theo 752
Colorless corpuscles, 153
    and thymus gland, 338
Colostrum, 323
  corpuscles of, 321, 323
Columnæ carneæ, 190
Column of Burdach, 580
  of Goll, 580
Common sensations, 674
Complemental air, 281
Compound proteids, 118
Concentric corpuscles of Hassall, 337
Conjunctiva, 711
Connective tissues, 40
  adenoid, 46
  adipose, 48
  areolar, 45
  basement membrane, 51
  classification of, 43
  cells of, 40
  development of, 47
  fibrous, 47
  gelatinous, 46
  intercellular substance of, 41
  structure of, 40
  vessels and nerves of, 50
  white fibrous, 42, 43
  yellow elastic, 44
Consonants, 564
Contractility of muscle, 521
Cornea, structure of, 713
Corona radiata, 629
Coronary circulation, 256
Corpora cavernosa, 773
  dentata, 602, 632
  geniculata, 602, 632
    functions of, 664
  quadrigemina, 602, 632
    functions of, 664

Corpora striata, 602, 680
        functions of, 657
Corpus albicans, 598
    Arantii, 191
    callosum, 597
    luteum, 778
    spongiosum, 778
    striatum, 597, 602, 632
Corpuscles of blood, 148, 153
    of Golgi, 107
    of Krause, 106
    of Meissner, 105
Coughing, 292
Cowper's glands, 778
Cranial nerves, 611
    development of, 824
Cranium, development of, 809
Crassamentum, 142
Crura cerebri, 628
Crusta, 629
    petrosa, 76
    phlogistica, 148
Crypts of Lieberkühn, 386
Crystalloids, 179
Cutaneous sensations, centre for, 657
Cutis vera, 505
Cystin in urine, 495

DALTONISM, 754
Daniel's battery, 522
Decidua reflexa, 808
    serotina, 808
    vera, 808
Decussation of pyramids, 605
Defecation, 420
    centre for, 594
    nervous mechanism of, 420
Degeneration in spinal cord, 581
Deglutition, 365
    centres, 609
    nervous mechanism of, 366
    time occupied in, 366
Demarcation currents, 516
Demilunes of Heidenhain, 348
Dendrite, 91
Dental papilla, 78
Depressor nerve, 260
Descemet, membrane of, 714
Descendens noni, 627
Deutero-proteose, 375, 395
Development, 22, 784, 806
Dextrin, 180
Dextrose, 180
Diabetes mellitus, 452
Diabetic centre, 611
Dialysis, 179
Diapedesis, 236
Diaphragm, in respiration, 274, 277
Diastole of heart, 200, 204
Dicrotic wave, 232
Diencephalon, 827
Diet, effect of albuminoid, 453
        of carbohydrate, 453
        of fatty, 458
        of proteid, 458
    normal requisites, 455
        tables, 456, 457
    variations in, 458
Diffusion, 179
    of impulses in cord, 572
Digestion, 339, 344
    enzymes in, 344
    in intestines, 392
    in mouth, 345
    in stomach, 371
Diplopia, 613, 756
Direct cell division, 13
Direction, visual estimation of, 750
Discharge of nerve impulses, 571
Dobie's line, 85
Dogiel's cells, 346
Dreams, 658
Du Bois-Reymond's induction coil, 523
    key, 528
Ductless glands, 325
Ducts of Cuvier, 821
Ductus arteriosus, 819
    venosus, 828
Dura mater, 573
Dyspnœa, 298, 305

EAR, cochlea of, 697
    development of, 831
    external, 693
    internal, 696
    membranous labyrinth of, 697
    middle, 694
    ossicles of, 695
    vestibule of, 696
Eck's fistula, 446
Edestrine, 117
Efferent impulses, 568
Egg albumen, 114
    yolk, 785

Eggs, as food, 841
  holoblastic, 785
  meroblastic, 785
Eighth nerve, 621
    cochlear branch, 621
    vestibular branch, 622
Elastin, 43, 21
Electrodes, 522
  non-polarizable, 517
Electrotonus, 544
Eleventh nerve, 626
Embryonic shield, 790
Emission of semen centre, 594
Emulsification, 396
Enamel cap, 79
  organ, 76
Enchylema, 9
Endocardiac pressure, 209
Endocardium, 189
Endoderm, 23
Endomysium, 83
Endoneurium, 97
Endothelium, 39
Energy, income and output of, 456
Enterokinase, 394
Enzymes, 344
Eosinophile, 154
Epencephalon, 827
Epiblast, 22, 789
  organs developed from, 806
Epicardium, 183
Epidermis, 28
  structure of, 503
Epididymis, 769
Epiglottis, 266
Epimysium, 82
Epinephrin, 330
Epineurium, 97
Epithelial tissues, 28
Epithelium, 29
  classification of, 29
  ciliated, 34
  columnar, 33
  functions of, 39
  glandular, 33
  prickle cell, 38
  simple, 29
  squamous, 29
  stratified, 37
  transitional, 37
Erection centre, 595
Erythroblasts, 178
Erythrodextrin, 352
Excreta, elements of, 442
Excretion, 474
  from skin, 510
Expiration, quiet, 277
  forced, 278
Expired air, 284
  changes effected in, 285
  volume of, 286
External capsule, 631
Extremities, development of, 812
Eye, anatomy of, 711
  and the camera, 740
  chambers of, 712
  chromatic aberration, 739
  development of, 828
  movements of, 735
  muscles concerned in, 735
  optical axis, 727
  refractive surfaces and media, 727
  spherical aberration of, 738
Eyeball, 711
  blood-vessels of, 726
  corneo-scleral junction, 718
  iris of, 716
  lens of, 717
  nerves of, 714
  retina of, 719
  structure of choroid coat, 715
    of cornea, 718
    of sclerotic coat, 712
Eustachian tube, 705
  valve, 187

FACIAL nerve, 619
  functions of, 620
  paralysis of, 620
  relation to taste, 621
  secretory, 620
Fæces, composition of, 418
Fallopian tubes, 766
Fasciculus cuneatus, 603
  gracilis, 603
  of Rolando, 603
  solitarius, 622
Fat-splitting ferments, 128
Fats, 128
  as food, 448
  digestion of, 396, 397
  emulsification of, 396
  saponification of, 396
Fatty acids, 131

Fechner's law, 793
Fenestra ovalis, 696
Fermentation in intestine, 414
Ferments, 127
Fibres of Remak, 95
Fibrin, 118, 142
  digestion of, 376
  ferment, 146
  formation of, 143
  sources of, 146
Fibrinogen, 117, 145
Fictitious feeding, 380
Fifth nerve, 614
  ventricle, 598
Fillet, 628, 631, 647
Filtration, 423
  of urine, 496
Fission, 9
Fixed cells, 40
Fœtal membranes, 797
Food and digestion, 339
  effects of deprivation of, 453
    of too much, 452
  mastication of, 345
  salts of, 339, 453
Foods, 339
  effect of cooking, 343
  heat-production from, 446
  income and output of energy, 458
  inorganic, 339
  liquid, 343
  nitrogenous, 339
  non-nitrogenous, 342
  organic, 339
  percentage composition of, 340, 341
Foramen of Munro, 598
Forced movements, 664
Fore-brain, 600, 827
Fore-gut, 797
Form, estimation of, 750
Fornix, 598
Fossa ovalis, 187
Fourth nerve, 613
Fovea centralis, 716, 719
Frontal lobe, 632

GALACTOPHOROUS ducts, 320
Galactose, 131
Gall bladder, 402
Galvanic currents, 522
Ganglia, spinal, functions of, 587
Gastric digestion, products of, 375
Gastric digestion, time of, 377
  juice, 371
    action on adipose tissue, 377
    action on milk, 376
    action on proteids, 374
    anti-putrefactive action of, 377
    chemical composition of, 371, 372
    combined acid in, 373
    enzymes of, 373, 374
    fictitious meals, action on, 380
    functions of, 374
    quantity of, 372
    peptones as a stimulus to secretion of, 380, 381
    theories of secretion of hydrochloric acid in, 373
  secretion, nervous mechanism of, 379
Gelatin, 120
Gelatinous tissue, 46
Gemmation, 9
Genital organs of female, 762
    of male, 768
Genito-spinal centre, 594
Germinal disc, 764
  matter, 2
  spot, 764
  vesicle, 765
  wall, 793
Glands, ductless, 325
  mammary, 819
  secreting, 315
  types of, 315
Globulins, 116
Globus pallidus, 630
Glomerulus, 479
Glosso-pharyngeal nerve, 622
    in respiration, 296
Glucose, 351, 396
Gluconucleo-proteids, 118
Glucoproteids, 118
Glucose, 130
  quantitative estimation of, 136
  tests for, 135
Glycin, 123
Glycogen, 129
  destination of, 450
  relation to metabolism, 451
  sources of, 449
Glycogenesis, 449
Glycocol, 123
Glycosuria, 451

- Gmelin's test, 405
- Goblet cells, 34
- Golgi, corpuscles of, 107
  - cells of, 661
- Goll, column of, 580
- Graafian follicles, 763
- Gramme-calorie, 466
- Granulose, 351
- Gray matter of brain, 602
  - of cord, 578
- Guanidin, 123
- Guanin, 122, 125
- Gullet, 364
- Gustatory buds, 362
  - cells, 362
- Gyrus fornicatus, 633

- HÆMACHROMOGEN, 170
- Hæmacytometer, 156
- Hæmatin, 169
- Hæmatoidin, 170
- Hæmatoporphyrin, 170
- Hæmin, 171
- Hæmoglobin, 164
  - action of gases on, 166
  - derivatives of, 169
  - estimation of, 167
  - reduced, 166
- Hæmoglobinometer, 167
- Hæmolymph glands, 434
- Hæmolysis, 174
- Hair, 508
- Haversian canals, 58
- Hearing, physiology of, 701
- Heart, 183
  - action of, 200
  - anatomy of, 188
  - capacity of, 188
  - chambers of, 185
  - character of contraction, 247
  - coronary circulation of, 256
  - cycle of, 204
  - development of, 818
  - electrical phenomena of, 255
  - force of action, 215, 244
  - frequency of action, 214, 244
  - ganglia of, 246
  - impulse of, 207
  - influence of nervous system, 249
    - of drugs, 253
    - of sympathetic, 251
    - of temperature, 252
- Heart, influence of vagus, 249
  - metabolism of, 255
  - methods of investigating beat, 2
  - morphology of, 816
  - muscle, 88
    - properties of, 244
  - nerves of, 246
  - origin of nerve fibres, 251
  - regulation of force and frequenc
    contraction, 244
  - size of, 188
  - sounds of, 205
  - structure of, 188
  - valves of, 189
    - action of, 201
  - weight of, 188
  - work per diem, 216, 459
- Heat, animal, 463
  - accompaniment of muscle cont
    tion, 528
  - dissipation of, 468
    - from lungs, 469
    - from skin, 468
  - influence of extreme, 473
    - of nervous system on produc
      of, 471
  - -producing tissues, 466
  - production of body, 465
  - regulation of body, 467
  - variations in loss of, 467
    - in production of, 470
- Heidenhain's experiments on urine se
  tion, 501
- Hemianopsia, 655
- Henle's membrane, 45
  - loop, 477
- Henson's disc, 85
- Heteroproteose, 375, 395
- Hiccough, 292
- Hindbrain, 600, 827
- Hippocampus major, 634
  - minor, 634
- Hippuric acid, 124, 491
  - formation of, 448
- Homoiothermal animals, 464
- Hyaloplasm, 9
- Hydrobilirubin, 405, 492
- Hydrochloric acid, 372
  - combined, 373
  - test for free, 373
  - theories of secretion of, 373
- Hymen, 768

Hypermetropia, 738
Hyperpnœa, 305
Hypoblast, 22, 789
    organs developed from, 807
Hypoglossal nerve, 627
Hypoxanthin, 122, 125, 493

ILEO-CÆCAL valve, 391
Income of energy, 458
Indican, 126, 492
Indigo, 126
    in urine, 492
Indirect cell division, 14
Indol, 126, 416
Indoxyl, 416
Induced currents, 523
Induction coil, 523
Inhibition, function of nerve centres in, 578
Inogen, 549
Inorganic foods, 339
Inosite, 131
Insalivation, 346
Inspiration, 274
    forced, 277
    muscles of, 276
    quiet, 276
Intercellular substance, 27, 41
Interlobular veins, 400
Internal capsule, 629, 645
    secretions, 325
Intestinal digestion, 392
        duration of, 418
    influence of nervous system, 417
    secretion, 411
        functions of, 411
Intestine, large, 389
        cæcum of, 389
        colon of, 391
        glands of, 391
        ileo-cæcal valve in, 391
        longitudinal bands of, 390
        mucous membrane of, 391
        structure of, 390
        summary of digestive changes in, 414
    small, 384
        glands of, 386
        lacteals in, 389
        mucosa of, 385
        nerves of, 384
        structure of, 384
Intestine, small, summary of digestive changes in, 411
        valvulæ conniventes of, 385
Intestines, action of micro-organisms in, 414
    absorption from, 438
    defecation, 420
    duration of digestion in, 418
    fæces in, 418
    fermentation in, 415
    gases in, 418
    influences of nervous system on, 417
    movements of, 416
    putrefaction in, 416
Intralobular veins, 401
Intrinsic cells, 580
Invertin, 411
Inverting ferments, 127
Iodothyrin, 327
Iris, 716
Iron, 135
Island of Reil, 633
Iter a tertio ad quartum ventriculum, 599

JACOBSON'S organ, 691
    nerve, 676
Judgment of form and size of bodies, 691
Judgments, 676

KARYOKINESIS, 14
Karyoplasm, 12
Karyosomes, 12
Katabolism, 441
Katacrotic wave, 231
Katelectrotonus, 545
Kathode, 544
Keratin, 121
Kidneys, action of diuretics, 498
    blood-vessels of, 479
    effect of blood pressure on, 498
    factors affecting secretion from, 499
    glomeruli of, 479
    Malpighian bodies of, 475
    nerves of, 482
    structure of, 474
    tubuli uriniferi of, 475
    vasa efferentia of, 481
        recta of, 481
    volume of, 497
Kilogramme-calorie, 466
Krause, corpuscles of, 106

- Krause, membrane of, 86
- Kreatin, 123
- Kreatinin, 124, 448, 493
- Kronecker-Meltzer, theory of deglutition, 365
- Kymograph, 219

- Labyrinth, 696
- Lachrymal gland, 711
- Lactalbumin, 324
- Lacteals, 389, 436
- Lactiferous ducts, 320
- Lacto-globulin, 324
- Lactose, 130
- Lacunæ, 59
- Lævulose, 131
- Laky blood, 141
- Lamina cribrosa, 720
- minæ dorsalis, 792
- ge intestine, 389
    - summary of digestive changes in, 414
- Laryngoscope, 556
- Larynx, 551
    - anatomy of, 552
- Latent period of muscle, 527
- Lateral gray column, cells of, 579
    - plate, 798
- Laughing, 294
- Lecithin, 124
- Leguminous fruits, 343
- Lenticular nucleus, 630
- Leucin, 123
- Leucocytes, 153
- Levers, action of, 538
- Lieberkühn, cysts of, 386
    - jelly, 116
- Life, phenomena of, 1
- Linin, 12
- Lipochromes, 126
- Liquid foods, 343
- Liquor sanguinis, 140
- Lissauer, tract of, 582
- Liver, 398
    - bile capillaries of, 402
    - development of, 833
    - function of, 403
    - gall bladder of, 402
    - glycogenic function of, 449
    - hepatic artery of, 401
        - veins, 401
    - internal secretions of, 331
    - portal canals of, 400
        - vein of, 400
    - structure of, 398
    - urea formation in, 445
- Locus cœruleus, 602, 628
    - niger, 602, 628
- Ludwig's theory of urine secretion,
- Lungs, absorption from, 440
    - blood supply of, 273
    - development of, 835
    - lymphatics of, 274
    - nerves of, 274
    - structure of, 269
- Luxus consumption, 444
- Lymph, 434
    - capillaries, 426
        - origin of, 427
    - channels of absorption, 436
    - chemical composition of, 435
    - flow, 429
    - hearts, 430
        - centres for, 595
    - quantity of, 436
- Lymphatic glands, 430
    - ducts, 426
    - system, 425
        - communications of, 428
        - of diaphragm, 428
    - tissue, 46
- Lymphocyte, 154
- Lymphoid tissue, 46

- Macula lutea, 719
- Malpighian bodies, 475
- Maltose, 130
    - inversion of, 396
- Mammary gland, 319
    - areola of, 321
    - function of, 321
    - structure of, 320
- Manometer, 218
- Marginal convolution, 634
- Marrow, bone, 56
- Mastication, 345
    - centres for, 609
    - muscles of, 346
    - nervous mechanism of, 346
- Mastoid cells, 694
- Meconium, 407
- Medulla oblongata, 597
    - functions of, 608
- Medullary folds, 792

Medullary groove, 792
    plate, 792
    sheath, 92
Meissner's corpuscles, 105
    plexus, 384
Melanin, 126
Membrana decidua, 802
    propria, 27
    tympani, 695
Membranes of brain and cord, 573
Membranous labyrinth, 697
        structure of, 699
Menstrual discharge, 778
Menstruation, 776
Mesencephalon, 827
Mesoblast, 22, 789
    organs developed from, 807
Mesoblastic somites, 794
Mesoderm, 22, 789
Metabolism, 7
    nutrition and diet, 441
Metaphases, 16
Metencephalon, 827
Methæmoglobin, 167
Microsomes, 9
Micturition, 502
    centre, 594
Midbrain, 600, 827
Milk, 322
    chemical composition of, 323, 341
    coagulation of, 323
    digestion of, 376
    globules of, 323
    salts of, 324
Millon's reaction, 118
Mineral foods, 342
Mitosis, 14
Mitral valve, 201
Moist chamber, 526
Motor areas of cortex, 641
        of human brain, 642
        of monkey's brain, 644
    impressions, 589
    oculi nerve, 612
    tracts in human brain, 645
Mouth, description of, 345
Movement, visual estimation of, 751
Mucin, 118
Mucous membranes, 313
Mucus, 314
    in urine, 493
Muroxide test, 491
Muscle, action of voluntary, 538
    at rest, 516
    blood supply of, 89
    caskets, theory, 85
    chemical changes of, 530
        composition of, 514
    coagulation of, 514
    conditions affecting irritability of, 519
    contraction of, 521
    contracture, 538
    curve, 524
    effect of blood supply on, 519
        of disease on, 520
        of drugs on, 532
        of separation from nerve supply, 520
        of single induction shocks on, 526
        of temperature on, 531
        of use on, 520
    electrical phenomena of, 516
    fatigue of, 520, 531, 534
    heart, 88
    in activity, 519
    microscopic appearance of, 530
    -nerve physiology, 514
    nitrogenous crystalline bodies of, 516
    plain, 81
    plasma, 514
    prism, 518
    record of contraction of, 524
    reticulum theory, 86
    rigor mortis in, 536
    serum, 514, 515
    sound, 528, 529
    stimuli of, 521
    striated, 83
Muscles, action of involuntary, 542
        of voluntary, 538
    as heat producers, 466
    centre for tone of, 595
Muscular contraction, 521
    accompaniments of, 528
    changes in shape during, 529
    co-ordination centres for, 653
    differences between voluntary and involuntary, 535
    latent period of, 527
    metabolism, 548
    phenomena of, 521

Muscular contraction, response to stimuli in voluntary and involuntary, 535
    record of, 524
    single twitch, 527
    stage of contraction, 527
        of elastic after-vibration, 528
        of elongation, 528
    summation of contractions, 532
    sensations, centre for, 657
    sense, 682
    tetanus, 532
    tissue, 81
    work, 533
sculi papillares, 1
yeline sheath, 92
yelocyte, 154
Myeloplaxe, 56
ograph, penduli
ohæmatin, 515
opia, 737
osin, 116,
ferment,
xœdema,

NAILS, 509
Nasal region, smell, 687
    other functions, 691
Native albumins, 114
Nerve cells, 99
Nerve centres, automatism of, 572
        functions of, 570
        units of cord, 585
    collaterals, 98
    corpuscles, 93
    effect of constant current on, 543
    electrotonus in, 544
    fibres, 91
        functions of, 567
        medullated, 91
    impulse, velocity of, 568
    plexuses, 99
    stimuli, 543
    terminations, 102
    trunks, 97
Nerves, effect of battery currents on human, 546
    electrical currents in, 542
    vasomotor, 258, 259
Nervous metabolism, 548
    system, 567
        cerebro-spinal, 569
Nervous system, development of, 82
        sympathetic, 667
    tissues, 91
        axones of, 91
        dendrites, 91
        ganglia, 101
        non-medullated fibres, 95
        Pacinian bodies, 104
        tactile menisques, 107
Neural canal, 792
Neuraxone, 91
Neurenteric canal, 796
Neurilemma, 93
Neuroglia, 107, 576
Neurokeratin, 122
Neuron, 91
Neutrophil, 154
Ninth nerve, 622, 623
Nitrogen equilibrium, 443
Nitrogenous bases, 122
Nodes of Ranvier, 95
Nœud vital, 295
Normal saline solution, 35
Nose, development of, 832
Notochord, 792
Nuclear matrix, 13
Nucleic acid, 119
Nuclein bases, 122
Nucleins, 119
Nucleoli, 12
Nucleo-proteids, 118
Nucleus, 11
    ambiguus, 622
    of Pander, 789
    structure of, 12

OCCIPITAL lobe, 633
Odontoblasts, 72
Œsophagus, 864
Oils, 128
Olfactory bulb, 688
    centre, 656
    tract, 656
Olivary bodies, 602, 605
Olive, superior, 622, 628
Omphalo-mesenteric duct, 796
Oncograph, 498
Oncometer, 497
Ophthalmoscope, 743
Optic centres, 654
    lobes, 664
    thalami, 597, 602, 631

Optic thalami, functions of, 657
Optical apparatus, 710
        anatomy of, 710
        defects of, 733
    axis, 729
Organ of Corti, 700
Organic substances, 111
Organized ferments, 414
Organs, development of, 807
Osmosis, 179
Osseous labyrinth, 696
Ossicles of ear, 695
Osteoclasts, 65
Osteogenetic fibres, 61
Output of energy, 458
Ovaries, 762
Oviducts, 766
Ovum, 763
    changes in, 784
        following impregnation, 785
        prior to impregnation, 784
Oxaluric acid, 493
Oxygen in expired air, 284
Oxyhæmoglobin, 165
Oxyntic cells, 369
Oxyphil, 154

PACCHIONIAN bodies, 575
Pacinian corpuscles, 104
Pain, sense of, 681
Pancreas, 392
    action of secretin on, 398
        of nerves on, 398
    changes in cells during secretion, 393
    development of, 833
    extracts of, 394
    functions of, 395
    internal secretion of, 331
    islands of Langerhans in, 393
    structure of, 392, 393
    secretion of, 394
Pancreatic diabetes, 331
    juice, 394
        chemical composition, 395
        conditions favoring action of, 397
        enzymes of, 395
        enterokinase, action on, 394
        functions of, 395
        secretion of, 394
        secretion of, action of nerves on, 398
Pancreatic juice, secretion of, action of secretin on, 398
Papillæ of skin, 505
Paraglobulin, 117, 159
Paralytic secretion of saliva, 356
Parathyroids, 326
Parietal lobe, 632
Parotid gland, 357
Parturition centre, 595
Penis, 772
Pepsin, 3
    action of, 375, 376
    functions of, 376
    how obtained, 377
Pepsinogen, 371
Peptones, 117, 374
    characteristics of, 375
Perceptions, 676
    taste and smell, 685
Perforating fibres of Sharpey, 60
Perfusion cannula, 254
Pericardium, 183
Perimysium, 82
Perineurium, 97
Periosteum, 57
Peripheral resistance, 217, 258
Perspiration, 510
Pettenkofer's test, 404
Peyer's patches, 387
Pflüger's law of contractions, 545
Phagocyte, 156
Pharynx, 362
Phenols formed in intestines, 416
Phosphates, estimation of, 139
Phosphoric acid in urine, 494
Phrenograph, 279
Pia mater, 573
Pigments, 125
Pineal gland, 338
Pituitary body, 330
    development of, 809
Placenta, 803
    formation of, 802
Plasma, 141
    cells, 41
    salted, 147
Pleura, 269
Pleuro-peritoneal cavity, 793
Pneumogastric nerve, 623
Pneumograph, 279
Poikilothermal animals, 464
Polar bodies, 784

Polar cell, 781
Pons Varolii, 627
Pork, composition of, 340
Postdicrotic wave, 231
Posterior commissure of spinal cord, 575
  longitudinal bundle, 628
  marginal zone, 582
  pyramids, 603
  roots of spinal nerves, 583
Poultry, composition of, 340
Precipitins, 175
Predicrotic wave, 231
Presbyopia, 735, 740
Pressor nerves, 259
Prickle cells, 38
Primary areolæ, 64
Primitive groov
  streak, 790
Pronucleus, f
Prophases, 15
Prosecretin, 398
Prosencephalon,
Prostate gland, 7
Protamines, 122
Protargons, 123
Proteids, 111
  chemical reactions of, 112, 118
  circulating, 444
  coagulated, 117
  compound, 118
  decomposition products, 122
  digestion of, 374, 395
  effects of diet of, 445
  floating, 444
  morphotic, 444
  properties of, 112
  tissue, 444
  varieties, 114
Proteoids, 120
Proteolytic ferments, 127
Proteoses, 117
  primary, 375, 395
  reactions of, 376
  secondary, 375, 395
Protoplasm, 2
  chemistry of, 3
  definition of, 3
  growth of, 7
  irritability of, 6
  movement of, 4
  properties of, 3
  reproduction of, 8
Protoplasm, stimuli of, 6
  vital characteristics of, 4
Protoproteose, 376, 395
Protovertebræ, 794
Pseudoscope, 761
Pseudostomata, 32
Ptosis, 613
Ptyalin, 351
  action of, 352, 353
Pulse, 227
Pulvinar, 631
Pupil, 717
  movements of, 735
Purin base, 122
Purkinje's cells, 659
  figures, 741
Putamen, 630
Putrefaction in intestines, 416
Pyramids, 603

Ranvier, nodes of, 95
Reaction of degeneration, 546
Rectum, the, 390
Recurrent sensibility, 587
Red corpuscles, 148
  action of reagents on, 148
  destruction of, 335
  development of, 176
  enumeration of, 156
  origin of, 178, 335
  varieties of, 150
Red nucleus, 602
Reflex action, 570
  arc, 570
  cord in, 590
Reflexes, 591
  cutaneous, 591
  inhibition of, 592
  morbid, 598
  muscle, 591
  special centres for, 593
Remak's fibres, 95
  ganglion, 246
Rennin, 376
Reproductive organs, 762
Reserve air, 282
Residual air, 282
Respiration, 264
  effect of altitude on, 309
    of, on circulation, 300
    of various gases on, 308
    of vitiated air on, 300

Respiration, influence of general sensory nerves, 297
        of glosso-pharyngeal, 297
        of superior laryngeal, 296
        of vagus on, 296
    inspiration, 274
    mechanism of, 274
    movements of vocal cords in, 559
    nervous apparatus of, 294
    rhythm of, 280
    special acts, 291
Respirations, number of, 288
Respiratory apparatus, 265
    capacity, 282
    centre, 295, 610
        automatic action of, 297
        stimulation of, 298
    changes in air breathed, 285
        in the blood, 289
        in the tissues, 290
    movements, recording of, 278
        of nostrils and glottis, 281
    murmur, 281
    muscles, force of, 282
    quotient, 287
    terms for quantity of air breathed, 281
Restiform body, 605
    tissue, 46
Reticular formation in medulla, 605
        lateral, 579
        posterior, 579
Retina, 719
    cones of, 721
    excitation of, 741
    layers of, 720
    movement of pigment cells, 746
    reciprocal action of parts, 754
    rods of, 721
Rheoscopic frog, 548
Rhythmical contractility, 245
Ribs, movements of, in respiration, 276
Rigor mortis, 536
        cause of, 536
        heat, 537
        order of occurrence, 537
        water, 537
Rima glottidis, 266
Ringer's solution, 256
Ritter's tetanus, 546
Roy's tonometer, 254
Running, 542

SACCHAROSES, 185
Saliva, 350
    action of, on starch, 351
    chemical composition, 350
    conditions favoring action, 353
    nervous centres for, 610
        mechanism of secretion, 354
    properties of, 350, 351
    ptyalin in, 352
    quantity of, 351
    rate of secretion of, 351
    uses of, 351
Salivary digestion in stomach, 354
    glands, 346
        blood-vessels of, 349
        changes in cells during secretion, 357
        development of, 833
        nerves of, 349
        structure of, 346
        varieties of, 348
Sanson's images, 733
Saponification, 396
Sarcode, 2
Sarcolemma, 88
Sarcomeres, 87
Sarcoplasm, 85
Sarcosin, 123
Schiff's test for uric acid, 491
Schwann, sheath of, 98
Sebaceous glands, 507
Sebum, 507, 511
Secretin, 398
Secreting glands, 315
Secretion, 310
    circumstances influencing, 318
    discharge of, 317
    internal, 325
    organs and tissues of, 311
    process of, 317
Segmentation in chick, 787
Semicircular canals, 697
Semilunar valves, 202
Sensations, common, 674
    of color, 752
    special, 675
Sense, hearing, 693
    muscular, 682
    of pain, 681
    of sight, 710
    of smell, 687
    of taste, 684

Sense of temperature, 680
    of touch, 678
    organs, development of, 826
Senses, the, 674
    special, 677
Sensory centres, 654
    impressions, 588
Septum lucidum, 597
Serous membranes, 811
        functions of, 812
Serum, 160
    albumin, 115, 158
    globulin, 116, 158
    globulicidal action of, 174
    hæmolytic action of, 174
    precipitins of, 174
Seventh nerve, 619
Sexual organs, female, physiology of, 775
        male, physiology of, 781
Sighing, 292
Sight, 711
Silicon, 185
Singing, 293
Sixth nerve, 619
Sinus rhomboidalis, 793
Size, estimation of, 749
Skatol, 126
Skein, 15
Skeletal muscle, 82
Skin, absorption from, 439
    appendages of, 508, 509
    functions of, 510
    glands of, 506
    papillæ of, 505
    structure of, 503
Sleep, 652
Small intestine, 384
        glands of, 386
        lacteals in, 389
        mucosa of, 385
        nerves of, 384
        structure of, 384
        summary of digestive changes in, 411
Smell, centre for, 656
    sense of, 687
Sneezing, 293
    centre, 610
Sniffing, 293
Soaps, 131
Sobbing, 294
Solidity, judgment of, 760
Somatopleure, 793
Somnambulism, 653
Sound of contracting muscle, 528
Sounds, 708
Spasm centres, 611
Speaking, 293
Special centres in bulb, 609
    respiratory acts, 291
    sensations, 675
Speech, 564
    action of tongue in, 566
Spermatoblasts, 771
Spermatozoa, 781
Sphygmogram, 228
Sphygmograph, 228
Sphygmometer, 230
Spinal accessory nerve, 626
    bulb, 597, 602
    centres, 593
    cord, 580
        antero-lateral ascending trac
          582
        antero-lateral descending trac
          581
        ascending degeneration of, 58
        columns of, 580
        comma-tract of, 581
        course of motor impulses in, 5
        course of sensory impulses i
          588
        conduction in, 587
        crossed pyramidal tract, 581
        descending degeneration of, 5
        development of, 825
        direct cerebellar tract of, 582
        direct pyramidal tract of, 581
        functions of, 586
        gray matter of, 578
        Lissauer's tract, 582
        peculiarities of different regions
          585
        postero-lateral column, 581
        postero-marginal zone, 582
        postero-medi[illegible] column, 581
        reflex acti
        white matt
        weight of.
    nerve roots,
    nerves, 582
        anterior
        course c

Spinal nerves, development of, 824
    posterior roots of, 584
Spirem, 15
Spirometer, 282
Splanchnic nerves, 670
Splanchnopleure, 793
Spleen, 331
    functions of, 334
    influence of drugs on, 336
        of nervous system on, 336
    lobules of, 333
    Malpighian corpuscles of, 333, 334
    pulp, 333
    structure, 332
Spongioplasm, 9
Stammering, 566
Stannius' experiment, 248
Starch, 129
    action of amylopsin on, 396
        of ptyalin on, 352
    formation of, 19
    granules, structure of, 351
Starvation, 454
    death from, 454, 455
    effect on body temperature, 454
    symptoms of, 454
Steapsin, 397
Stellate cells, 659
Stercobilin, 405
Stercorin, 410
Stereoscope, 750
Stethograph, 279
Stethometer, 279
Stokes' fluid, 166
Stomach, 367
    absorption from, 438
    action of pylorus in, 378
    blood-vessels of, 370
    changes in glands during secretion, 370
    digestion of, after death, 381
    functions of, 371
    gases in, 419
    glands of, 369
    lymphatics of, 370
    movements of, 377, 379
    nerves of, 371
    nervous control of secretion, 379
        control of movements, 379
    secretion in, 371
    structure of, 367
Stomata, 31
Strabismus, 618
Stratum granulosum, 503
    intermedium of Hanover, 79
    lucidum, 503
    Malpighii, 503
Striated muscle, 82
Stromuhr, Ludwig's, 238
Sublobular veins, 401
Submaxillary gland, action of atropine on, 356
        paralytic secretion of, 356
        secretion of, 355
        secretion of, nervous influence on, 355
Substania centralis, 578
    gelatinosa, 578
    lateralis, 578
Subzonal membrane, 799
Succus entericus, 411
Sucking, 294
    centres, 609
Sudoriferous glands, 506
Sugar, test for, 353
Summation of stimuli, 571
Superior laryngeal nerve, in respiration, 296
Suprarenal capsules, 327
    active principle of, 330
    composition of, 328
    functions of, 329
    nerves of, 328
    relation to Addison's disease, 330
    structure of, 327
Swallowing, 365
Sweat, 506, 510, 511
    centres, 611
    glands of, 506
    influence of nervous system on secretion of, 512
Sympathetic ganglia, functions and structure, 667, 672
    nervous system, 667
        system, functions of, 670
Synapsis, 570
Synovial fluid, 312
    membranes, 311
Systole of heart, 200, 204

TACTILE corpuscles, 105
    menisques, 107
Taste, 684
    after-, 686

- Taste, centre, 656
  - conditions necessary for, 684
  - goblets, 362
  - seat of, 684
  - varieties of, 685
- Taurin, 124
- Teeth, 69
  - composition of, 73
  - crusta petrosa, 76
  - dentine of, 73
  - development of, 76
  - enamel of, 75
  - permanent, 71
  - structure of, 72
  - temporary, 70
  - wisdom, 71
- Tegmentum, 628, 629
- Telophases, 17
- Temperature, body, 463
  - dissipation of, 468
  - influence of extreme heat and cold on, 473
  - regulation of, 467
  - sense of, 680
  - variations of, 463
- Temporal lobe, 638
- Tenth nerve, 623
- Testes, 769
- Testicles, descent into scrotum, 888
- Tetanus, 588
  - Ritter's, 546
- Thalamencephalon, 827
- Thebesius, vessels of, 257
- Third eye, 838
  - nerve, 612
  - ventricle, 597
- Thoracic duct, 426
- Thorax, respiratory changes in diameter, 275
- Thrombin, 146
- Thymus gland, 337
  - functions of, 338
- Thyroid glands, 325
  - accessory, 326
  - functions of, 327
- Tidal air, 281
- Tissue elements, 27
- Tissues, connective, 40
  - elementary, 26
  - epithelial, 28
- Tongue, 359
  - epithelium of, 361
- Tongue, muscles of, 359
  - papillæ of, 361
  - structure of, 360
- Tonic centres, 611
- Tonometer, 254
- Tonsils, 363
- Touch corpuscles, 105, 678
  - sense of, 678
- Trachea, 276
- Tract of Gowers and Tooth, 582
  - of Lissauer, 582
- Traube-Herring curves, 305
- Tricuspid valve, action of, 201
- Trigeminus nerve, 614
- Trochlearis nerve, 613
- Trypsin, 395
  - action of, 395
- Tunica albuginea, 763
- Tubuli seminiferi, 770
  - uriniferi, 475
- Twelfth nerve, 627
- Tympanum, 694
- Tyrosin, 124

- UMBILICAL cord, 806
  - vesicle, 796, 797
- Uncinate gyrus, 634
- Unstriped muscle, 81
- Urea, 122
  - antecedents of, 446
  - biuret reaction of, 488
  - chemical nature of, 488
  - formation of, in the liver, 445
  - in the urine, 486
  - other places of formation, 447
  - properties of, 487
  - quantitative estimation of, 137, 489
  - variations in amount excreted, 488
- Ureters, 482
  - structure of, 482
- Urethra, 778
- Uric acid, 122, 125, 489
  - condition of, in urine, 490
  - formation of, 445, 447
  - properties of, 489
  - tests for, 490, 491
  - variations in quantity of, 490
- Urina cibi, 486
  - potus, 486
  - sanguinis, 486
- Urinary bladder, 483
- Urine, 483

Urine, abnormal constituents of, 486
  average daily quantity of constituents, 485
  chemical composition of, 484
  chlorine in, 495
  colored by medicines, 492
  cystin in, 495
  estimation of solids of, 485
  extractives of, 493
  factors affecting secretion of, 499
  filtration theory of secretion, 496
  gases in, 496
  hippuric acid in, 491
  indican in, 492
  indigo in, 492
  kreatinin in, 493
  method of secretion of, 496
  mucus in, 493
  occasional constituents, 495
  passage into bladder, 502
  physical properties of, 483
  phosphoric acid in, 494
  pigments in, 491
  quantity of, 486
  reaction of, 484
  relation of secretion to blood pressure and flow, 499
  saline matter, 493
  secretion, theories of, 500
    influence of heart's action, 496, 497
  solids of, 486
  sulphuric acid in, 493
  urea in, 486
  uric acid of, 489
  variations in quantity of constituents, 485
    in specific gravity, 485
  xanthin in, 493
Urobilin, 126, 405
Urochrome, 126
Uroërythrin, 126, 492
Uromelanin, 492
Uterus, 767

VAGINA, 768
Vagus nerve, 623
    effects of section, 625
    functions of, 624
    relation to deglutition, 366
    relatition to gastric secretion, 380
    relation to heart's action, 249
    relation to movements of stomach, 380
    relation to respiration, 296
Valsalva, sinuses of, 191
Valve of Vieussens, 600
Valves of heart, 201
  of veins, 197
Valvulæ conniventes, 385
Vascular system, development of, 818
Vas deferens, 769
Vasa vasorum, 198
Vasomotor nerves, 258
  centres, 259, 610
  reflexes, 259
Veins, 197
  development of, 820
  distribution of, 197
  structure of, 197
  valves of, 197
Velum interpositum, 598
Venous flow, 237
Ventilation, 300
Ventricles of heart, action of, 200
Ventriloquism, 566
Vernix caseosa, 511
Vertebral column, development of, 807
  plate, 798
Vertebrate brain, 688
Vesico-spinal centre, 594
Vesiculæ seminales, 711
Vesicular breathing, 280
Villi. 389
Visceral arches, 810
  clefts, 810
  folds, 810
  plates, 796
Vision, accommodation of, 731
  binocular, 756
  field of, 748
  mechanism of accommodation, 733
  range of distinct, 734
  reversion of image, 746
Visual axis, 720
  centre, 654
  judgments, 746
  perceptions, 746
  purple, 745
  sensations, 741
    after-images, 742
    duration of, 742

Visual sensations, intensity of, 742
  sense, 710
Vital capacity, 282
Vitellin, 120
Vitelline duct, 796
Vocal cords, movements of, 559
Voice, 551
  difference between male and female, 561
  in singing and speaking, 560
Vomiting, 382
  action of abdominal muscles, 382
    of diaphragm, 382, 383
    of pylorus, 383
  nervous mechanism of, 383
Vowels, 565

WALKING, 540
Wallerian degeneration, 575
Wharton's jelly, 46
Wolffian bodies, 835

XANTHIN, 125
  base, 122
  in urine, 493
Xantho-proteic reaction, 113

YAWNING, 294
Yellow spot of Soemmering, 719
Yolk sac, 807

ZONA pellucida, 786

LANE MED

To avoid fine, this bo
or before the dat

JAN 27 1943

F34 Kirkes,W.S. 47311
K59 Handbook of physiology
1905 rev.by Busch,5th Amer.
revision

| NAME | DATE DUE |
|---|---|
| Mary Jane Morris | JAN 27 1943 |